

44856.3.36

Jun 19, 2024

DJ00517

TIP NO W-5710AH

0.670 MILES

FED AID NO HSIP-0200(014)

GRADING, DRAINAGE, PAVEMENT REMOVAL, PAVING, CONCRETE ISLAND

INTERSECTION IMPROVEMENTS AT SR 1137 (POTTER RD), NC 200 (LANCASTER HWY) AND SR 1201 (MARVIN FOWLER RD)

TRUEROCK CONSTRUCTION LLC

KEMP SIGMON CONSTRUCTION CO
INC

EFFICIENT DEVELOPMENTS LLC

MONROE, NC

CLAREMONT, NC

CHARLOTTE, NC

ROADWAY ITEMS

Item ID	Code	Quantity	Description	Unit	Rate	TRUEROCK	KEMP SIGMON	EFFICIENT	Total
0001	0000100000-N	800	MOBILIZATION			110,000.00			119,100.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING			40,000.00		20,000.00	30,000.00
0003	0008000000-E	200	SUPP CLEARING & GRUBBING	1 ACR	10,000.00	10,000.00	100.00	100.00	12,000.00
0004	0057000000-E	226	UNDERCUT EXCAVATION	100 CY	103.55	10,355.00	30.00	3,000.00	60.00
0005	0063000000-N	SP	GRADING (SP)			257,245.00		530,000.00	450,000.00
0006	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	100 SY	6.50	650.00	4.00	400.00	2.50
0007	0234000000-E	SP	GENERIC GRADING ITEM (CY) BORROW EXCAVATION (PIPE INSTALLATION)	100 CY	40.00	4,000.00	30.00	3,000.00	40.00
0008	0318000000-E	300	FND CONDIT MATL MINOR STRS	60 TON	91.80	5,508.00	10.00	600.00	70.00
0009	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	190 SY	4.15	788.50	1.00	190.00	2.50
0010	0335200000-E	305	15" DRAINAGE PIPE	104 LF	97.50	10,140.00	130.00	13,520.00	75.00
0011	0335300000-E	305	18" DRAINAGE PIPE	44 LF	113.80	5,007.20	140.00	6,160.00	78.00
0012	0366000000-E	310	15" RC PIPE CULV III	80 LF	128.85	10,308.00	150.00	12,000.00	105.00
0013	0372000000-E	310	18" RC PIPE CULV III	36 LF	146.85	5,286.60	160.00	5,760.00	108.00
0014	0448200000-E	310	15" RCP CULV CLASS IV	52 LF	249.90	12,994.80	160.00	8,320.00	125.00
0015	0448300000-E	310	18" RCP CULV CLASS IV	144 LF	151.75	21,852.00	170.00	24,480.00	125.00
0016	0448400000-E	310	24" RCP CULV CLASS IV	100 LF	157.60	15,760.00	220.00	22,000.00	160.00
0017	0995000000-E	340	PIPE REMOVAL	161 LF	75.00	12,075.00	15.00	2,415.00	30.00
0018	1220000000-E	545	INCIDENTAL STONE BASE	50 TON	71.65	3,582.50	75.00	3,750.00	50.00
0019	1330000000-E	607	INCIDENTAL MILLING	150 SY	56.90	8,535.00	35.00	5,250.00	16.00
0020	1491000000-E	610	ASP CONC BASE CRS B25.0C	2,700 TON	93.10	251,370.00	87.50	236,250.00	95.00
0021	1503000000-E	610	ASP CONC INTR CRS I19.0C	950 TON	113.65	107,967.50	87.50	83,125.00	95.00
0022	1523000000-E	610	ASP CONC SURF CRS S9.5C	1,550 TON	96.75	149,962.50	87.50	135,625.00	95.00
0023	1575000000-E	620	ASP FOR PLANT MIX	270 TON	678.25	183,127.50	650.00	175,500.00	687.00
0024	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY	88.00	2,024.00	10.00	230.00	20.00
0025	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	100 SY	1.00	100.00	1.00	100.00	2.00
0026	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	17 CY	172.70	2,935.90	10.00	170.00	50.00
0027	2043000000-E	815	4" PERF SUBDRN PIPE	100 LF	22.40	2,240.00	1.00	100.00	15.00
0028	2070000000-N	815	SUBDRN PIPE OUTLET	1 EA	138.30	138.30	1.00	1.00	350.00
0029	2076000000-E	815	4" OUTLET PIPE	6 LF	139.15	834.90	1.00	6.00	45.00
0030	2286000000-N	840	MASNRY DRAINAGE STRUCT	4 EA	5,413.00	21,652.00	5,000.00	20,000.00	3,500.00
0031	2364000000-N	840	FRAME W/2GRTS 840.16 STD	4 EA	1,400.00	5,600.00	1,100.00	4,400.00	1,200.00
0032	2451000000-N	852	CONC TRANS SECT FOR DROP INLET	4 EA	2,360.90	9,443.60	1,600.00	6,400.00	600.00
0033	2535000000-E	846	***X*** CONCRETE CURB (8" X 18")	300 LF	34.15	10,245.00	30.00	9,000.00	32.50
0034	2612000000-E	848	6" CONCRETE DRIVEWAY	3 SY	622.05	1,866.15	396.00	1,188.00	89.00
0035	2647000000-E	852	5" MONO CONC ISLANDS (SURF MTD)	330 SY	93.40	30,822.00	89.00	29,370.00	81.00
0036	2738000000-E	SP	GENERIC PAVING ITEM (SY) 12" TRUCK MOUNTED CONCRETE ISLAND, CLASS AA CONCRETE	575 SY	170.15	97,836.25	150.00	86,250.00	150.00

44856.3.36

Jun 19, 2024

DJ00517

TIP NO W-5710AH

0.670 MILES

FED AID NO HSIP-0200(014)

GRADING, DRAINAGE, PAVEMENT REMOVAL, PAVING, CONCRETE ISLAND

INTERSECTION IMPROVEMENTS AT SR 1137 (POTTER RD), NC 200 (LANCASTER HWY) AND SR 1201 (MARVIN FOWLER RD)

				TRUEROCK CONSTRUCTION LLC	KEMP SIGMON CONSTRUCTION CO INC				EFFICIENT DEVELOPMENTS LLC	
				MONROE, NC	CLAREMONT, NC				CHARLOTTE, NC	
0037	2738000000-E	SP	GENERIC PAVING ITEM (SY) 12" TRUCK MOUNTED CONCRETE ISLAND, CLASS AA CONCRETE (BLACK TINT)	650 SY	164.75	107,087.50	246.00	159,900.00	205.00	133,250.00
0038	2752000000-E	SP	GENERIC PAVING ITEM (LF) 1'-6" CONCRETE CURB & GUTTER, CLASS AA CONCRETE	1,375 LF	28.55	39,256.25	36.00	49,500.00	33.00	45,375.00
0039	2760000000-N	848	GENERIC PAVING ITEM 848 (EA) 12" APRON DRAINAGE TROUGH	5 EA	2,919.65	14,598.25	1,500.00	7,500.00	550.00	2,750.00
0040	2845000000-N	858	ADJ METER OR VALVE BOXES	1 EA	1,075.30	1,075.30	1,500.00	1,500.00	250.00	250.00
0041	3642000000-E	876	RIP RAP, CLASS A	16 TON	116.55	1,864.80	100.00	1,600.00	90.00	1,440.00
0042	3649000000-E	876	RIP RAP, CLASS B	146 TON	109.35	15,965.10	100.00	14,600.00	90.00	13,140.00
0043	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	115 SY	9.90	1,138.50	5.00	575.00	2.00	230.00
0044	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	525 LF	7.55	3,963.75	9.99	5,244.75	10.50	5,512.50
0045	4102000000-N	904	SIGN ERECTION, TYPE E	37 EA	225.00	8,325.00	65.00	2,405.00	153.00	5,661.00
0046	4108000000-N	904	SIGN ERECTION, TYPE F	2 EA	325.00	650.00	75.00	150.00	78.00	156.00
0047	4116100000-N	904	SIGN ERECT, RELOC ** GRD MTD (TYPE E)	5 EA	250.00	1,250.00	115.00	575.00	120.00	600.00
0048	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	13 EA	15.00	195.00	10.00	130.00	10.50	136.50
0049	4400000000-E	1110	WORK ZONE SIGNS (STAT)	120 SF	7.55	906.00	6.75	810.00	7.00	840.00
0050	4405000000-E	1110	WORK ZONE SIGNS (PORT)	288 SF	8.75	2,520.00	14.00	4,032.00	16.00	4,608.00
0051	4410000000-E	1110	WORK ZONE SIGNS (BARR)	60 SF	8.95	537.00	7.00	420.00	8.00	480.00
0052	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	4 EA	900.00	3,600.00	10,000.00	40,000.00	5,000.00	20,000.00
0053	4430000000-N	1130	DRUMS	300 EA	46.00	13,800.00	125.00	37,500.00	46.00	13,800.00
0054	4435000000-N	1135	CONES	100 EA	22.00	2,200.00	125.00	12,500.00	28.00	2,800.00
0055	4445000000-E	1145	BARRICADES (TYPE III)	120 LF	25.00	3,000.00	23.00	2,760.00	26.50	3,180.00
0056	4455000000-N	1150	FLAGGER	40 DAY	1,000.00	40,000.00	450.00	18,000.00	400.00	16,000.00
0057	4685000000-E	1205	THERMO PVT MKG LINES 4"90	15,195 LF	0.75	11,396.25	0.75	11,396.25	0.80	12,156.00
0058	4695000000-E	1205	THERMO PVT MKG LINES 8"90 MILS	463 LF	2.80	1,296.40	2.80	1,296.40	2.95	1,365.85
0059	4709000000-E	1205	24"WIDE THERMO 90 MILS	35 LF	10.00	350.00	10.00	350.00	10.50	367.50
0060	4720000000-E	1205	THERMO PVT MKG CHARACTER 90	16 EA	35.00	560.00	35.00	560.00	36.75	588.00
0061	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	38 EA	35.00	1,330.00	35.00	1,330.00	36.75	1,396.50
0062	4810000000-E	1205	PAINT PVT MARKINGS 4"	15,195 LF	0.34	5,166.30	0.34	5,166.30	0.36	5,470.20
0063	4820000000-E	1205	PAINT PVT MARKINGS 8"	419 LF	0.68	284.92	0.68	284.92	0.72	301.68
0064	4835000000-E	1205	PAINT PVT MKG LINES 24"	35 LF	1.00	35.00	1.00	35.00	1.05	36.75
0065	4845000000-N	1205	PAINT PVT MKG SYMBOL	38 EA	5.00	190.00	5.00	190.00	5.25	199.50
0066	4905100000-N	1253	NON-CAST IRON SNOWPLB PVT MRKER	55 EA	125.00	6,875.00	125.00	6,875.00	131.25	7,218.75
0067	5835000000-E	1540	*** ENCASEMENT PIPE (4")	75 LF	94.95	7,121.25	125.00	9,375.00	35.00	2,625.00
0068	5888000000-E	SP	GENERIC UTILITY ITEM (LF) 2" SEPTIC DRAIN FIELD SUPPLY LINE	450 LF	43.25	19,462.50	40.00	18,000.00	25.00	11,250.00
0069	5888000000-E	SP	GENERIC UTILITY ITEM (LF) 4" PVC CONDUIT	75 LF	15.15	1,136.25	50.00	3,750.00	30.00	2,250.00
0070	6000000000-E	1605	TEMPORARY SILT FENCE	4,600 LF	5.85	26,910.00	3.00	13,800.00	3.00	13,800.00

44856.3.36

TIP NO W-5710AH

0.670 MILES

FED AID NO HSIP-0200(014)

GRADING, DRAINAGE, PAVEMENT REMOVAL, PAVING, CONCRETE ISLAND

INTERSECTION IMPROVEMENTS AT SR 1137 (POTTER RD), NC 200 (LANCASTER HWY) AND SR 1201 (MARVIN FOWLER RD)

				TRUEROCK CONSTRUCTION LLC			KEMP SIGMON CONSTRUCTION CO INC		EFFICIENT DEVELOPMENTS LLC		
				MONROE, NC			CLAREMONT, NC		CHARLOTTE, NC		
0071	6006000000-E	1610	EROS CONTRL STONE CL A	55	TON	93.70	5,153.50	75.00	4,125.00	80.00	4,400.00
0072	6009000000-E	1610	EROS CONTRL STONE CL B	1,440	TON	85.00	122,400.00	20.00	28,800.00	80.00	115,200.00
0073	6012000000-E	1610	SEDIMENT CONTROL STONE	420	TON	68.35	28,707.00	20.00	8,400.00	65.00	27,300.00
0074	6015000000-E	1615	TEMPORARY MULCHING	5	ACR	1,700.00	8,500.00	1,700.00	8,500.00	1,200.00	6,000.00
0075	6018000000-E	1620	SEED FOR TEMP SEEDING	800	LB	6.00	4,800.00	6.00	4,800.00	3.00	2,400.00
0076	6021000000-E	1620	FERT FOR TEMP SEEDING	4	TON	1,900.00	7,600.00	1,900.00	7,600.00	1,350.00	5,400.00
0077	6029000000-E	SP	SAFETY FENCE	200	LF	4.00	800.00	2.00	400.00	2.10	420.00
0078	6030000000-E	1630	SILT EXCAVATION	60	CY	20.00	1,200.00	25.00	1,500.00	30.00	1,800.00
0079	6036000000-E	1631	MATTING FOR EROS CONTROL	10,220	SY	1.95	19,929.00	1.95	19,929.00	1.50	15,330.00
0080	6038000000-E	SP	PERM SOIL REINF MAT	1,080	SY	3.75	4,050.00	3.75	4,050.00	4.70	5,076.00
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	235	LF	10.00	2,350.00	5.00	1,175.00	5.25	1,233.75
0082	6071002000-E	1642	FLOCCULANT	25	LB	25.00	625.00	15.00	375.00	15.00	375.00
0083	6071010000-E	1642	WATTLE	810	LF	10.00	8,100.00	9.00	7,290.00	9.00	7,290.00
0084	6071030000-E	1640	COIR FIBER BAFFLE	45	LF	25.00	1,125.00	8.00	360.00	8.00	360.00
0085	6084000000-E	1660	SEEDING AND MULCHING	5	ACR	2,750.00	13,750.00	2,750.00	13,750.00	2,300.00	11,500.00
0086	6087000000-E	1660	MOWING	2	ACR	500.00	1,000.00	500.00	1,000.00	158.00	316.00
0087	6090000000-E	1661	SEED FOR REPAIR SEEDING	150	LB	8.00	1,200.00	8.00	1,200.00	8.00	1,200.00
0088	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	2,600.00	650.00	2,600.00	650.00	1,700.00	425.00
0089	6096000000-E	1662	SEED FOR SUPP SEEDING	300	LB	6.00	1,800.00	6.00	1,800.00	6.00	1,800.00
0090	6108000000-E	1665	FERTILIZER TOPDRESSING	8.75	TON	1,900.00	16,625.00	1,900.00	16,625.00	1,300.00	11,375.00
0091	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	75.00	750.00	75.00	750.00	80.00	800.00
0092	6117000000-N	1675	RESPONSE FOR EROS CONTROL	25	EA	250.00	6,250.00	250.00	6,250.00	210.00	5,250.00
0093	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,900.00	1,900.00	15.00	15.00	1,200.00	1,200.00
0094	0022000000-E	225	UNCLASSIFIED EXCAVATION	12,000	CY	25.00	300,000.00	20.00	240,000.00	25.00	300,000.00
CONTRACT TOTAL				TOTAL			2,325,564.02	TOTAL	2,375,114.62	TOTAL	2,382,777.48
ROADWAY ITEMS				SUB-TOTAL			2,325,564.02	SUB-TOTAL	2,375,114.62	SUB-TOTAL	2,382,777.48

44856.3.36

Jun 19, 2024

DJ00517

TIP NO W-5710AH

0.670 MILES

FED AID NO HSIP-0200(014)

GRADING, DRAINAGE, PAVEMENT REMOVAL, PAVING, CONCRETE ISLAND

INTERSECTION IMPROVEMENTS AT SR 1137 (POTTER RD), NC 200 (LANCASTER HWY) AND SR 1201 (MARVIN FOWLER RD)

				NASSIRI DEVELOPMENT LLC MATTHEWS, NC	BLYTHE DEVELOPMENT LLC CHARLOTTE, NC	NJR GROUP INC ALBEMARLE, NC				
ROADWAY ITEMS										
0001	0000100000-N	800	MOBILIZATION	Lump Sum		180,000.00		150,000.00		152,000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		40,000.00		80,000.00		72,500.00
0003	0008000000-E	200	SUPP CLEARING & GRUBBING	1 ACR	4,000.00	4,000.00	14,000.00	14,000.00	1,000.00	1,000.00
0004	0057000000-E	226	UNDERCUT EXCAVATION	100 CY	50.00	5,000.00	150.00	15,000.00	60.00	6,000.00
0005	0063000000-N	SP	GRADING (SP)	Lump Sum		500,000.00		395,000.00		639,680.00
0006	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	100 SY	9.00	900.00	8.00	800.00	5.00	500.00
0007	0234000000-E	SP	GENERIC GRADING ITEM (CY) BORROW EXCAVATION (PIPE INSTALLATION)	100 CY	28.00	2,800.00	105.00	10,500.00	75.00	7,500.00
0008	0318000000-E	300	FND CONDIT MATL MINOR STRS	60 TON	45.00	2,700.00	90.00	5,400.00	50.00	3,000.00
0009	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	190 SY	8.00	1,520.00	15.00	2,850.00	5.00	950.00
0010	0335200000-E	305	15" DRAINAGE PIPE	104 LF	95.00	9,880.00	104.00	10,816.00	100.00	10,400.00
0011	0335300000-E	305	18" DRAINAGE PIPE	44 LF	95.00	4,180.00	113.00	4,972.00	125.00	5,500.00
0012	0366000000-E	310	15" RC PIPE CULV III	80 LF	95.00	7,600.00	101.00	8,080.00	180.00	14,400.00
0013	0372000000-E	310	18" RC PIPE CULV III	36 LF	95.00	3,420.00	121.00	4,356.00	215.00	7,740.00
0014	0448200000-E	310	15" RCP CULV CLASS IV	52 LF	95.00	4,940.00	109.00	5,668.00	250.00	13,000.00
0015	0448300000-E	310	18" RCP CULV CLASS IV	144 LF	95.00	13,680.00	118.00	16,992.00	300.00	43,200.00
0016	0448400000-E	310	24" RCP CULV CLASS IV	100 LF	100.00	10,000.00	157.00	15,700.00	350.00	35,000.00
0017	0995000000-E	340	PIPE REMOVAL	161 LF	25.00	4,025.00	75.00	12,075.00	100.00	16,100.00
0018	1220000000-E	545	INCIDENTAL STONE BASE	50 TON	45.00	2,250.00	60.00	3,000.00	55.00	2,750.00
0019	1330000000-E	607	INCIDENTAL MILLING	150 SY	50.00	7,500.00	60.00	9,000.00	35.00	5,250.00
0020	1491000000-E	610	ASP CONC BASE CRS B25.0C	2,700 TON	135.00	364,500.00	102.00	275,400.00	128.13	345,951.00
0021	1503000000-E	610	ASP CONC INTR CRS I19.0C	950 TON	135.00	128,250.00	100.00	95,000.00	133.59	126,910.50
0022	1523000000-E	610	ASP CONC SURF CRS S9.5C	1,550 TON	145.00	224,750.00	101.00	156,550.00	134.67	208,738.50
0023	1575000000-E	620	ASP FOR PLANT MIX	270 TON	775.00	209,250.00	605.00	163,350.00	750.00	202,500.00
0024	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY	40.00	920.00	200.00	4,600.00	50.00	1,150.00
0025	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	100 SY	9.00	900.00	8.00	800.00	5.00	500.00
0026	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	17 CY	45.00	765.00	250.00	4,250.00	75.00	1,275.00
0027	2043000000-E	815	4" PERF SUBDRN PIPE	100 LF	40.00	4,000.00	50.00	5,000.00	50.00	5,000.00
0028	2070000000-N	815	SUBDRN PIPE OUTLET	1 EA	650.00	650.00	325.00	325.00	500.00	500.00
0029	2076000000-E	815	4" OUTLET PIPE	6 LF	75.00	450.00	150.00	900.00	100.00	600.00
0030	2286000000-N	840	MASNRY DRAINAGE STRUCT	4 EA	4,500.00	18,000.00	5,900.00	23,600.00	6,500.00	26,000.00
0031	2364000000-N	840	FRAME W/2GRTS 840.16 STD	4 EA	1,250.00	5,000.00	1,000.00	4,000.00	1,500.00	6,000.00
0032	2451000000-N	852	CONC TRANS SECT FOR DROP INLET	4 EA	1,250.00	5,000.00	1,200.00	4,800.00	2,500.00	10,000.00
0033	2535000000-E	846	***X*** CONCRETE CURB (8" X 18")	300 LF	40.00	12,000.00	45.00	13,500.00	46.00	13,800.00
0034	2612000000-E	848	6" CONCRETE DRIVEWAY	3 SY	500.00	1,500.00	145.00	435.00	165.00	495.00
0035	2647000000-E	852	5" MONO CONC ISLANDS (SURF MTD)	330 SY	125.00	41,250.00	120.00	39,600.00	135.00	44,550.00
0036	2738000000-E	SP	GENERIC PAVING ITEM (SY) 12" TRUCK MOUNTED CONCRETE ISLAND, CLASS AA CONCRETE	575 SY	140.00	80,500.00	240.00	138,000.00	245.00	140,875.00
0037	2738000000-E	SP	GENERIC PAVING ITEM (SY) 12" TRUCK MOUNTED CONCRETE ISLAND, CLASS AA CONCRETE (BLACK TINT)	650 SY	150.00	97,500.00	330.00	214,500.00	310.00	201,500.00

44856.3.36

Jun 19, 2024

DJ00517

TIP NO W-5710AH

0.670 MILES

FED AID NO HSIP-0200(014)

GRADING, DRAINAGE, PAVEMENT REMOVAL, PAVING, CONCRETE ISLAND

INTERSECTION IMPROVEMENTS AT SR 1137 (POTTER RD), NC 200 (LANCASTER HWY) AND SR 1201 (MARVIN FOWLER RD)

				NASSIRI DEVELOPMENT LLC MATTHEWS, NC			BLYTHE DEVELOPMENT LLC CHARLOTTE, NC			NJR GROUP INC ALBEMARLE, NC	
0038	2752000000-E	SP	GENERIC PAVING ITEM (LF) 1'-6" CONCRETE CURB & GUTTER, CLASS AA CONCRETE	1,375	LF	25.00	34,375.00	40.00	55,000.00	52.00	71,500.00
0039	2760000000-N	848	GENERIC PAVING ITEM 848 (EA) 12" APRON DRAINAGE TROUGH	5	EA	750.00	3,750.00	3,300.00	16,500.00	2,500.00	12,500.00
0040	2845000000-N	858	ADJ METER OR VALVE BOXES	1	EA	1,150.00	1,150.00	2,100.00	2,100.00	1,500.00	1,500.00
0041	3642000000-E	876	RIP RAP, CLASS A	16	TON	75.00	1,200.00	120.00	1,920.00	60.00	960.00
0042	3649000000-E	876	RIP RAP, CLASS B	146	TON	75.00	10,950.00	140.00	20,440.00	55.00	8,030.00
0043	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	115	SY	9.00	1,035.00	10.00	1,150.00	5.00	575.00
0044	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	525	LF	38.00	19,950.00	12.00	6,300.00	13.20	6,930.00
0045	4102000000-N	904	SIGN ERECTION, TYPE E	37	EA	285.00	10,545.00	80.00	2,960.00	90.00	3,330.00
0046	4108000000-N	904	SIGN ERECTION, TYPE F	2	EA	360.00	720.00	90.00	180.00	114.00	228.00
0047	4116100000-N	904	SIGN ERECT, RELOC ** GRD MTD (TYPE E)	5	EA	195.00	975.00	140.00	700.00	114.00	570.00
0048	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	13	EA	65.00	845.00	13.00	169.00	18.00	234.00
0049	4400000000-E	1110	WORK ZONE SIGNS (STAT)	120	SF	65.00	7,800.00	9.00	1,080.00	7.20	864.00
0050	4405000000-E	1110	WORK ZONE SIGNS (PORT)	288	SF	65.00	18,720.00	17.00	4,896.00	14.40	4,147.20
0051	4410000000-E	1110	WORK ZONE SIGNS (BARR)	60	SF	65.00	3,900.00	9.00	540.00	12.00	720.00
0052	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	4	EA	18,750.00	75,000.00	5,000.00	20,000.00	15,000.00	60,000.00
0053	4430000000-N	1130	DRUMS	300	EA	75.00	22,500.00	75.00	22,500.00	88.00	26,400.00
0054	4435000000-N	1135	CONES	100	EA	65.00	6,500.00	50.00	5,000.00	60.00	6,000.00
0055	4445000000-E	1145	BARRICADES (TYPE III)	120	LF	65.00	7,800.00	40.00	4,800.00	50.00	6,000.00
0056	4455000000-N	1150	FLAGGER	40	DAY	500.00	20,000.00	2,400.00	96,000.00	500.00	20,000.00
0057	4685000000-E	1205	THERMO PVT MKG LINES 4"90	15,195	LF	2.40	36,468.00	1.85	28,110.75	0.90	13,675.50
0058	4695000000-E	1205	THERMO PVT MKG LINES 8"90 MILS	463	LF	6.50	3,009.50	4.50	2,083.50	3.36	1,555.68
0059	4709000000-E	1205	24"WIDE THERMO 90 MILS	35	LF	31.00	1,085.00	25.00	875.00	12.00	420.00
0060	4720000000-E	1205	THERMO PVT MKG CHARACTER 90	16	EA	215.00	3,440.00	170.00	2,720.00	42.00	672.00
0061	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	38	EA	235.00	8,930.00	200.00	7,600.00	42.00	1,596.00
0062	4810000000-E	1205	PAINT PVT MARKINGS 4"	15,195	LF	1.25	18,993.75	0.75	11,396.25	0.42	6,381.90
0063	4820000000-E	1205	PAINT PVT MARKINGS 8"	419	LF	3.50	1,466.50	2.00	838.00	0.82	343.58
0064	4835000000-E	1205	PAINT PVT MKG LINES 24"	35	LF	18.00	630.00	10.00	350.00	1.20	42.00
0065	4845000000-N	1205	PAINT PVT MKG SYMBOL	38	EA	100.00	3,800.00	90.00	3,420.00	20.00	760.00
0066	4905100000-N	1253	NON-CAST IRON SNOWPLB PVT MRKER	55	EA	158.00	8,690.00	200.00	11,000.00	150.00	8,250.00
0067	5835000000-E	1540	*** ENCASEMENT PIPE (4")	75	LF	75.00	5,625.00	300.00	22,500.00	200.00	15,000.00
0068	5888000000-E	SP	GENERIC UTILITY ITEM (LF) 2" SEPTIC DRAIN FIELD SUPPLY LINE	450	LF	40.00	18,000.00	20.00	9,000.00	75.00	33,750.00
0069	5888000000-E	SP	GENERIC UTILITY ITEM (LF) 4" PVC CONDUIT	75	LF	75.00	5,625.00	90.00	6,750.00	60.00	4,500.00
0070	6000000000-E	1605	TEMPORARY SILT FENCE	4,600	LF	4.00	18,400.00	3.50	16,100.00	5.00	23,000.00
0071	6006000000-E	1610	EROS CONTRL STONE CL A	55	TON	43.75	2,406.25	80.00	4,400.00	50.00	2,750.00
0072	6009000000-E	1610	EROS CONTRL STONE CL B	1,440	TON	43.75	63,000.00	80.00	115,200.00	50.00	72,000.00
0073	6012000000-E	1610	SEDIMENT CONTROL STONE	420	TON	43.75	18,375.00	80.00	33,600.00	50.00	21,000.00
0074	6015000000-E	1615	TEMPORARY MULCHING	5	ACR	2,000.00	10,000.00	2,100.00	10,500.00	1,380.00	6,900.00

44856.3.36

Jun 19, 2024

DJ00517

TIP NO W-5710AH

0.670 MILES

FED AID NO HSIP-0200(014)

GRADING, DRAINAGE, PAVEMENT REMOVAL, PAVING, CONCRETE ISLAND


INTERSECTION IMPROVEMENTS AT SR 1137 (POTTER RD), NC 200 (LANCASTER HWY) AND SR 1201 (MARVIN FOWLER RD)

				NASSIRI DEVELOPMENT LLC MATTHEWS, NC		BLYTHE DEVELOPMENT LLC CHARLOTTE, NC		NJR GROUP INC ALBEMARLE, NC			
0075	6018000000-E	1620	SEED FOR TEMP SEEDING	800	LB	2.50	2,000.00	8.00	6,400.00	3.60	2,880.00
0076	6021000000-E	1620	FERT FOR TEMP SEEDING	4	TON	1,365.00	5,460.00	2,300.00	9,200.00	1,620.00	6,480.00
0077	6029000000-E	SP	SAFETY FENCE	200	LF	3.00	600.00	3.00	600.00	2.40	480.00
0078	6030000000-E	1630	SILT EXCAVATION	60	CY	10.00	600.00	200.00	12,000.00	12.00	720.00
0079	6036000000-E	1631	MATTING FOR EROS CONTROL	10,220	SY	2.50	25,550.00	3.00	30,660.00	1.68	17,169.60
0080	6038000000-E	SP	PERM SOIL REINF MAT	1,080	SY	9.50	10,260.00	5.00	5,400.00	5.40	5,832.00
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	235	LF	4.75	1,116.25	15.00	3,525.00	6.00	1,410.00
0082	6071002000-E	1642	FLOCCULANT	25	LB	30.00	750.00	100.00	2,500.00	18.00	450.00
0083	6071010000-E	1642	WATTLE	810	LF	14.50	11,745.00	15.00	12,150.00	10.80	8,748.00
0084	6071030000-E	1640	COIR FIBER BAFFLE	45	LF	11.00	495.00	8.00	360.00	9.60	432.00
0085	6084000000-E	1660	SEEDING AND MULCHING	5	ACR	3,687.50	18,437.50	3,300.00	16,500.00	2,640.00	13,200.00
0086	6087000000-E	1660	MOWING	2	ACR	368.75	737.50	600.00	1,200.00	180.00	360.00
0087	6090000000-E	1661	SEED FOR REPAIR SEEDING	150	LB	5.25	787.50	9.50	1,425.00	9.60	1,440.00
0088	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,365.00	341.25	3,100.00	775.00	2,040.00	510.00
0089	6096000000-E	1662	SEED FOR SUPP SEEDING	300	LB	6.23	1,869.00	8.00	2,400.00	7.20	2,160.00
0090	6108000000-E	1665	FERTILIZER TOPDRESSING	8.75	TON	1,365.00	11,943.75	2,300.00	20,125.00	120.00	1,050.00
0091	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	93.75	937.50	90.00	900.00	90.00	900.00
0092	6117000000-N	1675	RESPONSE FOR EROS CONTROL	25	EA	125.00	3,125.00	300.00	7,500.00	240.00	6,000.00
0093	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	4,500.00	4,500.00	10,000.00	10,000.00	650.00	650.00
0094	0022000000-E	225	UNCLASSIFIED EXCAVATION	12,000	CY	5.00	60,000.00	30.00	360,000.00	16.00	192,000.00
CONTRACT TOTAL				TOTAL		2,636,494.25		TOTAL	2,961,117.50	TOTAL	3,078,771.46
ROADWAY ITEMS				SUB-TOTAL		2,636,494.25		SUB-TOTAL	2,961,117.50	SUB-TOTAL	3,078,771.46

BIDDERS IN ORDER

TRUEROCK CONSTRUCTION LLC	1	2,325,564.02
KEMP SIGMON CONSTRUCTION CO INC	2	2,375,114.62
EFFICIENT DEVELOPMENTS LLC	3	2,382,777.48
NASSIRI DEVELOPMENT LLC	4	2,636,494.25
BLYTHE DEVELOPMENT LLC	5	2,961,117.50
NJR GROUP INC	6	3,078,771.46

CONTRACT TOTAL

DocuSigned by:

 8DD1CB4DB58F4FC...