REFERENCE:

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	SF-830035	1	7

STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION **DIVISION OF HIGHWAYS** GEOTECHNICAL ENGINEERING UNIT

STRUCTURE SUBSURFACE INVESTIGATION

COUNTY STANLY

SITE DESCRIPTION BRIDGE NO. 35 ON SR 1134 (MILLINGPORT RD.) OVER LONG CREEK

CONTENTS

SHEET NO.

2. 2A

3 4-6 **DESCRIPTION**

TITLE SHEET LEGEND (SOIL & ROCK) SITE PLAN

BORE LOG(S) SITE PHOTOGRAPH(S) PERSONNEL

J.K. STICKNEY

C.L. SMITH

B.E. FOSTER

INVESTIGATED BY J.E. BEVERLY

DRAWN BY J.E. BEVERLY

CHECKED BY __C.R. LAVENDER, III

SUBMITTED BY __K.B. MILLER

DATE _DECEMBER 2020

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY DIPPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT 199) 707-850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.


GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU INN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOL THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE OF INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN IN FORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEERN EXCESSARY TO SATISY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED OF PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:

 I. THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.

 BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PROJECT REFERENCE NO.	SHEET NO.
SF-830035	2

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS GEOTECHNICAL ENGINEERING UNIT

SUBSURFACE INVESTIGATION

SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS (PAGE 1 OF 2)

														(1 2	IUL	1 OF 2)		
	SOIL DESCRIPTION														GRADATION			
BE PENE ACCORE IS CONSIST	SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM DISBG). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM, BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINET FACTORS SUCH										WEAT O YIEL 206, GENER ON, AN	.D LES ASTM (ALLY) D OTH	S THAN 100 1586). SOIL NCLUDE TH ER PERTINE	Ø BLOWS PI _ CLASSIFI IE FOLLOWI ENT FACTOR	WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES. ANGULARITY OF GRAINS			
AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE PLASTICITY, ETC. FOR EXAMPLE, VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6										FINE	SAND	LAYER.	S.HIGHLY PLA	ASTIC, A-7-6	THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.			
CENEDA							DNA	AA					CATION	l		MINERALOGICAL COMPOSITION		
GENERAL GRANULAR MATERIALS CLASS. (≤ 35% PASSING *200)						SILT-CLAY MATERIALS (> 35% PASSING =200) ORGANIC MATERIALS						IALS	MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC.					
GROUP CLASS.		4-1 A-1-b	A-3	_	_	A-2 -5 A-2	2-6 A-	_	A-4	A-5	A-6	A-7 A-7-5 A-7-6	A-1, A-2 A-3	A-4, A-5 A-6, A-7		ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE. COMPRESSIBILITY		
SYMBOL		00000						S		77.7		A-7-6				SLIGHTLY COMPRESSIBLE LL < 31 MODERATELY COMPRESSIBLE LL = 31 - 50		
% PASSING	0000	00000	4:::::	3310/2533			3			22.			· · · · · · · · · · · · · · · · · · ·	SILT-		HIGHLY COMPRESSIBLE LL > 50		
*10 *40 *200		50 M	K 51 MN K 10 M)		X 35 M	4X 35	MX 35	5 MX 3	6 MN	36 MN	36 MN	36 MN	Granular Soils	CLAY SOILS	MUCK, PEAT	PERCENTAGE OF MATERIAL GRANULAR SILT - CLAY ORGANIC MATERIAL SOILS SOILS OTHER MATERIAL		
MATERIAL PASSING *40 LL PI	6	_ MX	– NP					I MN 4			40 MX 11 MN	41 MN 11 MN	LITT	S WITH LE OR ERATE	HIGHLY	TRACE OF ORGANIC MATTER 2 - 3% 3 - 5% TRACE 1 - 10% LITTLE ORGANIC MATTER 3 - 5% 5 - 12% LITTLE 10 - 20% MODERATELY ORGANIC 5 - 10% 12 - 20% SOME 20 - 35%, HIGHLY ORGANIC > 10% > 20% HIGHLY 35% AND ABOVE		
GROUP INDEX	_	0	0		0		4 MX		3 мх	12 MX	16 MX	NO MX		nts of Anic	ORGANIC SOILS	GROUND WATER		
USUAL TYPES OF MAJOR MATERIALS	MAJOR GRAVEL, AND SAND CRAVEL AND SAND				SIL SOII	TY CLAYEY MATTER						▼ water level in Bore hole immediately after drilling ▼ static water level after 24 hours ▼						
GEN, RATING EXCELLENT TO GOOD AS SUBGRADE							0 P00R		FAIR TO POOR	POOR	UNSUITABLE	<u>▽PW</u> PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA						
			PI OF										> LL - 30			MISCELLANEOUS SYMBOLS		
PRIMARY SOIL TYPE COMPACTNESS OR CONSISTENCY				Ī	OR DENSENESS RANGE OF STANDARD PENETRATION RESISTENCE (N-YALUE) RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)					RESSIVE S	STRENGTH	ROADWAY EMBANKMENT (RE) 25/025 DIP & DIP DIRECTION OF ROCK STRUCTURES						
GENERALLY GRANULAR				RY LO	E			< 4 4 TO 10							SOIL SYMBOL SOIL SYMBOL SLOPE INDICATOR INSTALLATION			
MATERIAL (NON-COHESIVE)				IUM I DENS RY DI		-		10 TO 30 30 TO 50 > 50					N/A		ARTIFICIAL FILL (AF) OTHER AUGER BORING CONE PENETROMETER THAN ROADWAY EMBANKMENT			
GENERALLY SILT-CLAY MATERIAL (COHESIVE)			VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD					< 2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 > 30				< 0.25 0.25 TO 0.5 0.5 TO 1.0 1 TO 2 2 TO 4 > 4			INFERRED SOIL BOUNDARY OCORE BORING SOUNDING ROD TEST BORING WITH CORE THE CORE BORING WITH CORE BORING WITH CORE THE CORE BORING WITH CORE BORING WITH CORE THE CORE BORING WITH CO			
					TE	ΧTι	JRE	OR	GF	RAIN	SI	ZE				RECOMMENDATION SYMBOLS		
U.S. STD. SI OPENING (M		SIZE				4 .76	10 2.0	0	40 0.42		60 0.25	200 0.07	5 0.053			UNDERCUT UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE SHALLOW UNCLASSIFIED EXCAVATION - USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL UNDERCUT UNDERCUT UNDERCUT OCCEPTABLE DEGRADABLE ROCK		
	BOULDER COBBLE (BLDR.) GRAVEL (GR.) COARSE SAND FINE SAND (BLDR.) (COB.) (GR.) (CSE. SD.) (F SD.))	SILT (SL.)	(CL.)	UNDERCUT ACCEPTABLE DEGRADABLE ROCK EMBANKMENT OR BACKFILL ABBRE VIATIONS												
									0. 25		0.05	0.005	AR - AUGER REFUSAL MED MEDIUM VST - VANE SHEAR TEST BT - BORING TERMINATED MICA MICACEOUS WEA WEATHERED CL CLAY MOD MODERATELY 7 - UNIT WEIGHT					
COL	MOI		SOIL		DIST					LAT	ION	OF	TERMS			CPT - CONE PENETRATION TEST NP - NON PLASTIC 7/d - DRY UNIT WEIGHT CSE COARSE ORG ORGANIC		
	SOIL MOISTURE SCALE FIELD MOISTURE GUIDE FOR FIELD MOISTURE DESCRIPTION										DMT - DILATOMETER TEST PMT - PRESSUREMETER TEST <u>SAMPLE ABBREVIATIONS</u> DPT - DYNAMIC PENETRATION TEST SAP SAPROLITIC S - BULK							
LL LIQUID LIMIT			ĮΤ	_	- SATURATED - USUALLY L (SAT.) FROM BELC						BELO!	W THE GRO	OUND WATE	R TABLE	e - VOID RATIO SD SAND, SANDY SS - SPLIT SPOON F - FINE SL SILT, SILTY ST - SHELBY TUBE FOSS FOSSILIFEROUS SLI SLIGHTLY RS - ROCK FRAC FRACTURED, FRACTURES TCR - TRICONE REFUSAL RT - RECOMPACTED TRIAXIAL			
RANGE (PI) PL PLASTI		IC LI	- WET -						ATTAIN OPTIMU						FRAGS FRAGMENTS ## - MOISTURE CONTENT CBR - CALIFORNIA BEARING HI HIGHLY V - VERY RATIO FOLUDATION FOR CONTENT CBR - CALIFORNIA BEARING RATIO			
OM OPTIMU SL SHRINK				M MOISTURE - MOIST					(M) SOLID; AT OR				R NEAR OF	PTIMUM MO	DISTURE	DRILL UNITS: ADVANCING TOOLS: HAMMER TYPE:		
						- 1	DRY	- (D)					DDITIONAL IMUM MOIS		0	CME-45C CLAY BITS X AUTOMATIC MANUAL G* CONTINUOUS FLIGHT AUGER CORE SIZE:		
							PL	.AS	TICI	ΤY								
NUI	PLASTICITY INDEX (PI) DRY STRENGTH NON PLASTIC Ø-5 VERY LOW				DI	CME-550												
SLIGHTLY PLASTIC 6-15 SLIGH MODERATELY PLASTIC 16-25 MEDIU			SLIGHT MEDIUM HIGH	•	VANE SHEAR TEST X CASING W/ ADVANCER HAND TOOLS: POST HOLE DIGGER													
-	COLOR										PORTABLE HOIST X TRICONE STEEL TEETH HAND AUGER							
								R CO	MBINA	NOITE			YELLOW-B ESCRIBE A			X CME-550X TRICONE TRICONE SOUNDING ROD CORE BIT VANE SHEAR TEST		

SF-63003

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS GEOTECHNICAL ENGINEERING UNIT

SUBSURFACE INVESTIGATION

SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS (PAGE 2 OF 2)

ROCK DESCRIPTION HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN I.FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK.

ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS: NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES 3 $100~\mathrm{BLOWS}$ PER FOOT IF TESTED. FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT FINE TO COARSE GRAIN IONEQUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.

FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YELLD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.

COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC. CRYSTALLINE ROCK (CR) NON-CRYSTALLINE ROCK (NCR) COASTAL PLAIN SEDIMENTARY ROCK WEATHERING **ERESH** ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING, ROCK RINGS UNDER VERY SLIGHT ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS II OF A CRYSTALLINE NATURE. (V SLI.) ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO SLIGHT 1 INCH, OPEN JOINTS MAY CONTAIN CLAY, IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED, CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS. SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN MODERATE GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY, ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK. ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH MODERATELY SEVERE (MOD, SEV.) AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. IF TESTED, WOULD YIELD SPT REFUSAL ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT SEVERE REDUCED IN STRENOTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. (SEV.) IF TESTED. WOULD YIELD SPT N VALUES > 100 BPF ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VERY SEVERE (V SEV.) VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF COMPLETE ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ROCK HARDNESS VERY HARD CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK. CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED HARD TO DETACH HAND SPECIMEN. MODERATELY CAN BE SCRATCHED BY KNIFE OR PICK, GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK, HAND SPECIMENS CAN BE DETACHED

MEDIUM CAN BE EXCAVATED IN SMALL CHIPS TO PEICES I INCH MAXIMUM SIZE BY HARD BLOWS OF THE

POINT OF A GEOLOGIST'S PICK.

SOFT

CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS
FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN
PIECES CAN BE BROKEN BY FINGER PRESSURE.

VERY CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK, PIECES I INCH SOFT OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE, CAN BE SCRATCHED READILY BY FINGERNAL

FRACTURE SPACING BEDDING TERM TERM THICKNESS SPACING VERY WIDE MORE THAN 10 FEET 3 TO 10 FEET VERY THICKLY BEDDED THICKLY BEDDED 4 FEET 1.5 - 4 FEET 0.16 - 1.5 FEET WIDE THINLY BEDDED VERY THINLY BEDDED THICKLY LAMINATED MODERATELY CLOSE 1 TO 3 FEET 0.03 - 0.16 FEET 0.008 - 0.03 FEET VERY CLOSE LESS THAN 0.16 FEET THINLY LAMINATED < 0.008 FEET

INDURATION

FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.

FRIABLE

MUDBING WITH FINDER FREES NUMEROUS GRAINS;
GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.

GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE;
BREAKS EASILY WHEN HIT WITH HAMMER.

INDURATED

GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE;
DIFFICULT TO BREAK WITH HAMMER.

EXTREMELY INDURATED

SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE;
SAMPLE BREAKS ACROSS GRAINS.

TERMS AND DEFINITIONS

ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER.

AOUIFER - A WATER BEARING FORMATION OR STRATA.

ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND.

ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC.

<u>ARTESIAN</u> - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SUBFACE.

CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE.

COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM
OF SLOPE.

 $\underline{\text{CORE}}$ RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.

 $\underline{\text{DIKE}}$ - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK.

 $\overline{ ext{DIP}}$ - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL.

 $\underline{\text{DIP DIRECTION (DIP AZIMUTH)}}$ - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH,

 $\underline{\text{FAULT}}$ - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE.

FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES.

 $\underline{\mathsf{FLOAT}}$ - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL.

JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED.

 $\underline{\mathsf{LEDGE}}$ - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT.

LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS.

MOTILED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS, MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE.

PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM.

 $\underline{\textit{RESIDUAL (RES.)} \, \textit{SOIL}} \, \, \textit{-} \, \, \textit{SOIL} \, \, \textit{FORMED IN PLACE BY THE WEATHERING OF ROCK.}$

ROCK QUALITY DESIGNATION (ROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.

SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK.

 $\underline{\text{SILL}}$ - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS.

 $\underline{\text{SLICKENSIDE}}$ - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE.

STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER, SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS.

STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE.

STRATA ROCK QUALITY DESIGNATION (SROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE.


TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.

BENCH MARK: BM2: BL STATION 18+46, 56' RT, SET IN 16 INCH ELM
N617,419 E1,620,545
ELEVATION: 519.67 FEET


NOTES:

FIAD= FILLED IMMEDIATELY AFTER DRILLING


DATE: 8-15-14




GEOTECHNICAL BORING REPORT BORE LOG



GEOTECHNICAL BORING REPORT BORE LOG



GEOTECHNICAL BORING REPORT BORE LOG



Bridge No. 35 on SR 1134 (Millingport Rd.) over Long Creek SITE PHOTOGRAPHS



Photograph No. 1: View looking EB1 to EB2



Photograph No. 2: Creek flowing left to right.