


TIP PROJECT: BD-5110AC

CONTRACT:

See Sheet 1-A For Index of Sheets  
See Sheet 1-B For Standard Symbology Sheet




FINAL PLANS

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**UNION COUNTY**

LOCATION: BRIDGE #330 OVER BRANCH OF LITTLE RICHARDSON CREEK  
ON SR 2133 (SANDY RIDGE ROAD)

TYPE OF WORK: GRADING, PAVING, DRAINAGE, & STRUCTURE

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	BD-5110AC	1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
45356.1.29	BRZ-2133(1)	P.E.	
45356.2.29	BRZ-2133(1)	R /W & UTILITIES	
45356.3.29	BRZ-2133(1)	CONST.	




BEGIN TIP PROJECT BD-5110AC  
-L- STA. 13+25.00


END TIP PROJECT BD-5110AC  
-L- STA. 17+35.00

TO WOLF POND ROAD  
(NC 207)

TO MONROE



CLEARING ON THIS PROJECT SHALL BE PERFORMED  
TO THE LIMITS ESTABLISHED BY METHOD II.



DESIGN DATA

ADT 2013	= 738
ADT 2035	= 1,475
DHV	= N/A
D	= N/A
T	= 6%
V	= 55 MPH
FUNC. CLASSIFICATION:	LOCAL

PROJECT LENGTH

LENGTH OF ROADWAY TIP PROJECT BD-5110AC	= 0.066 MILES
LENGTH OF STRUCTURE TIP PROJECT BD-5110AC	= 0.012 MILES
TOTAL LENGTH OF TIP PROJECT BD-5110AC	= 0.078 MILES

NCDOT CONTACT: GARLAND HAYWOOD, PE  
Division Bridge Manager

PLANS PREPARED FOR THE NCDOT BY:  
STV/RALPH WHITEHEAD ASSOCIATES, INC.  
900 West Trade St., Ste. 715, Charlotte NC, 28202  
NC License Number F-0991

2012 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:  
DECEMBER 18, 2012

LETTING DATE:  
~~APRIL 16, 2014~~  
October 15, 2014

NIKKI T. HONEYCUTT, PE  
PROJECT ENGINEER


JOSEPH BOULOS, EI  
PROJECT DESIGNER


HYDRAULICS ENGINEER

ROADWAY DESIGN ENGINEER

SIGNATURE: Devin C. Morrison

SIGNATURE: Nikki T. Honeycutt




PROJECT REFERENCE NO.	SHEET NO.
BD-51/OAC	I-A
RW SHEET NO.	
	
<p>STV / Ralph Whitehead Associates, Inc.</p> <p>900 West Trade St., Ste. 715          Charlotte, NC 28202          NC License Number F-0991</p>	



STV / Ralph Whitehead Associates, Inc

900 West Trade St., Ste. 715  
Charlotte, NC 28202  
NC License Number F-0991

## ROADWAY DESIGN ENGINEER



## INDEX OF SHEETS

## GENERAL NOTES

## STANDARD DRAWINGS

SHEET NUMBER	SHEET
1	TITLE SHEET
1-A	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS
1-B	CONVENTIONAL SYMBOLS
2	STRUCTURE ANCHOR UNITS DETAILS
3	SUMMARIES AND TYPICALS
4	PLAN AND PROFILE SHEET
TCP-1	TRAFFIC CONTROL PLANS
EC-1 THRU EC-4	EROSION CONTROL PLANS
UO-1 THRU UO-2	UTILITIES BY OTHERS PLANS
X-1 THRU X-2	CROSS-SECTIONS

GENERAL NOTES:

2012 SPECIFICATIONS  
EFFECTIVE: 01-01-2012

GRADE LINE:  
GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

EFF. January, 2012

The following Roadway Standards as appear in "Roadway Standard Drawings"  
 Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C.,  
 Dated January, 2012 are applicable to this project and by reference hereby are  
 considered a part of these plans:

STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	Method of Clearing - Method II
225.02	Guide for Grading Subgrade - Secondary and Local
225.04	Method of Obtaining Superelevation - Two Lane Pavement
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS	
560.01	Method of Shoulder Construction - High Side of Superelevated Curve - Method I
DIVISION 8 - INCIDENTALS	
840.29	Frames and Narrow Slot Flat Grates
840.35	Traffic Bearing Grated Drop Inlet
846.01	Concrete Curb, Gutter and Curb & Gutter
862.01	Guardrail Placement
862.02	Guardrail Installation
862.D.03	Structure Anchor Units
876.02	Guide for Rip Rap at Pipe Outlets
DIVISION 11 - WORK ZONE TRAFFIC CONTROL	
1110.01	Stationary Work Zone Signs - Mounting Height & Lateral Clearance
1145.01	Barricades - Type III
DIVISION 16 - EROSION CONTROL AND ROADSIDE DEVELOPMENT	
1605.01	Temporary Silt Fence
1606.01	Special Sediment Control Fence
1607.01	Gravel Construction Entrance
1622.01	Guide for Temporary Berms and Slope Drains
1630.04	Stilling Basin For Pumped Effluent
1630.06	Special Stilling Basin
1631.01	Matting Installation
1633.01	Temporary Rock Silt Check Type A

*Note: Not to Scale*

*\*S.U.E. = Subsurface Utility Engineering*

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
BD-5110AC	I-B

CONVENTIONAL PLAN SHEET SYMBOLS

BOUNDARIES AND PROPERTY:

State Line	
County Line	
Township Line	
City Line	
Reservation Line	
Property Line	
Existing Iron Pin	⊙ EIP
Property Corner	✕
Property Monument	⊠ ECM
Parcel/Sequence Number	(123)
Existing Fence Line	-x-x-x-x-
Proposed Woven Wire Fence	-○-
Proposed Chain Link Fence	-□-
Proposed Barbed Wire Fence	-◇-
Existing Wetland Boundary	- - - WLB - - -
Proposed Wetland Boundary	- - - WLB - - -
Existing Endangered Animal Boundary	- - - EAB - - -
Existing Endangered Plant Boundary	- - - EPB - - -
Known Soil Contamination: Boundary or Site	☠
Potential Soil Contamination: Boundary or Site	?

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	○
Sign	⊙ S
Well	⊙ W
Small Mine	⌵
Foundation	⊠
Area Outline	⊠
Cemetery	⊠ †
Building	⊠
School	⊠
Church	⊠
Dam	⊠

HYDROLOGY:

Stream or Body of Water	
Hydro, Pool or Reservoir	⊠
Jurisdictional Stream	- - - JS - - -
Buffer Zone 1	- - - BZ 1 - - -
Buffer Zone 2	- - - BZ 2 - - -
Flow Arrow	➔
Disappearing Stream	➤
Spring	⊙
Wetland	⌵
Proposed Lateral, Tail, Head Ditch	➔ FLOW
False Sump	⊠

RAILROADS:

Standard Gauge	CSX TRANSPORTATION
RR Signal Milepost	⊙ MILEPOST 35
Switch	⊠ SWITCH
RR Abandoned	- - -
RR Dismantled	- - -

RIGHT OF WAY:

Baseline Control Point	◆
Existing Right of Way Marker	△
Existing Right of Way Line	- - -
Proposed Right of Way Line	- - - (R/W) - - -
Proposed Right of Way Line with Iron Pin and Cap Marker	- - - (R/W) ▲ - - -
Proposed Right of Way Line with Concrete or Granite Marker	- - - (R/W) ● - - -
Existing Control of Access	⊠ C/A
Proposed Control of Access	⊠ C/A
Existing Easement Line	- - - E - - -
Proposed Temporary Construction Easement	- - - E - - -
Proposed Temporary Drainage Easement	- - - TDE - - -
Proposed Permanent Drainage Easement	- - - PDE - - -
Proposed Permanent Drainage / Utility Easement	- - - DUE - - -
Proposed Permanent Utility Easement	- - - PUE - - -
Proposed Temporary Utility Easement	- - - TUE - - -
Proposed Aerial Utility Easement	- - - AUE - - -

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	- - -
Existing Curb	- - -
Proposed Slope Stakes Cut	- - - C - - -
Proposed Slope Stakes Fill	- - - F - - -
Proposed Curb Ramp	⊠ CR
Curb Cut Future Ramp	⊠ CCFR

Existing Metal Guardrail	- - - T - - -
Proposed Guardrail	- - - T - - -
Existing Cable Guiderail	- - - □ - - -
Proposed Cable Guiderail	- - - □ - - -
Equality Symbol	⊙
Pavement Removal	⊠

VEGETATION:

Single Tree	⊙
Single Shrub	⊙
Hedge	⌵
Woods Line	⌵

Orchard	⊙
Vineyard	⊠ Vineyard

EXISTING STRUCTURES:

MAJOR:	
Bridge, Tunnel or Box Culvert	⊠ CONC
Bridge Wing Wall, Head Wall and End Wall	⊠ CONC WW
MINOR:	
Head and End Wall	⊠ CONC HW
Pipe Culvert	⊠
Footbridge	⊠
Drainage Box: Catch Basin, DI or JB	⊠ CB
Paved Ditch Gutter	- - -
Storm Sewer Manhole	⊙
Storm Sewer	- - - S - - -

UTILITIES:

POWER:	
Existing Power Pole	●
Proposed Power Pole	○
Existing Joint Use Pole	●
Proposed Joint Use Pole	○
Power Manhole	⊙
Power Line Tower	⊠
Power Transformer	⊠
U/G Power Cable Hand Hole	⊠
H-Frame Pole	●
Recorded U/G Power Line	- - - P - - -
Designated U/G Power Line (S.U.E.*)	- - - P - - -

TELEPHONE:

Existing Telephone Pole	●
Proposed Telephone Pole	○
Telephone Manhole	⊙
Telephone Booth	⊠
Telephone Pedestal	⊠
Telephone Cell Tower	⊙
U/G Telephone Cable Hand Hole	⊠
Recorded U/G Telephone Cable	- - - T - - -
Designated U/G Telephone Cable (S.U.E.*)	- - - T - - -
Recorded U/G Telephone Conduit	- - - TC - - -
Designated U/G Telephone Conduit (S.U.E.*)	- - - TC - - -
Recorded U/G Fiber Optics Cable	- - - T FO - - -
Designated U/G Fiber Optics Cable (S.U.E.*)	- - - T FO - - -

WATER:

Water Manhole	⊙
Water Meter	⊙
Water Valve	⊙
Water Hydrant	⊙
Recorded U/G Water Line	- - - W - - -
Designated U/G Water Line (S.U.E.*)	- - - W - - -
Above Ground Water Line	- - - A/G Water - - -

TV:

TV Satellite Dish	⊙
TV Pedestal	⊠
TV Tower	⊙
U/G TV Cable Hand Hole	⊠
Recorded U/G TV Cable	- - - TV - - -
Designated U/G TV Cable (S.U.E.*)	- - - TV - - -
Recorded U/G Fiber Optic Cable	- - - TV FO - - -
Designated U/G Fiber Optic Cable (S.U.E.*)	- - - TV FO - - -

GAS:

Gas Valve	⊙
Gas Meter	⊙
Recorded U/G Gas Line	- - - G - - -
Designated U/G Gas Line (S.U.E.*)	- - - G - - -
Above Ground Gas Line	- - - A/G Gas - - -

SANITARY SEWER:

Sanitary Sewer Manhole	⊙
Sanitary Sewer Cleanout	⊙
U/G Sanitary Sewer Line	- - - SS - - -
Above Ground Sanitary Sewer	- - - A/G Sanitary Sewer - - -
Recorded SS Forced Main Line	- - - FSS - - -
Designated SS Forced Main Line (S.U.E.*)	- - - FSS - - -

MISCELLANEOUS:

Utility Pole	●
Utility Pole with Base	⊠
Utility Located Object	⊙
Utility Traffic Signal Box	⊠
Utility Unknown U/G Line	- - - ZUTL - - -
U/G Tank; Water, Gas, Oil	⊠
Underground Storage Tank, Approx. Loc.	⊠ UST
A/G Tank; Water, Gas, Oil	⊠
Geoenvironmental Boring	⊙
U/G Test Hole (S.U.E.*)	⊙
Abandoned According to Utility Records	AATUR
End of Information	E.O.I.



#####SYTIME#####  
#####USERNAME#####

STATE OF  
NORTH CAROLINA  
DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
RALEIGH, N.C.


ENGLISH DETAIL DRAWING FOR  
**STRUCTURE ANCHOR UNITS**  
GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO  
RAIL ON BRIDGE - SUB REGIONAL TIER

SHEET 2 OF 7  
**862d03**


STATE OF  
NORTH CAROLINA  
DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
RALEIGH, N.C.

ENGLISH DETAIL DRAWING FOR  
**STRUCTURE ANCHOR UNITS**  
GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO  
RAIL ON BRIDGE - SUB REGIONAL TIER

SHEET 2 OF 7  
**862d03**



**NOTE:**  
\*\*POST NOT REQUIRED FOR SKEW ANGLES GREATER THAN 150° OR LESS THAN 30° UNLESS OTHERWISE DIRECTED BY THE ENGINEER.  
\*THE DISTANCE FROM END OF BRIDGE RAIL TO CENTER LINE OF THE FIRST POST SHOULD BE 11½" IF CONCRETE BACKWALL IS NOT PRESENT.  
-SHOULDER BERM GUTTER MUST BE INSTALLED TO THE LIMITS 8" x 4" LIP CURB IS SHOWN IF ANCHOR UNIT IS NOT ADJACENT TO AN APPROACH SLAB.  
-MEASURE GUARDRAIL HEIGHT FROM THE TOP OF ADJACENT SURFACE (SHOULDER, BERM, OR GUTTER).  
-LAP JOINTS IN THE DIRECTION OF TRAFFIC FLOW.  
-SEE SHEET 5 FOR POST SECTIONS 1 THRU 9.



**GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO  
RAIL ON BRIDGE - SUB REGIONAL TIER**

STATE OF  
NORTH CAROLINA  
DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
RALEIGH, N.C.


ENGLISH DETAIL DRAWING FOR  
**STRUCTURE ANCHOR UNITS**  
GUARDRAIL ANCHOR UNIT, TYPE III

SHEET 3 OF 7  
**862d03**

STATE OF  
NORTH CAROLINA  
DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
RALEIGH, N.C.

ENGLISH DETAIL DRAWING FOR  
**STRUCTURE ANCHOR UNITS**  
GUARDRAIL ANCHOR UNIT, TYPE III

SHEET 3 OF 7  
**862d03**





**CONTRACT STANDARDS  
AND DEVELOPMENT UNIT**  
Office 919-707-6950 FAX 919-250-4119  
**SEE TITLE BLOCK**  
ORIGINAL BY: J HOWERTON DATE: 06-22-12  
MODIFIED BY: DATE:  
CHECKED BY: DATE:  
FILE SPEC.:




## **EARTHWORK SUMMARY (IN CUBIC YARDS)**

PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
C2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 1.5" IN DEPTH OR GREATER THAN 2.0" IN DEPTH.
D1	PROP. APPROX. 3.5" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 399 LBS. PER SQ. YD.
D2	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 2.5" IN DEPTH OR GREATER THAN 4" IN DEPTH.
E1	PROP. APPROX. 3" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3.0" IN DEPTH OR GREATER THAN 5.5" IN DEPTH.
R	CONCRETE SHOULDER BERM GUTTER
T	EARTH MATERIAL
U	EXISTING PAVEMENT
W	PAVEMENT WEDGING



The diagram illustrates the cross-section of a bridge deck. Key dimensions and components include:

- Overall Width:** 4'-0" (variable) + 10'-0" + 10'-0" + 4'-0" (variable) = 28'-0" total width.
- Deck Thickness:** 8" (constant across the entire width).
- Deck Slope:** 2:1 (constant across the entire width).
- Deck Components:**
  - CI (Concrete Infill):** Located at the ends of the deck, with a minimum width of 4'-0" and a height of 0.08'.
  - W (Water):** Located in the center of the deck, with a height of 0.02'.
  - GRADE POINT:** Located in the center of the deck, with a height of 0.02'.
  - U (Underpass):** Located in the center of the deck, with a height of 8" and a width of 10'-0" (variable).
- Labels:**
  - EXIST. GROUND:** Indicated on both sides of the deck.
  - GRADE TO THIS LINE:** Indicated on both sides of the deck.
  - CL:** Centerline of the bridge.
  - Labels (T, EI, D1):** Located at the bottom of the diagram, indicating specific points or components.



Approximate quantities only. Unclassified Excavation, Borrow Excavation, Fine Grading, Clearing and Grubbing, Breaking of Existing Pavement, and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading."

TYPICAL SECTION 2

-L- STA. 14+00.00 TO 14+87.88 (BEGIN BRIDGE)

-L- STA. 15+50.13 (END BRIDGE) TO 16+40.00

\* 7'-0" WITH GUARDRAIL

\*\* ALL PAVEMENT SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.

\* W = MEASURED FROM "N" AT THE BEGINNING OF THE ANCHOR TO "N" AT THE END OF THE ANCHOR.  
 "N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL.  
 TOTAL SHOULDER WIDTH = DISTANCE FROM EDGE OF TRAVEL LANE TO SHOULDER BREAK POINT.  
 FLARE LENGTH = DISTANCE FROM LAST SECTION OF PARALLEL GUARDRAIL TO END OF GUARDRAIL.  
 W = TOTAL WIDTH OF FLARE FROM BEGINNING OF TAPER TO END OF GUARDRAIL.  
 G = GATING IMPACT ATTENUATOR TYPE 350  
 NG = NON-GATING IMPACT ATTENUATOR TYPE 350

[illegible]



PROJECT REFERENCE NO.  
BD-510AC

SHEET NO.  
4

R/W SHEET NO.

ROADWAY DESIGN ENGINEER



HYDRAULICS ENGINEER

SEAL  
038053  
3/17/14  
NORTH CAROLINA  
PROFESSIONAL  
ENGINEER  
W. T. HENRY

SEAL  
038053  
3/17/14  
NORTH CAROLINA  
PROFESSIONAL  
ENGINEER  
W. T. HENRY

STV / Ralph Whitehead Associates, Inc.


900 West Trade St., Ste. 715  
Charlotte, NC 28202  
NC License Number F-0991





3/11/2014  
R:\Roadway\Proj\BD510AC\_rdy\_pst04.dgn



DETOUR ROUTE



PROJECT REFERENCE NO.	SHEET NO.
BD-5110AC	TCP-1
RW SHEET NO.	
 STV / Ralph Whitehead Associates, Inc. 1000 West Morehead St., Ste. 200 Charlotte, NC 28208 NC License Number F-0991	




CONTRACT:

TIP PROJECT: BD-5110AC

These Erosion and Sediment Control Plans comply with the regulations set forth by the NCG010000 general construction permit effective August 3, 2011 issued by the North Carolina Department of Environment and Natural resources Division of Water Quality.


CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.



ROADSIDE ENVIRONMENTAL UNIT  
DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA

Level III Designer  
Davin Morrison, PE #3126


Prepared In the Office of:  
**STV/RALPH WHITEHEAD ASSOCIATES, INC.**  
900 West Trade St., Ste. 715, Charlotte NC, 28202  
NC License Number F-0991  
FOR NORTH CAROLINA DEPARTMENT OF TRANSPORTATION  
**2012 STANDARD SPECIFICATIONS**




EROSION CONTROL PLANS

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
PLAN FOR PROPOSED  
HIGHWAY EROSION CONTROL  
**UNION COUNTY**

LOCATION: BRIDGE #330 OVER BRANCH OF LITTLE RICHARDSON CREEK  
ON SR 2133 (SANDY RIDGE ROAD)



**EC-4**



STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	BD-5110AC	EC-1	4
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
45356.1.29	BRZ-2133(1)	P.E.	
45356.2.29	BRZ-2133(1)	R /W & UTILITIES	
45356.3.29	BRZ-2133(1)	CONST.	


EROSION AND SEDIMENT CONTROL MEASURES

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N.C. Department of Transportation - Raleigh, N.C., dated January 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

Std. #	Description	Symbol
1605.01	Temporary Silt Fence	
1606.01	Special Sediment Control Fence	
1607.01	Gravel Construction Entrance	
1622.01	Temporary Berms and Slope Drains	
1630.01	Riser Basin	
1630.03	Temporary Silt Ditch	
1630.04	Stilling Basin	
1630.05	Temporary Diversion	
1630.06	Special Stilling Basin	
1632.01	Rock Inlet Sediment Trap Type A	A
1632.02	Rock Inlet Sediment Trap Type B	B
1632.03	Rock Inlet Sediment Trap Type C	C
1633.01	Temporary Rock Silt Check Type-A	
1633.02	Temporary Rock Silt Check Type-B	
1634.01	Temporary Rock Sediment Dam Type-A	
1634.02	Temporary Rock Sediment Dam Type-B	
1635.01	Rock Pipe Inlet Sediment Trap Type-A	
1635.02	Rock Pipe Inlet Sediment Trap Type-B	
SP	Silt Basin Type B	
SP	Skimmer Basin	
SP	Tiered Skimmer Basin	
SP	Infiltration Basin	
SP	Wattle	
SP	Wattle w/ Polyacrylamide (PAM)	
SP	Coir Fiber Matting	



TEMPORARY ROCK SILT CHECK TYPE 'A' WITH  
EXCELSIOR MATTING AND POLYACRYLAMIDE (PAM)




NOTES

USE EXCELSIOR FOR MATTING MATERIAL AND ANCHOR MATTING SECTION AT TOP AND BOTTOM WITH CLASS B STONE.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH ROCK SILT CHECK.

INITIALLY APPLY 3.5 OUNCES OF POLYACRYLAMIDE (PAM) TO TOP OF MATTING SECTION AND AFTER EVERY RAINFALL EVENT THAT EQUALS OR EXCEEDS 0.50 INCHES.




NOT TO SCALE

STABILIZATION REQUIREMENTS

Stabilization for this project shall comply with the time frame guidelines as specified by the NCG-010000 general construction permit effective August 3, 2011 issued by the North Carolina Department of Environment and Natural Resources Division of Water Quality. Temporary or permanent ground cover stabilization shall occur within 7 calendar days from the last land-disturbing activity, with the following exceptions in which temporary or permanent ground cover shall be provided in 14 calendar days from the last land-disturbing activity:

- Slopes between 2:1 and 3:1, with a slope length of 10 ft. or less
- Slopes 3:1 or flatter, with a slope of length of 50 ft. or less
- Slopes 4:1 or flatter

The stabilization timeframe for High Quality Water (HQW) Zones shall be 7 calendar days with no exceptions for slope grades or lengths. High Quality Water Zones (HQW) Zones are defined by North Carolina Administrative Code 15A NCAC 04A.0105 (25). Temporary and permanent ground cover stabilization shall be achieved in accordance with the provisions in this contract and as directed.


PROJECT REFERENCE NO.	SHEET NO.
BD-510AC	EC-2
RW SHEET NO.	
 STV/ Ralph Whitehead Associates, Inc. 900 West Trade St., Ste. 715 Charlotte, NC 28202 NC License Number F-0991	

DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA

PROJECT REFERENCE NO.  
BD-5110AC

SHEET NO.  
EC-3

RW SHEET NO.



STV / Ralph Whitehead Associates, Inc.  
900 West Trade St., Ste. 715  
Charlotte, NC 28202  
NC License Number F-0991

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL  
(FOR SLOPE STABILIZATION)

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
			SUBTOTAL		675
	MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER				75
			TOTAL		750
			SAY		750

COIR FIBER MATTING  
(FOR FLOOD BENCH STABILIZATION)

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
			SUBTOTAL		110
	MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER				15
			TOTAL		125
			SAY		125

PERMANENT SOIL REINFORCEMENT MATTING  
(FOR DITCH STABILIZATION)

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-TOE PROTECT.	16+00	16+50	LT	20
			SUBTOTAL		20
	MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER				5
			TOTAL		25
			SAY		25





TIP PROJECT: BD-5110AC

CONTRACT:


PRELIMINARY PLANS  
\$DATES

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS


UNION COUNTY

LOCATION: BRIDGE #330 OVER BRANCH OF LITTLE RICHARDSON CREEK  
ON SR 2133 (SANDY RIDGE ROAD)

TYPE OF WORK: AERIAL POWER, TELEPHONE AND CABLE




T.I.P. NO.	SHEET NO.
BD-5110 AC	UO-1



BEGIN TIP PROJECT BD-5110AC  
-L- STA. 13+25.00


TO WOLF POND ROAD  
(NC 207)



END TIP PROJECT BD-5110AC  
-L- STA. 17+35.00

TO MONROE

GRAPHIC SCALES



INDEX OF SHEETS

SHEET NO.	DESCRIPTION
UO-1	TITLE SHEET
UO-2	UTILITIES BY OTHERS PLANS

UTILITY OWNERS ON PROJECT

- (1) POWER - DUKE ENERGY
- (2) TELEPHONE - FRONTIER
- (3) CABLE - TIME WARNER CABLE

SEAL



PREPARED IN THE OFFICE OF:  
DIVISION OF HIGHWAYS  
UTILITIES ENGINEERING  
SECTION

1591 MAIL SERVICES CENTER  
RALEIGH NC 27699-1591  
PHONE (919) 250-4128  
FAX (919) 250-4119

Roger Worthington, P.E. UTILITIES SECTION ENGINEER  
Xxxxx Xxxxx, P.E. UTILITIES SQUAD LEADER PROJECT ENGINEER  
Reece Schuler, PE UTILITIES PROJECT DESIGNER



# UTILITIES BY OTHERS


NOTE:  
ALL PROPOSED UTILITY WORK  
SHOWN ON THIS SHEET WILL  
BE DONE BY OTHERS

**V&M**  
Vaughn & Melton  
Consulting Engineers

Charlotte,  
North Carolina  
704-357-0488

Asheville,  
North Carolina  
828-253-2796  
Tri-Cities,  
Tennessee  
423-467-8401  
Knoxville,  
Tennessee  
606-248-6600  
Middlesboro,  
Kentucky  
606-248-6600  
Spartanburg,  
South Carolina  
864-574-4775

Copyright © 2006 Vaughn & Melton, Inc.  
All Rights Reserved




PI Sta 11+97.82  
Δ = 19° 37' 33.7" (LT)  
D = 7° 38' 22.0"  
L = 256.90'  
T = 129.72'  
R = 750.00'



8/23/99

3/11/2014  
R:\Roadway\XSC\BD5110AC.rdy-ypj.L.dgn  
BoulasB




0 2.5 5	PROJ. REFERENCE NO.	SHEET NO.
	BD-5110AC	X-1











I HEREBY CERTIFY THESE  
ARE THE AS-BUILT PLANS

RESIDENT ENGINEER

PROJECT NO. BD-5110AC  
 UNION \_\_\_\_\_ COUNTY \_\_\_\_\_  
 STATION: 15+19.00 -L-


SHEET 1 OF 2      REPLACES BRIDGE NO. 330

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH

GENERAL DRAWING  
FOR BRIDGE ON SR 2133  
(SANDY RIDGE ROAD) OVER  
BRANCH OF LITTLE  
RICHARDSON CREEK BETWEEN  
SR 2132 AND SR 2115

REVISIONS						SHEET NO. S-1
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 12
2			4			

DRAWN BY : JWJ DATE : 04-13  
CHECKED BY : JAD DATE : 05-13

 **STV/Ralph Whitehead Associates, Inc.**  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991

+


+

R:\Structures\FIndis\02 Total BOM.dgn

10:23:43 AM

1/10/2014

JJones



HYDRAULIC DATA

DESIGN DISCHARGE:-----1300 CFS  
FREQUENCY OF DESIGN FLOOD:-----25 YRS.  
DESIGN HIGH WATER ELEVATION:-----577.3  
DRAINAGE AREA:-----4.2 SQ. MI.  
BASE DISCHARGE (Q100):-----1830 CFS  
BASE HIGH WATER ELEVATION:-----579.32

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE:----->2500 CFS  
FREQUENCY OF OVERTOPPING FLOOD:----->500 YRS.  
OVERTOPPING FLOOD ELEVATION:-----580.8

GENERAL NOTES

ASSUMED LIVE LOAD = HL 93 OR ALTERNATE LOADING.

THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.

THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE "STANDARD NOTES" SHEET.

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

THE EXISTING STRUCTURE CONSISTING OF (1) 25.5'± TIMBER DECK ON STEEL I-BEAM SPAN WITH A CLEAR ROADWAY OF 24'± AND SUPPORTED BY TIMBER CAPS ON TIMBER PILES SHALL BE REMOVED. TIMBER ABUTMENTS SHALL BE CUT OFF 1' BELOW NATURAL GROUND.

REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL INTO THE WATER. THE CONTRACTOR SHALL REMOVE THE BRIDGE AND SUBMIT PLANS FOR DEMOLITION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.

INASMUCH AS THE PAINT SYSTEM ON THE EXISTING STRUCTURAL STEEL CONTAINS LEAD, THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 107-1 OF THE STANDARD SPECIFICATIONS. ANY COSTS RESULTING FROM COMPLIANCE WITH APPLICABLE STATE OR FEDERAL REGULATIONS PERTAINING TO HANDLING OF MATERIALS CONTAINING LEAD BASED PAINT SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR "REMOVAL OF EXISTING STRUCTURE".

THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE BARS FROM WHICH THE SAMPLES ARE TAKEN MUST THEN BE SPLICED WITH REPLACEMENT BARS OF THE SIZE AND LENGTH OF THE SAMPLE, PLUS A MINIMUM LAP SPLICE OF THIRTY BAR DIAMETERS. PAYMENT FOR THE SAMPLES OF REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.

THE MATERIAL SHOWN IN THE CROSS-HATCHED AREA (ON SHEET 1 OF 2) SHALL BE EXCAVATED FOR A DISTANCE FROM THE CENTERLINE OF ROADWAY OF APPROXIMATELY 30 FT. (LEFT AND RIGHT) AT BOTH END BENTS AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR UNCLASSIFIED STRUCTURE EXCAVATION. SEE SECTION 412 OF THE STANDARD SPECIFICATIONS.

THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH HEC 18, "EVALUATING SCOUR AT BRIDGES", MAY, 2001.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

ASPHALT WEARING SURFACE IS INCLUDED IN ROADWAY QUANTITY ON ROADWAY PLANS.

FOUNDATION NOTES

FOR PILES, SEE SECTION 450 OF THE STANDARD SPECIFICATIONS.

PILES AT END BENT NO.1 ARE DESIGNED FOR A FACTORED RESISTANCE OF 90 TONS PER PILE. DRIVE PILES AT END BENT NO.1 TO A REQUIRED DRIVING RESISTANCE OF 150 TONS PER PILE.

PILES AT END BENT NO.2 ARE DESIGNED FOR A FACTORED RESISTANCE OF 90 TONS PER PILE. DRIVE PILES AT END BENT NO.2 TO A REQUIRED DRIVING RESISTANCE OF 150 TONS PER PILE.

STEEL H-PILE POINTS ARE REQUIRED FOR STEEL H-PILES AT BOTH END BENTS. FOR STEEL PILE POINTS, SEE SECTION 450 OF THE STANDARD SPECIFICATIONS.

TOTAL BILL OF MATERIAL


	REMOVAL OF EXISTING STRUCTURE	UNCLASSIFIED STRUCTURE EXCAVATION	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	HP 12 X 53 STEEL PILES		STEEL PILE POINTS	VERTICAL CONCRETE BARRIER RAIL	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE	ELASTOMERIC BEARINGS	3'-0" x 2'-0" PRESTRESSED CONCRETE CORED SLAB UNIT	
						NO.	LIN. FT.						NO.	LIN. FT.
SUPERSTRUCTURE	LUMP SUM	LUMP SUM	CU. YDS.	LUMP SUM	LBS.			EA.	LIN. FT.	TONS	SQ. YDS.	LUMP SUM	NO.	LIN. FT.
				LUMP SUM					120.25			LUMP SUM	10	600.0
END BENT 1		LUMP SUM	20.2		2,449	5	80.0	5		70	80			
END BENT 2		LUMP SUM	20.2		2,449	5	80.0	5		85	90			
TOTAL	LUMP SUM	LUMP SUM	40.4	LUMP SUM	4,898	10	160.0	10	120.25	155	170	LUMP SUM	10	600.0

PROJECT NO. BD-5110AC

UNION \_\_\_\_\_ COUNTY

STATION: 15+19.00 -L-

SHEET 2 OF 2



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH

GENERAL DRAWING  
TOTAL BILL OF MATERIAL  
AND GENERAL NOTES

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-2
2			4			
TOTAL SHEETS						12



STV/Ralph Whitehead Associates, Inc.  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991



1/10/2014 10:23:57 AM R:\Structures\Finals\03\ LRFR.dgn Jones

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS																								
LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE										SERVICE III LIMIT STATE						COMMENT NUMBER		
						LIVE LOAD FACTORS	MOMENT					SHEAR					LIVE LOAD FACTORS	MOMENT						
							DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)		DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION		DISTANCE FROM LEFT END OF SPAN (ft)	
DESIGN LOAD RATING	HL-93(Inv)	N/A	1	1.32	--	1.75	0.276	1.32	60'	EL	29.5	0.520	1.51	60'	EL	5.9	0.80	0.276	1.34	60'	EL	29.5		
	HL-93(0pr)	N/A	--	1.71	--	1.35	0.276	1.71	60'	EL	29.5	0.520	2.00	60'	EL	5.9	N/A	--	--	--	--	--		
	HS-20(Inv)	36.000	2	1.67	60.120	1.75	0.276	1.67	60'	EL	29.5	0.520	1.87	60'	EL	5.9	0.80	0.276	1.70	60'	EL	29.5		
	HS-20(0pr)	36.000	--	2.17	78.120	1.35	0.276	2.17	60'	EL	29.5	0.520	2.48	60'	EL	5.9	N/A	--	--	--	--	--		
LEGAL LOAD RATING	SV	SNSH	13.500	--	3.67	49.545	1.4	0.276	4.50	60'	EL	29.5	0.520	5.75	60'	EL	5.9	0.80	0.276	3.67	60'	EL	29.5	
		SNGARBS2	20.000	--	2.81	56.200	1.4	0.276	3.44	60'	EL	29.5	0.520	4.09	60'	EL	5.9	0.80	0.276	2.81	60'	EL	29.5	
		SNAGRIS2	22.000	--	2.69	59.180	1.4	0.276	3.30	60'	EL	29.5	0.520	3.80	60'	EL	5.9	0.80	0.276	2.69	60'	EL	29.5	
		SNC0TTS3	27.250	--	1.83	49.868	1.4	0.276	2.24	60'	EL	29.5	0.520	2.78	60'	EL	5.9	0.80	0.276	1.83	60'	EL	29.5	
		SNAGGRS4	34.925	--	1.56	54.483	1.4	0.276	1.91	60'	EL	29.5	0.520	2.32	60'	EL	5.9	0.80	0.276	1.56	60'	EL	29.5	
		SNS5A	35.550	--	1.52	54.036	1.4	0.276	1.86	60'	EL	29.5	0.520	2.36	60'	EL	5.9	0.80	0.276	1.52	60'	EL	29.5	
		SNS6A	39.950	--	1.41	56.330	1.4	0.276	1.72	60'	EL	29.5	0.520	2.15	60'	EL	5.9	0.80	0.276	1.41	60'	EL	29.5	
		SNS7B	42.000	--	1.34	56.280	1.4	0.276	1.64	60'	EL	29.5	0.520	2.13	60'	EL	5.9	0.80	0.276	1.34	60'	EL	29.5	
	TTST	TNAGRIT3	33.000	--	1.72	56.760	1.4	0.276	2.11	60'	EL	29.5	0.520	2.57	60'	EL	5.9	0.80	0.276	1.72	60'	EL	29.5	
		TNT4A	33.075	--	1.73	57.220	1.4	0.276	2.12	60'	EL	29.5	0.520	2.51	60'	EL	5.9	0.80	0.276	1.73	60'	EL	29.5	
		TNT6A	41.600	--	1.43	59.488	1.4	0.276	1.75	60'	EL	29.5	0.520	2.33	60'	EL	5.9	0.80	0.276	1.43	60'	EL	29.5	
		TNT7A	42.000	--	1.44	60.480	1.4	0.276	1.76	60'	EL	29.5	0.520	2.22	60'	EL	5.9	0.80	0.276	1.44	60'	EL	29.5	
		TNT7B	42.000	--	1.50	63.000	1.4	0.276	1.84	60'	EL	29.5	0.520	2.06	60'	EL	5.9	0.80	0.276	1.50	60'	EL	29.5	
		TNAGRIT4	43.000	--	1.42	61.060	1.4	0.276	1.74	60'	EL	29.5	0.520	1.99	60'	EL	5.9	0.80	0.276	1.42	60'	EL	29.5	
		TNAGT5A	45.000	--	1.33	59.850	1.4	0.276	1.63	60'	EL	29.5	0.520	2.01	60'	EL	5.9	0.80	0.276	1.33	60'	EL	29.5	
		TNAGT5B	45.000	3	1.31	58.950	1.4	0.276	1.61	60'	EL	29.5	0.520	1.89	60'	EL	5.9	0.80	0.276	1.31	60'	EL	29.5	

LOAD FACTORS:

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ <sub>DC</sub>	γ <sub>DW</sub>
	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.

ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

COMMENTS:

1.
2.
3.
4.

# CONTROLLING LOAD RATING

1 DESIGN LOAD RATING (HL-93)


2 DESIGN LOAD RATING (HS-20)

3 LEGAL LOAD RATING \*\*

\*\* SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION


I - INTERIOR GIRDER  
EL - EXTERIOR LEFT GIRDER  
ER - EXTERIOR RIGHT GIRDER



PROJECT NO. BD-5110AC

UNION \_\_\_\_\_ COUNTY \_\_\_\_\_

STATION: 15+19.00 -L-



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH

LRFR SUMMARY FOR  
60' CORED SLAB UNIT  
90° SKEW  
(NON-INTERSTATE TRAFFIC)

REVISIONS					SHEET NO. S-3
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

TOTAL SHEETS  
12

STV/ Ralph Whitehead Associates, Inc.  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991




RA\Structures\Finals\04 Typ Sect and Details.dgn

10/24/21 AM

1/10/2014

Jones




HALF SECTION  
AT INTERMEDIATE DIAPHRAGMS

TYPICAL SECTION


HALF SECTION  
THROUGH VOIDS

\* - THE MAXIMUM BARRIER RAIL HEIGHT AND ASPHALT THICKNESS IS SHOWN. THE HEIGHT OF THE BARRIER RAIL AND ASPHALT THICKNESS VARIES WHILE THE TOP OF THE BARRIER RAIL FOLLOWS THE PROFILE OF THE GUTTERLINE. FOR RAIL HEIGHT DETAILS AND ASPHALT THICKNESS, SEE THE "VERTICAL CONCRETE BARRIER RAIL SECTION" DETAIL.


FIXED END



SECTION AT END BENT




GROUTED RECESS AT END OF  
POST-TENSIONED STRAND-CORED SLABS



SHEAR KEY DETAIL

NOTE: OMIT SHEAR KEY ON OUTSIDE FACE  
OF EXTERIOR CORED SLABS.




INTERIOR SLAB SECTION (60' UNIT)  
(24 STRANDS REQUIRED)

0.6" Ø LOW  
RELAXATION STRAND LAYOUT


- ☐ BOND SHALL BE BROKEN ON THESE STRANDS FOR A DISTANCE OF 10'-0" FROM END OF CORED SLAB UNIT. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.
- ◆ BOND SHALL BE BROKEN ON THESE STRANDS FOR A DISTANCE OF 12'-0" FROM END OF CORED SLAB UNIT. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.
- OPTIONAL FULL LENGTH DEBONDED STRANDS. THESE STRANDS ARE NOT REQUIRED. IF THE FABRICATOR CHOOSES TO INCLUDE THESE STRANDS IN THE CORED SLAB UNIT, THE STRANDS SHALL BE DEBONDED FOR THE FULL LENGTH OF THE UNIT AT NO ADDITIONAL COST. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.

DEBONDING LEGEND



EXTERIOR SLAB SECTION

(FOR PRESTRESSED STRAND LAYOUT, SEE  
INTERIOR SLAB SECTION.)



END ELEVATION


SHOWING PLACEMENT OF DOUBLE STIRRUPS  
AND LOCATION OF DOWEL HOLES.  
(STRAND LAYOUT NOT SHOWN.)  
INTERIOR SLAB UNIT SHOWN-EXTERIOR SLAB  
UNIT SIMILAR EXCEPT SHEAR KEY LOCATION.

PROJECT NO. **BD-5110AC**

UNION COUNTY

STATION: **15+19.00 -L-**

SHEET 1 OF 3





STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH  
STANDARD  
3'-0" X 2'-0"  
PRESTRESSED CONCRETE  
CORED SLAB UNIT  
90° SKEW


ASSEMBLED BY :	JWJ	DATE :	04-13
CHECKED BY :	JAD	DATE :	05-13
DRAWN BY :	MAA	6/10	REV. 12/11
CHECKED BY :	MKT	7/10	MAA/AAC

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-4
1			3			TOTAL SHEETS
2			4			12


STD. NO. 24PCS4.30\_90S

PLAN OF UNITDETAIL "A"

NOTE: EXTERIOR UNIT SHOWN - INTERIOR  
UNIT SIMILAR EXCEPT OMIT #5 S12 BARS.

DETAIL "B"

#4 S11 BARS MAY BE SHIFTED AS NECESSARY  
TO MAINTAIN 1" CLEAR TO GROUTED RECESS AND  
1/2" Ø TRANSVERSE POST-TENSIONING STRAND HOLES



PROJECT NO. BD-5110AC  
UNION COUNTY  
STATION: 15+19.00 -L-

SHEET 2 OF 3

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH

PLAN OF 60' UNIT  
27'-10" CLEAR ROADWAY  
90° SKEW


ASSEMBLED BY :	JWJ	DATE :	04-13
CHECKED BY :	JAD	DATE :	05-13
DRAWN BY :	MAA	6/10	REV. 12/5/11
CHECKED BY :	MKT	7/10	MAA/AAC

STV / Ralph Whitehead Associates, Inc.  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-5
1			3			TOTAL SHEETS
2			4			12

STD, NO. 24PCS\_30-90S-60L





FIXED END  
(TYPE I - 20 REQ'D)

## ELASTOMERIC BEARING DETAILS

ELASTOMER IN ALL BEARINGS SHALL BE 60 DUROMETER HARDNESS.


DEAD LOAD DEFLECTION AND CAMBER	
	3'-0" X 2'-0"
60' CORED SLAB UNIT	0.6" Ø L.R. STRAND
CAMBER (SLAB ALONE IN PLACE)	2 3/4" ↑
DEFLECTION DUE TO SUPERIMPOSED DEAD LOAD**	5/8" ↓
FINAL CAMBER	2 1/8" ↑

\*\* INCLUDES FUTURE WEARING SURFACE

GRADE 270 STRANDS	
	0.6" Ø L.R.
AREA ( SQUARE INCHES )	0.217
ULTIMATE STRENGTH ( LBS. PER STRAND )	58,600
APPLIED PRESTRESS ( LBS. PER STRAND )	43,950

CONCRETE RELEASE STRENGTH	
UNIT	PSI
60' UNITS	4800

GUTTERLINE ASPHALT THICKNESS & RAIL HEIGHT		
27'-10" CLEAR ROADWAY NORMAL CROWN SECTION	ASPHALT OVERLAY THICKNESS @ MID-SPAN	RAIL HEIGHT @ MID-SPAN
60' UNITS	3 1/8"	3'-9 3/8"



## NOTES

ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW RELAXATION GRADE 270 STRANDS AND SHALL CONFORM TO AASHTO M203 EXCEPT FOR SAMPLING REQUIREMENTS WHICH SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

ALL REINFORCING STEEL CAST WITH THE CORED SLAB SECTIONS SHALL BE GRADE 60 AND SHALL BE INCLUDED IN THE UNIT PRICE BID FOR PRESTRESSED CONCRETE CORED SLABS.

RECESSES FOR TRANSVERSE STRANDS SHALL BE GROUTED AFTER THE TENSIONING OF THE STRANDS.

THE 2 1/2" Ø DOWEL HOLES AT FIXED ENDS OF SLAB SECTIONS SHALL BE FILLED WITH NON-SHRINK GROUT.

THE BACKER RODS SHALL CONFORM TO THE REQUIREMENTS OF TYPE M BOND BREAKER, SEE SECTION 1028 OF THE STANDARD SPECIFICATIONS.

WHEN CORED SLABS ARE CAST, AN INTERNAL HOLD-DOWN SYSTEM SHALL BE EMPLOYED TO PREVENT VOIDS FROM RISING OR MOVING SIDEWAYS. AT LEAST SIX WEEKS PRIOR TO CASTING CORED SLABS, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER FOR REVIEW AND COMMENT, DETAILED DRAWINGS OF THE PROPOSED HOLD-DOWN SYSTEM. IN ADDITION TO STRUCTURAL DETAILS, LOCATION AND SPACING OF THE HOLD-DOWNS SHALL BE INDICATED.

THE TRANSFER OF LOAD FROM THE ANCHORAGES TO THE CORED SLAB UNIT SHALL BE DONE WHEN THE CONCRETE HAS REACHED A COMPRESSIVE STRENGTH OF NOT LESS THAN THE REQUIRED STRENGTH SHOWN IN THE "CONCRETE RELEASE STRENGTH" TABLE.

ALL REINFORCING STEEL IN VERTICAL CONCRETE BARRIER RAILS SHALL BE EPOXY COATED.

PRESTRESSING STRANDS SHALL BE CUT FLUSH WITH THE CORED SLAB UNIT ENDS.

APPLY EPOXY PROTECTIVE COATING TO CORED SLAB UNIT ENDS.

GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE BARRIER RAIL AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. A CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN BARRIER RAIL EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF BARRIER RAIL SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.

TRANSVERSE POST TENSIONING OF THE CORED SLAB UNITS SHALL BE DONE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

MAINTAIN A SYMMETRIC TENSION FORCE BETWEEN EACH PAIR OF TRANSVERSE POST TENSIONING STRANDS IN THE DIAPHRAGM.

THE #4 S11 STIRRUPS MAY BE SHIFTED AS NECESSARY TO MAINTAIN 1" CLEAR TO THE GROUTED RECESS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.


BILL OF MATERIAL FOR ONE 60' CORED SLAB UNIT							
BAR	NUMBER	SIZE	TYPE	EXTERIOR UNIT		INTERIOR UNIT	
				LENGTH	WEIGHT	LENGTH	WEIGHT
B20	6	#4	STR	21'-2"	85	21'-2"	85
S10	8	#5	3	4'-9"	40	4'-9"	40
S11	124	#4	3	5'-10"	483	5'-10"	483
*S12	69	#5	1	6'-4"	456		
S14	4	#4	3	5'-7"	15	5'-7"	15
S15	4	#5	3	7'-1"	30	7'-1"	30
REINFORCING STEEL				LBS.		653	
* EPOXY COATED REINFORCING STEEL				LBS.		456	
6000 P.S.I. CONCRETE				CU. YDS.		10.2	
0.6" Ø L.R. STRANDS				No.		24	

BILL OF MATERIAL FOR VERTICAL CONCRETE BARRIER RAIL						
BAR	BARS PER PAIR OF EXTERIOR UNITS	TOTAL NO.	SIZE	TYPE	LENGTH	WEIGHT
	60' UNIT					
*B23	40	40	#5	STR	29'-7"	1234
*S13	138	138	#5	2	7'-2"	1032
* EPOXY COATED REINFORCING STEEL						LBS. 2266
CLASS AA CONCRETE						CU. YDS. 16.2
TOTAL VERTICAL CONCRETE BARRIER RAIL						LN. FT. 120.25

CORED SLABS REQUIRED			
	NUMBER	LENGTH	TOTAL LENGTH
60' UNIT			
EXTERIOR C.S.	2	60'-0"	120'-0"
INTERIOR C.S.	8	60'-0"	480'-0"
TOTAL	10		600'-0"

PROJECT NO. **BD-5110AC**  
UNION COUNTY  
STATION: **15+19.00 -L-**

SHEET 3 OF 3



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH




3'-0" X 2'-0"  
PRESTRESSED CONCRETE  
CORED SLAB UNIT  
90° SKEW

REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S-6
2			4			TOTAL SHEETS 12



STV/ Ralph Whitehead Associates, Inc.  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991



## VERTICAL CONCRETE BARRIER RAIL DETAILS

## END OF RAIL DETAILS


DRAWN BY : JWJ DATE : 04-13  
CHECKED BY : JAD DATE : 05-13

R:\Structures\Finals\07) Guardrail\Attach.dgn



10:42:09 AM

1/10/2014


Jjones



FOR LOCATION OF GUARDRAIL ANCHOR ASSEMBLY, SEE "PLAN" BELOW



GUARDRAIL ANCHOR ASSEMBLY DETAILS



LOCATION OF ANCHORS FOR GUARDRAIL

END BENT #1 SHOWN, END BENT #2 SIMILAR.

## NOTES

THE GUARDRAIL ANCHOR ASSEMBLY SHALL CONSIST OF A 1/4" HOLD DOWN PLATE AND 7 - 1/8" Ø BOLTS WITH NUTS AND WASHERS.

THE HOLD-DOWN PLATE SHALL CONFORM TO AASHTO M270 GRADE 36. AFTER FABRICATION, THE HOLD-DOWN PLATE SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH AASHTO M111.

BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307 AND NUTS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M291. BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS, NUTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 1/8" Ø GALVANIZED BOLTS, NUTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)


THE GUARDRAIL ANCHOR ASSEMBLY IS REQUIRED AT ALL POINTS WHERE APPROACH GUARDRAIL IS TO BE ATTACHED TO THE END OF BARRIER RAIL. FOR POINTS OF ATTACHMENT, SEE SKETCH.

AFTER INSTALLATION, THE EXPOSED THREAD OF THE BOLT SHALL BE BURRED WITH A SHARP POINTED TOOL.

THE COST OF THE GUARDRAIL ANCHOR ASSEMBLY SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR VERTICAL CONCRETE BARRIER RAIL.

THE VERTICAL REINFORCING BARS MAY BE SHIFTED SLIGHTLY IN THE VERTICAL CONCRETE BARRIER RAIL TO CLEAR ASSEMBLY BOLTS.

THE 1 1/4" Ø HOLES SHALL BE FORMED OR DRILLED WITH A CORE BIT. IMPACT TOOLS WILL NOT BE PERMITTED. ANY CONCRETE DAMAGED BY THIS WORK SHALL BE REPAIRED TO THE SATISFACTION OF THE ENGINEER.




SKETCH SHOWING POINTS OF ATTACHMENT

\* DENOTES GUARDRAIL ANCHOR ASSEMBLY

PROJECT NO. **BD-5110AC**

UNION COUNTY

STATION: **15+19.00 -L-**



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH

STANDARD  
GUARDRAIL ANCHORAGE  
FOR VERTICAL CONCRETE  
BARRIER RAIL

ASSEMBLED BY :	JWJ	DATE :	04-13
CHECKED BY :	JAD	DATE :	11-13
DRAWN BY :	MAA 5/10	ADDED 5/6/10	
CHECKED BY :	GM 5/10	REV. 10/1/11	MAA/GM
		REV. 12/5/11	MAA/GM

STV / Ralph Whitehead Associates, Inc.  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-7
2			4			TOTAL SHEETS 12

STD. NO. GRA3



STIRRUPS IN CAP MAY BE SHIFTED AS  
NECESSARY TO CLEAR DOWELS.

FOR PILE SPLICE DETAILS, SEE SHEET 4 OF 4.

FOR WING DETAILS, SEE SHEET 3 OF 4.




SHEET 1 OF 4

SUBSTRUCTURE  
END BENT No. 1

REVISIONS						SHEET NO. S-8
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 12
2			4			

STD. NO. EB\_30\_90S4

ASSEMBLED BY :	JWJ	DATE :	04-13
CHECKED BY :	JAD	DATE :	05-13
DRAWN BY :	WJH 12/11		
CHECKED BY :	AAC 12/11		

 **STV/ Ralph Whitehead Associates, Inc.**  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991


# NOTES

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR DOWELS.


THE CONCRETE IN THE SHADED AREA OF THE WING SHALL BE POURED AFTER THE VERTICAL CONCRETE BARRIER RAIL IS CAST IF SLIP FORMING IS USED.

FOR PILE SPLICE DETAILS, SEE SHEET 4 OF 4.

FOR WING DETAILS, SEE SHEET 3 OF 4.



PLAN



ELEVATION

WINGS NOT SHOWN FOR CLARITY.  
FOR SECTION A-A, SEE SHEET 4 OF 4.  
CONCRETE COLLARS FOR STEEL PILES NOT SHOWN IN PLAN AND ELEVATION VIEWS FOR CLARITY.  
SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL", SHEET 4 OF 4.

PROJECT NO. **BD-5110AC**


UNION COUNTY

STATION: **15+19.00 -L-**

SHEET 2 OF 4

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH

SUBSTRUCTURE  
END BENT No. 2



## REVISIONS


NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S-9
2			4			TOTAL SHEETS 12

STV/ Ralph Whitehead Associates, Inc.  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991


STD. NO. EB-30-90S4

ASSEMBLED BY :	JWJ	DATE :	04-13
CHECKED BY :	JAD	DATE :	05-13
DRAWN BY :	WJH	12/11	
CHECKED BY :	AAC	12/11	







PLAN OF WING (W1)



PLAN OF WING (W2)




ELEVATION OF WING (W1)




ELEVATION OF WING (W2)

## WING DETAILS




SECTION X-X



SECTION Y-Y

PROJECT NO. **BD-5110AC**  
UNION COUNTY  
STATION: **15+19.00 -L-**

SHEET 3 OF 4



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH


SUBSTRUCTURE  
END BENT  
WING DETAILS

ASSEMBLED BY :	JWJ	DATE :	04-13
CHECKED BY :	JAD	DATE :	05-13
DRAWN BY :	WJH 12/11		
CHECKED BY :	AAC 12/11		

STV / Ralph Whitehead Associates, Inc.  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-10	
1			3			TOTAL SHEETS	
2			4			12	

STD. NO. EB\_30\_90S4




BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.


BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.



### TEMPORARY DRAINAGE AT END BENT




### PILE SPLICE DETAILS



BILL OF MATERIAL						
FOR ONE END BENT						
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	
B1	8	#9	1	38'-0"	1034	
B2	28	#4	STR	19'-1"	357	
B3	9	#4	STR	2'-5"	15	
D1	20	#6	STR	1'-6"	45	
H1	40	#4	2	9'-4"	249	
K1	16	#4	STR	2'-11"	31	
S1	46	#4	3	10'-5"	320	
S2	46	#4	4	3'-2"	97	
S3	20	#4	5	6'-6"	87	
V1	52	#4	STR	6'-2"	214	
REINFORCING STEEL (FOR ONE END BENT)					2449 LBS.	
CLASS A CONCRETE BREAKDOWN (FOR ONE END BENT)						
POUR #1		CAP, LOWER PART OF WINGS & COLLARS			17.9 C.Y.	
POUR #2		UPPER PART OF WINGS			2.3 C.Y.	
TOTAL CLASS A CONCRETE					20.2 C.Y.	



### CORROSION PROTECTION FOR STEEL PILES DETAIL



PROJECT NO. **BD-5110AC**  
UNION COUNTY  
STATION: **15+19.00 -L-**


SHEET 4 OF 4

STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
RALEIGH

SUBSTRUCTURE  
END BENT No. 1 & 2  
DETAILS

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-11
1			3			TOTAL SHEETS 12
2			4			

STV / Ralph Whitehead Associates, Inc.  
900 West Trade Street, Suite 715  
Charlotte, NC 28202  
NC License Number F-0991







## STANDARD NOTES

DESIGN DATA:

SPECIFICATIONS	- - - - -	A.A.S.H.T.O. (CURRENT)
LIVE LOAD	- - - - -	SEE PLANS
IMPACT ALLOWANCE	- - - - -	SEE A.A.S.H.T.O.
STRESS IN EXTREME FIBER OF		
STRUCTURAL STEEL - AASHTO M270 GRADE 36	-	20,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50W	-	27,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50	-	27,000 LBS. PER SQ. IN.
REINFORCING STEEL IN TENSION		
	GRADE 60 - -	24,000 LBS. PER SQ. IN.
CONCRETE IN COMPRESSION	- - - - -	1,200 LBS. PER SQ. IN.
CONCRETE IN SHEAR	- - - - -	SEE A.A.S.H.T.O.
STRUCTURAL TIMBER - TREATED OR		
UNTREATED - EXTREME FIBER STRESS	- - - - -	1,800 LBS. PER SQ. IN.
COMPRESSION PERPENDICULAR TO GRAIN OF TIMBER	- - - -	375 LBS. PER SQ. IN.
EQUIVALENT FLUID PRESSURE OF EARTH	- - - - -	30 LBS. PER CU. FT.  (MINIMUM)

MATERIAL AND WORKMANSHIP:

EXCEPT AS MAY OTHERWISE BE SPECIFIED ON PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2012 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N. C. DEPARTMENT OF TRANSPORTATION.

STEEL SHEET PILING FOR PERMANENT OR TEMPORARY APPLICATIONS SHALL BE HOT ROLLED.

CONCRETE:

UNLESS OTHERWISE REQUIRED ON PLANS, CLASS A CONCRETE SHALL BE USED FOR ALL PORTIONS OF ALL STRUCTURES WITH THE EXCEPTION THAT: CLASS AA CONCRETE SHALL BE USED IN BRIDGE SUPERSTRUCTURES, ABUTMENT BACKWALLS, AND APPROACH SLABS; AND CLASS B CONCRETE SHALL BE USED FOR SLOPE PROTECTION AND RIP RAP.

## CONCRETE CHAMFERS:

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS; TOP CORNERS OF CURBS MAY BE ROUNDED TO 1-1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.

DOWELS:

DOWELS WHEN INDICATED ON PLANS AS FOR CULVERT EXTENSIONS, SHALL BE EMBEDDED AT LEAST 12" INTO THE OLD CONCRETE AND GROUTED INTO PLACE WITH 1:2 CEMENT MORTAR.

ALLOWANCE FOR DEAD LOAD DEFLECTION, SETTLEMENT, ETC. IN CASTING SUPERSTRUCTURES:

BRIDGES SHALL BE BUILT ON THE GRADE OR VERTICAL CURVE SHOWN ON PLANS.  
SLABS, CURBS AND PARAPETS SHALL CONFORM TO THE GRADE OR CURVE.

ALL DIMENSIONS WHICH ARE GIVEN IN SECTION AND ARE AFFECTED BY DEAD LOAD DEFLECTIONS ARE DIMENSIONS AT CENTER LINE OF BEARING UNLESS OTHERWISE NOTED ON PLANS. IN SETTING FORMS FOR STEEL BEAM BRIDGES AND PRESTRESSED CONCRETE GIRDER BRIDGES, ADJUSTMENTS SHALL BE MADE DUE TO THE DEAD LOAD DEFLECTIONS FOR THE ELEVATIONS SHOWN. WHERE BLOCKS ARE SHOWN OVER BEAMS FOR BUILDING UP TO THE SLAB, THE VERTICAL DIMENSIONS OF THE BLOCKS SHALL BE ADJUSTED BETWEEN BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTIONS, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. WHERE BOTTOM OF SLAB IS IN LINE WITH BOTTOM OF TOP FLANGES, DEPTH OF SLAB BETWEEN BEARINGS SHALL BE ADJUSTED TO COMPENSATE FOR DEAD LOAD DEFLECTION, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER.

IN SETTING FALSEWORK AND FORMS FOR REINFORCED CONCRETE SPANS, AN ALLOWANCE SHALL BE MADE FOR DEAD LOAD DEFLECTIONS, SETTLEMENT OF FALSEWORK, AND PERMANENT CAMBER WHICH SHALL BE PROVIDED FOR IN ADDITION TO THE ELEVATIONS SHOWN. AFTER REMOVAL OF THE FALSEWORK, THE FINISHED STRUCTURES SHALL CONFORM TO THE PROFILE AND ELEVATIONS SHOWN ON THE PLANS AND CONSTRUCTION ELEVATIONS FURNISHED BY THE ENGINEER.

DETAILED DRAWINGS FOR FALSEWORK OR FORMS FOR BRIDGE SUPERSTRUCTURE AND ANY STRUCTURE OR PARTS OF A STRUCTURE AS NOTED ON THE PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BEFORE CONSTRUCTION OF THE FALSEWORK OR FORMS IS STARTED.

## REINFORCING STEEL:

ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS.

WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.

## STRUCTURAL STEEL:

AT THE CONTRACTOR'S OPTION, HE MAY SUBSTITUTE 7/8"Ø SHEAR STUDS FOR THE 3/4"Ø STUDS SPECIFIED ON THE PLANS. THIS SUBSTITUTION SHALL BE MADE AT THE RATE OF 3 - 7/8"Ø STUDS FOR 4 - 3/4"Ø STUDS, AND STUD SPACING CHANGES SHALL BE MADE AS NECESSARY TO PROVIDE THE SAME EQUIVALENT NUMBER OF 7/8"Ø STUDS ALONG THE BEAM AS SHOWN FOR 3/4"Ø STUDS BASED ON THE RATIO OF 3 - 7/8"Ø STUDS FOR 4 - 3/4"Ø STUDS. STUDS OF THE LENGTH SPECIFIED ON THE PLANS MUST BE PROVIDED. THE MAXIMUM SPACING SHALL BE 2'-0".

EXCEPT AT THE INTERIOR SUPPORTS OF CONTINUOUS BEAMS WHERE THE COVER PLATE IS IN CONTACT WITH BEARING PLATE, THE CONTRACTOR MAY, AT HIS OPTION, SUBSTITUTE FOR THE COVER PLATES DESIGNATED ON THE PLANS COVER PLATES OF THE EQUIVALENT AREA PROVIDED THESE PLATES ARE AT LEAST 5/16" IN THICKNESS AND DO NOT EXCEED A WIDTH EQUAL TO THE FLANGE WIDTH LESS 2" OR A THICKNESS EQUAL TO 2 TIMES THE FLANGE THICKNESS. THE SIZE OF FILLET WELDS SHALL CONFORM TO THE REQUIREMENTS OF THE CURRENT ANSI/AASHTO/AWS "BRIDGE WELDING CODE". ELECTROSLAG WELDING WILL NOT BE PERMITTED.

WITH THE SOLE EXCEPTION OF EDGES AT SURFACES WHICH BEAR ON OTHER SURFACES, ALL SHARP EDGES AND ENDS OF SHAPES AND PLATES SHALL BE SLIGHTLY ROUNDED BY SUITABLE MEANS TO A RADIUS OF APPROXIMATELY 1/16 INCH OR EQUIVALENT FLAT SURFACE AT A SUITABLE ANGLE PRIOR TO PAINTING, GALVANIZING, OR METALLIZING.

### HANDRAILS AND POSTS:

METAL STANDARDS AND FACES OF THE CONCRETE END POSTS FOR THE METAL RAIL SHALL BE SET NORMAL TO THE GRADE OF THE CURB, UNLESS OTHERWISE SHOWN ON PLANS. THE METAL RAIL AND TOPS OF CONCRETE POSTS USED WITH THE ALUMINUM RAIL SHALL BE BUILT PARALLEL TO THE GRADE OF THE CURB.

METAL HANDRAILS SHALL BE IN ACCORDANCE WITH THE PLANS. RAILS SHALL BE AS MANUFACTURED FOR BRIDGE RAILING. CASTINGS SHALL BE OF A UNIFORM APPEARANCE. FINIS AND OTHER DEFORMATIONS RESULTING FROM CASTING OR OTHERWISE SHALL BE REMOVED IN A MANNER SO THAT A UNIFORM COLORING OF THE COMPLETED CASTING SHALL BE OBTAINED. CASTINGS WITH DISCOLORATIONS OR OF NON-UNIFORM COLORING WILL NOT BE ACCEPTED. CERTIFIED MILL REPORTS ARE REQUIRED FOR METAL RAILS AND POSTS.

SPECIAL NOTES:

GENERALLY, IN CASE OF DISCREPANCY, THIS STANDARD SHEET OF NOTES SHALL GOVERN OVER THE SPECIFICATIONS, BUT THE REMAINDER OF THE PLANS SHALL GOVERN OVER NOTES HEREON, AND SPECIAL PROVISIONS SHALL GOVERN OVER ALL. SEE SPECIFICATIONS ARTICLE 105-4.