

BP10.R047.3

Nov 05, 2025

DJ00583

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING AND STRUCTURE

SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

				NJR GROUP INC		EASTERN STRUCTURES LLC		SMITH-ROWE, LLC	
				ALBEMARLE, NC		MOCKSVILLE, NC		MOUNT AIRY, NC	
ROADWAY ITEMS									
0001	0000100000-N	800	MOBILIZATION	Lump Sum		120,000.00	129,000.00		129,500.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		22,400.00	20,000.00		17,500.00
0003	0036000000-E	225	UNDERCUT EXCAVATION	750 CY	1.00	750.00	15.00	11,250.00	1.00 750.00
0004	0043000000-N	226	GRADING (226)	Lump Sum		401,550.33	200,000.00		348,000.00
0005	0050000000-E	226	SUPP CLEARING & GRUBBING	1 ACR	1.00	1.00	100.00	100.00	1.00 1.00
0006	0106000000-E	230	BORROW EXCAVATION	3,750 CY	1.00	3,750.00	30.00	112,500.00	1.00 3,750.00
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	100 CY	1.00	100.00	15.00	1,500.00	1.00 100.00
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY	1.00	400.00	45.00	18,000.00	1.00 400.00
0009	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	400 SY	1.00	400.00	3.00	1,200.00	1.00 400.00
0010	0234000000-E	SP	GENERIC GRADING ITEM (CY) BORROW EXCAVATION (PIPE INSTALLATION)	60 CY	1.00	60.00	100.00	6,000.00	1.00 60.00
0011	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1 APPROACH FILL, STATION 19+14.00 -L-	Lump Sum		18,500.00	15,000.00		20,000.00
0012	0318000000-E	300	FND CONDIR MATL MINOR STRS	40 TON	1.00	40.00	45.00	1,800.00	1.00 40.00
0013	0321000000-E	300	FND CONDIR GEOTEXTILE (4A)	130 SY	1.00	130.00	3.00	390.00	1.00 130.00
0014	0335200000-E	305	15" DRAINAGE PIPE	132 LF	95.00	12,540.00	80.00	10,560.00	75.00 9,900.00
0015	0335850000-E	305	*** DRAINAGE PIPE ELBOW (15")	10 EA	500.00	5,000.00	450.00	4,500.00	1.00 10.00
0016	0343000000-E	310	15" SIDE DRAIN PIPE	32 LF	95.00	3,040.00	80.00	2,560.00	86.00 2,752.00
0017	0344000000-E	310	18" SIDE DRAIN PIPE	36 LF	105.00	3,780.00	100.00	3,600.00	103.00 3,708.00
0018	0448200000-E	310	15" RCP CULV CLASS IV	176 LF	95.00	16,720.00	80.00	14,080.00	90.00 15,840.00
0019	0995000000-E	340	PIPE REMOVAL	29 LF	1.00	29.00	30.00	870.00	25.00 725.00
0020	1099500000-E	505	SHALLOW UNDERCUT	100 CY	1.00	100.00	15.00	1,500.00	12.00 1,200.00
0021	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	100 TON	1.00	100.00	45.00	4,500.00	43.00 4,300.00
0022	1110000000-E	510	STABILIZER AGGREGATE	200 TON	1.00	200.00	50.00	10,000.00	43.00 8,600.00
0023	1111000000-E	SP	CLASS IV AGGREGATE STABILIZATION	100 TON	1.00	100.00	50.00	5,000.00	43.00 4,300.00
0024	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	200 SY	1.00	200.00	3.00	600.00	1.00 200.00
0025	1220000000-E	545	INCIDENTAL STONE BASE	30 TON	1.00	30.00	50.00	1,500.00	43.00 1,290.00
0026	1297000000-E	607	MILL ASP PVMT ***** DTH (1.5" DEPTH)	1,270 SY	8.00	10,160.00	10.00	12,700.00	8.00 10,160.00
0027	1330000000-E	607	INCIDENTAL MILLING	190 SY	25.00	4,750.00	10.00	1,900.00	25.00 4,750.00
0028	1491000000-E	610	ASP CONC BASE CRS B25.0C	835 TON	83.08	69,371.80	103.00	86,005.00	83.08 69,371.80
0029	1503000000-E	610	ASP CONC INTR CRS I19.0C	830 TON	83.55	69,346.50	103.00	85,490.00	83.55 69,346.50
0030	1523000000-E	610	ASP CONC SURF CRS S9.5C	750 TON	83.18	62,385.00	103.00	77,250.00	83.18 62,385.00
0031	1575000000-E	620	ASP FOR PLANT MIX	125 TON	645.00	80,625.00	670.00	83,750.00	645.00 80,625.00
0032	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY	1.00	44.80	5.00	224.00	1.00 44.80
0033	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200 SY	1.00	200.00	3.00	600.00	1.00 200.00
0034	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6 CY	1.00	33.60	5.00	168.00	1.00 33.60
0035	2044000000-E	815	6" PERF SUBDRN PIPE	200 LF	1.00	200.00	1.00	200.00	1.00 200.00
0036	2070000000-N	815	SUBDRN PIPE OUTLET	1 EA	1.00	1.00	200.00	200.00	1.00 1.00
0037	2077000000-E	815	6" OUTLET PIPE	6 LF	1.00	6.00	5.00	30.00	1.00 6.00
0038	2286000000-N	840	MASNRY DRAINAGE STRUCT	9 EA	4,000.00	36,000.00	3,500.00	31,500.00	2,500.00 22,500.00
0039	2367000000-N	840	FRAME W/2GRTS 840.29 STD	9 EA	1,000.00	9,000.00	1,000.00	9,000.00	650.00 5,850.00

BP10.R047.3

Nov 05, 2025

DJ00583

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING AND STRUCTURE

SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

						NJR GROUP INC ALBEMARLE, NC	EASTERN STRUCTURES LLC MOCKSVILLE, NC		SMITH-ROWE, LLC MOUNT AIRY, NC		
0040	2556000000-E	846	SHOULDER BERM GUTTER	590	LF	52.80	31,152.00	50.00	29,500.00	37.78	22,290.20
0041	3030000000-E	862	STL BEAM GUARDRAIL	1,300	LF	24.75	32,175.00	25.00	32,500.00	22.50	29,250.00
0042	3150000000-N	862	ADDIT GUARDRAIL POSTS	10	EA	12.10	121.00	20.00	200.00	1.00	10.00
0043	3215000000-N	862	GR ANCHOR TYPE III	4	EA	2,420.00	9,680.00	2,600.00	10,400.00	2,200.00	8,800.00
0044	3287000000-N	862	GR END TYPE TL-3	4	EA	3,520.00	14,080.00	3,600.00	14,400.00	3,200.00	12,800.00
0045	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,520	LF	1.10	1,672.00	2.00	3,040.00	1.00	1,520.00
0046	3635000000-E	876	RIP RAP, CLASS II	90	TON	80.00	7,200.00	70.00	6,300.00	72.00	6,480.00
0047	3649000000-E	876	RIP RAP, CLASS B	180	TON	65.00	11,700.00	60.00	10,800.00	69.00	12,420.00
0048	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,640	SY	0.01	16.40	3.00	4,920.00	1.00	1,640.00
0049	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	30	LF	8.42	252.60	12.00	360.00	12.00	360.00
0050	4102000000-N	904	SIGN ERECTION, TYPE E	2	EA	275.00	550.00	200.00	400.00	150.00	300.00
0051	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	8	EA	16.50	132.00	30.00	240.00	5.00	40.00
0052	4400000000-E	1110	WORK ZONE SIGNS (STAT)	647	SF	7.37	4,768.39	12.00	7,764.00	12.00	7,764.00
0053	4410000000-E	1110	WORK ZONE SIGNS (BARR)	119	SF	9.74	1,159.06	12.00	1,428.00	9.00	1,071.00
0054	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	27.50	2,200.00	22.00	1,760.00	36.00	2,880.00
0055	4685000000-E	1205	THERMO PVT MKG LINES 4"90	4,990	LF	2.09	10,429.10	2.75	13,722.50	1.90	9,481.00
0056	4846000000-E	1205	POLYUREA LINES (***, *** MILS) (4", 30 MILS)	660	LF	3.03	1,999.80	3.00	1,980.00	2.75	1,815.00
0057	6000000000-E	1605	TEMPORARY SILT FENCE	2,905	LF	3.58	10,399.90	3.50	10,167.50	1.00	2,905.00
0058	6006000000-E	1610	EROS CONTRL STONE CL A	65	TON	0.01	0.65	50.00	3,250.00	1.00	65.00
0059	6009000000-E	1610	EROS CONTRL STONE CL B	495	TON	0.01	4.95	1.00	495.00	1.00	495.00
0060	6012000000-E	1610	SEDIMENT CONTROL STONE	540	TON	0.01	5.40	1.00	540.00	1.00	540.00
0061	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	0.01	0.02	2,000.00	4,000.00	1.00	2.00
0062	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	0.01	2.00	3.00	600.00	1.00	200.00
0063	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	0.01	0.01	1,100.00	1,100.00	1.00	1.00
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	255	LF	0.01	2.55	5.00	1,275.00	1.00	255.00
0065	6029000000-E	SP	SAFETY FENCE	1,060	LF	0.01	10.60	3.00	3,180.00	1.00	1,060.00
0066	6030000000-E	1630	SILT EXCAVATION	840	CY	0.01	8.40	6.00	5,040.00	1.00	840.00
0067	6036000000-E	1631	MATTING FOR EROS CONTROL	2,300	SY	2.15	4,945.00	2.60	5,980.00	2.00	4,600.00
0068	6037000000-E	1629	COIR FIBER MAT	100	SY	4.40	440.00	9.00	900.00	4.00	400.00
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	525	LF	10.00	5,250.00	5.00	2,625.00	2.00	1,050.00
0070	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	155	SY	85.00	13,175.00	27.00	4,185.00	4.00	620.00
0071	6070000000-N	1639	SPECIAL STILLING BASINS	14	EA	550.00	7,700.00	250.00	3,500.00	1.00	14.00
0072	6071002000-E	1642	FLOCCULANT	130	LB	11.00	1,430.00	15.00	1,950.00	1.00	130.00
0073	6071010000-E	1642	WATTLE	200	LF	12.00	2,400.00	14.00	2,800.00	3.00	600.00
0074	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	2,530.00	7,590.00	3,000.00	9,000.00	800.00	2,400.00
0075	6087000000-E	1660	MOWING	3	ACR	0.01	0.03	150.00	450.00	1.00	3.00
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	0.01	0.50	15.00	750.00	1.00	50.00
0077	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	0.01	0.00	1,600.00	400.00	1.00	0.25
0078	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	0.01	0.50	15.00	750.00	1.00	50.00
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	0.01	0.01	1,600.00	2,000.00	1.00	1.25
0080	6111000000-E	SP	IMPERVIOUS DIKE	110	LF	55.00	6,050.00	50.00	5,500.00	30.00	3,300.00

BP10.R047.3

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING AND STRUCTURE

SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

						NJR GROUP INC ALBEMARLE, NC	EASTERN STRUCTURES LLC MOCKSVILLE, NC	SMITH-ROWE, LLC MOUNT AIRY, NC			
0081	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	0.01	0.10	150.00	1,500.00	1.00	10.00
0082	6117000000-N	1675	RESPONSE FOR EROS CONTROL	19	EA	0.01	0.19	50.00	950.00	1.00	19.00
0083	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	850.00	850.00	750.00	750.00	450.00	450.00
0084	6123000000-E	1670	REFORESTATION	0.3	ACR	2,200.00	660.00	4,000.00	1,200.00	4,000.00	1,200.00
0085	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	2	EA	1,000.00	2,000.00	750.00	1,500.00	450.00	900.00
STRUCTURE ITEMS											
0086	8035000000-N	402	REMV EXIST STR ***** BRG (402) (STATION 19+14.00 -L-)	Lump Sum			100,000.00		100,000.00		154,360.00
0087	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			1,650.00		52,500.00		850.00
0088	8105520000-E	411	3'-0" DRILLD PIER IN SOIL	63	LF	1,207.50	76,072.50	1,180.00	74,340.00	855.70	53,909.10
0089	8105620000-E	411	3'-0" DRILLD PIER NO SOIL	60	LF	1,207.50	72,450.00	1,920.00	115,200.00	2,311.83	138,709.80
0090	8111200000-E	411	PERM STL CASING FOR 3' PIER	63	LF	287.50	18,112.50	20.00	1,260.00	108.04	6,806.52
0091	8115000000-N	411	CSL TESTING	1	EA	1,610.00	1,610.00	3,000.00	3,000.00	3,380.00	3,380.00
0092	8121000000-N	412	UNCL STR EXCAV STA ***** (STATION 19+14.00-L-)	Lump Sum			12,500.00		5,000.00		50,000.00
0093	8156000000-E	SP	CONCRETE WEARING SURFACE	5,903	SF	18.40	108,615.20	20.00	118,060.00	19.27	113,750.81
0094	8161000000-E	420	GROOVING BRIDGE FLOORS	6,383	SF	1.15	7,340.45	2.00	12,766.00	1.69	10,787.27
0095	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	87.9	CY	1,400.00	123,060.00	1,200.00	105,480.00	2,057.31	180,837.55
0096	8210000000-N	422	BRG APPR SLAB ***** (STATION 19+14.00 -L-)	Lump Sum			40,000.00		42,700.00		54,700.00
0097	8217000000-E	425	REINF STEEL (BRIDGE)	26,107	LB	1.75	45,687.25	1.80	46,992.60	1.70	44,381.90
0098	8238000000-E	425	SPIRAL COL REINF STL BRG	3,502	LB	4.00	14,008.00	3.50	12,257.00	3.63	12,712.26
0099	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (12 X 53)	14	EA	1,000.00	14,000.00	1,000.00	14,000.00	1,037.31	14,522.34
0100	8364000000-E	450	HP12X53 PILES	280	LF	65.00	18,200.00	60.00	16,800.00	61.95	17,346.00
0101	8475000000-E	460	TWO BAR METAL RAIL	305.5	LF	189.20	57,800.60	180.00	54,990.00	223.40	68,248.70
0102	8517000000-E	460	1'-***X*****CONC PARAPET (1'-2" X 2'-11 3/16")	320.5	LF	164.45	52,706.23	200.00	64,100.00	238.03	76,288.62
0103	8608000000-E	876	RIP RAP II (2'-0")	348	TON	75.00	26,100.00	70.00	24,360.00	72.00	25,056.00
0104	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	387	SY	4.00	1,548.00	3.00	1,161.00	2.00	774.00
0105	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			7,500.00		9,000.00		9,250.00
0106	8763000000-E	430	3'-0" X 2'-0"PRESTR SLABS	2,080	LF	230.00	478,400.00	251.00	522,080.00	246.90	513,552.00
CONTRACT TOTAL						TOTAL	2,421,617.92	TOTAL	2,577,125.60	TOTAL	2,590,234.27
ROADWAY ITEMS						SUB-TOTAL	1,144,257.19	SUB-TOTAL	1,181,079.00	SUB-TOTAL	1,040,011.40
STRUCTURE ITEMS						SUB-TOTAL	1,277,360.73	SUB-TOTAL	1,396,046.60	SUB-TOTAL	1,550,222.87

BP10.R047.3

Nov 05, 2025

DJ00583

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING AND STRUCTURE

SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

				KEMP SIGMON CONSTRUCTION CO INC CLAREMONT, NC		SEALAND CONTRACTORS CORP MIDLAND, NC		REEVES CONSTRUCTION COMPANY DUNCAN, SC			
ROADWAY ITEMS											
0001	0000100000-N	800	MOBILIZATION	Lump Sum		130,000.00	174,050.00		194,000.00		
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		20,000.00	55,000.00		57,500.00		
0003	0036000000-E	225	UNDERCUT EXCAVATION	750	CY	15.00	11,250.00	36.00	27,000.00	1.00	750.00
0004	0043000000-N	226	GRADING (226)	Lump Sum		250,000.00	583,090.75		500,000.00		
0005	0050000000-E	226	SUPP CLEARING & GRUBBING	1	ACR	100.00	100.00	15,000.00	15,000.00	1.00	1.00
0006	0106000000-E	230	BORROW EXCAVATION	3,750	CY	20.00	75,000.00	40.00	150,000.00	1.00	3,750.00
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	100	CY	20.00	2,000.00	25.00	2,500.00	1.00	100.00
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400	CY	15.00	6,000.00	85.00	34,000.00	1.00	400.00
0009	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	400	SY	2.00	800.00	4.00	1,600.00	1.00	400.00
0010	0234000000-E	SP	GENERIC GRADING ITEM (CY) BORROW EXCAVATION (PIPE INSTALLATION)	60	CY	75.00	4,500.00	55.00	3,300.00	1.00	60.00
0011	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1 APPROACH FILL, STATION 19+14.00 -L-	Lump Sum		17,500.00	14,250.00		20,000.00		
0012	0318000000-E	300	FND CONDIR MATL MINOR STRS	40	TON	30.00	1,200.00	85.00	3,400.00	1.00	40.00
0013	0321000000-E	300	FND CONDIR GEOTEXTILE (4A)	130	SY	2.00	260.00	3.00	390.00	1.00	130.00
0014	0335200000-E	305	15" DRAINAGE PIPE	132	LF	85.00	11,220.00	165.00	21,780.00	75.00	9,900.00
0015	0335850000-E	305	*** DRAINAGE PIPE ELBOW (15")	10	EA	500.00	5,000.00	600.00	6,000.00	1.00	10.00
0016	0343000000-E	310	15" SIDE DRAIN PIPE	32	LF	95.00	3,040.00	125.00	4,000.00	86.00	2,752.00
0017	0344000000-E	310	18" SIDE DRAIN PIPE	36	LF	95.00	3,420.00	145.00	5,220.00	103.00	3,708.00
0018	0448200000-E	310	15" RCP CULV CLASS IV	176	LF	95.00	16,720.00	130.00	22,880.00	90.00	15,840.00
0019	0995000000-E	340	PIPE REMOVAL	29	LF	15.00	435.00	40.00	1,160.00	25.00	725.00
0020	1099500000-E	505	SHALLOW UNDERCUT	100	CY	10.00	1,000.00	38.00	3,800.00	12.00	1,200.00
0021	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	100	TON	20.00	2,000.00	46.00	4,600.00	43.00	4,300.00
0022	1110000000-E	510	STABILIZER AGGREGATE	200	TON	20.00	4,000.00	85.00	17,000.00	43.00	8,600.00
0023	1111000000-E	SP	CLASS IV AGGREGATE STABILIZATION	100	TON	20.00	2,000.00	46.00	4,600.00	43.00	4,300.00
0024	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	200	SY	6.00	1,200.00	5.00	1,000.00	1.00	200.00
0025	1220000000-E	545	INCIDENTAL STONE BASE	30	TON	50.00	1,500.00	70.00	2,100.00	43.00	1,290.00
0026	1297000000-E	607	MILL ASP PVMT ***** DTH (1.5" DEPTH)	1,270	SY	8.00	10,160.00	12.00	15,240.00	9.00	11,430.00
0027	1330000000-E	607	INCIDENTAL MILLING	190	SY	25.00	4,750.00	30.00	5,700.00	26.00	4,940.00
0028	1491000000-E	610	ASP CONC BASE CRS B25.0C	835	TON	83.08	69,371.80	120.00	100,200.00	104.00	86,840.00
0029	1503000000-E	610	ASP CONC INTR CRS I19.0C	830	TON	83.55	69,346.50	120.00	99,600.00	100.00	83,000.00
0030	1523000000-E	610	ASP CONC SURF CRS S9.5C	750	TON	18.18	13,635.00	110.00	82,500.00	86.00	64,500.00
0031	1575000000-E	620	ASP FOR PLANT MIX	125	TON	645.00	80,625.00	695.00	86,875.00	740.00	92,500.00
0032	2022000000-E	815	SUBDRAIN EXCAVATION	44.8	CY	20.00	896.00	35.00	1,568.00	1.00	44.80
0033	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200	SY	2.00	400.00	3.00	600.00	1.00	200.00
0034	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6	CY	85.00	2,856.00	130.00	4,368.00	1.00	33.60
0035	2044000000-E	815	6" PERF SUBDRN PIPE	200	LF	10.00	2,000.00	25.00	5,000.00	1.00	200.00
0036	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	500.00	500.00	400.00	400.00	1.00	1.00
0037	2077000000-E	815	6" OUTLET PIPE	6	LF	50.00	300.00	60.00	360.00	1.00	6.00
0038	2286000000-N	840	MASNRY DRAINAGE STRUCT	9	EA	2,500.00	22,500.00	4,500.00	40,500.00	2,500.00	22,500.00

BP10.R047.3

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING AND STRUCTURE

SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

				KEMP SIGMON CONSTRUCTION CO INC CLAREMONT, NC		SEALAND CONTRACTORS CORP MIDLAND, NC		REEVES CONSTRUCTION COMPANY DUNCAN, SC			
0039	2367000000-N	840	FRAME W/2GRTS 840.29 STD	9	EA	1,200.00	10,800.00	1,500.00	13,500.00	650.00	5,850.00
0040	2556000000-E	846	SHOULDER BERM GUTTER	590	LF	45.00	26,550.00	50.00	29,500.00	85.00	50,150.00
0041	3030000000-E	862	STL BEAM GUARDRAIL	1,300	LF	22.50	29,250.00	24.50	31,850.00	22.50	29,250.00
0042	3150000000-N	862	ADDIT GUARDRAIL POSTS	10	EA	11.00	110.00	12.00	120.00	11.00	110.00
0043	3215000000-N	862	GR ANCHOR TYPE III	4	EA	2,200.00	8,800.00	2,400.00	9,600.00	2,200.00	8,800.00
0044	3287000000-N	862	GR END TYPE TL-3	4	EA	3,200.00	12,800.00	3,500.00	14,000.00	3,200.00	12,800.00
0045	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,520	LF	1.00	1,520.00	1.05	1,596.00	1.00	1,520.00
0046	3635000000-E	876	RIP RAP, CLASS II	90	TON	85.00	7,650.00	125.00	11,250.00	72.00	6,480.00
0047	3649000000-E	876	RIP RAP, CLASS B	180	TON	85.00	15,300.00	110.00	19,800.00	69.00	12,420.00
0048	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,640	SY	3.00	4,920.00	3.00	4,920.00	1.00	1,640.00
0049	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	30	LF	7.65	229.50	8.25	247.50	7.65	229.50
0050	4102000000-N	904	SIGN ERECTION, TYPE E	2	EA	250.00	500.00	265.00	530.00	250.00	500.00
0051	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	8	EA	15.00	120.00	16.25	130.00	15.00	120.00
0052	4400000000-E	1110	WORK ZONE SIGNS (STAT)	647	SF	6.70	4,334.90	7.50	4,852.50	6.70	4,334.90
0053	4410000000-E	1110	WORK ZONE SIGNS (BARR)	119	SF	8.85	1,053.15	10.00	1,190.00	8.85	1,053.15
0054	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	25.00	2,000.00	35.00	2,800.00	25.00	2,000.00
0055	4685000000-E	1205	THERMO PVT MKG LINES 4"90	4,990	LF	1.90	9,481.00	2.05	10,229.50	1.90	9,481.00
0056	4846000000-E	1205	POLYUREA LINES (***, *** MILS) (4", 30 MILS)	660	LF	2.75	1,815.00	2.95	1,947.00	2.75	1,815.00
0057	6000000000-E	1605	TEMPORARY SILT FENCE	2,905	LF	3.00	8,715.00	3.25	9,441.25	1.00	2,905.00
0058	6006000000-E	1610	EROS CONTRL STONE CL A	65	TON	20.00	1,300.00	110.00	7,150.00	1.00	65.00
0059	6009000000-E	1610	EROS CONTRL STONE CL B	495	TON	20.00	9,900.00	110.00	54,450.00	1.00	495.00
0060	6012000000-E	1610	SEDIMENT CONTROL STONE	540	TON	20.00	10,800.00	85.00	45,900.00	1.00	540.00
0061	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	1,600.00	3,200.00	1,475.00	2,950.00	1.00	2.00
0062	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	4.00	800.00	1.35	270.00	1.00	200.00
0063	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	1,700.00	1,700.00	1,650.00	1,650.00	1.00	1.00
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	255	LF	10.00	2,550.00	25.00	6,375.00	1.00	255.00
0065	6029000000-E	SP	SAFETY FENCE	1,060	LF	2.50	2,650.00	2.00	2,120.00	1.00	1,060.00
0066	6030000000-E	1630	SILT EXCAVATION	840	CY	1.00	840.00	28.00	23,520.00	1.00	840.00
0067	6036000000-E	1631	MATTING FOR EROS CONTROL	2,300	SY	1.95	4,485.00	1.60	3,680.00	2.00	4,600.00
0068	6037000000-E	1629	COIR FIBER MAT	100	SY	4.00	400.00	6.00	600.00	4.00	400.00
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	525	LF	5.00	2,625.00	7.15	3,753.75	2.00	1,050.00
0070	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	155	SY	50.00	7,750.00	38.00	5,890.00	4.00	620.00
0071	6070000000-N	1639	SPECIAL STILLING BASINS	14	EA	100.00	1,400.00	160.00	2,240.00	2,350.00	32,900.00
0072	6071002000-E	1642	FLOCCULANT	130	LB	15.00	1,950.00	14.00	1,820.00	1.00	130.00
0073	6071010000-E	1642	WATTLE	200	LF	12.00	2,400.00	8.00	1,600.00	3.00	600.00
0074	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	2,300.00	6,900.00	3,150.00	9,450.00	800.00	2,400.00
0075	6087000000-E	1660	MOWING	3	ACR	200.00	600.00	310.00	930.00	1.00	3.00
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	5.00	250.00	9.25	462.50	1.00	50.00
0077	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	2,100.00	525.00	1,700.00	425.00	1.00	0.25
0078	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	4.00	200.00	9.25	462.50	1.00	50.00

BP10.R047.3

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING AND STRUCTURE

SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

				KEMP SIGMON CONSTRUCTION CO INC CLAREMONT, NC		SEALAND CONTRACTORS CORP MIDLAND, NC		REEVES CONSTRUCTION COMPANY DUNCAN, SC			
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	2,100.00	2,625.00	1,800.00	2,250.00	1.00	1.25
0080	6111000000-E	SP	IMPERVIOUS DIKE	110	LF	100.00	11,000.00	95.00	10,450.00	30.00	3,300.00
0081	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	75.00	750.00	100.00	1,000.00	1.00	10.00
0082	6117000000-N	1675	RESPONSE FOR EROS CONTROL	19	EA	175.00	3,325.00	325.00	6,175.00	1.00	19.00
0083	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,500.00	1,500.00	1,400.00	1,400.00	450.00	450.00
0084	6123000000-E	1670	REFORESTATION	0.3	ACR	2,000.00	600.00	10,500.00	3,150.00	4,000.00	1,200.00
0085	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	2	EA	1,000.00	2,000.00	700.00	1,400.00	450.00	900.00
STRUCTURE ITEMS											
0086	8035000000-N	402	REMV EXIST STR ***** BRG (402) (STATION 19+14.00 -L-)	Lump Sum			350,000.00		60,250.00		195,000.00
0087	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			1,500.00		3,250.00		850.00
0088	8105520000-E	411	3'-0" DRILLD PIER IN SOIL	63	LF	1,250.00	78,750.00	945.00	59,535.00	1,912.00	120,456.00
0089	8105620000-E	411	3'-0" DRILLD PIER NO SOIL	60	LF	2,250.00	135,000.00	1,900.00	114,000.00	1,912.00	114,720.00
0090	8111200000-E	411	PERM STL CASING FOR 3' PIER	63	LF	10.00	630.00	10.95	689.85	245.00	15,435.00
0091	8115000000-N	411	CSL TESTING	1	EA	2,500.00	2,500.00	2,700.00	2,700.00	2,500.00	2,500.00
0092	8121000000-N	412	UNCL STR EXCAV STA ***** (STATION 19+14.00-L-)	Lump Sum			10,000.00		15,250.00		80,000.00
0093	8156000000-E	SP	CONCRETE WEARING SURFACE	5,903	SF	20.00	118,060.00	19.75	116,584.25	22.00	129,866.00
0094	8161000000-E	420	GROOVING BRIDGE FLOORS	6,383	SF	1.25	7,978.75	1.55	9,893.65	2.50	15,957.50
0095	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	87.9	CY	1,250.00	109,875.00	1,750.00	153,825.00	2,650.00	232,935.00
0096	8210000000-N	422	BRG APPR SLAB ***** (STATION 19+14.00 -L-)	Lump Sum			40,000.00		43,950.00		85,000.00
0097	8217000000-E	425	REINF STEEL (BRIDGE)	26,107	LB	2.00	52,214.00	3.25	84,847.75	2.75	71,794.25
0098	8238000000-E	425	SPIRAL COL REINF STL BRG	3,502	LB	2.50	8,755.00	7.50	26,265.00	4.00	14,008.00
0099	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (12 X 53)	14	EA	1,250.00	17,500.00	1,575.00	22,050.00	4,500.00	63,000.00
0100	8364000000-E	450	HP12X53 PILES	280	LF	50.00	14,000.00	49.00	13,720.00	55.00	15,400.00
0101	8475000000-E	460	TWO BAR METAL RAIL	305.5	LF	148.28	45,299.54	190.00	58,045.00	350.00	106,925.00
0102	8517000000-E	460	1'-***X*****CONC PARAPET (1'-2" X 2'-11 3/16")	320.5	LF	175.00	56,087.50	255.00	81,727.50	215.00	68,907.50
0103	8608000000-E	876	RIP RAP II (2'-0")	348	TON	85.00	29,580.00	87.50	30,450.00	80.00	27,840.00
0104	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	387	SY	3.00	1,161.00	3.25	1,257.75	2.00	774.00
0105	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			10,000.00		9,850.00		40,000.00
0106	8763000000-E	430	3'-0" X 2'-0"PRESTR SLABS	2,080	LF	225.00	468,000.00	290.00	603,200.00	528.00	1,098,240.00
CONTRACT TOTAL						TOTAL	2,635,349.64	TOTAL	3,481,000.00	TOTAL	3,899,359.70
ROADWAY ITEMS						SUB-TOTAL	1,078,458.85	SUB-TOTAL	1,969,659.25	SUB-TOTAL	1,399,751.45
STRUCTURE ITEMS						SUB-TOTAL	1,556,890.79	SUB-TOTAL	1,511,340.75	SUB-TOTAL	2,499,608.25

BP10.R047.3

Nov 05, 2025

DJ00583

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING AND STRUCTURE

SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

PERFORMANCE MANAGED
CONSTRUCTION INC
CONCORD, NC

ROADWAY ITEMS

0001	0000100000-N	800	MOBILIZATION	Lump Sum			189,000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum			42,000.00
0003	0036000000-E	225	UNDERCUT EXCAVATION	750	CY	10.00	7,500.00
0004	0043000000-N	226	GRADING (226)	Lump Sum			935,400.00
0005	0050000000-E	226	SUPP CLEARING & GRUBBING	1	ACR	2.00	2.00
0006	0106000000-E	230	BORROW EXCAVATION	3,750	CY	20.00	75,000.00
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	100	CY	20.00	2,000.00
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400	CY	30.00	12,000.00
0009	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	400	SY	3.00	1,200.00
0010	0234000000-E	SP	GENERIC GRADING ITEM (CY) BORROW EXCAVATION (PIPE INSTALLATION)	60	CY	20.00	1,200.00
0011	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1 APPROACH FILL, STATION 19+14.00 -L-	Lump Sum			35,000.00
0012	0318000000-E	300	FND CONDIT MATL MINOR STRS	40	TON	50.00	2,000.00
0013	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	130	SY	5.00	650.00
0014	0335200000-E	305	15" DRAINAGE PIPE	132	LF	75.00	9,900.00
0015	0335850000-E	305	*** DRAINAGE PIPE ELBOW (15")	10	EA	500.00	5,000.00
0016	0343000000-E	310	15" SIDE DRAIN PIPE	32	LF	75.00	2,400.00
0017	0344000000-E	310	18" SIDE DRAIN PIPE	36	LF	90.00	3,240.00
0018	0448200000-E	310	15" RCP CULV CLASS IV	176	LF	150.00	26,400.00
0019	0995000000-E	340	PIPE REMOVAL	29	LF	10.00	290.00
0020	1099500000-E	505	SHALLOW UNDERCUT	100	CY	15.00	1,500.00
0021	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	100	TON	50.00	5,000.00
0022	1110000000-E	510	STABILIZER AGGREGATE	200	TON	70.00	14,000.00
0023	1111000000-E	SP	CLASS IV AGGREGATE STABILIZATION	100	TON	50.00	5,000.00
0024	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	200	SY	3.00	600.00
0025	1220000000-E	545	INCIDENTAL STONE BASE	30	TON	50.00	1,500.00
0026	1297000000-E	607	MILL ASP PVMT ***** DTH (1.5" DEPTH)	1,270	SY	10.00	12,700.00
0027	1330000000-E	607	INCIDENTAL MILLING	190	SY	30.00	5,700.00
0028	1491000000-E	610	ASP CONC BASE CRS B25.0C	835	TON	88.00	73,480.00
0029	1503000000-E	610	ASP CONC INTR CRS I19.0C	830	TON	88.00	73,040.00
0030	1523000000-E	610	ASP CONC SURF CRS S9.5C	750	TON	88.00	66,000.00
0031	1575000000-E	620	ASP FOR PLANT MIX	125	TON	650.00	81,250.00
0032	2022000000-E	815	SUBDRAIN EXCAVATION	44.8	CY	15.00	672.00
0033	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200	SY	3.00	600.00
0034	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6	CY	90.00	3,024.00
0035	2044000000-E	815	6" PERF SUBDRN PIPE	200	LF	5.00	1,000.00
0036	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	250.00	250.00
0037	2077000000-E	815	6" OUTLET PIPE	6	LF	20.00	120.00
0038	2286000000-N	840	MASNRY DRAINAGE STRUCT	9	EA	2,500.00	22,500.00

BP10.R047.3

Nov 05, 2025

DJ00583

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING AND STRUCTURE

SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

PERFORMANCE MANAGED
CONSTRUCTION INC
CONCORD, NC

0039	2367000000-N	840	FRAME W/2GRTS 840.29 STD	9	EA	1,000.00	9,000.00
0040	2556000000-E	846	SHOULDER BERM GUTTER	590	LF	45.00	26,550.00
0041	3030000000-E	862	STL BEAM GUARDRAIL	1,300	LF	25.00	32,500.00
0042	3150000000-N	862	ADDIT GUARDRAIL POSTS	10	EA	11.00	110.00
0043	3215000000-N	862	GR ANCHOR TYPE III	4	EA	2,500.00	10,000.00
0044	3287000000-N	862	GR END TYPE TL-3	4	EA	3,500.00	14,000.00
0045	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,520	LF	5.00	7,600.00
0046	3635000000-E	876	RIP RAP, CLASS II	90	TON	100.00	9,000.00
0047	3649000000-E	876	RIP RAP, CLASS B	180	TON	80.00	14,400.00
0048	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,640	SY	2.00	3,280.00
0049	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	30	LF	10.00	300.00
0050	4102000000-N	904	SIGN ERECTION, TYPE E	2	EA	200.00	400.00
0051	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	8	EA	30.00	240.00
0052	4400000000-E	1110	WORK ZONE SIGNS (STAT)	647	SF	10.00	6,470.00
0053	4410000000-E	1110	WORK ZONE SIGNS (BARR)	119	SF	10.00	1,190.00
0054	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	30.00	2,400.00
0055	4685000000-E	1205	THERMO PVT MKG LINES 4"90	4,990	LF	2.00	9,980.00
0056	4846000000-E	1205	POLYUREA LINES (**, ** MILS) (4", 30 MILS)	660	LF	3.00	1,980.00
0057	6000000000-E	1605	TEMPORARY SILT FENCE	2,905	LF	3.00	8,715.00
0058	6006000000-E	1610	EROS CONTRL STONE CL A	65	TON	70.00	4,550.00
0059	6009000000-E	1610	EROS CONTRL STONE CL B	495	TON	60.00	29,700.00
0060	6012000000-E	1610	SEDIMENT CONTROL STONE	540	TON	50.00	27,000.00
0061	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	900.00	1,800.00
0062	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	2.00	400.00
0063	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	950.00	950.00
0064	6024000000-E	1622	TEMPORARY SLOPE DRAINS	255	LF	15.00	3,825.00
0065	6029000000-E	SP	SAFETY FENCE	1,060	LF	2.00	2,120.00
0066	6030000000-E	1630	SILT EXCAVATION	840	CY	10.00	8,400.00
0067	6036000000-E	1631	MATting FOR EROS CONTROL	2,300	SY	3.00	6,900.00
0068	6037000000-E	1629	COIR FIBER MAT	100	SY	8.00	800.00
0069	6042000000-E	1632	1/4" HARDWARE CLOTH	525	LF	3.00	1,575.00
0070	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	155	SY	25.00	3,875.00
0071	6070000000-N	1639	SPECIAL STILLING BASINS	14	EA	500.00	7,000.00
0072	6071002000-E	1642	FLOCCULANT	130	LB	5.00	650.00
0073	6071010000-E	1642	WATTLE	200	LF	12.00	2,400.00
0074	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	2,750.00	8,250.00
0075	6087000000-E	1660	MOWING	3	ACR	125.00	375.00
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	12.00	600.00
0077	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,500.00	375.00
0078	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	12.00	600.00

BP10.R047.3

Nov 05, 2025

DJ00583

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED

GRADING, DRAINAGE, PAVING AND STRUCTURE

SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

PERFORMANCE MANAGED
CONSTRUCTION INC
CONCORD, NC

0079	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	1,500.00	1,875.00
0080	6111000000-E	SP	IMPERVIOUS DIKE	110	LF	5.00	550.00
0081	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	125.00	1,250.00
0082	6117000000-N	1675	RESPONSE FOR EROS CONTROL	19	EA	450.00	8,550.00
0083	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,000.00	1,000.00
0084	6123000000-E	1670	REFORESTATION	0.3	ACR	3,800.00	1,140.00
0085	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	2	EA	500.00	1,000.00

STRUCTURE ITEMS

0086	8035000000-N	402	REMV EXIST STR ***** BRG (402) (STATION 19+14.00 -L-)	Lump Sum			175,000.00
0087	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			1,100.00
0088	8105520000-E	411	3'-0" DRILLD PIER IN SOIL	63	LF	2,000.00	126,000.00
0089	8105620000-E	411	3'-0" DRILLD PIER NO SOIL	60	LF	2,800.00	168,000.00
0090	8111200000-E	411	PERM STL CASING FOR 3' PIER	63	LF	520.00	32,760.00
0091	8115000000-N	411	CSL TESTING	1	EA	1,100.00	1,100.00
0092	8121000000-N	412	UNCL STR EXCAV STA ***** (STATION 19+14.00-L-)	Lump Sum			35,000.00
0093	8156000000-E	SP	CONCRETE WEARING SURFACE	5,903	SF	11.00	64,933.00
0094	8161000000-E	420	GROOVING BRIDGE FLOORS	6,383	SF	1.00	6,383.00
0095	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	87.9	CY	2,600.00	228,540.00
0096	8210000000-N	422	BRG APPR SLAB ***** (STATION 19+14.00 -L-)	Lump Sum			60,000.00
0097	8217000000-E	425	REINF STEEL (BRIDGE)	26,107	LB	2.50	65,267.50
0098	8238000000-E	425	SPIRAL COL REINF STL BRG	3,502	LB	5.00	17,510.00
0099	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (12 X 53)	14	EA	3,000.00	42,000.00
0100	8364000000-E	450	HP12X53 PILES	280	LF	60.00	16,800.00
0101	8475000000-E	460	TWO BAR METAL RAIL	305.5	LF	170.00	51,935.00
0102	8517000000-E	460	1'-***X*****CONC PARAPET (1'-2" X 2'-11 3/16")	320.5	LF	160.00	51,280.00
0103	8608000000-E	876	RIP RAP II (2'-0")	348	TON	90.00	31,320.00
0104	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	387	SY	5.00	1,935.00
0105	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			25,000.00
0106	8763000000-E	430	3'-0" X 2'-0"PRESTR SLABS	2,080	LF	375.00	780,000.00

CONTRACT TOTAL				TOTAL	3,985,606.50
ROADWAY ITEMS				SUB-TOTAL	2,003,743.00
STRUCTURE ITEMS				SUB-TOTAL	1,981,863.50

BP10.R047.3

TIP NO BP10-R047

0.267 MILES

FED AID NO STATE FUNDED
GRADING, DRAINAGE, PAVING AND STRUCTURE
SR 2408 (GOLD HILL ROAD) OVER DUTCH BUFFALO CREEK

BIDDERS IN ORDER

CONTRACT TOTAL

NJR GROUP INC	1	2,421,617.92
EASTERN STRUCTURES LLC	2	2,577,125.60
SMITH-ROWE, LLC	3	2,590,234.27
KEMP SIGMON CONSTRUCTION CO INC	4	2,635,349.64
SEALAND CONTRACTORS CORP	5	3,481,000.00
REEVES CONSTRUCTION COMPANY	6	3,899,359.70
PERFORMANCE MANAGED CONSTRUCTION INC	7	3,985,606.50

DocuSigned by:

Jason Brooks

C387DBA8ACEC4A9...