

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J.R. "JOEY" HOPKINS
SECRETARY

October 23, 2024

WBS No: 17BP.10.R.141

Contract ID: DJ00521 County: Union

Description: Replace Bridge #329 iver West Fork of Twelvemile Creek on SR 1315 (New

Town Road)

Addendum No. 1 November 6, 2024 Letting

To: Prospective Bidders

Please note the following revision to the Proposal for the above referenced project.

- Special provision "Removal of Existing Traffic Signal" has been added on Page 106.
- Line item 25, Work Zone Signs (Stationary), quantity has been updated from 288 SF to 384 SF.
- Line item 29, Thermoplastic Pavement Marking Lines (4", 90 Mils), quantity has been updated from 1300 LF to 2600 LF.
- Line item 61, Signal Cable, quantity has been updated from 350 LF to 700 LF.
- Line item 62, Vehicle Signal Head (12", 3 Section), quantity has been updated from 6 EA to 8 EA.
- Line item 64, Messenger Cable (1/4"), has been removed.
- Line item 65, Messenger Cable (3/8"), quantity has been updated from 170 LF to 250 LF.
- Line item 69, Camera Without Internal Loop Emulator Processing Unit, quantity has been updated from 3 EA to 1 EA.
- Line item 71, Sign for Signals, quantity has been updated from 1 EA to 3 EA.
- Line item 72, Controllers with Cabinet (Type 2070L, Pole Mounted), title has changed too Controllers with Cabinet (Type 2070LX, Pole Mounted).
- Line item 78, Sign Erection, Type E, has been added.
- Line item 79, Stockpile Sign D, E, or F, has been added.
- Line item 80, 2" Riser With Weather Head, has been added.
- Line item 81, Site Survey, has been added.
- Line item 82, Luminaire Arm for Video System, has been added.
- Line item 83, Relocate Camera Sensor Unit, has been added.
- Line item 84, Traffic Signal Removal, has been added.

Please note the following revision to the Plans for the above referenced project.

- Signal plans, Sig 1.0, has been updated to remove the proposed Roundabout label.
- Signal plans, Sig 2.0, has the following updates:
 - o Added Signal Ahead W3-3 signs to SR 1008 approaches.
 - o Added notes 8 and 9.
 - o Updated title block/superseded note.
 - o Updated table of operation for all red flash.
- Signal plans, Sig 2.1, has the following updates:
 - o Added startup flash programming detail.
 - o Added output channel configuration.
 - o Updated title block/superseded note.

The changes and attachments included with this addendum will become part of contract DJ00521.

If you have any questions, please contact me at (704) 983-4400.

Sincerely,

DocuSigned by:

Jand S Mathis

Jared Mathis, PE

Contracts Engineer

cc: file

REMOVAL OF EXISTING TRAFFIC SIGNAL

Revise the Standard Specifications as Follows:

Page 17-43, Article 1757-3 Measurement and Payment, Replace paragraph with the following:

Traffic Signal Removal will be measured and paid as the actual number of intersections that were maintained and completely cleared of all traffic signal equipment. The above price and payment will be full compensation for all work covered by this provision, including but not limited to removal, disposal and maintenance of the traffic signal during the life of the project. The contractor shall return the removed signal to the Traffic Services Office as stated in 1757-2 (C) and will be of no cost to the department.