PROJECT REFERENCE NO.	SHEET NO.
33879.2.91	ITS-13

NOTES:

A. EXISTING FIBER OPTIC CABLE AND CONDUIT SYSTEM RUNS FROM THE WEIGH STATION BUILDING TO THE EXISTING "OPEN/CLOSED" SIGN. IN ADDITION, THERE IS AN EXISTING QUEUE DETECTION SYSTEM AND OVERHEAD LIGHTING CIRCUITS ON THE RAMP. BEFORE BEGINNING ANY UNDERGROUND WORK CONTACT THE DIVISION TRAFFIC ENGINEER (DANIEL ADAMS) AT (336) 903-9136 TO LOCATE THE EXISTING UNDERGROUND COMPONENTS.

B. INDUCTIVE LOOP SAW SLOTS, INCLUDING TAIL AND LEAD-IN SECTIONS, CAN BE WET CUT AT THIS LOCATION.

C. THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS ARE CONCEPTUAL AND MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. CONSULT THE DIVISION AND THE ENGINEER TO COORDINATE GUARDRAIL INSTALLATION.

D. MODIFY EXISTING OPEN/CLOSED SIGN ELECTRICAL SERVICE BY ADDING A DOUBLE POLE 50A BREAKER AND ROUTING NEW COPPER FEEDER CONDUCTORS TO NEW EQUIPMENT CABINET DISCONNECT MOUNTED ON A 6" X 6" TREATED WOOD PEDESTAL.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared in the Offices of:

750 N. Greenfield Pkwy., Garner, NC 27529

SCALE: NOT TO SCALE

NOTIFICATION LOCATION, AVI READER, & CHANGEABLE MESSAGE SIGNS

DIVISION 11 SURRY CO. MT. AIRY

PLAN DATE: JANUARY 2020

PREPARED BY: A. J. SKUCE

REVIEWED BY: DocuSigned by: Neil Avery

REVISIONS | INIT. | DATE

SEAL: NORTH CAROLINA PROFESSIONAL SEAL 032108 ENGINEER AUREF ASLAMI

DocuSigned by: Aurif Aslami, PE

SIGNATURE

1/9/2020

DATE