


TIP PROJECT: X-XXXX



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
PLAN FOR PROPOSED
HIGHWAY EROSION CONTROL

CALDWELL COUNTY


**LOCATION: SR 1732 MILL POND ROAD
FROM SR 1730 DUCK CREEK ROAD
TO ALEXANDER COUNTY LINE
TYPE OF WORK: GRADING, DRAINAGE, BASE
AND PAVING - 0.63 MILES**

Porous Baffle Spacing
*Baffles in Silt Basins at drainage
turnouts and all other temporary
rock sediment dams-Type B:
-If basin length=10' or less;1 baffle
-If basin length=11' to 20';2 baffles
-If basin length=20' or more;3 baffles
equally spaced in basin

NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE
INSTALLED DURING CLEARING AND GRUBBING PHASE.

Level III-A Cert # 391
Level III-B Cert# 382

GRAPHIC SCALE



ROADSIDE ENVIRONMENTAL UNIT
DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY
WITH THE REGULATIONS SET FORTH BY THE
NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011
ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND
NATURAL RESOURCES DIVISION OF WATER QUALITY.

Prepared In the Office of:
DIVISION OF HIGHWAYS
DIVISION 11, DISTRICT 2 BOONE
P. O. BOX 1460, BOONE, N.C. 28607
2012 STANDARD SPECIFICATIONS

Roadway Standard Drawings

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

1604.01 Railroad Erosion Control Detail	1632.01 Rock Inlet Sediment Trap Type A
1605.01 Temporary Silt Fence	1632.02 Rock Inlet Sediment Trap Type B
1606.01 Special Sediment Control Fence	1632.03 Rock Inlet Sediment Trap Type C
1607.01 Gravel Construction Entrance	1633.01 Temporary Rock Silt Check Type A
1622.01 Temporary Berms and Slope Drains	1633.02 Temporary Rock Silt Check Type B
1630.01 Riser Basin	1634.01 Temporary Rock Sediment Dam Type A
1630.02 Silt Basin Type B	1634.02 Temporary Rock Sediment Dam Type B
1630.03 Temporary Silt Ditch	1635.01 Rock Pipe Inlet Sediment Trap Type A
1630.04 Stilling Basin	1635.02 Rock Pipe Inlet Sediment Trap Type B
1630.05 Temporary Diversion	1640.01 Coir Fiber Baffle
1630.06 Special Stilling Basin	1645.01 Temporary Stream Crossing
1631.01 Matting Installation	

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	11C.0140??	EC-1	9
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	


EROSION AND SEDIMENT CONTROL MEASURES

Std. #	Description	Symbol
1630.03	Temporary Silt Ditch	---
1630.05	Temporary Diversion	TD
1605.01	Temporary Silt Fence	III
1606.01	Special Sediment Control Fence	III
1622.01	Temporary Berms and Slope Drains	T
1630.02	Silt Basin Type B	SB
1633.01	Temporary Rock Silt Check Type-A	TRSC
	Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM)	TRSC-PAM
1633.02	Temporary Rock Silt Check Type-B	TRSC-B
	Wattle/ Coir Fiber Wattle	W
	Wattle/ Coir Fiber Wattle with Polyacrylamide (PAM)	W-PAM
1634.01	Temporary Rock Sediment Dam Type-A	TRSD-A
1634.02	Temporary Rock Sediment Dam Type-B	TRSD-B
1635.01	Rock Pipe Inlet Sediment Trap Type-A	RPIST-A
1635.02	Rock Pipe Inlet Sediment Trap Type-B	RPIST-B
1630.04	Stilling Basin	SB
1630.06	Special Stilling Basin	SSB
	Rock Inlet Sediment Trap:	
1632.01	Type A	A
1632.02	Type B	B
1632.03	Type C	C
	Skimmer Basin	SKB
	Tiered Skimmer Basin	TSKB
	Infiltration Basin	IB



THIS PROJECT CONTAINS
EROSION CONTROL PLANS
FOR CLEARING AND
GRUBBING PHASE OF
CONSTRUCTION.

C:\MAN\2012\115 Mill Pond\EC Work\PlanSheets\CA1732_Rdy_tah.dgn

SR 1732 Mill Pond Rd



Legend

-  Undisturbed Drainage Area
-  Cut and Fill Area

EROSION CONTROL & PIPE INSTALLATION SCHEDULE

TROUT BUFFER ZONE SEQUENCE

GENERAL E&SC NOTES

GROUND STABILIZATION CHART

Erosion Control Schedule and Notes

1. Generally, the order of installation of the erosion control measures will be as follows:
 - A. Temporary silt basins shall be installed before clearing and grubbing begins.
 - B. Silt fences and temporary silt ditches shall be installed after clearing and before grading.
 - C. Temporary stone ditch checks with PAM or wattles with PAM shall be installed in all disturbed areas as soon as the disturbance begins.
 - D. Final stone ditch checks or wattles shall be installed as soon as ditch line is established.
 - E. Pipe outlet and inlet protection will be done as soon as the pipe is installed.
 - F. Other permanent erosion control measures are to be implemented as soon as practical.
2. Temporary rock silt checks, type B will be spaced by percent grade as shown in the erosion control plan.
3. No. 5 stone, or equivalent, will be used in conjunction with the temporary rock silt checks in locations where water is leaving the project or entering a pipe.
4. All devices are to be cleaned out when half full.
5. Establish permanent vegetation per ground stabilization chart.

Notes:

For silt basin size see the attached erosion control plans.

PAM is to be placed on all Type A checks and wattles in the erosion control chain except for the final device in HWQ and Trout projects.

Wet Pipe Installation Schedule and Notes

1. Prior to installing any E&SC measures identify permit conditions and impact area limits.
2. Install erosion control devices.
3. Manage the water course. The pipe must be placed in the dry. Install dewatering measures.
4. Remove material and existing pipe while limiting material and sediment from entering stream and escaping the project.
5. Excavation of stream channel shall not exceed 10' on either side of new pipe or culvert unless indicated on permit.
6. Per permit conditions for Corps of Engineers and the Wildlife Resources Commission, all pipes in streams 48" or greater must be buried 12" below streambed elevation. Pipes less than 48" must be buried with 20% of the diameter below streambed elevation.
7. Place the new pipe and compact backfill.
8. Install slope protection on the outlet and inlet ends of the pipe. Also complete installation of erosion control measures and perform maintenance as needed on existing measures.
9. Establish permanent vegetation per ground stabilization chart.
10. More information on wet pipe installation can be found in the BMP manual section 4.2 "Pipe & Culvert installation"

General Erosion Control Sequence & Notes for NC DOT Projects in Trout Buffer Zones

1. Prior to installing any E&SC measures identify permit conditions and impact area limits. Review trout buffer variance approval conditions for any special provisions.
2. All materials should be on the hand before work is commenced.
3. Install EC devices
4. Work within the buffer zone should be sequenced to minimize the length of time that disturbed areas are exposed. Stream bank stabilization, which includes the area from the edge of water to the top of bank, should be phased so that each day's work is a completed work, including provision of adequate ground cover.
5. Graded slopes and fills within the trout buffer zone will within 7 calendar days of completion of any phase of grading be planted or otherwise provided with temporary or permanent ground cover, devices, or structures sufficient to restrain erosion.
6. Graded slopes and fills within the trout buffer zone (excluding road shoulders) shall be protected with rolled erosion control product, bonded fiber matrix, or flexible growth medium after seeding.

Notes:

Silt fence backed by woven wire, with a post spacing of 6 feet, shall be used instead of standard silt fence in trout buffer zone. Special sediment control fence shall be used in areas where bedrock is encountered which prohibits the proper anchoring of fabric, and in low points of the silt fence in 3-foot sections to allow for concentrated flows.

The disturbed areas within the stream buffer shall be restored to native vegetation characteristic of an undisturbed buffer to the extent practical upon completion of construction.

Flyrock protection such as blast mats should be provided for blasting in close proximity to streams.




PAM is to be placed on all Type A checks and wattles in the erosion control chain except for the final device in HWQ and Trout projects.

GROUND STABILIZATION CHART

Site Area Description	Stabilization Time Frame	Stabilization Time Frame Exceptions
Perimeter dikes, swales, ditches and slopes	7 days	None
High Quality Water Zones	7 days	None
Slopes steeper than 3:1	7 days	If slopes are 10 ft. or less in length and are not steeper than 2:1, 14 days are allowed
Slopes 3:1 or flatter	14 days	7 days for slopes greater than 50' in length
All other areas flatter than 4:1	14 days	None (except for perimeters and HQW zones)

6/2/99
05-MAR-2002 11:45
R:\Road_Proj\CA-1732\Secondary\Caldwell\SR1732_M11_Pond\Dgm\cal1732_sht_2.dgn
\$\$\$\$\$USING\$\$\$\$\$

PROJECT REFERENCE NO.	SHEET NO.
CA-1732	2
ROADWAY DESIGN ENGINEER	PAVEMENT DESIGN ENGINEER



DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA


SOIL STABILIZATION TIMEFRAMES

PROJECT REFERENCE NO. <i>CA-1732</i>	SHEET NO. <i>EC-3B</i>
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HOW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HOW ZONES.

8/17/99
 REVISIONS
 01-JUN-2012 12:48
 R:\Road Projects\Secondary\Caldwell\SR1732.M11_Pond\EC_Work\PlanSheets\EC4.dgn
 \$\$\$USE IN FIELD ONLY\$\$\$

PROJECT REFERENCE NO.	SHEET NO.
EC-1732	4
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER



8/17/99
REVISIONS
01-JUN-2012 12:48
R:\Roads\Projects\Secondary\Caldwell\SR1732.M11_Pond\EC_Work\PlanSheets\EC5.dgn
C:\Users\jensie\Documents


PROJECT REFERENCE NO.	SHEET NO.
EC-1732	5
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

60 DAY OPTION
THIS SECTION MUST BE PERMANENTLY STABILIZED WITHIN 60 DAYS FROM THE TIME CLEARING & GRUBBING BEGINS

5+00

DOTSON, JOHN & MARJORIE E
DB 1211 PG 2031

CASSAVAUGH, WILLIAM M. & ANGELA
DB 1210 PG 21



12" Wattles
INSTALL MATTING FOR EROSION CONTROL IN THE PROPOSED DITCH LINE.

INSTALL MATTING FOR EROSION CONTROL IN THE PROPOSED DITCH LINE.

9 x 3 x 3
2 ft. weir
ID 5.1

9 x 3 x 3
2 ft. weir
ID 5.2

INSTALL MATTING FOR EROSION CONTROL IN THE PROPOSED DITCH LINE.

Type B
or wattle
ID 5.3

Add Special Sediment Control Fence F.I. in low points of Silt fence along project.

15" CSP

15' x 94' Gravel

STA 2+40

STA 8+90

C1.0
19.5

C4.6
24.9

C4.8
25.2

C6.0
27.0

C5.0
25.5

C6.0
27.0

C1.3
20.0

C0.4
18.6

F1.0
18.0

F0.0
16.0

C1.2
19.8

+27

+72

1385

1380

1380

1375

1370

1370

1375

1365

1365

1365

1365

1370

1360

1355

1360

1360

1355

1360

1355

1355

1340

1335

1330

1330

1330

1365

1360

1350

1340

1335

1330

1330

1330

8/17/99
REVISIONS
01-JUN-2012 12:48
R:\Road\Projects\Secondary\Caldwell\SR1732.M11_Pond\EC_Work\PlanSheets\EC6.dgn
C:\Users\JENNER\Documents

PROJECT REFERENCE NO.	SHEET NO.
EC-1732	6
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

60 DAY OPTION
THIS SECTION MUST BE PERMANENTLY STABILIZED WITHIN 60 DAYS FROM THE TIME CLEARING & GRUBBING BEGINS

INSTALL MATTING FOR EROSION CONTROL IN THE PROPOSED DITCH LINE.

9 x 3 x 3
2 ft. weir
(See Infiltration Basin Detail)
ID 6.1

9 x 3 x 3
2 ft. weir
ID 6.2


INSTALL MATTING FOR EROSION CONTROL IN THE PROPOSED DITCH LINE.

Type B or Wattle
ID 6.5

9 x 3 x 3
2 ft. weir
ID 6.7

STA 8+90

STA 15+40



ANDERSON, JERRY DEAN & GLENNA
DB 1226 PG 107

CASSAUAUGH, WILLIAM M & ANGELA
DB 1210 PG 21

BROWN, RONALD W
DB 1252 PG 1264

BENTLEY, HARLEY R, JR & KIMBERLY
DB-1208 - PG 1090

Add Special Sediment Control Fence
in low points of Silt fence along
project.

CONC. MONUMENT
& E.I.P.

9 x 3 x 3
2 ft. weir
ID 6.3

9 x 3 x 3
2 ft. weir
ID 6.4

INSTALL MATTING FOR EROSION CONTROL IN THE PROPOSED DITCH LINE.


9 x 3 x 3
2 ft. weir
ID 6.6

PROJECT REFERENCE NO.	SHEET NO.
EC-1732	7
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

8/17/99

REVISIONS

01-JUN-2012 12:48
 R:\Roads\Projects\Secondary\Caldwell1\SR1732.M11_Pond\EC_Work\PlanSheets\EC7.dgn
 *****USER DEFINED*****




STA 15+40
 STA 21+90

PROJECT REFERENCE NO.	SHEET NO.
EC-1732	8
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

8/17/99

REVISIONS



ANDERSON, JERRY DEAN & GLENNA
DB 1203 PG 1057

PRICE, RONNIE D JR & SHANNON L
DB 1328 PG 964

PRICE, RONNIE D & ELAINE
DB 1075 PG 1371

PRICE, RONNIE D & ELAINE
DB 1048 PG 641

INSTALL MATTING FOR
EROSION CONTROL IN THE
PROPOSED DITCH LINE.

INSTALL MATTING FOR
EROSION CONTROL IN THE
PROPOSED DITCH LINE.

9 x 3 x 3
2 ft. weir
ID 8.3

9 x 3 x 3
ID 8.1

9 x 3 x 3
2 ft. weir
ID 8.4

9 x 3 x 3
2 ft. weir
ID 8.2

Add Special Sediment Control Fence
in low points of Silt fence along
project.

No Embankment Construction
ST A. 25+69 Rt. to E.O.P.

P/L FOLLOWS
C/L of BRANCH

01-JUN-2012 12:48
R:\Road\Projects\Secondary\Caldwell1\SR1732.M11_Pond\EC_Work\PlanSheets\ECB.dgn
S:\USERS\JEN\WORK

8/17/99
 REVISIONS
 01-JUN-2012 12:48
 R:\Road Projects\Secondary\Caldwell\SR1732.M11_Pond\EC_Work\PlanSheets\EC.dgn
 \$\$\$\$USE ENVELOPE\$\$\$\$

PROJECT REFERENCE NO.	SHEET NO.
EC-1732	9
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

