PROJECT REFERENCE NO.	SHEET NO.
R-5755	SIGN-2

APPROVED: _____

DATE: _____

SEAL

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

(401) QUANTITY REQ'D 4

30" X 24"
R6-4

ONE "U" POST PER SIGN

(402) QUANTITY REQ'D 4

24" X 30"
R4-7

ONE "U" POST PER SIGN

(403) QUANTITY REQ'D 9

48" X 48" X 48"
R1-2

ONE "U" POST PER SIGN

(404) QUANTITY REQ'D 4

30" X 30"
W3-2

ONE "U" POST PER SIGN

(405) QUANTITY REQ'D 4

30" X 30"
W2-6

ONE "U" POST PER SIGN

(406) QUANTITY REQ'D 4

30" X 30"
R5-1

ONE "U" POST PER SIGN

(407) QUANTITY REQ'D 4

24" X 24"
R3-2

MOUNT BELOW SIGN R1-2
IN DESIGNATED INSTALLATIONS

(408) QUANTITY REQ'D 4

24" X 12"
W16-17P

MOUNT BELOW SIGN W2-6
IN DESIGNATED INSTALLATIONS

(409) QUANTITY REQ'D 1

36" X 12"
R6-1 (R)

TWO "U" POSTS PER SIGN

(410) QUANTITY REQ'D 3

24" X 12"
M3-3

AUXILIARY SIGN NO "U" POST

(411) QUANTITY REQ'D 1

24" X 12"
M3-1

AUXILIARY SIGN NO "U" POST

(412) QUANTITY REQ'D 4

24" X 12"
M4-2

AUXILIARY SIGN NO "U" POST

(413) QUANTITY REQ'D 4

24" X 24"
M1-1

ONE "U" POST PER SIGN

(414) QUANTITY REQ'D 2

21" X 15"
M6-2 (R)

AUXILIARY SIGN NO "U" POST

(415) QUANTITY REQ'D 3

21" X 15"
M6-2 (L)

AUXILIARY SIGN NO "U" POST