DocuSign Envelope ID: C9DF7108-0EA3-40B7-81FC-1B88507EF0CA

COMPUTED BY: M. Brewer DATE: 11/7/17
CHECKED BY: M. Walko DATE: 11/7/17

(2-16-16)

PROJECT NO.	SHEET NO.
R-5730	3G-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
CONTINGENCY				SD	500
				TOTAL LF:	500

*UD = Underdrain
*BD = Blind Drain
*SD = Subsurface Drain

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

LINE	Station	Station	Aggregate Type* ASU/AST	Aggregate Thickness INCHES	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Soil Stabilization SY	Stabilizer Aggregate TONS	Class IV Aggregate Stabilization TONS
CONTINGENCY			ASU	12	300	590	900		
			TOTAL CY/TONS/SY:		300	590	900*	0	0

*ASU = Aggregate Subgrade
*AST = Aggregate Stabilization

**Total square yards of "Geotextile for Soil Stabilization" is only the estimated quantity for ASU/AST and may only represent a portion of the geotextile quantity shown in the Item Sheets of the Proposal.