DocuSign Envelope ID: 5E5BA466-1BB3-403C-885E-FEBC45E19F26

PROJECT REFERENCE NO.	SHEET NO.
U-5776	2B-2
R/W SHEET NO.	

ROADWAY DESIGN ENGINEER: NORTH CAROLINA PROFESSIONAL SEAL 35018 ENGINEER JIMMY L. IZBRY — 6/15/2018 5:17:11 AM PDT

HYDRAULICS ENGINEER: NORTH CAROLINA PROFESSIONAL SEAL 038697 ENGINEER DAVID B. PETTY — 6/15/2018 7:04:23 AM PDT

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275



NOTES:

ALL THE EXISTING PAVEMENT ON EACH SIDE OF EXISTING TRACK CENTERLINE WILL BE REMOVED BY THE RAILROAD CONTRACTOR.

CONTRACTOR SHALL SEED AND MULCH THE DISTURBED AREA OUTSIDE THE RAILROAD BALLAST LINE.

CONTRACTOR SHALL CONTACT NORTH CAROLINA 811 TO LOCATE ALL UNDERGROUND UTILITIES IN THE WORK AREA.

THE RR CROSSING ADVANCE WARNING PAVEMENT MARKINGS ON DUKE STREET TO THE SOUTH NEED TO BE REMOVED.

REVISE THE PAVEMENT MARKINGS AND MARKERS FOR US 321A, DUKE ST, CENTRAL AVE, AND COMMERCE ST ACCORDING TO THE FINAL PAVEMENT MARKING PLANS.

REMOVE THE SIGNAL SYSTEM AT THE INTERSECTION.

PROVIDE PERMANENT SIGNING FOR US 321A, DUKE ST, CENTRAL AVE, AND COMMERCE ST ACCORDING TO THE SIGNING PLANS.

PROVIDE SIGNING AND DEVICES REQUIRED TO CLOSE THE ROAD ACCORDING TO THE ROADWAY STANDARD DRAWINGS AND TRAFFIC CONTROL PLANS.

ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

SUMMARY OF PAVEMENT REMOVAL

IN SQUARE YARDS

ITEM	QUANTITY
ASPHALT	230

PAVEMENT REMOVAL

CLOSURE OF RAILROAD CROSSING

20' 0' 20' 40'
10'

REVISIONS

8/17/99

6/14/2018
R:\NCDOT\U-5776\Roadway\Proj\U-5776_Rdy_Detail 2B_2(Railroad Crossing Closure).dgn
User:smelvin