
# O



# STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PLAN FOR PROPOSED HIGHWAY EROSION CONTROL

# CALDWELL COUNTY

LOCATION: SR 1890 BLUE DOVE LANE FROM SR 1751 CAMPGROUND RD TO E.O.P. STA 0+00 TO EOP STA 18+94TYPE OF WORK: GRADING, DRAINAGE, BASE AND PAVING - 0.36 MILES

STATE EC-1 10 N.C. 11C.0140% STATE PROLNO.

EROSION AND SEDIMENT CONTROL MEASURES 1630.03 Temporary Silt Ditch\_\_\_\_\_ 1630.05 Temporary Silt Fence \_\_\_\_\_ | III | III | III | III 1605.01 Special Sediment Control Fonce Temporary Berms and Slope Drains \_\_\_\_\_ T 1622.01 Silt Basin Type B..... Temporary Rock Silt Check Type-A..... Temporary Rock Silt Check Type A. with Matting and Polyacrylamide (PAM) -Temporary Rock Silt Check Type-B Wattle / Coir Fiber Wattle Wattle / Coir Fiber Wattle with Polyacrylamide (PAM)\_\_\_\_\_ Temporary Rock Sediment Dam Type-A. Temporary Rock Sediment Dam Type-B. Rock Pipe Inlet Sediment Trap Type-A. 1634.02 Rock Pipe Inlet Sediment Trap Type-B\_\_\_ 1635.02 1630.04 Stilling Basin 1630.06 Special Stilling Basin\_\_\_\_\_ Rock Inlet Sediment Trap: Туре А.....А 1632.01 1632.02 вП Type C\_\_\_\_\_ - C 🔲 Tiered Skimmer Basin Infiltration Basin

> THIS PROJECT CONTAINS EROSION CONTROL PLANS FOR CLEARING AND GRUJJING PHASE OF CONSTRUCTION.

Porous Baffle Spacing \*Baffles in Silt Basins at drainage turnouts and all other temporary rock sediment dams-Type B: -If basin length = 10' or less;1 baffle -If basin length = 11' to 20';2 baffles -If basin length = 20' or more; 3 baffles equally spaced in basin

PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.

Level III Cert # 3498

#### GRAPHIC SCALE PLANS PROFILE (HORIZONTAL) 200 PROFILE (VERTICAL)

ROADSIDE ENVIRONMENTAL UNIT DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA

> THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011 ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER QUALITY.

Prepared in the Office of:

#### **DIVISION OF HIGHWAYS**

DIVISION 11, DISTRICT 2 BOONE P.O. BOX 1460, BOONE, N.C. 28607

2012 STANDARD SPECIFICATIONS

#### Roadway Standard Drawings

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2012 and the latest revison thereto are applicable to this project and by reference hereby are considered a part of

1604.01 Railroad Erosion Control Detail 1605.01 Temporary Silt Fence 1606.01 Special Sediment Control Fence 1632.01 Rock Inlet Sediment Trap Type A 1632.02 Rock Inlet Sediment Trap Type 3 1632.03 Rock Inlet Sediment Trap Type C 1607.01 Special Sediment Control Fence
1622.01 Gravel Construction Entrance
1630.01 Riser Jasin
1630.02 Silit Jasin Type J
1630.03 Temporary Silt Ditch
1630.04 Stilling Jasin
1630.05 Temporary Diversion
1630.06 Special Stilling Jasin
1631.01 Matting Installation 1633.01 Temporary Rock Silt Check Type A 1633.02 Temporary Rook Silt Check Type 3 1634.01 Temporary Rock Sediment Dam Type A
1634.02 Temporary Rock Sediment Dam Type A
1635.01 Rock Pipe Inlet Sediment Trap Type A
1635.02 Rock Pipe Inlet Sediment Trap Type A 1640.01 Coir Fiber Jaffle 1645.01 Temporary Stream Crossins

# EROSION CONTROL & PIPE INSTALLATION SCHEDULE TROUT BUFFER ZONE SEQUENCE GENERAL E&SC NOTES GROUND STABILIZATION CHART

#### Erosion Control Schedule and Notes

- 1. Generally, the order of installation of the erosion control measures will be as follows:
  - A. Temporary silt basins shall be installed before clearing and grubbing begins.
  - B. Silt fences and temporary silt ditches shall be installed after clearing and before grading.
  - C. Temporary stone ditch checks with PAM or wattles with PAM shall be installed in all disturbed areas as soon as the disturbance begins.
  - D. Final stone ditch checks or wattles shall be installed as soon as ditch line is established.
  - E. Pipe outlet and inlet protection will be done as soon as the pipe is installed.
  - F. Other permanent erosion control measures are to be implemented as soon as practical.
- 2. Temporary rock silt checks, type B will be spaced by percent grade as shown in the erosion control plan.
- 3. No. 5 stone, or equivalent, will be used in conjunction with the temporary rock silt checks in locations where water is leaving the project or entering a pipe.
- 4. All devices are to be cleaned out when half full.
- 5. Establish permanent vegetation per ground stabilization chart.

#### Notes:

For silt basin size see the attached erosion control plans.

PAM is to be placed on all Type A checks and wattles in the erosion control chain except for the final device in HWQ and Trout projects.

#### Wet Pipe Installation Schedule and Notes

- 1. Prior to installing any E&SC measures identify permit conditions and impact area limits.
- 2. Install erosion control devices.
- 3. Manage the water course. The pipe must be placed in the dry. Install dewatering measures.
- 4. Remove material and existing pipe while limiting, material and sediment from entering stream and escaping the project.
- 5. Excavation of stream channel shall not exceed 10' on either side of new pipe or culvert unless indicated on permit.
- 6. Per permit conditions for Corps of Engineers and the Wildlife Resources Commission, all pipes in streams 48" or greater must be buried 12" below streambed elevation. Pipes less than 48" must be buried with 20% of the diameter below streambed elevation.
- 7. Place the new pipe and compact backfill.
- 8. Install slope protection on the outlet and inlet ends of the pipe. Also complete installation of erosion control measures and perform maintenance as needed on existing measures.
- 9. Establish permanent vegetation per ground stabilization chart.
- 10. More information on wet pipe installation can be found in the BMP manual section 4.2 "Pipe & Culvert installation"

# General Erosion Control Sequence & Notes for NC DOT Projects in Trout Buffer Zones

- 1. Prior to installing any E&SC measures identify permit conditions and impact area limits. Review trout buffer variance approval conditions for any special provisions.
- 2. All materials should be on the hand before work is commenced.
- 3. Install EC devices
- 4. Work within the buffer zone should be sequenced to minimize the length of time that disturbed areas are exposed. Stream bank stabilization, which includes the area from the edge of water to the top of bank, should be phased so that each day's work is a completed work, including provision of adequate ground cover.
- 5. Graded slopes and fills within the trout buffer zone will within 7 calendar days of completion of any phase of grading be planted or otherwise provided with temporary or permanent ground cover, devices, or structures sufficient to restrain erosion.
- 6. Graded slopes and fills within the trout buffer zone (excluding road shoulders) shall be protected with rolled erosion control product, bonded fiber matrix, or flexible growth medium after seeding.

#### Notes:

Silt fence backed by woven wire, with a post spacing of 6 feet, shall be used instead of standard silt fence in trout buffer zone. Special sediment control fence shall be used in areas where bedrock is encountered which prohibits the proper anchoring of fabric, and in low points of the silt fence in 3-foot sections to allow for concentrated flows.

The disturbed areas within the stream buffer shall be restored to native vegetation characteristic of an undisturbed buffer to the extent practical upon completion of construction.

Flyrock protection such as blast mats should be provided for blasting in close proximity to streams.

PAM is to be placed on all Type A checks and wattles in the erosion control chain except for the final device in HWQ and Trout projects.

#### **GROUND STABILIZATION CHART**

Site Area Description	Stabilization Time Frame	Stabilization Time Frame Exceptions					
Perimeter dikes, swales, ditches and slopes	7 days	None					
High Quality Water Zones	7 days	None					
Slopes steeper than 3:1	7 days	If slopes are 10 ft. or less in length and are not steeper than 2:1, 14 days are allowed					
Slopes 3:1 or flatter	14 days	7 days for slopes greater than 50' in lenght					
All other areas flatter than 4:1	14 days	None (except for perimeters and HQW zones)					

### DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA

PROJECT REFERENCE NO	. SHEET NO.
IIC.014096	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

# SOIL STABILIZATION SUMMARY SHEET

#### MATTING FOR EROSION CONTROL

#### PERMANENT SOIL REINFORCEMENT MAT

	MAITING .	FUN EN	OSION	COMIN	<i>OL</i>	PERMANENI SUIL REINFURCEMENI MAI									
CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)	CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)				
6	6 - 14		18+25	LT	290	4	-レ-	1+50	0+25	LT	135				
						4	-レ-	1+25	0+25	R1	105				
						5	-レ-	2+00	10+25	R1	865				
						5	-レ-	1+50	9+25	LT	810				
			·			6	-レ-	11+50	14+00	LT	265				
						6	-レ-	10+50	16+25	R1	605				
			<b>5</b> U8	TOTAL	290										
MISCELLANE DUS	S MATTING TO BE INSTA	LLED AS DIRE	CTED BY THE	engineer						TOTAL	2785				
						MISCELLANE OUS	S MATTING TO BE INS	ITALLED AS DIRE	CTED BY THE	ENGINEER	·				
				TOTAL	290										
				SAY	290					TOTAL	2785				
										SAY	2800				
							<del></del>								
	·														
	·														
					•										
											•				
										<u> </u>					

## DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA

PROJECT REFERENCE N	PROJECT REFERENCE NO.									
IIC.014096	IIC.014096									
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	1							
ENGINEER	1	ENGINEER	1							
			ı							
	1		1							
	1		ı							
	1		1							
			ı							
	Į.	•	1							
l	1									

# SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HOW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3: OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HOW ZONES.

# STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS


PROJECT NO. SHEET NO.


11C.014096 3-C

revised: 07/14/17

# LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)

NEW PIPES								1			E	PIPES					5							
						GE PIPE P, HDPE, C	R PVC)								· · · · · · · · · · · · · · · · · · ·	***		·		TD. 840.	RATE	OR 840.3	38.05	
SIZE S	LOCATION (LT, RT, OR CL)	12"	15"	18"	24"	30"	36"	42"	48"		12"	15"	18"	24"	30"	36"	42"	48"	PIPE REMOVAL	DROP INLET STD. 840.14 OR STD. 840.15	D.I.FRAME AND GRATE STD. 840.16	J.B. STD. 840.31 OR 840.32	ENDWALL STD. 838.05 (CUBIC YARDS)	
TYPE	T, RT,		:																PE R	70 P.	1.FRA TD. 84	B. ST	NDW	REMARKS
STATION 02+41	LT		25'									24'							24'	o o o	8 0		<u> </u>	
02+56	RT		25'					-																ADD DWY PIPE
04+06	RT		25'									24'							24'					
04+70	LT		25'									24'							24'					
05+68	RT		25'									24'							24'					
																			44'					
06+26	LT		45'					<del>                                     </del>	 			44'		·			<del>                                     </del>	<u> </u>	+++					
06+42	RT		25'									24'							24'					
07+93	LT		25'									24'							24'	<u> </u>				
08+58	LT		35'			-						34'						ļ	34'	<u> </u>		-	-	
												35'							35'	<u> </u>				
08+70	RT		62'																					
09+21	LT		25'									24'					-		24'	<u> </u>	-	<u> </u>	-	
09 <del>+9</del> 1	RT		35'			-			<b></b>			34'							34'				"	
10+40	CL	<del> </del>		45'			<u> </u>	<del> </del>					41'		<del> </del>			ļ	41'	<u> </u>				
10+ <del>9</del> 3	RT	<b></b>	25'									24'				-	<del> </del>		24'	<del> </del>		<del> </del>	<u> </u>	
•												24'							24'		1			
11+99	LT		25'												<u> </u>									
12+67	RT	1	25'		<del> </del>				<del> </del>			24'	<u> </u>		-	<del> </del>	+	-	24'	1	+			
13+26	LT		27'					<b> </b>				27'							27'		1			
13+91	RT		25'	<del> </del>	+				<u> </u>			24'							24'					
14+94	RT		25'		-			Ţ				24'		ļ		ļ			24'	<del> </del>	-	-	<del> </del>	
								1						ļ			1							
17+60	LT	1	25'	ļ		-	+	╂	-	<u> </u>	<del> </del>	24'			<u> </u>		+	<del> </del>	24'	┼─	<del>-</del>	<del>-}</del>		
			<u>  </u>				1			<u> </u>				ļ	<b>.</b>	1		<b>_</b>		<b>_</b>				
			-	1	+	1	1	+-	<u> </u>	1	+			<del>                                     </del>	1	$\pm$								
				1	<u> </u>	_		1	4	ļ	<b>_</b>					ļ						<u> </u>		
<del></del>		$\pm$	1													<u> </u>								
			-									ļ	-		-									
													1							1				
		<u> </u>	-					-			1	+-	-	-	<b>-</b>	+	<del> </del>	-	-		-	+		
** ****				1.			ļ			1			1	<b> </b>				_						
	+	+	4	+	1	-	+		-	+	+	1	+	<del> </del>		-		<del> </del>	-	-	4	+	+	<u></u>





PROJECT REFERENCE NO.

SHEET NO.

]]\SR1890\_Blue Dove Lane\EC\_Work\PlanShee

-JUL-2017 14:36

