

DF18311.2005102.PR

TIP NO

0.031 MILES

FED AID NO DF18311.2005102.PR

GRADING, DRAINAGE, PAVING, AND STRUCTURE

REPLACE BRIDGE NO. 262 ON SR 1317 (RICH HILL ROAD)

JAMES R VANNOY & SONS
CONSTRUCTION COMPANY INC
JEFFERSON, NC

ROADWAY ITEMS

0001	0000100000-N	800	MOBILIZATION	Lump Sum			54,080.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum			25,650.00
0003	0036000000-E	225	UNDERCUT EXCAVATION	450	CY	1.00	450.00
0004	0043000000-N	226	GRADING (226)	Lump Sum			155,678.00
0005	0050000000-E	226	SUPP CLEARING & GRUBBING	1	ACR	1.00	1.00
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	400	CY	1.00	400.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	400	SY	1.00	400.00
0008	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1A BRIDGE APPROACH FILL 10+80 -L-	Lump Sum			78,653.00
0009	0318000000-E	300	FND CONDIT MATL MINOR STRS	10	TON	101.28	1,012.80
0010	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	20	SY	5.36	107.20
0011	0335000000-E	305	*** DRAINAGE PIPE 8"	32	LF	83.26	2,664.32
0012	0335200000-E	305	15" DRAINAGE PIPE	48	LF	125.27	6,012.96
0013	0654000000-E	310	***X***CSP ARCH CULV ***** (112" X 75", 0.109")	26	LF	809.95	21,058.70
0014	0995000000-E	340	PIPE REMOVAL	60	LF	1.00	60.00
0015	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	200	TON	1.00	200.00
0016	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	300	SY	2.88	864.00
0017	1121000000-E	520	AGGREGATE BASE COURSE	96	TON	92.17	8,848.32
0018	1220000000-E	545	INCIDENTAL STONE BASE	50	TON	63.42	3,171.00
0019	1275000000-E	600	PRIME COAT	95	GAL	10.00	950.00
0020	1491000000-E	610	ASP CONC BASE CRS B25.0C	70	TON	169.83	11,888.10
0021	1519000000-E	610	ASP CONC SURF CRS S9.5B	90	TON	172.15	15,493.50
0022	1575000000-E	620	ASP FOR PLANT MIX	10	TON	684.52	6,845.20
0023	2022000000-E	815	SUBDRAIN EXCAVATION	45	CY	21.00	945.00
0024	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200	SY	4.00	800.00
0025	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34	CY	40.00	1,360.00
0026	2044000000-E	815	6" PERF SUBDRN PIPE	200	LF	3.53	706.00
0027	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	319.81	319.81
0028	2077000000-E	815	6" OUTLET PIPE	6	LF	12.04	72.24
0029	2286000000-N	840	MASNRY DRAINAGE STRUCT	1	EA	2,236.33	2,236.33
0030	3635000000-E	876	RIP RAP, CLASS II	27	TON	70.46	1,902.42
0031	3649000000-E	876	RIP RAP, CLASS B	20	TON	78.99	1,579.80
0032	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	100	SY	4.00	400.00
0033	4400000000-E	1110	WORK ZONE SIGNS (STAT)	48	SF	9.57	459.36
0034	4405000000-E	1110	WORK ZONE SIGNS (PORT)	96	SF	14.15	1,358.40
0035	4410000000-E	1110	WORK ZONE SIGNS (BARR)	36	SF	10.04	361.44
0036	4424500000-N	SP	TEMP PORT TRAF SIGNAL SYS	1	EA	33,297.66	33,297.66
0037	4430000000-N	1130	DRUMS	50	EA	24.89	1,244.50
0038	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	26.22	839.04
0039	4455000000-N	1150	FLAGGER	10	DAY	373.16	3,731.60

DF18311.2005102.PR

TIP NO

0.031 MILES

FED AID NO DF18311.2005102.PR

GRADING, DRAINAGE, PAVING, AND STRUCTURE

REPLACE BRIDGE NO. 262 ON SR 1317 (RICH HILL ROAD)

JAMES R VANNOY & SONS
CONSTRUCTION COMPANY INC
JEFFERSON, NC

0040	4516000000-N	1180	SKINNY DRUM	55	EA	23.84	1,311.20
0041	4810000000-E	1205	PAINT PVMT MARKINGS 4"	2,110	LF	0.60	1,266.00
0042	4835000000-E	1205	PAINT PVT MKG LINES 24"	50	LF	1.20	60.00
0043	4870000000-E	1205	LINE REMOVAL 24" WIDE	24	LF	2.39	57.36
0044	6000000000-E	1605	TEMPORARY SILT FENCE	320	LF	3.48	1,113.60
0045	6006000000-E	1610	EROS CONTRL STONE CL A	90	TON	69.42	6,247.80
0046	6009000000-E	1610	EROS CONTRL STONE CL B	95	TON	70.04	6,653.80
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	40	TON	78.28	3,131.20
0048	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	1,740.30	870.15
0049	6018000000-E	1620	SEED FOR TEMP SEEDING	100	LB	1.16	116.00
0050	6021000000-E	1620	FERT FOR TEMP SEEDING	0.5	TON	2,320.40	1,160.20
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	1.00	200.00
0052	6029000000-E	SP	SAFETY FENCE	260	LF	2.32	603.20
0053	6030000000-E	1630	SILT EXCAVATION	160	CY	1.00	160.00
0054	6036000000-E	1631	MATTING FOR EROS CONTROL	6,305	SY	2.32	14,627.60
0055	6037000000-E	1629	COIR FIBER MAT	100	SY	6.96	696.00
0056	6038000000-E	SP	PERM SOIL REINF MAT	65	SY	6.96	452.40
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	20	LF	4.64	92.80
0058	6071002000-E	1642	FLOCCULANT	15	LB	5.80	87.00
0059	6071012000-E	1642	COIR FIBER WATTLE	30	LF	11.60	348.00
0060	6071014000-E	1642	COIR FIBER WATTLE BARRIER	100	LF	11.60	1,160.00
0061	6084000000-E	1660	SEEDING AND MULCHING	0.5	ACR	3,480.60	1,740.30
0062	6087000000-E	1660	MOWING	0.5	ACR	1.18	0.59
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	1.16	58.00
0064	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,160.20	290.05
0065	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	1.16	58.00
0066	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	2,320.40	580.10
0067	6111000000-E	SP	IMPERVIOUS DIKE	175	LF	99.17	17,354.75
0068	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	58.01	580.10
0069	6117000000-N	1675	RESPONSE FOR EROS CONTROL	13	EA	58.01	754.13
0070	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	596.44	596.44
0071	6123000000-E	1670	REFORESTATION	1	ACR	3,480.59	3,480.59
0072	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	3	EA	596.00	1,788.00
STRUCTURE ITEMS							
0073	8035000000-N	402	REMV EXIST STR ***** BRG (402) (10+80.00 -L-)	Lump Sum			27,853.65
0074	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			1,624.28
0075	8121000000-N	412	UNCL STR EXCAV STA ***** (10+80.00 -L-)	Lump Sum			45,674.00
0076	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	117.7	CY	1,634.00	192,321.80

DF18311.2005102.PR

Nov 20, 2025

DK00441

TIP NO

0.031 MILES

FED AID NO DF18311.2005102.PR

GRADING, DRAINAGE, PAVING, AND STRUCTURE

REPLACE BRIDGE NO. 262 ON SR 1317 (RICH HILL ROAD)

JAMES R VANNOY & SONS
CONSTRUCTION COMPANY INC
JEFFERSON, NC

0077	8217000000-E	425	REINF STEEL (BRIDGE)	11,519	LB	2.15	24,765.85
0078	8280000000-E	440	STRUCTURAL STEEL 49,000.00 LB	Lump Sum			135,789.00
0079	8608000000-E	876	RIP RAP II (2'-0")	63	TON	76.36	4,810.68
0080	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	71	SY	3.62	257.02
0081	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			685.54
0082	8860000000-N	SP	GENERIC STRUCTURE ITEM (LS) TIMBER DECK SYSTEM	Lump Sum			107,543.00
0083	8867000000-E	SP	GENERIC STRUCTURE ITEM (LF) TIMBER BRIDGE RAIL SYSTEM	71	LF	375.89	26,688.19
CONTRACT TOTAL						TOTAL	1,081,810.07
ROADWAY ITEMS						SUB-TOTAL	513,797.06
STRUCTURE ITEMS						SUB-TOTAL	568,013.01

BIDDERS IN ORDER

CONTRACT TOTAL

JAMES R VANNOY & SONS CONSTRUCTION COMPANY INC

1

1,081,810.07