DocuSign Envelope ID: 451F98F2-9ACA-4E80-A16D-E15C5819C39F

6/2/99

PROJECT REFERENCE NO.	SHEET NO.
17BP.11.R.146	2A-2

ROADWAY DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 21122 ENGINEER MICHAEL T. MERRITT 10/21/2019

DocuSigned by: Michael T. Merritt

PAVEMENT DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 024964 ENGINEER JOSEPH T. HOLLAND 10/21/2019

DocuSigned by: Joseph T. Holland

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

FINAL PAVEMENT SCHEDULE

C1	2.5" S9.5B
C2	VAR. S9.5B
E1	4" B25.0C
J1	6" ABC
T	EARTH MATERIAL



TYPICAL SECTION NO. 3

USE TYPICAL SECTION NO. 3
–DR1– STA. 10+70.29 TO 10+80.90
–DR2– STA. 11+02.37 TO 11+10.89



TYPICAL SECTION NO. 4

USE TYPICAL SECTION NO. 4
–DR1– STA. 10+45.00 TO 10+70.29
–DR2– STA. 10+85.00 TO 11+02.37



TYPICAL SECTION NO. 5

USE TYPICAL SECTION NO. 5
–L– STA. 12+82.31 (BEGIN BRIDGE) TO 13+99.69 (END BRIDGE)

PLANS PREPARED BY :
RK&K
RUMMEL, KLEPPER & KAHL, LLP
900 RIDGEFIELD DRIVE SUITE 350
RALEIGH, NORTH CAROLINA 27609-3960
NC LICENSE NO. F-0112 • (919) 878-9560

10/28/2019
R:\Roadway\Proj\980020_Rdy_typ.dgn
default