



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

DANIEL H. JOHNSON
SECRETARY

March 13, 2026

Contract No.: DL00380
WBS No.: DF18312.2023011
FA Number: Helene
County: Cleveland
Description: Replacing Bridge No. 262 on SR 1529.

March 24, 2026 Letting

RE: Addendum #1 to Contract No. DL00380

To Whom It May Concern:

Reference is made to the proposal furnished to you on this project.

The following revisions have been made to the proposal and proposal item sheets:

Sheet No.	Revision
R-17	Special Provision entitled <i>Streambank Reestablishment</i> has been added to the proposal.
S-2	Pay Item No. 20 has been revised to <i>Select Material, Class VII</i> .
S-5	Pay Item No. 95 for <i>Type 1 Bridge Approach Fill, Sta. 16+16.07 (LS)</i> has been added.

Please download the revised proposal named 032426_DL00380_CLEV_PROPADD1 from the Division 12 Bid Page and discard any previous versions. You are also required to download and apply the addendum file when bidding. The electronic bid file and addendum file are available on the Division 12 Bid Page located at <https://connect.ncdot.gov/letting/Pages/Division12Letting> or from our current electronic bidding provider (Bidx) through their website.

The contract will be prepared accordingly


Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION 12
PO BOX 47
SHELBY, NC 28151-0047

Telephone: (980) 552-4200
Fax: (704) 480-5401
Courier: 06-53-03
Website: www.ncdot.gov

Location:
1710 E. MARION STREET
SHELBY, NC 28152

If you have any questions please contact Greg Brittain at (980) 552-4222.

Sincerely,

A handwritten signature in black ink that reads "Mark E. Stafford". The signature is written in a cursive style with a large, prominent "M" and "S".

Mark E. Stafford, P.E.
Division Engineer

MES/ghb

Attachments

Cc: Cole Gurley, PE, Deputy Division Engineer
Rodney Gantt, Division Construction Engineer
Bryan Sowell, PE, Division Project Development Engineer
Christian Listoe, PE, Asst. Division Construction Engineer

STREAMBANK REESTABLISHMENT

Description

The Contractor shall construct and reestablish the streambank areas at the locations shown on the plans, in accordance with the details, as directed by the Engineer using coir fiber matting, earthen material and Class VII Select Material.

Materials

All materials shall meet the requirements of Division 10 of the *Standard Specifications*.

Payment

Coir Fiber Mat will be measured and paid in accordance with Section 1629 of the *Standard Specifications*.

Select Material, Class VII will be measured and paid in tons, in accordance with Article 106-7 of the *Standard Specifications*, for all material accepted and placed.

The contract unit prices for *Lump Sum Grading, Coir Fiber Mat* and *Select Material, Class VII* will be considered full compensation for all labor, equipment and materials necessary to complete the work of Streambank Reestablishment.

Pay Item

Select Material, Class VII

Pay Unit

Ton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	225 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	98 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0010	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	50 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	36 LF		
0012	0335600000-E	305	36" DRAINAGE PIPE	40 LF		
0013	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (54")	56 LF		
0014	0995000000-E	340	PIPE REMOVAL	82 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	75 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	500 TON		

ITEMIZED PROPOSAL FOR CONTRACT NO. DL00380

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	435 TON		
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	50 TON		
0020	0314000000-E	SP	SELECT MATERIAL, CLASS ***** CLASS VII	500 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0022	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	100 SY		
0023	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	16.8 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0025	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE	6 LF		
0027	2220000000-E	838	REINFORCED ENDWALLS	5 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0029	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		
0031	3030000000-E	862	STEEL BEAM GUARDRAIL	87.5 LF		
0032	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	87.5 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-83 SHOP CURVED)	1 EA		

ITEMIZED PROPOSAL FOR CONTRACT NO. DL00380

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III SHOP CURVED)	2 EA		
0036	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	2 EA		
0037	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	1 EA		
0038	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	2 EA		
0039	3628000000-E	876	RIP RAP, CLASS I	76 TON		
0040	3635000000-E	876	RIP RAP, CLASS II	15 TON		
0041	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,135 SY		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	363 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	131 SF		
0044	4430000000-N	1130	DRUMS	20 EA		
0045	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0046	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,800 LF		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	1,050 LF		
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180 TON		
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	375 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		

ITEMIZED PROPOSAL FOR CONTRACT NO. DL00380

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0055	6029000000-E	SP	SAFETY FENCE	260 LF		
0056	6030000000-E	1630	SILT EXCAVATION	280 CY		
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	800 SY		
0058	6037000000-E	1629	COIR FIBER MAT	350 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	280 LF		
0060	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	105 SY		
0061	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0062	6071002000-E	1642	FLOCCULANT	45 LB		
0063	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0064	6087000000-E	1660	MOWING	0.5 ACR		
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6111000000-E	SP	IMPERVIOUS DIKE	190 LF		
0070	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0071	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	25 EA		
0072	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		
0073	6132000000-N	SP	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT	3 EA		
0095	0248000000-N	SP	GENERIC GRADING ITEM TYPE 1 BRIDGE APPROACH FILL, STA. 16+16.07	Lump Sum	L.S.	
STRUCTURE ITEMS						
0074	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+15 -L-)	Lump Sum	L.S.	
0075	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0076	8096000000-E	450	PILE EXCAVATION IN SOIL	63.8 LF		
0077	8097000000-E	450	PILE EXCAVATION NOT IN SOIL	24.5 LF		
0078	8105540000-E	411	3'-6" DIA DRILLED PIERS IN SOIL	90.8 LF		
0079	8105640000-E	411	3'-6" DIA DRILLED PIERS NOT IN SOIL	62.2 LF		
0080	8111400000-E	411	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	63.3 LF		
0081	8115000000-N	411	CSL TESTING	1 EA		
0082	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+15 -L-)	Lump Sum	L.S.	
0083	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	106.1 CY		

ITEMIZED PROPOSAL FOR CONTRACT NO. DL00380

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0084	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+15 -L-)	Lump Sum	L.S.	
0085	8217000000-E	425	REINFORCING STEEL (BRIDGE)	29,998 LB		
0086	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,861 LB		
0087	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12X53)	14 EA		
0088	8364000000-E	450	HP 12 X 53 STEEL PILES	530 LF		
0089	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	320.29 LF		
0090	8590000000-E	876	RIP RAP, CLASS ** (II)	90 TON		
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	185 TON		
0092	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	300 SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,920 LF		

1405/Mar13/Q52826.94/D429064282000/E95

Total Amount Of Bid For Entire Project :