



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

July 3, 2017

Contract No.: DL00148
WBS No.: 44034.3.1
Location: NC 279 (S. New Hope Rd.)
County: Gaston

RE: Addendum No. 2

To Whom It May Concern:

This letter is to advise all prospective bidders of the following changes to Contract No. DL00148. The following changes/additions/deletions/clarifications have been made.

Inquiry:

- Q: Will night work be permitted/required because of the flagging restrictions?
A: Night work will be permitted but is not a requirement. The TMP is designed to allow the maximum amount of work without flagging or full lane closures.

Pay Items:

- Pay Items #116 thru # 123 have been added to coincide with the pay items shown in the TMP plans on sheet TMP-1A.

If submitting a paper bid please replace the original bid form with the revised bid form prior to submitting your bid. Also the receipt of Addenda #1 and #2 must be acknowledged on the page entitled "Addendum(s)" included in the contract. Any paper bids received not containing the revised bid form and the executed addendum acknowledgement shall be considered irregular and will not be considered for award.

If bidding electronically then you must apply the addendum **files**, which can be found on the Division 12 website at www.ncdot.gov/doh/operations/division12/bids under the July 11, 2017 letting folder, to the original EBS file when placing your bid. To apply the addendum files, open the original EBS file using Expedite Software and select Load Amendment from the File Menu. Each addendum must be loaded separately before saving and submitting the bid. Expedite will not allow the bid to be submitted unless each addendum is acknowledged.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION 12
PO BOX 47
SHELBY, NC 28151-0047

Telephone: (704) 480-9020
Fax: (704) 480-5401
Courier: 06-53-03
Website: www.ncdot.gov

Location:
1710 E. MARION STREET
SHELBY, NC 28152

Please contact Greg Brittain at 704-480-9022 with any questions.

Sincerely,

A handwritten signature in black ink that reads "Mark E. Stafford". The signature is written in a cursive style with a large, stylized initial "M".

Mark Stafford, P.E.
Division Engineer

gb

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0141000000-E	240	BERM DITCH CONSTRUCTION	130 LF		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	300 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	900 SY		
0008	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	36 LF		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,444 LF		
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	60 LF		
0011	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	80 LF		
0012	0995000000-E	340	PIPE REMOVAL	670 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	810 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0015	1275000000-E	600	PRIME COAT	100 GAL		
0016	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5")	300 SY		
0017	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	14,000 SY		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1.5")	500 SY		
0019	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (1.5" TO 3")	160 SY		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,900 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,100 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,900 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	470 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	110 TON		
0025	2000000000-N	806	RIGHT OF WAY MARKERS	30 EA		
0026	2253000000-E	840	PIPE COLLARS	1.6 CY		
0027	2264000000-E	840	PIPE PLUGS	0.2 CY		
0028	2275000000-E	SP	FLOWABLE FILL	10 CY		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	44 EA		
0030	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	11 LF		
0031	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	5 EA		
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0033	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	7 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	12 EA		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	11 EA		
0036	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0037	2418000000-E	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	51 LF		
0038	2535000000-E	846	***X *** CONCRETE CURB (9"X12")	100 LF		
0039	2538000000-E	846	**!.*** CONCRETE CURB & GUTTER (2'-0")	310 LF		
0040	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	100 LF		
0041	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	4,500 LF		
0042	2580000000-E	846	CONCRETE VALLEY GUTTER	140 LF		
0043	2591000000-E	848	4" CONCRETE SIDEWALK	2,000 SY		
0044	2600000000-N	SP	RETROFIT EXISTING CURB RAMP	4 EA		
0045	2605000000-N	848	CONCRETE CURB RAMP	14 EA		
0046	2612000000-E	848	6" CONCRETE DRIVEWAY	1,200 SY		
0047	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	26 SY		
0048	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	9 EA		
0049	2830000000-N	858	ADJUSTMENT OF MANHOLES	19 EA		
0050	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	18 EA		
0051	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC Black Vinyl Coated Chain Link (48")	110 LF		
0052	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	12 EA		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	3 EA		
0054	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,315 SY		
0055	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	170 LF		
0056	4102000000-N	904	SIGN ERECTION, TYPE E	9 EA		
0057	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
0058	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (TYPE D)	1 EA		
0059	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	8 EA		
0060	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	240 SF		
0061	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0062	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	9,539 LF		
0063	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	375 LF		
0064	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	400 LF		
0065	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	260 LF		
0066	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	43 EA		
0067	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	185 EA		
0068	5325600000-E	1510	6" WATER LINE	100 LF		
0069	5326200000-E	1510	12" WATER LINE	100 LF		
0070	5648000000-N	1515	RELOCATE WATER METER	19 EA		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	5672000000-N	1515	RELOCATE FIRE HYDRANT	5		EA
0072	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	4		EA
0073	6000000000-E	1605	TEMPORARY SILT FENCE	4,500		LF
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	550		TON
0075	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120		TON
0076	6012000000-E	1610	SEDIMENT CONTROL STONE	475		TON
0077	6015000000-E	1615	TEMPORARY MULCHING	1		ACR
0078	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100		LB
0079	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5		TON
0080	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200		LF
0081	6029000000-E	SP	SAFETY FENCE	100		LF
0082	6030000000-E	1630	SILT EXCAVATION	350		CY
0083	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,610		SY
0084	6042000000-E	1632	1/4" HARDWARE CLOTH	1,660		LF
0085	6071010000-E	SP	WATTLE	250		LF
0086	6071013000-E	SP	WATTLE BARRIER	124		LF
0087	6071020000-E	SP	POLYACRYLAMIDE (PAM)	40		LB
0088	6084000000-E	1660	SEEDING & MULCHING	3		ACR
0089	6087000000-E	1660	MOWING	3		ACR
0090	6090000000-E	1661	SEED FOR REPAIR SEEDING	50		LB

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0092	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0093	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75	TON	
0094	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0095	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13	EA	
0096	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (CONCRETE WASHOUT STRUCTURE)	3	EA	
0097	7060000000-E	1705	SIGNAL CABLE	490	LF	
0098	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	8	EA	
0099	7264000000-E	1710	MESSENGER CABLE (3/8")	240	LF	
0100	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2"))	200	LF	
0101	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	5	EA	
0102	7360000000-N	1720	WOOD POLE	1	EA	
0103	7372000000-N	1721	GUY ASSEMBLY	4	EA	
0104	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,710	LF	
0105	7456000000-E	1726	LEAD-IN CABLE (***** (14-2))	1,985	LF	
0106	7481000000-N	SP	SITE SURVEY	2	EA	
0107	7481200000-N	SP	LUMINAIRE ARM FOR VIDEO SYSTEM	4	EA	
0108	7481220000-N	SP	CAMERA WITH INTERNAL LOOP EMU- LATOR PROCESSING UNIT	4	EA	
0109	7552000000-N	1731	INTERCONNECT CENTER	1	EA	

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	7576000000-N	SP	METAL STRAIN SIGNAL POLE	1 EA		
0111	7613000000-N	SP	SOIL TEST	1 EA		
0112	7614100000-E	SP	DRILLED PIER FOUNDATION	18.5 CY		
0113	7720000000-N	1751	CONTROLLER WITH CABINET (TYPE 170E, BASE MOUNTED)	1 EA		
0114	7744000000-N	1751	DETECTOR CARD (TYPE 170)	5 EA		
0115	8802040000-E	SP	CIP GRAVITY RETAINING WALLS	800 SF		
0116	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,500 LF		
0117	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	225 LF		
0118	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	125 LF		
0119	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	22,500 LF		
0120	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	225 LF		
0121	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	125 LF		
0122	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	30 EA		
0123	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	45 EA		

1322/Jul03/Q119070.8/D511043503000/E123

Total Amount Of Bid For Entire Project :

CONTRACTOR _____ Federal ID No. _____

ADDRESS _____ Contr. License No. _____

_____ Telephone No. _____

Vendor Number _____

Authorized Agent _____ Title _____

Signature _____ Date _____

Witness _____ Title _____

Signature _____ Date _____

