

BID FORM

GARDNER WEBB UNIVERSITY

STADIUM DRIVE IMPROVEMENTS

WBS ELEMENT: 36333.3.FD11, 43943, 12CR.20231.18

DESCRIPTION: STADIUM DRIVE ROAD IMPROVEMENTS

COUNTY: CLEVELAND

LINE #	ITEM NUMBER	SECT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT BID
1.	0000100000-N	800	MOBILIZATION	1	LS		
2.	0000400000-N	810	CONSTRUCTION SURVEYING	1	LS		
3.	0043000000-N	SP	GRADING	1	LS		
4.	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	190	TON		
5.	0320000000-E	300	FOUNDATION CONDITIONING	580	SY		
6.	0372000000-E	310	18" RCP PIPE CULVERTS, CLASS III	1,000	LF		
7.	0378000000-E	310	24" RCP PIPE CULVERTS, CLASS III	580	LF		
8.	0390000000-E	310	36" RCP PIPE CULVERTS, CLASS III	140	LF		
9.	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	560	TON		
10.	1498000000-E	610	ASPHALT CONC BASE COURSE, TYPE I19.0B	1,450	TON		
11.	1519000000-E	610	ASPHALT CONC BASE COURSE, TYPE S9.5B	775	TON		
12.	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	145	TON		
13.	2264000000-E	840	PIPE PLUGS	10	CY		
14.	2275000000-E	SP	FLOWABLE FILL	90	CY		
15.	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	22	EA		
16.	2374000000-N	840	FRAME WITH GRATE, & HOOD, STD. 840.03, TYPE E	2	EA		
17.	2374000000-N	840	FRAME WITH GRATE, & HOOD, STD. 840.03, TYPE F	9	EA		
18.	2374000000-N	840	FRAME WITH GRATE, & HOOD, STD. 840.03, TYPE G	10	EA		
19.	2472000000-N	840	GENERIC DRAINAGE ITEM (OPEN THROAT INLET STD, 840.05)	1	EA		
20.	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	10,461	LF		
21.	2591000000-E	848	4" CONCRETE SIDEWALK	2,900	SY		
22.	2605000000-N	848	CONCRETE CURB RAMP	22	EA		
23.	2759000000-N	SP	GENERIC PAVING ITEM (MATERIALS AND LABOR TO REMOVE SPEED BUMPS)	3	EA		
24.	3030000000-E	862	STEEL BM GUARDRAIL	325	LF		
25.	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2	EA		
26.	3360000000-E	863	REMOVE EXISTING GUARDRAIL	320	LF		
27.	3536000000-E	866	WOVEN WIRE FENCE 48" FABRIC	1,000	LF		
28.	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	83	EA		
29.	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	400	SF		
30.	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	150	SF		

31.	4445000000-E	1145	BARRICADES (TYPE III)	64	LF		
32.	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,000	LF		
33.	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) (STD. DETAIL 1205.08)	6	EA		
34.	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	13,700	LF		
35.	5325800000-E	1510	8" WATER LINE (C900 PVC DR-18)	120	LF		
36.	5546000000-E	1515	8" VALVE	7	EA		
37.	5648000000-N	1515	RELOCATE WATER METER (RELOCATE METER VAULT STA. 50+60)	1	EA		
38.	5672000000-N	1515	RELOCATE FIRE HYDRANT	4	EA		
39.	6000000000-E	1605	TEMPORARY SILT FENCE	8,000	LF		
40.	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200	TON		
41.	6012000000-E	1610	SEDIMENT CONTROL STONE	65	TON		
42.	6015000000-E	1615	TEMPORARY MULCHING	1	ACR		
43.	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	500	LB		
44.	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.50	TON		
45.	6030000000-E	1630	SILT EXCAVATION	1,000	CY		
46.	6036000000-E	1631	MATTING FOR EROSION CONTROL	10,000	SY		
47.	6084000000-E	1660	SEEDING & MULCHING	4	ACR		
48.	6090000000-E	1661	SEED FOR REPAIR SEEDING	200	LB		
49.	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.50	TON		
50.	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	500	LB		
51.	6108000000-E	1665	FERTILIZER FOR TOP DRESSING	0.50	TON		
52.	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15	EA		

CONTRACTOR _____

NOTE: CONTRACT QUANTITIES ARE APPROXIMATE AND USED FOR DETERMINING THE LOWEST RESPONSIBLE BIDDER ONLY. NO MINIMUM OR MAXIMUM AMOUNT OF WORK IS GUARANTEED UNDER THIS CONTRACT.

TOTAL BID FOR PROJECT: _____

CONTRACTOR _____

ADDRESS _____

PHONE NO. _____

Federal Identification Number _____ Contractors License Number _____

Authorized Agent _____ Title _____

Signature _____ Date _____

Witness _____ Title _____

Signature _____ Date _____

Corporate Seal

