

STATE OF NORTH CAROLINA  
 DIVISION OF HIGHWAYS

FOR BIDDING PURPOSES ONLY

**SUMMARY OF QUANTITIES**

Line Item	Des	Sec No.	Description	Quantity	Unit
0000100000-N		800	MOBILIZATION	1	LS
0000400000-N		801	CONSTRUCTION SURVEYING	1	LS
0000900000-N		SP	GENERIC MISCELLANEOUS ITEM - BMP SAND FILTER	1	LS
0043000000-N		226	COMPREHENSIVE GRADING	1	LS
0036000000-E		225	UNDERCUT EXCAVATION	200	CY
0196000000-E		270	GEOTEXTILE SOIL STABILIZATION	700	SY
0318000000-E		300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	6	TN
0360000000-E		310	12" RC PIPE CULV III	71	LF
0366000000-E		310	15" RC PIPE CULV III	163	LF
0372000000-E		310	18" RC PIPE CULV III	10	LF
0414000000-E		310	60" RC PIPE CULV III	107	LF
0453000000-E		310	18" PIPE END SECTION	1	EA
1489000000-E		610	ASP CONC BASE CRS B25.0B	1350	TON
1498000000-E		610	ASP CONC INTR CRS I19.0B	910	TON
1519000000-E		610	ASP CONC SURF CRS S9.5B	670	TON
1575000000-E		620	ASP FOR PLANT MIX	145	TON
2209000000-E		838	ENDWALLS	11.2	CY
2286000000-N		840	MASNRY DRAINAGE STRUCT	6	EA
2308000000-E		840	MASNRY DRAINAGE STRUCT	10	LF
2374000000-N		840	FRAME-GRT-HD 840.03**	6	EA
2549000000-E		846	2'-6" CONC CURB & GUTTER	2265	LF
3628000000-E		876	RIP RAP, CLASS I	25	TON
3635000000-E		876	RIP RAP, CLASS II	53	TON
3656000000-E		876	GEOTEXTILE FOR DRAINAGE	170	SY
3691000000-N		SP	SPECIAL SILT CHECK	13	EA
4399000000-N		1105	TEMP TRAFFIC CONTROL	1	LS
4410000000-E		1110	WORK ZONE SIGNS (BARR)	20	SF
4445000000-E		1145	BARRICADES (TYPE III)	32	LF
6000000000-E		1605	TEMPORARY SILT FENCE	2995	LF
6006000000-E		1610	EROS CONTRL STONE CL A	35	TON
6012000000-E		1610	SEDIMENT CONTROL STONE	10	TON
6015000000-E		1610	TEMPORARY MULCHING	3.5	ACR
6018000000-E		1620	SEED FOR TEMP SEEDING	150	LB
6021000000-E		1622	FERT FOR TEMP SEEDING	0.75	TON
6024000000-E		1622	TEMPORARY SLOPE DRAINS	200	LF
6029000000-E		SP	SAFETY FENCE	100	LF
6030000000-E		1630	SILT EXCAVATION	140	CY
6036000000-E		1631	MATTING FOR EROS CONTROL	11565	SY
6037000000-E		SP	COIR FIBER MAT	490	SY
6042000000-E		1632	1/4" HARDWARE CLOTH	35	LF
6084000000-E		1660	SEEDING AND MULCHING	2	ACR
6084000000-E		1660	NATIVE GRASS SEEDING AND MULCHING	0.55	ACR
6090000000-E		1661	SEED FOR REPAIR SEEDING	50	LB
6093000000-E		1661	FERT FOR REPAIR SEEDING	0.25	TON
6096000000-E		1662	SEED FOR SUPP SEEDING	100	LB
6108000000-E		1665	FERTILIZER TOPDRESSING	3	TON
6111000000-E		SP	IMPERVIOUS DIKE	170	LF
6117000000-N		SP	RESPONSE FOR EROSION CONTROL	7	EA

3:45:46 PM  
 P:\Projects\13-0210-000-Proposed\_Road.at.Plato.Lee.Rd.in.Shelby\Roadway\Proj\43-798\_Rdu.sht\_3.dgn  
 10/2/2013