

**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**


**This file or an individual page
shall not be considered a certified document.**

09/08/19

TIP PROJECT: 17BP.12.R.43

CONTRACT: DL00127

See Sheet 1-A For Index of Sheets
See Sheet 1-B For Conventional Symbols




STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
CLEVELAND COUNTY


**LOCATION: STRUCTURE NO. 275 OVER KNOB CREEK
ON CARPENTER HOYLE RD. SR 1603**

TYPE OF WORK: GRADING, DRAINAGE, PAVING, & STRUCTURE

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.12.R.43	1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
17BP.12.R.43		PE, RW, UTILITY & CONST.	



**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**



DESIGN DATA

ADT 2011 = 140 vpd
V = 55 MPH
FUNC CLASS = R. LOCAL
SUBREGIONAL TIER

PROJECT LENGTH

LENGTH ROADWAY PROJECT 17BP.12.R.43	=	0.107 MI
LENGTH STRUCTURE PROJECT 17BP.12.R.43	=	0.025 MI
TOTAL LENGTH OF PROJECT 17BP.12.R.43	=	0.132 MI

NCDOT CONTACT: STEVE RACKLEY, PE
DIVISION 12

Prepared In the Office of:
Michael Baker International
2012 STANDARD SPECIFICATIONS

Michael Baker Engineering, Inc.
8000 Regency Parkway, Suite 600
Cary, NC 27518
Professional Corporation License Number: F-1084

RIGHT OF WAY DATE: TODD H. BUCKNER, PE
JULY 22, 2015
PROJECT ENGINEER


LETTING DATE: WARREN JOHNSON
NOVEMBER 28, 2017
PROJECT DESIGN ENGINEER


HYDRAULICS ENGINEER

DocuSigned by:
Steven D. Swygger
829900704CE54DA
SIGNATURE: *Steven D. Swygger*
10/26/2017

ROADWAY DESIGN ENGINEER

DocuSigned by:
Todd H. Buckner
198701180778455
SIGNATURE: *Todd H. Buckner*
10/26/2017





**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

INDEX OF SHEETS

GENERAL NOTES

STANDARD DRAWINGS

SHEET NUMBER	SHEET
1	TITLE SHEET
1A-1	INDEX OF SHEETS, GENERAL NOTES, AND STANDARD DRAWINGS
1B-1	CONVENTIONAL PLAN SHEET SYMBOLS
1C-1	SURVEY CONTROL SHEET
2A-1	TYPICAL SECTIONS
2C-1 THRU 2C-3	GUARDRAIL PLACEMENT DETAILS
2C-4 THRU 2C-6	GUARDRAIL INSTALLATION DETAILS
2C-7 THRU 2C-8	GUARDRAIL ANCHOR UNIT DETAILS
3A-1	SUMMARY OF QUANTITIES
4	ROADWAY PLAN AND PROFILE SHEET
TMP-1 THRU TMP-3	TRANSPORTATION MANAGEMENT PLANS
PMP-1	PAVEMENT MARKING PLANS
EC-1 THRU EC-5	EROSION CONTROL PLANS
UO-1 THRU UO-2	UTILITIES BY OTHERS PLANS
X-1	CROSS SECTION SUMMARY
X-2 THRU X-4	CROSS SECTIONS
S-1 THRU S-20	STRUCTURE PLANS
SN	STRUCTURE STANDARD NOTES

GENERAL NOTES: 2012 SPECIFICATIONS
EFFECTIVE: 01-17-12
REVISED: 07/30/12

**GRADE LINE:
GRADING AND SURFACING:**
THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:
CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION:
ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:
ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

GUARDRAIL:
THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

SUBSURFACE PLANS:
NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

END BENTS:
THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:
UTILITY OWNERS ON THIS PROJECT ARE DUKE PROGRESS AND AT&T.
ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

RIGHT-OF-WAY MARKERS:
ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	Method of Clearing - Method II
225.02	Guide for Grading Subgrade - Secondary and Local
225.04	Method of Obtaining Superlevation - Two Lane Pavement
DIVISION 3 - PIPE CULVERTS	
300.01	Method of Pipe Installation
DIVISION 4 - MAJOR STRUCTURES	
422.11	Reinforced Bridge Approach Fills - Sub Regional Tier
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS	
560.01	Method of Shoulder Construction - High Side of Superelevated Curve - Method I
DIVISION 8 - INCIDENTALS	
838.27	Reinforced Concrete Endwall - for Single 60" Pipe 90 Skew
840.00	Concrete Base Pad for Drainage Structures
840.25	Anchorage for Frames - Brick or Concrete or Precast
840.29	Frames and Narrow Slot Flat Grates
840.35	Traffic Bearing Grated Drop Inlet - for Cast Iron Double Frame and Grates
840.46	Traffic Bearing Precast Drainage Structure
840.66	Drainage Structure Steps
846.01	Concrete Curb, Gutter and Curb & Gutter
846.04	Drop Inlet Installation in Shoulder Berm Gutter
866.02	Woven Wire Fence - with Wood Post
876.01	Rip Rap in Channels
876.02	Guide for Rip Rap at Pipe Outlets

8/17/99

29-SEP-2017 08:43
F:\Projects\17BP.12.R.43\Roadway\Proj\22-0275-RDY_PSH_01A.dgn

STATE OF NORTH CAROLINA, DIVISION OF HIGHWAYS

CONVENTIONAL PLAN SHEET SYMBOLS

Note: Not to Scale *S.U.E. = *Subsurface Utility Engineering*

BOUNDARIES AND PROPERTY:

State Line	
County Line	
Township Line	
City Line	
Reservation Line	
Property Line	
Existing Iron Pin	
Property Corner	
Property Monument	
Parcel/Sequence Number	
Existing Fence Line	
Proposed Woven Wire Fence	
Proposed Chain Link Fence	
Proposed Barbed Wire Fence	
Existing Wetland Boundary	
Proposed Wetland Boundary	
Existing Endangered Animal Boundary	
Existing Endangered Plant Boundary	
Existing Historic Property Boundary	
Known Contamination Area: Soil	
Potential Contamination Area: Soil	
Known Contamination Area: Water	
Potential Contamination Area: Water	
Contaminated Site: Known or Potential	

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	
Sign	
Well	
Small Mine	
Foundation	
Area Outline	
Cemetery	
Building	
School	
Church	
Dam	

HYDROLOGY:

Stream or Body of Water	
Hydro, Pool or Reservoir	
Jurisdictional Stream	
Buffer Zone 1	
Buffer Zone 2	
Flow Arrow	
Disappearing Stream	
Spring	
Wetland	
Proposed Lateral, Tail, Head Ditch	
False Sump	

RAILROADS:

Standard Gauge	
RR Signal Milepost	
Switch	
RR Abandoned	
RR Dismantled	

RIGHT OF WAY:

Baseline Control Point	
Existing Right of Way Marker	
Existing Right of Way Line	
Proposed Right of Way Line	
Proposed Right of Way Line with Iron Pin and Cap Marker	
Proposed Right of Way Line with Concrete or Granite RW Marker	
Proposed Control of Access Line with Concrete CA Marker	
Existing Control of Access	
Proposed Control of Access	
Existing Easement Line	
Proposed Temporary Construction Easement	
Proposed Temporary Drainage Easement	
Proposed Permanent Drainage Easement	
Proposed Permanent Drainage / Utility Easement	
Proposed Permanent Utility Easement	
Proposed Temporary Utility Easement	
Proposed Aerial Utility Easement	
Proposed Permanent Easement with Iron Pin and Cap Marker	

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	
Existing Curb	
Proposed Slope Stakes Cut	
Proposed Slope Stakes Fill	
Proposed Curb Ramp	
Existing Metal Guardrail	
Proposed Guardrail	
Existing Cable Guiderail	
Proposed Cable Guiderail	
Equality Symbol	
Pavement Removal	

VEGETATION:

Single Tree	
Single Shrub	
Hedge	
Woods Line	

Orchard	
Vineyard	

EXISTING STRUCTURES:

MAJOR:	
Bridge, Tunnel or Box Culvert	
Bridge Wing Wall, Head Wall and End Wall	
MINOR:	
Head and End Wall	
Pipe Culvert	
Footbridge	
Drainage Box: Catch Basin, DI or JB	
Paved Ditch Gutter	
Storm Sewer Manhole	
Storm Sewer	

UTILITIES:

POWER:	
Existing Power Pole	
Proposed Power Pole	
Existing Joint Use Pole	
Proposed Joint Use Pole	
Power Manhole	
Power Line Tower	
Power Transformer	
U/G Power Cable Hand Hole	
H-Frame Pole	
U/G Power Line LOS B (S.U.E.*)	
U/G Power Line LOS C (S.U.E.*)	
U/G Power Line LOS D (S.U.E.*)	

TELEPHONE:

Existing Telephone Pole	
Proposed Telephone Pole	
Telephone Manhole	
Telephone Pedestal	
Telephone Cell Tower	
U/G Telephone Cable Hand Hole	
U/G Telephone Cable LOS B (S.U.E.*)	
U/G Telephone Cable LOS C (S.U.E.*)	
U/G Telephone Cable LOS D (S.U.E.*)	
U/G Telephone Conduit LOS B (S.U.E.*)	
U/G Telephone Conduit LOS C (S.U.E.*)	
U/G Telephone Conduit LOS D (S.U.E.*)	
U/G Fiber Optics Cable LOS B (S.U.E.*)	
U/G Fiber Optics Cable LOS C (S.U.E.*)	
U/G Fiber Optics Cable LOS D (S.U.E.*)	

WATER:

Water Manhole	
Water Meter	
Water Valve	
Water Hydrant	
U/G Water Line LOS B (S.U.E.*)	
U/G Water Line LOS C (S.U.E.*)	
U/G Water Line LOS D (S.U.E.*)	
Above Ground Water Line	

TV:

TV Pedestal	
TV Tower	
U/G TV Cable Hand Hole	
U/G TV Cable LOS B (S.U.E.*)	
U/G TV Cable LOS C (S.U.E.*)	
U/G TV Cable LOS D (S.U.E.*)	
U/G Fiber Optic Cable LOS B (S.U.E.*)	
U/G Fiber Optic Cable LOS C (S.U.E.*)	
U/G Fiber Optic Cable LOS D (S.U.E.*)	

GAS:

Gas Valve	
Gas Meter	
U/G Gas Line LOS B (S.U.E.*)	
U/G Gas Line LOS C (S.U.E.*)	
U/G Gas Line LOS D (S.U.E.*)	
Above Ground Gas Line	


SANITARY SEWER:

Sanitary Sewer Manhole	
Sanitary Sewer Cleanout	
U/G Sanitary Sewer Line	
Above Ground Sanitary Sewer	
SS Forced Main Line LOS B (S.U.E.*)	
SS Forced Main Line LOS C (S.U.E.*)	
SS Forced Main Line LOS D (S.U.E.*)	

MISCELLANEOUS:

Utility Pole	
Utility Pole with Base	
Utility Located Object	
Utility Traffic Signal Box	
Utility Unknown U/G Line LOS B (S.U.E.*)	
U/G Tank; Water, Gas, Oil	
Underground Storage Tank, Approx. Loc.	
A/G Tank; Water, Gas, Oil	
Geoenvironmental Boring	
U/G Test Hole LOS A (S.U.E.*)	
Abandoned According to Utility Records	
End of Information	

SURVEY CONTROL SHEET



DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCDOT FOR MONUMENT "22-0275-1"

WITH NAD 83/NA 2011 STATE PLANE GRID COORDINATES OF
 NORTHING: 653872.096(ft) EASTING: 1245371.786(ft)
 ELEVATION: 935.48(ft)

THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.9998438799

THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "22-0275-1" TO -L- STATION 10+00.00 IS
 N 16°25'24.8" E 234.163'

ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES
 VERTICAL DATUM USED IS NAVD 88

BL	POINT	DESC.	NORTH	EAST	ELEVATION	L STATION	OFFSET
1	22-0275-1		653872.0960	1245371.7860	935.48	OUTSIDE PROJECT LIMITS	
2	22-0275-2		654618.1400	1245551.7080	923.30	15+34.15	14.88 LT
3	22-0275-3		655122.4678	1245727.0213	936.52	OUTSIDE PROJECT LIMITS	

 BM1 ELEVATION = 935.48
 N 653872 E 1245372
 L STATION 10+00
 S 16°25'24.8" W DIST 234.16'
 ALUMINUM CAP SET FLUSH WITH THE GROUND
 STAMPED 22-0275-1 ON VIC RANDAL RD.

 BM2 ELEVATION = 934.30
 N 654799 E 1245730
 L STATION 17+57 105 RIGHT
 R/R SPIKE SET IN BASE OF 28' HICKORY

NOTES:

- THE CONTROL DATA FOR THIS PROJECT CAN BE FOUND ELECTRONICALLY BY SELECTING PROJECT CONTROL DATA AT:
[HTTPS://CONNECT.NCDOT.GOV/RESOURCES/LOCATION](https://connect.ncdot.gov/resources/location)
 THE FILES TO BE FOUND ARE AS FOLLOWS:
 220275_LS_CONTROL.TXT
 220275_LS_LOCAL.TXT
- SITE CALIBRATION INFORMATION HAS NOT BEEN PROVIDED FOR THIS PROJECT. IF FURTHER INFORMATION IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
- PROJECT CONTROL ESTABLISHED USING GLOBAL POSITIONING SYSTEM, UTILIZING THE NCGS RTN SYSTEM (VRS).
 MONUMENTS USED OR SET FOR PROJECT CONTROL BY THE NCDOT LOCATION AND SURVEYS UNIT:
 ● INDICATES GEODETIC CONTROL MONUMENTS FOR HORIZONTAL CONTROL
 ■ INDICATES BASELINE MONUMENTS FOR HORIZONTAL PROJECT CONTROL
 ✕ INDICATES BENCHMARKS FOR VERTICAL CONTROL

ROW MARKER IRON PIN AND CAP				
ALIGN	STATION	OFFSET	NORTH	EAST
L	11+00.00	-45.00	654203.43096	1245404.58751
L	11+00.00	-30.15	654200.99449	1245419.23970
L	11+00.00	45.00	654188.66784	1245493.36842
L	11+00.00	29.89	654191.14670	1245478.46133
L	12+13.97	-45.00	654319.86225	1245431.48810
L	12+13.97	45.00	654294.18370	1245517.74708
L	15+88.15	-45.00	654678.48990	1245538.24844
L	15+88.15	45.00	654652.81135	1245624.50742
L	17+84.96	-45.00	654866.91768	1245592.99864
L	17+84.96	-30.00	654862.82577	1245607.43408
L	17+84.96	45.00	654842.37309	1245679.58711
L	17+84.96	30.00	654846.46271	1245665.15973

L			
TYPE	STATION	NORTH	EAST
PC	10+00.00	654096.7047	1245437.9922
PT	12+13.97	654307.0230	1245474.6176
PC	15+88.15	654665.6506	1245581.3779
PT	17+84.96	654854.6454	1245636.2929
POT	19+00.51	654965.8155	1245667.8054

PERMANENT EASEMENT MARKER IRON PIN AND CAP				
ALIGN	STATION	OFFSET	NORTH	EAST
L	12+85.00	45.00	654362.26058	1245538.01298
L	13+05.00	75.00	654372.86973	1245572.47231
L	13+20.00	45.00	654395.80574	1245547.99908
L	13+30.00	60.00	654401.11031	1245565.22875


NOTE: DRAWING NOT TO SCALE








5/14/99

PAVEMENT SCHEDULE

C1	PROP. APPROX. 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS PER SQ. YARD.	D2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YARD PER 1" DEPTH TO BE PLACED IN LAYERS NOT LESS THAN 2 1/2" OR GREATER THAN 4" IN DEPTH.	T	EARTH MATERIAL.
C2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YARD PER 1" DEPTH TO BE PLACED IN LAYERS NOT TO EXCEED 1 1/2" IN DEPTH.	E1	PROP. APPROX. 5 1/2" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 627 LBS PER SQ. YARD.	U	EXISTING PAVEMENT.
D1	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 456 LBS PER SQ. YARD.	E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YARD PER 1" DEPTH TO BE PLACED IN LAYERS NOT GREATER THAN 5 1/2" IN DEPTH OR LESS THAN 3" IN DEPTH.	W	VARIABLE DEPTH ASPHALT PAVEMENT (SEE STANDARD WEDGING DETAIL THIS SHEET)

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.

PROJECT REFERENCE NO. 17BP.12.R.43	SHEET NO. 2A-1
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	PAVEMENT DESIGN ENGINEER
	
Michael Baker Engineering, Inc. 1500 Regency Park Suite 600 Cary, NC 27518 Phone: 919.233.1100 Fax: 919.233.1101 International NC License: P-1084	
NC DEPARTMENT OF TRANSPORTATION PAVEMENT MANAGEMENT UNIT 1500 MAIL SERVICE CENTER RALEIGH, NC 27699-1593	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	




10/25/2016 10:38:12 AM
 I:\17BP\12\2A\2-0275-RDY-TYP_02.dgn
 USER: toddbuckner

31-AUG-2017 07:57 S:\Contracts\Special Details\Standard Drawings\Division 8\862d01 862d03 862d01.dgn
 Jhowerton AT: USD-292595

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 4 OF 11
862D01



ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 4 OF 11
862D01

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

GUARDRAIL INSTALLATION AT BRIDGE APPROACHES FOR TWO-LANE, TWO-WAY TRAFFIC

DESIGN SPEED (MPH)	"L" APPROACH LENGTH (FT.)		"L" TRAILING LENGTH (FT.)	
	DESIGN YEAR ADT OVER 2000	CURRENT YEAR ADT UNDER 400	DESIGN YEAR ADT OVER 2000	CURRENT YEAR ADT UNDER 400
70	362.5'	362.5'	350.0'	287.5'
60	300.0'	287.5'	275.0'	225.0'
50	212.5'	212.5'	200.0'	162.5'
40	175.0'	150.0'	137.5'	112.5'
X*	8'	6'	4'	4'

* USE FLARE RATE AS THE CONTROL IF THE "X" DISTANCE IS NOT OBTAINED. ("X" IS BASED ON SHOULDER WIDTHS IN THE HIGHWAY DESIGN BRANCH MANUAL, PART 1, 1-4B, F1).

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL WHERE GUARDRAIL IS PARALLEL TO LANE.

SEE STD. 862.03 FOR STRUCTURE ANCHOR UNITS


FOR POSTED SPEEDS ≥ 45mph USE GREU TYPE TL-3
FOR POSTED SPEEDS < 45mph USE GREU TYPE TL-2

LENGTHS AND OFFSETS FOR PROPOSED GUARDRAIL AT TWO LANE - TWO WAY LOCATIONS

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 3 OF 11
862D01



FOR POSTED SPEEDS ≥ 45mph USE GREU TYPE TL-3
FOR POSTED SPEEDS < 45mph USE GREU TYPE TL-2

DIMENSIONS FOR LENGTH OF GUARDRAIL APPROACHING DUAL LANE BRIDGES

MEDIAN WIDTH	-L-***		-L2- DIM.
	60 MPH	50 MPH	
30'	300.0'	250.0'	80.0'
36'	300.0'	250.0'	60.0'
40' & ABOVE	300.0'	250.0'	40.0'

NOTES: * MINOR VARIATION TO THE 25'-0" DIMENSION IS PERMISSIBLE TO ACCOMMODATE THE 12'-6" IN GUARDRAIL LENGTHS.

** NO GUARDRAIL IS REQUIRED ON THE TRAILING END WHEN THIS DISTANCE EXCEEDS CLEAR ROADSIDE RECOVERY AREA FOR THE APPROPRIATE DESIGN SPEED.

*** BASED ON "X" OF 12' USE FLARE RATE AS THE CONTROL IF THE "X" DISTANCE IS NOT OBTAINED. ("X" IS BASED ON SHOULDER WIDTHS IN THE HIGHWAY DESIGN BRANCH MANUAL, PART 1, 1-4B, F1A).

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL WHERE GUARDRAIL IS PARALLEL TO LANE. THE DESIGN LAYOUT FOR LENGTHS SHOWN ON THIS STANDARD ARE MINIMUM DESIGN LENGTHS. SEE SHEET 1 OF 12 FOR SECTIONS XX, YY


SEE STD. 862.03 FOR STRUCTURE ANCHOR UNITS

DETAIL OF GUARDRAIL APPROACHING DUAL LANE BRIDGES

CONTRACT STANDARDS AND DEVELOPMENT UNIT
Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.: DATE:




DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

94 MAY 2017 15:15 J:\projects\Special Details\Standard Drawings\Details in Lieu of Standards\Drawings\Division 8\862d01 862d03 862d03\862d01.dgn
 jhowerton AT CSD 292595

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.



ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT


ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 6 OF 11
862D01

SHEET 6 OF 11
862D01

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.



ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 5 OF 11
862D01


SHEET 5 OF 11
862D01

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

CONTRACT STANDARDS AND DEVELOPMENT UNIT
 Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE: _____
 CHECKED BY: DATE: _____
 FILE SPEC.: _____




C:\MAY-2017\5r6\Projects\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d03\862d01.dgn
 Jhowerton
 CSD-26258g

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ENGLISH DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 10 OF 11
862D01



FLEXIBLE PAVED SHOULDER

CONCRETE PAVED SHOULDER

NOTE: WHEN WOODEN GUARDRAIL POSTS ARE USED, DRILL HOLES THROUGH EARTH MATERIAL AND BASE COURSE. THE POST MAY THEN BE DRIVEN TO THE PROPER DEPTH. DRILL THE HOLE OF SUFFICIENT SIZE TO ACCOMMODATE THE PARTICULAR POST BEING USED. BACKFILL AND TAMP HOLES USING THE EXCAVATED MATERIAL.

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.


ENGLISH DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 9 OF 11
862D01

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 9 OF 11
862D01



DETAIL -3
 DIVIDED HIGHWAY

DETAIL -4
 UNDIVIDED HIGHWAY

NOTE: USE DETAIL 3 & 4 WHENEVER 20' OR LARGER RADIUS CANNOT BE UTILIZED.
 MAINTAIN CLEAR SIGHT DISTANCE.


FOR POSTED SPEEDS ≥ 45mph USE GREU TYPE TL-3
 FOR POSTED SPEEDS < 45mph USE GREU TYPE TL-2

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 9 OF 11
862D01

PROJECT REFERENCE NO. 17BP.12.R.43	SHEET NO. 2C-3
---------------------------------------	-------------------



DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED


**CONTRACT STANDARDS
 AND DEVELOPMENT UNIT**
 Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.:


23-MAY-2017 12:50
 S:\Contracts\Contractors\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01.862d03.862d02.dgn
 Jhowerton A1 CS0-29295

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.
 ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION
 SHEET 2 OF 8
862D02



**FLARED AND TANGENT
ELEVATION VIEW**

* WHEN INSTALLING GUARDRAIL END UNITS THAT ARE 2'-1" MOUNTING HEIGHT TO EXISTING GUARDRAIL, REMOVE THE EXISTING GUARDRAIL TO TRANSITION FROM THE EXISTING HEIGHT TO THE PROPOSED 2'-1" HEIGHT. SEE 862.02, SHEET 4 OF 8 FOR TRANSITION DETAILS.




**FLARED AND TANGENT
ELEVATION VIEW**

APPROACH END UNITS

SHEET 2 OF 8
862D02

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.
 ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION
 SHEET 2 OF 8
862D02

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.
 ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION
 SHEET 1 OF 8
862D02



PLAN

ELEVATION

**TRAILING END UNIT ASSEMBLY
C.A.T. - 1 SYSTEM**


STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.
 ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION
 SHEET 1 OF 8
862D02

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

**CONTRACT STANDARDS
AND DEVELOPMENT UNIT**
Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON	DATE: 06-22-12
MODIFIED BY:	DATE:
CHECKED BY:	DATE:
FILE SPEC.:	



9/8/2017

04-MAY-2017 15:20
 S:\Contracts\Construction\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d02.dgn
 JHowerton - N1 CSP-24298

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION	SHEET 6 OF 8 862D02
SYSTEM PARTS		
ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION		
SHEET 6 OF 8 862D02		

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION	SHEET 6 OF 8 862D02
"W6" STEEL POST		


STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION	SHEET 5 OF 8 862D02
ISOMETRIC VIEW		
FRONT - MID SPAN SPLICE		
TYPICAL GUARDRAIL AND GUARDRAIL POST ALTERNATIVES		
NOTES: A - 5/8" DIA. BUTTON HEAD SPLICE BOLT 1 1/4" LONG (8 REQ. PER SPLICE JOINT). B - 5/8" DIA. BUTTON HEAD BOLT 7 1/2" / 9" LONG WITH NUT FOR BOLTING 6" / 8" ROUNDED OFFSET BLOCK TO STEEL POSTS. C - FIELD PUNCHING OF HOLES INTO GUARDRAIL AS DIRECTED BY THE ENGINEER.		
ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION		
SHEET 5 OF 8 862D02		

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION	SHEET 5 OF 8 862D02
PLAN		

PROJECT REFERENCE NO. 17BP.12.R.43	SHEET NO. 2C-5
---------------------------------------	-------------------

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

CONTRACT STANDARDS AND DEVELOPMENT UNIT	
Office 919-707-6950	FAX 919-250-4119
SEE TITLE BLOCK	
ORIGINAL BY: J HOWERTON	DATE: 06-22-12
MODIFIED BY:	DATE:
CHECKED BY:	DATE:
FILE SPEC.:	



DocuSigned by:
 Joel S. Howerton
 873F3D17DCDC45F... 9/8/2017

04-MAY-2017 15:21 S:\Contracts\Construction\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d03\862d02.dgn
 Jhowerton - N: CSDP-24593

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION	SHEET 8 OF 8 862D02
SECTION X-X 		
BUFFERED END SECTION 		
TYPICAL END SHOE 		
SYSTEM PARTS - GENERAL USE		

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION	SHEET 7 OF 8 862D02
SOIL PLATE 		
BEARING PLATE 		
DETAIL OF STANDARD WASHER 		
DETAIL OF STANDARD HEX BOLT AND NUT 		
DETAIL OF BUTTON HEAD BOLT AND NUT 		
SYSTEM PARTS - GENERAL USE		

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION	SHEET 8 OF 8 862D02
ANCHOR PLATE ASSEMBLY 		
SWAGED CABLE 		
ANCHOR PLATE 		
CABLE ASSEMBLY 		
SYSTEM PARTS		

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL INSTALLATION
SHEET 8 OF 8 862D02	SHEET 7 OF 8 862D02
SEE TITLE BLOCK	
ORIGINAL BY: J HOWERTON DATE: 06-22-12 MODIFIED BY: DATE: CHECKED BY: DATE: FILE SPEC.:	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
CONTRACT STANDARDS AND DEVELOPMENT UNIT Office 919-707-6950 FAX 919-250-4119	
9/8/2017	

23-MAY-2017 12:51
 S:\Contracts\Contract\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01.862d03.862d03.dgn
 J:\Howerton\Standard Drawings\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01.862d03.862d03.dgn
 J:\Howerton\Standard Drawings\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01.862d03.862d03.dgn

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO
RAIL ON BRIDGE - SUB REGIONAL TIER

SHEET 2 OF 7
862D03

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO
RAIL ON BRIDGE - SUB REGIONAL TIER

SHEET 2 OF 7
862D03



ELEVATION

NOTE:
 **POST NOT REQUIRED FOR SKEW ANGLES GREATER THAN 150° OR LESS THAN 30° UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
 *THE DISTANCE FROM END OF BRIDGE RAIL TO CENTER LINE OF THE FIRST POST SHOULD BE 11½" IF CONCRETE BACKWALL IS NOT PRESENT.
 -SHOULDER BERM GUTTER MUST BE INSTALLED TO THE LIMITS 8' x 4" LIP CURB IS SHOWN IF ANCHOR UNIT IS NOT ADJACENT TO AN APPROACH SLAB.
 -MEASURE GUARDRAIL HEIGHT FROM THE TOP OF ADJACENT SURFACE (SHOULDER, BERM, OR GUTTER).
 -LAP JOINTS IN THE DIRECTION OF TRAFFIC FLOW.
 -SEE SHEET 5 FOR POST SECTIONS 1 THRU 9.



PLAN VIEW
**GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO
 RAIL ON BRIDGE - SUB REGIONAL TIER**

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO
RAIL ON BRIDGE - SUB REGIONAL TIER

SHEET 2 OF 7
862D03

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE

SHEET 1 OF 7
862D03

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE

SHEET 1 OF 7
862D03



ELEVATION

NOTE:
 **POST NOT REQUIRED FOR SKEW ANGLES GREATER THAN 150° OR LESS THAN 30° UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
 *THE DISTANCE FROM END OF BRIDGE RAIL TO CENTER LINE OF THE FIRST POST SHOULD BE 11½" IF CONCRETE BACKWALL IS NOT PRESENT.
 -SHOULDER BERM GUTTER MUST BE INSTALLED TO THE LIMITS 8' x 4" LIP CURB IS SHOWN IF ANCHOR UNIT IS NOT ADJACENT TO AN APPROACH SLAB.
 -MEASURE GUARDRAIL HEIGHT FROM THE TOP OF ADJACENT SURFACE (SHOULDER, BERM, OR GUTTER).
 -LAP JOINTS IN THE DIRECTION OF TRAFFIC FLOW.
 -SEE SHEET 5 FOR POST SECTIONS 1 THRU 9.



PLAN VIEW
**GUARDRAIL ANCHOR UNIT, TYPE III
 FOR ATTACHMENT TO RAIL ON BRIDGE**

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE


SHEET 1 OF 7
862D03

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

**CONTRACT STANDARDS
AND DEVELOPMENT UNIT**
Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.:




9/8/2017

23-MAY-2017 12:52
 S:\Contracts\Contract\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d03\862d03.dgn
 J:\Howerton\A\CS0-2\2595

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNIT
FOR F-SHAPE BARRIER

SHEET 4 OF 7
862D03



ELEVATION

- GENERAL NOTES:**
- POSTS 1 THROUGH 5 REQUIRE AN ADDITIONAL HOLE TO ATTACH LOWER BLOCKOUTS AND/OR RUBRAIL. RUBRAIL BLOCKOUTS LOCATED ON POSTS 1 THROUGH 4 ARE OFFSET DRILLED AND SECURED WITH 3/8" BUTT-ON BOLTS (SEE CHART FOR BOLT LENGTHS). SECURE RUBRAIL BLOCKOUTS TO POSTS 1 AND 4. SECURE RUBRAIL AND BLOCKOUTS TO POSTS 2 AND 3. RUBRAIL IS SECURED TO POST 5 WITH 3/8" BUTT-ON BOLTS. RUBRAIL IS NOT TO BE USED ON POST 6.
 - SECURE RUBRAIL AND BLOCKOUTS TO POSTS 1 AND 4. SECURE RUBRAIL AND BLOCKOUTS TO POSTS 2 AND 3. RUBRAIL IS SECURED TO POST 5 WITH 3/8" BUTT-ON BOLTS. RUBRAIL IS NOT TO BE USED ON POST 6.
 - STEEL SPACER TUBE IS A SCHEDULE 40 GALVANIZED PIPE 6" INSIDE DIAMETER X 9" LONG. ATTACH TUBE TO GUARDRAIL ONLY WITH 5/8" X 1 1/4" LONG BUTT-ON BOLT AND RECTANGULAR PLATE WASHER.
 - SEE DETAIL D FOR SLOPED RUBRAIL BLOCKOUT. BLOCKOUT IS ATTACHED TO RAIL ELEMENT ONLY. USE 3/8" X 3" LAG BOLT WITH FLAT WASHER.
 - SHOP FABRICATE THE C6 X 8.2 RUBRAIL END TO BE CONSISTENT WITH THE SLOPE OF THE F SHAPE AND ATTACH FLUSH WITH THE SLOPED END OF THE BARRIER OR BRIDGE RAIL.
 - ANCHOR THE BARRIER OR BRIDGE RAIL.
 - (a) AT EXISTING BRIDGE RAIL AND NEW OR EXISTING BARRIERS, ANCHOR RUBRAIL USING THREE 5/8" X 6" CHEMICALLY ANCHORED BOLTS WITH WASHERS. MAXIMUM PROJECTION FOR BOLTS IS 1/2".
(b) AT EXISTING BRIDGE RAIL AND NEW OR EXISTING BARRIERS, ANCHOR THE W-BEAM END SHOE USING A 4 BOLT HOLD DOWN PLATE (SEE STD. DWG. 862.04). A 4 BOLT INSERT ASSEMBLY IS ALLOWED ON PRECAST REINFORCED CONCRETE BARRIER (SEE STD. DWG. 857.01).
(c) AT NEW BRIDGE RAIL AND NEW OR EXISTING BARRIERS, ANCHOR THE W-BEAM END SHOE AND RUBRAIL AS DETAILED ON THE STRUCTURE PLANS.
 - POSTS 1 AND 2 ARE W8 X 13, 7'-6" LONG. ALL OTHER POSTS IN THE ANCHOR UNIT ARE W6 X 8.5.



PLAN

GUARDRAIL ANCHOR UNIT TYPE B-77

SHEET 4 OF 7
862D03

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
GUARDRAIL ANCHOR UNIT
GUARDRAIL ANCHOR UNIT TYPE B-77
FOR F-SHAPE BARRIER

SHEET 4 OF 7
862D03

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III

SHEET 3 OF 7
862D03



SECTION OF 'W' BEAM POST 9

SECTION OF WTR BEAM POST 8

SECTION OF THRIE BEAM POST 7

SECTION OF THRIE BEAM POSTS 1 THRU 6

ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III

SHEET 3 OF 7
862D03

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III

SHEET 3 OF 7
862D03


NOTE: THE MID POST AND OFFSET BLOCK OF THE WTR SECTION WILL REQUIRE SPECIAL BOLT HOLE DRILLING IN THE THRIE BEAM OFFSET BLOCK AND LINE POST.

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

**CONTRACT STANDARDS
AND DEVELOPMENT UNIT**
Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK


ORIGINAL BY: J. HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.:




9/8/2017

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


DETAIL 2 DECK DRAIN DISSIPATOR PAD (Not to Scale)






DETAIL 3 DECK DRAIN DISSIPATOR PAD (Not to Scale)



-L- LINE
 PI Sta 11+07.48
 $\Delta = 13^\circ 23' 54.6''$ (RT)
 $D = 6^\circ 15' 42.6''$
 $L = 213.97'$
 $T = 107.48'$
 $R = 915.00'$
 $D_s = 45$ MPH
 $SE = .04$



-L- LINE
 PI Sta 16+86.56
 $\Delta = 0^\circ 45' 06.4''$ (LT)
 $D = 0^\circ 22' 55.1''$
 $L = 196.81'$
 $T = 98.41'$
 $R = 15,000.00'$
 $D_s = 55$ MPH
 $SE = NC$





REVISIONS

8/17/19
9/27/2017 11:00:39 AM
U:\EIT\toad\bluckner\proj\22-0275-1\RDY_PSH_04.dgn



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

TRANSPORTATION MANAGEMENT PLAN

CLEVELAND COUNTY




VICINITY MAP
(NOT TO SCALE)




N.C.D.O.T. WORK ZONE TRAFFIC CONTROL
1561 MAIL SERVICE CENTER (MSC) RALEIGH, NC 27699-1561
750 N. GREENFIELD PARKWAY, GARNER, NC 27529 (DELIVERY)
PHONE: (919) 773-2800 FAX: (919) 771-2745

J. S. BOURNE, P.E. STATE TRAFFIC MANAGEMENT ENGINEER
BYRON ENGLE, PE DIVISION TRAFFIC ENGINEER
TODD H. BUCKNER, PE TRAFFIC CONTROL PROJECT ENGINEER




Michael Baker

INTERNATIONAL
MICHAEL BAKER ENGINEERING, INC.
8000 Regency Parkway, Suite 600
Cary, NC 27518
NC LICENSE NO. -F-1084

APPROVED: 
DATE: 1/12/2017

SEAL



INDEX OF SHEETS

SHEET NO.	TITLE
TMP-1	TITLE SHEET, AND INDEX OF SHEETS
TMP-1A	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, AND LEGEND
TMP-1B	GENERAL NOTES AND PHASING
TMP-2	OFFSITE DETOUR PLAN - CARPENTER HOYLE ROAD (SR 1603)
TMP-3	CARPENTER HOYLE ROAD SIGN DESIGN

SHEET NO.
TMP-1

17BP.12.R.43

TIP PROJECT:






ROADWAY STANDARD DRAWINGS





THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

<u>STD. NO.</u>	<u>TITLE</u>
1101.01	WORK ZONE WARNING SIGNS
1101.03	TEMPORARY ROAD CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1145.01	BARRICADES
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO LANE AND MULTILANE ROADWAYS
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION












LEGEND

GENERAL




-  DIRECTION OF TRAFFIC FLOW
-  DIRECTION OF PEDESTRIAN TRAFFIC FLOW
-  EXIST. PVMT.
-  NORTH ARROW
-  PROPOSED PVMT.

-  WORK AREA
-  REMOVAL
-  USER DEFINED (IF NEEDED)
-  USER DEFINED (IF NEEDED)




TRAFFIC CONTROL DEVICES

-  BARRICADE (TYPE III)
-  CONE
-  DRUM  SKINNY DRUM  TUBULAR MARKER
-  TEMPORARY CRASH CUSHION
-  FLASHING ARROW PANEL (TYPE C)
-  FLAGGER
-  LAW ENFORCEMENT
-  TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)
-  CHANGEABLE MESSAGE SIGN

TEMPORARY SIGNING

-  PORTABLE SIGN
-  STATIONARY SIGN
-  STATIONARY OR PORTABLE SIGN




SIGNALS

-  EXISTING
-  PROPOSED
-  TEMPORARY

PAVEMENT MARKINGS

-  EXISTING LINES
-  TEMPORARY LINES


PAVEMENT MARKERS



-  CRYSTAL/CRYSTAL
-  CRYSTAL/RED
-  YELLOW/YELLOW

PAVEMENT MARKING SYMBOLS

-  PAVEMENT MARKING SYMBOLS

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

APPROVED:  DATE: 1/12/2017



ROADWAY STANDARD DRAWINGS & LEGEND

Michael Baker Engineering, Inc.
Michael Baker
 INTERNATIONAL
 8000 Regency Pkwy
 Suite 600
 Cary, NC 27518
 NC License: F-1084

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS, AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS OR RESULT IN DUPLICATE OR UNDESIRED OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING, OR REMOVAL OF DEVICES AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

TRAFFIC PATTERN ALTERATIONS

A) NOTIFY THE ENGINEER TWENTY ONE (21) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

SIGNING

B) INSTALL ADVANCE WORK ZONE WARNING SIGNS WHEN WORK IS WITHIN 40 FT FROM THE EDGE OF TRAVEL LANE AND NO MORE THAN THREE (3) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.

C) PROVIDE SIGNING AND DEVICES REQUIRED TO CLOSE THE ROAD ACCORDING TO THE ROADWAY STANDARD DRAWINGS AND TRAFFIC CONTROL PLANS.

PROVIDE SIGNING REQUIRED FOR THE OFF-SITE DETOUR ROUTE AS SHOWN IN THE TRAFFIC CONTROL PLANS.

D) COVER OR REMOVE ALL SIGNS AND DEVICES REQUIRED TO CLOSE THE ROAD WHEN ROAD CLOSURE IS NOT IN OPERATION.

COVER OR REMOVE ALL SIGNS REQUIRED FOR THE OFF-SITE DETOUR WHEN THE DETOUR IS NOT IN OPERATION.

E) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

TRAFFIC CONTROL DEVICES

F) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.

PAVEMENT MARKINGS AND MARKERS

G) UPON COMPLETION OF ALL OTHER CONSTRUCTION OPERATIONS, INSTALL 2 APPLICATIONS OF PAINT PAVEMENT MARKINGS ON THE FINAL SURFACE, ACCORDING TO RSD 1205.01, 1205.02 AND 1205.12.

PHASING NOTES

TRAFFIC CONTROL PHASING

NOTES: COORDINATE WITH THE ENGINEER FOR INSTALLATION AND REMOVAL OF ALL SIGNING AND TRAFFIC CONTROL DEVICES.

STEP 1: USING RSD 1101.01, SHEET 3 OF 3, INSTALL ADVANCE WORK ZONE WARNING SIGNS ON CARPENTER HOYLE ROAD (SR 1603).

STEP 2: USING RSD 1101.03, SHEET 1 OF 9 AND SHEET TMP-2, INSTALL DETOUR SIGNS AND BARRICADES AND CLOSE CARPENTER HOYLE ROAD (SR 1603).



STEP 3: REMOVE EXISTING BRIDGE NO. 87 AND CONSTRUCT PROPOSED BRIDGE AND ROADWAY, UP TO AND INCLUDING THE FINAL LAYER OF SURFACE COURSE. PLACE FINAL PAVEMENT MARKINGS ON CARPENTER HOYLE ROAD (SR 1603) FROM STA. 10+45.00 TO STA. 15+00.00.

STEP 4: REMOVE ALL ADVANCE WORK ZONE DETOUR SIGNS AND TRAFFIC CONTROL DEVICES AND OPEN CARPENTER HOYLE ROAD (SR 1603) TO TRAFFIC.


I:\1\2017_40543_PM\R\17BP.12.R.43\TrafficControl\TrafficControl\17BP.12.R.43.tc_sht1B.dgn
USER: Todd.Buckner

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

Michael Baker Engineering, Inc.
Michael Baker
INTERNATIONAL
8000 Regency Pkwy
Suite 600
Cary, NC 27518
NC License: F-1084












**GENERAL NOTES
AND PHASING**



●●●●●
DETOUR ROUTE



REFER TO RSD 1101.03, SHEET 1 OF 9, FOR
ADDITIONAL SIGN AND BARRICADE PLACEMENT




DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

I:\11\2017_405\14_PM
 R:\17BP.12.R.43\TrafficControl\17BP.12.R.43.tc_detour.dgn
 USER: Todd.Buckner

Michael Baker Engineering, Inc.
Michael Baker
 INTERNATIONAL
 8000 Regency Pkwy
 Suite 600
 Cary, NC 27518
 NC License: F-1084

APPROVED:  DATE: 1/12/2017
 SEAL




OFFSITE DETOUR PLAN
CARPENTER HOYLE
ROAD
(SR 1603)

SIGN NUMBER: DET-1 TYPE: STATIONARY QUANTITY: SEE PLANS SIGN WIDTH: 7'-6" HEIGHT: 1'-6" TOTAL AREA: 11.3 Sq.Ft. BORDER TYPE: FLUSH RECESS: 0" WIDTH: 0.63" RADII: 1.5" NO. Z BARS: LENGTH:	BACKG COLOR: Fluorescent Orange COPY COLOR: Black <table border="1"> <thead> <tr> <th>SYMBOL</th> <th>X</th> <th>Y</th> <th>WID</th> <th>HT</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table> MAT'L: 1.6 mm ALUMINUM	SYMBOL	X	Y	WID	HT																																														DESIGN BY: _____ PROJECT ID: 17BP.12.R.43 CHECKED BY: _____ DIV: 12 DATE: Sept 9, 2014
SYMBOL	X	Y	WID	HT																																																

USE NOTES: 1,2

- Legend and border shall be direct applied black non-reflective sheeting.
- Background shall be NC GRADE B fluorescent orange retroreflective sheeting.

BORDER
R=1.5"
TH=0.63"

Panel Style: Detour.sst
M.U.T.C.D.: 2009 Edition

Spacing Factor is 1 unless specified otherwise

LETTER POSITIONS

Letter spacings are to start of next letter

Letter Spacings																	Series/Size	
C	A	R	P	E	N	T	E	R		H	O	Y	L	E		R	D	Text Length
6	10.1	14.7	19.1	23.7	27.8	32	35.9	39.9	43.3	49.3	53.9	58.1	62.8	66.7	69.8	75.8	80.1	C 2000
																		78

FILENAME: 17BP.12.R.43_tc_sign

NORTH CAROLINA D.O.T. SIGN DETAIL

I:\1\2017_4\05\45_PM
 R:\17BP.12.R.43\TrafficControl\17BP.12.R.43_tc_sign.dgn
 USER: Todd.Buckner

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

Michael Baker Engineering, Inc.
Michael Baker
 INTERNATIONAL
 8000 Regency Pkwy
 Suite 600
 Cary, NC 27518
 NC License: F-1084

APPROVED: _____ DATE: 1/12/2017

DocuSigned by: _____

SEAL

NORTH CAROLINA
 PROFESSIONAL
 SEAL
 034367
 ENGINEER
 TODD H. BUCKNER



**SPECIAL SIGN DESIGN
CARPENTER HOYLE RD**

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS



PAVEMENT MARKING PLAN

CLEVELAND COUNTY

**PAVEMENT MARKING
SCHEDULE**

SYMBOL	DESCRIPTION (PAINT - 4")
PA	WHITE EDGELINE
PB	YELLOW DOUBLE CENTER

NOTE: FINAL PAINT TO BE A DOUBLE COAT.



SHEET NO.
PMP-1

WBS ELEMENT: 17BP.12.R.43

I:\JAN-2017\16:07
V:\PMP\16070001\Div 12 On Call\17BP.12.R.43\Traffic\TrafficControl\TCP\17BP.12.R.43_PMP1.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

NOTE: NOT TO SCALE

<p>Michael Baker Engineering, Inc. 8000 Regency Pkwy Suite 600 Cary, NC 27518 NC License: F-1084</p> <p>Michael Baker INTERNATIONAL</p>	<p>APPROVED: <i>[Signature]</i> DATE: 1/12/2017</p>
	<p>SEAL</p>

TIP PROJECT: 17BP.12.R.43


STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS
 PLAN FOR PROPOSED
 HIGHWAY EROSION CONTROL
CLEVELAND COUNTY

LOCATION: STRUCTURE NO. 275 OVER KNOB CREEK ON CARPENTER HOYLE RD. SR 1603
TYPE OF WORK: GRADING, DRAINAGE, PAVING, & STRUCTURE

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.12.R.43	EC-1	
STATE PROJ. NO.	F. A. PROJ. NO.	DESCRIPTION	
17BP.12.R.43		PE, RW, UTILITY, CONST	


EROSION AND SEDIMENT CONTROL MEASURES

Std. #	Description	Symbol
1630.03	Temporary Silt Ditch	TD
1630.05	Temporary Diversion	TD
1605.01	Temporary Silt Fence	TSF
1606.01	Special Sediment Control Fence	TSF
1622.01	Temporary Berms and Slope Drains	TSF
1630.02	Silt Basin Type B	SB
1635.01	Temporary Rock Silt Check Type-A	TRSC
	Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM)	TRSC-PAM
1633.02	Temporary Rock Silt Check Type-B	TRSC
	Wattle / Coir Fiber Wattle	WF
	Wattle / Coir Fiber Wattle with Polyacrylamide (PAM)	WF-PAM
1634.01	Temporary Rock Sediment Dam Type-A	TRSD
1634.02	Temporary Rock Sediment Dam Type-B	TRSD
1635.01	Rock Pipe Inlet Sediment Trap Type-A	RPIST
1635.02	Rock Pipe Inlet Sediment Trap Type-B	RPIST
1630.04	Stilling Basin	SB
1630.06	Special Stilling Basin	SB
	Rock Inlet Sediment Trap:	
1632.01	Type A	A
1632.02	Type B	B
1632.03	Type C	C
	Skimmer Basin	SB
	Tiered Skimmer Basin	SB
	Infiltration Basin	SB



**THIS PROJECT CONTAINS
 EROSION CONTROL PLANS
 FOR CLEARING AND
 GRUBBING PHASE OF
 CONSTRUCTION.**


GRAPHIC SCALE



PLANS



PROFILE (HORIZONTAL)



PROFILE (VERTICAL)

**THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY
 WITH THE REGULATIONS SET FORTH BY THE
 NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011
 ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND
 NATURAL RESOURCES DIVISION OF WATER QUALITY.**

Prepared in the Office of:

Michael Baker

INTERNATIONAL
 Michael Baker Engineering, Inc.
 8000 Regency Parkway, Suite 600
 Cary, NC 27518
 Professional Corporation License Number:
 F-1084

NCDOT DIVISION 12
NCDOT Contact:

STEVE RACKLEY, PE

2012 STANDARD SPECIFICATIONS

TODD H. BUCKNER, PE
 LEVEL IIIA NAME

3542

LEVEL IIIA CERTIFICATION NO.


Roadway Standard Drawings

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

1604.01 Railroad Erosion Control Detail	1632.01 Rock Inlet Sediment Trap Type A
1605.01 Temporary Silt Fence	1632.02 Rock Inlet Sediment Trap Type J
1606.01 Special Sediment Control Fence	1632.03 Rock Inlet Sediment Trap Type C
1607.01 Gravel Construction Entrance	1633.01 Temporary Rock Silt Check Type A
1622.01 Temporary Berms and Slope Drains	1633.02 Temporary Rock Silt Check Type J
1630.01 Riser Basin	1634.01 Temporary Rock Sediment Dam Type A
1630.02 Silt Basin Type J	1634.02 Temporary Rock Sediment Dam Type J
1630.03 Temporary Silt Ditch	1635.01 Rock Pipe Inlet Sediment Trap Type A
1630.04 Stilling Basin	1635.02 Rock Pipe Inlet Sediment Trap Type J
1630.05 Temporary Diversion	1640.01 Coir Fiber Jaffle
1630.06 Special Stilling Basin	1645.01 Temporary Stream Crossing
1631.01 Matting Installation	

PROJECT REFERENCE NO.	SHEET NO.
17BP.12.R.44	EC-2
RW SHEET NO.	
TODD H. BUCKNER, PE	
LEVEL III NAME	
3542	
LEVEL III CERTIFICATION NO.	
Michael Baker INTERNATIONAL	Michael Baker Engineering, Inc. 3000 Regency Parkway Suite 600 Cary, NC 27519 NC License: F-1084

TEMPORARY ROCK SILT CHECK TYPE 'A' WITH EXCELSIOR MATTING AND POLYACRYLAMIDE (PAM)




NOTES


USE EXCELSIOR FOR MATTING MATERIAL AND ANCHOR MATTING SECTION AT TOP AND BOTTOM WITH CLASS B STONE.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH ROCK SILT CHECK.


INITIALLY APPLY 4 OUNCES OF POLYACRYLAMIDE (PAM) TO TOP OF MATTING SECTION AND AFTER EVERY RAINFALL EVENT THAT EQUALS OR EXCEEDS 0.50 INCHES.



INSET A



SECTION A-A



SECTION B-B

*T = 12" MIN., 18" MAX.

NOT TO SCALE

REVISIONS


5/14/99
 1/17/2017 4:01:31 PM
 User: Todd Buckner
 Path: \\17BP.12.R.44\2017\4\01\31\PM\17BP.12.R.44\22-0275-EC_PSH.02.dgn

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

REVISIONS



CLEARING AND GRUBBING PLAN

PROJECT REFERENCE NO.	SHEET NO.
17BP.12.R.43	EC.4CONST.4
RW SHEET NO.	


TODD H. BUCKNER, PE
LEVEL III NAME

3542
LEVEL III CERTIFICATION NO.


Michael Baker International
Michael Baker Engineering, Inc.
3000 Regency Parkway
Suite 600
Cary, NC 27518
NC License: F-1084

**CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 4**

-L- LINE
PI Sta 11+07.48
 $\Delta = 13^{\circ} 23' 54.6" (RT)$
 $D = 6' 15" 42.6"$
 $L = 213.97'$
 $T = 107.48'$
 $R = 915.00'$
 $Ds = 45 MPH$
 $SE = .04$




-L- LINE
PI Sta 16+86.56
 $\Delta = 0^{\circ} 45' 06.4" (LT)$
 $D = 0' 22' 55.1"$
 $L = 196.81'$
 $T = 98.41'$
 $R = 15,000.00'$
 $Ds = 55 MPH$
 $SE = NC$





BEGIN PROJECT 22-0275
-L- STA.11+00.00

END PROJECT 22-0275
-L- STA.17+95.00




NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.



NOTE: UTILIZE TEMPORARY SEDIMENT BASIN OR SPECIAL STILLING BASIN(S) AS STILLING BASIN WHERE APPLICABLE.



KNOB CREEK TRIB.



STAGE 1:
INSTALL IMPERVIOUS DIKE #1.
CONSTRUCT TEMPORARY CHANNEL CHANGE WITH LINER. TEMPORARY CHANNEL TO HAVE 1' BASE, 1.5' DEEP WITH 2:1 SIDESLOPES.
INSTALL SPECIAL STILLING BASIN.



STAGE 2:
INSTALL IMPERVIOUS DIKE #2 AND REMOVE IMPERVIOUS DIKE #1, DIVERTING FLOW INTO THE TEMPORARY CHANNEL.
INSTALL IMPERVIOUS DIKE #3 AND DEWATER CONSTRUCTION AREA AND TREAT EFFLUENT WATER USING A SPECIAL STILLING BASIN.
INSTALL 60" RCP CULVERT AND STABILIZE OUTLET WITH CLASS 'I' RIPRAP.
REMOVE IMPERVIOUS DIKE #3 AND #2 IN THAT ORDER AND DIVERT FLOW TO 60" RCP.

INSTALL PIPE(S) IN JURISDICTIONAL AREAS WITHOUT IMPACTING STREAM UNTIL AREA STABILIZED AND ACCORDING TO NCDOT BEST MANAGEMENT PRACTICES FOR CONSTRUCTION AND MAINTENANCE ACTIVITIES MANUAL.

REVISIONS


5/14/99
 9/2/2007 9:44:01AM
 17BP.12.R.43
 USER: todd.buckner

EROSION CONTROL FOR FINAL GRADING PLAN


PROJECT REFERENCE NO.	SHEET NO.
17BP.12.R.43	EC. 5CONST. 4
RW SHEET NO.	
TODD H. BUCKNER, PE LEVEL III NAME	
3542 LEVEL III CERTIFICATION NO.	
Michael Baker INTERNATIONAL	Michael Baker Engineering, Inc. 3000 Regency Parkway Suite 600 Cary, NC 27514 NC License: F-1084

Place Matting for Erosion Control
on Slope as Work Allows.

-L- LINE
 PI Sta 11+07.48
 $\Delta = 13^{\circ} 23' 54.6''$ (RT)
 $D = 6^{\circ} 15' 42.6''$
 $L = 213.97'$
 $T = 107.48'$
 $R = 915.00'$
 $D_s = 45$ MPH
 $SE = .04$






-L- LINE
 PI Sta 16+86.56
 $\Delta = 0^{\circ} 45' 06.4''$ (LT)
 $D = 0^{\circ} 22' 55.1''$
 $L = 196.81'$
 $T = 98.41'$
 $R = 15,000.00'$
 $D_s = 55$ MPH
 $SE = NC$



BEGIN PROJECT 22-0275
 -L- STA. 11+00.00

END PROJECT 22-0275
 -L- STA. 17+95.00



NOTE:
 UTILIZE TEMPORARY SEDIMENT BASIN OR SPECIAL STILLING BASIN(S) AS STILLING BASIN WHERE APPLICABLE.


REVISIONS

5/14/99

9/18/2017 9:41:14 AM
 I:\17BP\22-0275-01\22-0275-EC_PSH_05.dgn
 USER: todd.buckner

09/08/99

WBS ELEMENT: 17BP.12.R.43



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS


**UTILITIES BY OTHERS PLANS
CLEVELAND COUNTY**

**LOCATION: STRUCTURE NO. 275 OVER KNOB CREEK
ON CARPENTER HOYLE RD. SR 1603**

TYPE OF WORK: POWER DISTRIBUTION AND TELEPHONE RELOCATION


STATE PROJECT REFERENCE NO.	SHEET NO.
17BP.12.R.43	UO-1

NOTE:
ALL UTILITY WORK SHOWN ON THIS SHEET IS DONE BY OTHERS.
NO PAYMENT WILL BE MADE TO THE CONTRACTOR FOR UTILITY WORK SHOWN ON THIS SHEET.



UO-2

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.
THIS PROJECT IS NOT WITHIN ANY MUNICIPAL BOUNDARIES.



INDEX OF SHEETS

SHEET NO.:	DESCRIPTION:
UO-1	TITLE SHEET
UO-2	UBO PLAN SHEET

UTILITY OWNERS WITH CONFLICTS

(A) POWER DISTRIBUTION - DUKE ENERGY
(B) COMMUNICATIONS - AT&T

PREPARED IN THE OFFICE OF:
Michael Baker INTERNATIONAL
Michael Baker Engineering, Inc.
8000 Regency Parkway, Suite 600
Cary, NC 27518
919-463-5488

Brandy Creech UTILITY PROJECT MANAGER
Brandy Creech PROJECT UTILITY COORDINATOR
Christina Newsome PROJECT UTILITY TECHNICIAN

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS
DIVISION 12



DIVISION OFFICE ADDRESS
P.O. BOX 47
1710 E. MARION ST.
SHELBY, NC 28151

Steve Rackley, P.E. DIVISION BRIDGE MANAGER
Chad Drewery DIVISION UTILITY COORDINATOR

I:\JAN-2017 16:47
Y:\Projects\NCDOT\Div 12 On Call\17BP.12.R.43\Utilities\22-0275_ut_tsh_u01_psh.dgn
newsome AT CARY\WMOON3


UTILITIES BY OTHERS

NOTE:
ALL PROPOSED UTILITY WORK SHOWN ON THIS SHEET WILL BE DONE BY OTHERS. NO PAYMENT WILL BE MADE TO THE CONTRACTOR FOR PROPOSED UTILITY WORK SHOWN ON THIS SHEET.



Michael Baker
INTERNATIONAL
 Michael Baker Engineering, Inc.
 8000 Regency Parkway, Suite 600
 Cary, NC 27518
 919-463-5488

-L-



5/14/99
 08:55P:207.0852
 I:\D:\12\01\17\0852\170852.R43\Utilities\22-0275-ut_rdy4_U02_psh.dgn
 newking at Cary, NC 27518

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CLEVELAND COUNTY
17BP.12.R.43

INDEX OF SHEETS

DESCRIPTION SHEET NO.
INDEX OF SHEETS & CROSS-SECTION SUMMARY X-1

-L- X-2 TO X-7
CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
11+00.0000	0	0
11+50.0000	4	77
12+00.0000	2	159
12+50.0000	1	191
13+00.0000	0	245
13+50.0000	0	188
13+94.8000	1	103
15+27.3000	0	0
15+50.0000	0	38
16+00.0000	0	110
16+50.0000	0	106
17+00.0000	1	56
17+50.0000	13	21
17+95.0000	13	3

NOTE: APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, SHOULDER BORROW, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID AT THE CONTRACT LUMP SUM PRICE FOR "GRADING".

28-SEP-2017 08:36
R:\17BP.12.R.43\Roadway\CorridorModeling\22-0275-Rdy-XPL_01.dgn
\$\$\$USERNAME\$\$\$


REVISIONS

8/17/99


8/23/99




PROJ. REFERENCE NO.	SHEET NO.
17BP.12.R.43	X-2



I:\1\2017 4:14:09 PM
 17BP.12.R.43\Roadway\CorridorModeling\22-0275_Rdy_XPL.dgn
 User: Todd.Buckner




8/23/99




PROJ. REFERENCE NO.
17BP.12.R.43

SHEET NO.
X-4

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75




14 + 00.0000




13 + 94.7962

I:\1\2017 4:44:10 PM
17BP.12.R.43\Roadway\CorridorModeling\22-0275_Rdy_XPL.dgn
User: Todd.Buckner

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75







8/23/99





PROJ. REFERENCE NO.
17BP.12.R.43

SHEET NO.
X-7

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50




I:\2017 4:44:11PM
17BP.12.R.43\Roadway\CorridorModeling\22-0275_Rdy_XPL.dgn
USER: Todd.Buckner



I HEREBY CERTIFY THESE PLANS ARE THE AS-BUILT PLANS.

PROJECT NO. 17BP.12.R.43
 CLEVELAND COUNTY
 STATION: 14+61.05 -L-
 SHEET 1 OF 2 REPLACES BRIDGE NO. 275



Michael Baker International
 Michael Baker Engineering
 8000 Regency Parkway, Suite 600
 Cary, North Carolina 27518
 NC License No.: F-1084

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH


GENERAL DRAWING
 FOR BRIDGE ON SR 1603
 OVER KNOB CREEK
 BETWEEN SR 1623 AND SR 1604

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-1	
1			3			TOTAL SHEETS	
2			4			20	

DRAWN BY : N. B. SPEAKS DATE : 9-28-17
 CHECKED BY : B. J. BELL DATE : 9-28-17

PILES NOT SHOWN IN PLAN VIEW FOR CLARITY

nbspeaks 3:45:14 PM 9/28/2017
 File name: Y:\Projects\NC DOT\Div 12 On Call\17BP.12.R.43\Structures\Drawings\Final\275.S01.17BP.12.R.43.SMU.GD01.dgn



FOUNDATION NOTES:

FOR PILES, SEE GEOTECHNICAL SPECIAL PROVISIONS AND SECTION 450 OF THE STANDARD SPECIFICATIONS.

PILES AT END BENT NO. 1 AND END BENT NO. 2 ARE DESIGNED FOR A FACTORED RESISTANCE OF 66 TONS PER PILE.

DRIVE PILES AT END BENT NO. 1 AND END BENT NO. 2 TO A REQUIRED DRIVING RESISTANCE OF 110 TONS PER PILE.

STEEL H PILE POINTS ARE REQUIRED FOR STEEL H PILES AT END BENT NO. 1 AND END BENT NO. 2. FOR STEEL PILE POINTS, SEE SECTION 450 OF THE STANDARD SPECIFICATIONS.

FOR DRILLED PIERS, SEE GEOTECHNICAL SPECIAL PROVISIONS AND SECTION 411 OF THE STANDARD SPECIFICATIONS.

DRILLED PIERS AT BENT NO. 1 AND BENT NO. 2 ARE DESIGNED FOR A FACTORED RESISTANCE OF 340 TONS PER PIER. CHECK FIELD CONDITIONS FOR THE REQUIRED TIP RESISTANCE OF 25 TSF.

INSTALL DRILLED PIERS AT BENT NO. 1 TO A TIP ELEVATION NO HIGHER THAN 884 FT (LEFT) AND 888 FT (CENTER AND RIGHT) AND WITH THE REQUIRED TIP RESISTANCE AND PENETRATION OF AT LEAST 14 FT INTO WEATHERED ROCK OR ROCK AS DETERMINED BY THE ENGINEER.

INSTALL DRILLED PIERS AT BENT NO. 2 TO A TIP ELEVATION NO HIGHER THAN 890 FT AND WITH THE REQUIRED TIP RESISTANCE AND PENETRATION OF AT LEAST 13 FT INTO WEATHERED ROCK OR ROCK AS DETERMINED BY THE ENGINEER.

SID INSPECTIONS MAY BE REQUIRED FOR DRILLED PIERS. THE ENGINEER WILL DETERMINE THE NEED FOR SID INSPECTIONS. FOR SID INSPECTIONS, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.

SPT TESTING MAY BE REQUIRED AT BENT NO. 1 AND BENT NO. 2. THE ENGINEER WILL DETERMINE THE NEED FOR SPT. IF REQUIRED, THE SPT N60 VALUE IS 3 INCHES OR LESS PENETRATION IN 100 BLOWS. FOR SPT TESTING, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.

CSL TUBES ARE REQUIRED AND CSL TESTING MAY BE REQUIRED FOR DRILLED PIERS. THE ENGINEER WILL DETERMINE THE NEED FOR CSL TESTING. FOR CSL TESTING, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.

THE SCOUR CRITICAL ELEVATION FOR BENT NO. 1 AND BENT NO. 2 IS ELEVATION 900 FT. SCOUR CRITICAL ELEVATIONS ARE USED TO MONITOR POSSIBLE SCOUR PROBLEMS DURING THE LIFE OF THE STRUCTURE.

NOTES:

ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.

THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.

THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL INTO THE WATER. THE CONTRACTOR SHALL REMOVE THE BRIDGE AND SUBMIT PLANS FOR DEMOLITION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.

THE MATERIAL SHOWN ON SHEET 1 OF 2 IN THE CROSS-HATCHED AREA SHALL BE EXCAVATED FOR A DISTANCE OF 35 FT EACH SIDE OF CENTERLINE ROADWAY AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR UNCLASSIFIED STRUCTURE EXCAVATION. SEE SECTION 412 OF THE STANDARD SPECIFICATIONS.

THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

THE EXISTING STRUCTURE CONSISTING OF 3 SIMPLE SPANS (1 @ 40'-3", 1 @ 40'-0", 1 @ 40'-3") WITH A CLEAR ROADWAY WIDTH OF 19'-2" AND A TIMBER DECK SUPPORTED BY STEEL I-BEAMS ON TIMBER BULKHEADS, CAPS AND PILES, LOCATED AT THE PROPOSED SITE SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY POSTED FOR LOAD LIMIT. SHOULD THE STRUCTURAL INTEGRITY OF THE BRIDGE DETERIORATE DURING CONSTRUCTION OF THE PROPOSED BRIDGE, A LOAD LIMIT MAY BE POSTED AND MAY BE REDUCED AS FOUND NECESSARY DURING THE LIFE OF THE PROJECT. FOR REMOVAL OF EXISTING STRUCTURE, SEE SPECIAL PROVISIONS.

THE LOCATION OF THE CONSTRUCTION JOINT IN THE DRILLED PIERS IS BASED ON AN APPROXIMATE GROUND LINE ELEVATION. IF THE CONSTRUCTION JOINT IS ABOVE THE ACTUAL GROUND ELEVATION, THE CONTRACTOR SHALL PLACE THE CONSTRUCTION JOINT 1 FT. BELOW THE GROUND LINE.

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

ASPHALT WEARING SURFACE IS INCLUDED IN ROADWAY QUANTITY ON ROADWAY PLANS.

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH "HEC 18-EVALUATING SCOUR AT BRIDGES".

INASMUCH AS THE PAINT SYSTEM ON THE EXISTING STRUCTURAL STEEL CONTAINS LEAD, THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 107-1 OF THE STANDARD SPECIFICATIONS. ANY COSTS RESULTING FROM COMPLIANCE WITH APPLICABLE STATE OR FEDERAL REGULATIONS PERTAINING TO HANDLING OF MATERIALS CONTAINING LEAD BASED PAINT SHALL BE INCLUDED IN THE BID PRICE FOR "REMOVAL OF EXISTING STRUCTURE @ STA. 14+61.05 -L-".

FOR ASBESTOS ASSESSMENT FOR BRIDGE DEMOLITION AND RENOVATION ACTIVITIES, SEE SPECIAL PROVISIONS.

FOR UTILITY INFORMATION, SEE UTILITY PLANS AND SPECIAL PROVISIONS.

LOCATION SKETCH

HYDRAULIC DATA

DESIGN DISCHARGE	= 2,100 CFS.
FREQUENCY OF DESIGN FLOOD	= 25 YRS.
DESIGN HIGH WATER ELEVATION	= 917.2
DRAINAGE AREA	= 7.20 SQ. MI.
BASE DISCHARGE (Q100)	= 3,090 CFS.
BASE HIGH WATER ELEVATION	= 918.54

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE	= ** CFS.
FREQUENCY OF OVERTOPPING FLOOD	= 500+ YRS.
OVERTOPPING FLOOD ELEVATION	= 924.6

* OVERTOPPING FLOOD IS >500+ YEAR EVENT

TOTAL BILL OF MATERIAL

	REMOVAL OF EXISTING STRUCTURE	3'-0" Ø DRILLED PIERS IN SOIL	3'-0" Ø DRILLED PIERS NOT IN SOIL	SID INSPECTIONS	SPT TESTING	CSL TESTING	UNCLASSIFIED STRUCTURE EXCAVATION	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL
	LUMP SUM	LIN. FT.	LIN. FT.	EACH	EACH	EACH	LUMP SUM	CU. YDS.	LUMP SUM	LBS.
SUPERSTRUCTURE										
END BENT 1							LUMP SUM	18.8		2,299
BENT 1		29.50	42.00	1	2	1		15.3		9,875
BENT 2		27.50	39.00		2	1		14.5		9,370
END BENT 2							LUMP SUM	18.8		2,299
TOTAL	LUMP SUM	57.00	81.00	1	4	2	LUMP SUM	67.4	LUMP SUM	23,843

TOTAL BILL OF MATERIAL (CONT'D)

	SPIRAL COLUMN REINFORCING STEEL	PILE DRIVING EQUIPMENT SETUP FOR HP 12x53 STEEL PILES	HP 12x53 STEEL PILES	STEEL PILE POINTS	VERTICAL CONCRETE BARRIER RAIL	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE	ELASTOMERIC BEARINGS	3'-0" x 1'-9" PRESTRESSED CONCRETE CORED SLABS	ASBESTOS ASSESSMENT
	LBS.	EACH	NO. LIN. FT.	EACH	LIN. FT.	TONS	SQ. YDS.	LUMP SUM	NO. LIN. FT.	LUMP SUM
SUPERSTRUCTURE					260.50			LUMP SUM	27 1,170	
END BENT 1		5	5 150	5		137	152			
BENT 1	1,717									
BENT 2	1,555									
END BENT 2		5	5 90	5		125	139			
TOTAL	3,272	10	10 240	10	260.50	262	291	LUMP SUM	27 1,170	LUMP SUM

PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
 STATION: 14+61.05 -L-
 SHEET 2 OF 2

DRAWN BY : N. B. SPEAKS DATE : 9-28-17
 CHECKED BY : B. J. BELL DATE : 9-28-17

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH									
		GENERAL DRAWING									
		FOR BRIDGE ON SR 1603 OVER KNOB CREEK BETWEEN SR 1623 AND SR 1604									
		REVISIONS									
NO.		BY:		DATE:		NO.		BY:		DATE:	
1						3					
2						4					
										SHEET NO. S-2	
Michael Baker Engineering 8000 Regency Parkway, Suite 600 Cary, North Carolina 27518 NC License No.: F-1084										TOTAL SHEETS 20	

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR CORED SLAB UNITS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE										SERVICE III LIMIT STATE					COMMENT NUMBER			
						LIVELOAD FACTORS	MOMENT					SHEAR					LIVELOAD FACTORS	MOMENT						
							DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)		DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN		GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	
DESIGN LOAD RATING	HL-93(Inv)	N/A	①	1.319	--	1.75	0.278	1.76	A,C	EL	19.5	0.549	1.32	A,C	EL	1.95	0.80	0.278	1.55	A,C	EL	19.5		
	HL-93(Opr)	N/A	--	1.709	--	1.35	0.278	2.28	A,C	EL	19.5	0.549	1.71	A,C	EL	1.95	N/A	--	--	--	--	--		
	HS-20(Inv)	36.000	②	1.540	55.449	1.75	0.278	2.21	A,C	EL	19.5	0.549	1.54	A,C	EL	1.95	0.80	0.278	1.94	A,C	EL	19.5		
	HS-20(Opr)	36.000	--	1.997	71.878	1.35	0.278	2.86	A,C	EL	19.5	0.549	2.00	A,C	EL	1.95	N/A	--	--	--	--	--		
LEGAL LOAD RATING	SV	SNSH	13.500	--	3.606	48.687	1.40	0.278	5.10	A,C	EL	19.5	0.549	4.13	A,C	EL	1.95	0.80	0.278	3.61	A,C	EL	19.5	
		SNGARBS2	20.000	--	2.964	59.289	1.40	0.278	4.19	A,C	EL	15.6	0.549	3.07	A,C	EL	1.95	0.80	0.278	2.96	A,C	EL	19.5	
		SNAGRIS2	22.000	--	2.906	63.929	1.40	0.278	4.09	A,C	EL	15.6	0.549	2.91	A,C	EL	1.95	0.80	0.278	2.92	A,C	EL	15.6	
		SNCOTTS3	27.250	--	1.803	49.125	1.40	0.278	2.55	A,C	EL	19.5	0.549	2.07	A,C	EL	1.95	0.80	0.278	1.80	A,C	EL	19.5	
		SNAGGRS4	34.925	--	1.623	56.667	1.40	0.278	2.29	A,C	EL	19.5	0.549	1.82	A,C	EL	1.95	0.80	0.278	1.62	A,C	EL	19.5	
		SNS5A	35.550	--	1.578	56.107	1.40	0.278	2.23	A,C	EL	19.5	0.549	1.90	A,C	EL	1.95	0.80	0.278	1.58	A,C	EL	19.5	
		SNS6A	39.950	--	1.502	59.992	1.40	0.278	2.12	A,C	EL	19.5	0.549	1.77	A,C	EL	1.95	0.80	0.278	1.50	A,C	EL	19.5	
	SNS7B	42.000	③	1.432	60.149	1.40	0.278	2.02	A,C	EL	19.5	0.549	1.81	A,C	EL	1.95	0.80	0.278	1.43	A,C	EL	19.5		
	TTST	TNAGRIT3	33.000	--	1.848	60.976	1.40	0.278	2.61	A,C	EL	19.5	0.549	2.08	A,C	EL	1.95	0.80	0.278	1.85	A,C	EL	19.5	
		TNT4A	33.075	--	1.872	61.901	1.40	0.278	2.65	A,C	EL	19.5	0.549	1.98	A,C	EL	1.95	0.80	0.278	1.87	A,C	EL	19.5	
		TNT6A	41.600	--	1.587	66.032	1.40	0.278	2.24	A,C	EL	19.5	0.549	1.94	A,C	EL	1.95	0.80	0.278	1.59	A,C	EL	19.5	
		TNT7A	42.000	--	1.627	68.354	1.40	0.278	2.30	A,C	EL	19.5	0.549	1.79	A,C	EL	1.95	0.80	0.278	1.63	A,C	EL	19.5	
		TNT7B	42.000	--	1.664	69.888	1.40	0.278	2.35	A,C	EL	19.5	0.549	1.72	A,C	EL	1.95	0.80	0.278	1.66	A,C	EL	19.5	
		TNAGRIT4	43.000	--	1.619	69.610	1.40	0.278	2.28	A,C	EL	15.6	0.549	1.65	A,C	EL	1.95	0.80	0.278	1.62	A,C	EL	19.5	
TNAGT5A		45.000	--	1.498	67.412	1.40	0.278	2.12	A,C	EL	19.5	0.549	1.71	A,C	EL	1.95	0.80	0.278	1.50	A,C	EL	19.5		
TNAGT5B	45.000	--	1.455	65.486	1.40	0.278	2.06	A,C	EL	19.5	0.549	1.56	A,C	EL	1.95	0.80	0.278	1.46	A,C	EL	19.5			

LOAD FACTORS

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ _{DC}	γ _{DW}
	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.
ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

① CONTROLLING LOAD RATING

① DESIGN LOAD RATING (HL-93)


② DESIGN LOAD RATING (HS-20)

③ LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION

I - INTERIOR GIRDER
EL - EXTERIOR LEFT GIRDER
ER - EXTERIOR RIGHT GIRDER




SPANS A & C

LRFR SUMMARY

PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
STATION: 14+61.05 -L-

SHEET 1 OF 2



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
LRFR SUMMARY FOR
40' CORED SLAB UNIT
90° SKEW
(NON-INTERSTATE TRAFFIC)

ASSEMBLED BY : N.D'AIUTO DATE : 2/20/15
CHECKED BY : T.R.PETERSON DATE : 3/2/15
DRAWN BY : CVC 6/10
CHECKED BY : DNS 6/10

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-3	
1			3			TOTAL SHEETS	
2			4			20	

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR CORED SLAB UNITS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE										SERVICE III LIMIT STATE					COMMENT NUMBER			
						LIVELOAD FACTORS	MOMENT					SHEAR					LIVELOAD FACTORS	MOMENT						
							DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)		DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN		GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	
DESIGN LOAD RATING	HL-93(Inv)	N/A	①	1.394	--	1.75	0.276	1.57	B	EL	24.5	0.531	1.39	B	EL	24.5	0.80	0.276	1.44	B	EL	24.5		
	HL-93(0pr)	N/A	--	1.807	--	1.35	0.276	2.03	B	EL	24.5	0.531	1.81	B	EL	24.5	N/A	--	--	--	--	--		
	HS-20(Inv)	36.000	②	1.667	60.007	1.75	0.276	1.95	B	EL	24.5	0.531	1.67	B	EL	24.5	0.80	0.276	1.79	B	EL	24.5		
	HS-20(0pr)	36.000	--	2.161	77.787	1.35	0.276	2.52	B	EL	24.5	0.531	2.16	B	EL	24.5	N/A	--	--	--	--	--		
LEGAL LOAD RATING	SV	SNSH	13.500	--	3.635	49.079	1.40	0.276	4.95	B	EL	24.5	0.531	4.70	B	EL	24.5	0.80	0.276	3.64	B	EL	24.5	
		SNGARBS2	20.000	--	2.871	57.420	1.40	0.276	3.91	B	EL	24.5	0.531	3.42	B	EL	24.5	0.80	0.276	2.87	B	EL	24.5	
		SNAGRIS2	22.000	--	2.778	61.109	1.40	0.276	3.78	B	EL	19.6	0.531	3.21	B	EL	24.5	0.80	0.276	2.78	B	EL	24.5	
		SNCOTTS3	27.250	--	1.814	49.418	1.40	0.276	2.47	B	EL	24.5	0.531	2.36	B	EL	24.5	0.80	0.276	1.81	B	EL	24.5	
		SNAGGRS4	34.925	--	1.577	55.063	1.40	0.276	2.15	B	EL	24.5	0.531	2.01	B	EL	24.5	0.80	0.276	1.58	B	EL	24.5	
		SNS5A	35.550	--	1.537	54.657	1.40	0.276	2.09	B	EL	24.5	0.531	2.07	B	EL	24.5	0.80	0.276	1.54	B	EL	24.5	
		SNS6A	39.950	--	1.438	57.430	1.40	0.276	1.96	B	EL	24.5	0.531	1.91	B	EL	24.5	0.80	0.276	1.44	B	EL	24.5	
	SNS7B	42.000	--	1.370	57.540	1.40	0.276	1.87	B	EL	24.5	0.531	1.91	B	EL	24.5	0.80	0.276	1.37	B	EL	24.5		
	TTST	TNAGRIT3	33.000	--	1.761	58.118	1.40	0.276	2.40	B	EL	24.5	0.531	2.25	B	EL	24.5	0.80	0.276	1.76	B	EL	24.5	
		TNT4A	33.075	--	1.777	58.759	1.40	0.276	2.42	B	EL	24.5	0.531	2.17	B	EL	24.5	0.80	0.276	1.78	B	EL	24.5	
		TNT6A	41.600	--	1.480	61.558	1.40	0.276	2.01	B	EL	24.5	0.531	2.08	B	EL	24.5	0.80	0.276	1.48	B	EL	24.5	
		TNT7A	42.000	--	1.502	63.087	1.40	0.276	2.05	B	EL	24.5	0.531	1.94	B	EL	24.5	0.80	0.276	1.50	B	EL	24.5	
		TNT7B	42.000	--	1.566	65.773	1.40	0.276	2.13	B	EL	24.5	0.531	1.84	B	EL	24.5	0.80	0.276	1.57	B	EL	24.5	
		TNAGRIT4	43.000	--	1.486	63.902	1.40	0.276	2.02	B	EL	24.5	0.531	1.77	B	EL	24.5	0.80	0.276	1.49	B	EL	24.5	
TNAGT5A		45.000	--	1.388	62.470	1.40	0.276	1.89	B	EL	24.5	0.531	1.80	B	EL	24.5	0.80	0.276	1.39	B	EL	24.5		
TNAGT5B	45.000	--	③	1.360	61.206	1.40	0.276	1.85	B	EL	24.5	0.531	1.68	B	EL	24.5	0.80	0.276	1.36	B	EL	24.5		


LOAD FACTORS

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ _{DC}	γ _{OW}
	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES


MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.
ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

⊛	CONTROLLING LOAD RATING
①	DESIGN LOAD RATING (HL-93)
②	DESIGN LOAD RATING (HS-20)
③	LEGAL LOAD RATING **
** SEE CHART FOR VEHICLE TYPE	
GIRDER LOCATION	
I	INTERIOR GIRDER
EL	EXTERIOR LEFT GIRDER
ER	EXTERIOR RIGHT GIRDER



PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
STATION: 14+61.05 -L-

SHEET 2 OF 2




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

STANDARD
LRFR SUMMARY FOR
50' CORED SLAB UNIT
90° SKEW
(NON-INTERSTATE TRAFFIC)


ASSEMBLED BY : N.D.AIUTO DATE : 2/20/15
CHECKED BY : T.R.PETERSON DATE : 3/2/15
DRAWN BY : CVC 6/10
CHECKED BY : DNS 6/10

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-4
1			3			TOTAL SHEETS
2			4			20



GUTTERLINE ASPHALT THICKNESS & RAIL HEIGHT		
	ASPHALT OVERLAY THICKNESS	RAIL HEIGHT
	@ MIDSPAN	@ MIDSPAN
40' UNITS	2"	3'-8"
50' UNITS	1 5/8"	3'-7 5/8"




INTERIOR SLAB SECTION (40' UNIT)
(13 STRANDS REQUIRED)



EXT. SLAB SECTION
(FOR PRESTRESSED STRAND LAYOUT, SEE INTERIOR SLAB SECTION.)

* - THE MAXIMUM BARRIER RAIL HEIGHT AND ASPHALT THICKNESS IS SHOWN. THE HEIGHT OF THE BARRIER RAIL AND ASPHALT THICKNESS VARIES WHILE THE TOP OF THE BARRIER RAIL FOLLOWS THE PROFILE OF THE GUTTERLINE. FOR RAIL HEIGHT DETAILS AND ASPHALT THICKNESS SEE THE "GUTTERLINE ASPHALT THICKNESS & RAIL HEIGHT" TABLE & "VERTICAL CONCRETE BARRIER RAIL SECTION" DETAIL.




INTERIOR SLAB SECTION (50' UNIT)
(19 STRANDS REQUIRED)

0.6" Ø LOW RELAXATION STRAND LAYOUT


- ▲ BOND SHALL BE BROKEN ON THESE STRANDS FOR A DISTANCE OF 6'-0" FROM END OF CORED SLAB UNIT. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.
- BOND SHALL BE BROKEN ON THESE STRANDS FOR A DISTANCE OF 2'-0" FROM END OF CORED SLAB UNIT. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.
- OPTIONAL FULL LENGTH DEBONDED STRANDS. THESE STRANDS ARE NOT REQUIRED. IF THE FABRICATOR CHOOSES TO INCLUDE THESE STRANDS IN THE CORED SLAB UNIT, THE STRANDS SHALL BE DEBONDED FOR THE FULL LENGTH OF THE UNIT AT NO ADDITIONAL COST. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.

DEBONDING LEGEND


1/2" Ø THREADED INSERT @ 2'-0" SPACING, TO BE CAST IN OUTSIDE FACE OF EXTERIOR UNITS AND RECESSED 3/8"




THREADED INSERT DETAIL




SECTION AT END BENT



SECTION AT BENT




GROUTED RECESS AT END OF POST-TENSIONED STRAND OF CORED SLABS



SHEAR KEY DETAIL

NOTE: OMIT SHEAR KEY ON OUTSIDE FACE OF EXTERIOR CORED SLABS.



END ELEVATION

SHOWING PLACEMENT OF DOUBLE STIRRUPS AND LOCATION OF DOWEL HOLES. (STRAND LAYOUT NOT SHOWN.) INTERIOR SLAB UNIT SHOWN-EXTERIOR SLAB UNIT SIMILAR EXCEPT SHEAR KEY LOCATION.





PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
STATION: 14+61.05 -L-

SHEET 1 OF 5
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
3'-0" X 1'-9"
PRESTRESSED CONCRETE
CORED SLAB UNIT
90° SKEW

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-5	
1			3			TOTAL SHEETS 20	
2			4				

ASSEMBLED BY : N.D'AIUTO DATE : 2/20/15
CHECKED BY : T.R.PETERSON DATE : 3/2/15
DRAWN BY : DCE 5/09
CHECKED BY : BCH 6/09 REV. 8/14 MAA/TMG

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED




DETAIL "A"
 (TYPICAL EACH END OF UNIT)
 NOTE: EXTERIOR UNIT SHOWN - INTERIOR UNIT SIMILAR EXCEPT OMIT #5 S3 BARS.

PLAN OF UNIT
 SPAN A

PROJECT NO. 17BP.12.R.43
 CLEVELAND COUNTY
 STATION: 14+61.05 -L-

SHEET 2 OF 5





STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 PLAN OF 40' UNIT
 24'-10" CLEAR ROADWAY
 90° SKEW - SPAN A

ASSEMBLED BY : N.D'AIUTO	DATE : 2/20/15
CHECKED BY : T.R.PETERSON	DATE : 3/2/15
DRAWN BY : DGE 5/09	REV. 12/5/11 MAA/AAC
CHECKED BY : BCH 6/09	REV. 8/14 MAA/TMG

NO.	REVISIONS			NO.	REVISIONS			SHEET NO.
	BY:	DATE:	NO.		BY:	DATE:	TOTAL SHEETS	
1			3			20	S-6	
2			4					

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED



DETAIL "A"
 (TYPICAL EACH END OF UNIT)
 NOTE: EXTERIOR UNIT SHOWN - INTERIOR UNIT SIMILAR EXCEPT OMIT #5 S3 BARS.

PLAN OF UNIT
 SPAN B

PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
 STATION: 14+61.05 -L-

SHEET 3 OF 5





STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
PLAN OF 50' UNIT
24'-10" CLEAR ROADWAY
 90° SKEW - SPAN B

ASSEMBLED BY : N.D'AIUTO	DATE : 2/20/15
CHECKED BY : T.R.PETERSON	DATE : 3/2/15
DRAWN BY : DGE 5/09	REV. 12/5/11 MAA/AAC
CHECKED BY : BCH 6/09	REV. 8/14 MAA/TMG

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1			3			5-7
2			4			20




DETAIL "A"
 (TYPICAL EACH END OF UNIT)
 NOTE: EXTERIOR UNIT SHOWN - INTERIOR UNIT SIMILAR EXCEPT OMIT #5 S3 BARS.

PLAN OF UNIT
 SPAN C

PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
 STATION: 14+61.05 -L-

SHEET 4 OF 5



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH


PLAN OF 40' UNIT
24'-10" CLEAR ROADWAY

90° SKEW - SPAN C

ASSEMBLED BY : N.D.AIUTO	DATE : 2/20/15
CHECKED BY : T.R.PETERSON	DATE : 3/2/15
DRAWN BY : DGE 5/09	REV. 12/5/11 MAA/AAC
CHECKED BY : BCH 6/09	REV. 8/14 MAA/TMG

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS	
1			3			5	8
2			4			20	

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



FIXED END
(TYPE I - 54 REQ'D)

ELASTOMERIC BEARING DETAILS
ELASTOMER IN ALL BEARINGS SHALL BE 50 DUROMETER HARDNESS.

BILL OF MATERIAL FOR VERTICAL CONCRETE BARRIER RAIL

BAR	BARS PER PAIR OF EXTERIOR UNITS	TOTAL NO.	SIZE	TYPE	LENGTH	WEIGHT	
	SPAN A	SPAN B	SPAN C				
* B11	40	40	40	#5	STR	19'-7"	1634
* B13		40		#5	STR	24'-7"	1026
* S4	96	116	96	#5	2	7'-2"	2302
* EPOXY COATED REINFORCING STEEL						LBS.	4,962
CLASS AA CONCRETE						CU.YDS.	33.2
TOTAL VERTICAL CONCRETE BARRIER RAIL						LIN. FT.	260.50

GRADE 270 STRANDS

AREA (SQUARE INCHES)	0.6" Ø L.R.
ULTIMATE STRENGTH (LBS. PER STRAND)	58,600
APPLIED PRESTRESS (LBS. PER STRAND)	43,950


CORED SLABS REQUIRED

40' UNIT	NUMBER	LENGTH	TOTAL LENGTH
EXTERIOR C.S.	4	40'-0"	160'-0"
INTERIOR C.S.	14	40'-0"	560'-0"
50' UNIT			
EXTERIOR C.S.	2	50'-0"	100'-0"
INTERIOR C.S.	7	50'-0"	350'-0"
TOTAL	27		1170'-0"

DEAD LOAD DEFLECTION AND CAMBER

40' CORED SLAB UNIT	3'-0" x 1'-9"
CAMBER (SLAB ALONE IN PLACE)	7/8" ↓
DEFLECTION DUE TO SUPERIMPOSED DEAD LOAD**	1/8" ↓
FINAL CAMBER	3/4" ↓
50' CORED SLAB UNIT	
CAMBER (SLAB ALONE IN PLACE)	1/2" ↓
DEFLECTION DUE TO SUPERIMPOSED DEAD LOAD**	3/8" ↓
FINAL CAMBER	1/8" ↓

** INCLUDES FUTURE WEARING SURFACE



BILL OF MATERIAL FOR ONE 40' CORED SLAB UNIT

BAR	NUMBER	SIZE	TYPE	EXTERIOR UNIT LENGTH	EXTERIOR UNIT WEIGHT	INTERIOR UNIT LENGTH	INTERIOR UNIT WEIGHT
B4	4	#4	STR	20'-9"	55	20'-9"	55
S1	8	#5	3	4'-3"	35	4'-3"	35
S2	84	#4	3	5'-4"	299	5'-4"	299
* S3	48	#5	1	5'-7"	280		
REINFORCING STEEL				LBS.	389		389
* EPOXY COATED REINFORCING STEEL				LBS.	280		
5,000 P.S.I. CONCRETE				CU. YDS.	5.8		5.8
0.6" Ø L.R. STRANDS				No.	13		13

BILL OF MATERIAL FOR ONE 50' CORED SLAB UNIT

BAR	NUMBER	SIZE	TYPE	EXTERIOR UNIT LENGTH	EXTERIOR UNIT WEIGHT	INTERIOR UNIT LENGTH	INTERIOR UNIT WEIGHT
B6	4	#4	STR	25'-9"	69	25'-9"	69
S1	8	#5	3	4'-3"	35	4'-3"	35
S2	104	#4	3	5'-4"	371	5'-4"	371
* S3	58	#5	1	5'-7"	338		
REINFORCING STEEL				LBS.	475		475
* EPOXY COATED REINFORCING STEEL				LBS.	338		
6,500 P.S.I. CONCRETE				CU. YDS.	7.2		7.1
0.6" Ø L.R. STRANDS				No.	19		19

NOTES

ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW RELAXATION GRADE 270 STRANDS AND SHALL CONFORM TO AASHTO M203 EXCEPT FOR SAMPLING REQUIREMENTS WHICH SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

ALL REINFORCING STEEL CAST WITH THE CORED SLAB SECTIONS SHALL BE GRADE 60 AND SHALL BE INCLUDED IN THE UNIT PRICE BID FOR PRESTRESSED CONCRETE CORED SLABS.

RECESSES FOR TRANSVERSE STRANDS SHALL BE GROUTED AFTER THE TENSIONING OF THE STRANDS.

THE 2 1/2" Ø DOWEL HOLES AT FIXED ENDS OF SLAB SECTIONS SHALL BE FILLED WITH NON-SHRINK GROUT.

THE BACKER RODS SHALL CONFORM TO THE REQUIREMENTS OF TYPE M BOND BREAKER. SEE SECTION 1028 OF THE STANDARD SPECIFICATIONS.

WHEN CORED SLABS ARE CAST, AN INTERNAL HOLD-DOWN SYSTEM SHALL BE EMPLOYED TO PREVENT VOIDS FROM RISING OR MOVING SIDEWAYS. AT LEAST SIX WEEKS PRIOR TO CASTING CORED SLABS, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER FOR REVIEW AND COMMENT, DETAILED DRAWINGS OF THE PROPOSED HOLD-DOWN SYSTEM. IN ADDITION TO STRUCTURAL DETAILS, LOCATION AND SPACING OF THE HOLD-DOWNS SHALL BE INDICATED.

ALL REINFORCING STEEL IN THE VERTICAL CONCRETE BARRIER RAIL SHALL BE EPOXY COATED.

PRESTRESSING STRANDS SHALL BE CUT FLUSH WITH THE CORED SLAB UNIT ENDS.

APPLY EPOXY PROTECTIVE COATING TO CORED SLAB UNIT ENDS.

GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE BARRIER RAIL AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. A CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN BARRIER RAIL EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF BARRIER RAIL SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.

FLAME CUTTING OF THE TRANSVERSE POST-TENSIONING STRAND IS NOT ALLOWED.

THE TRANSFER OF LOAD FROM THE ANCHORAGES TO THE CORED SLAB UNIT SHALL BE DONE WHEN THE CONCRETE HAS REACHED A COMPRESSIVE STRENGTH OF NOT LESS THAN THE REQUIRED STRENGTH SHOWN IN THE "CONCRETE RELEASE STRENGTH" TABLE.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.





THE CONTRACTOR SHALL NOT GROUT THE 1/2" Ø INSERTS AND SHALL LEAVE THEM OPEN FOR USE BY NDOT MAINTENANCE FORCES.

THE 1/2" Ø THREADED INSERTS IN THE EXTERIOR UNITS SHALL BE SPACED AT 2'-0" CENTERS AND GALVANIZED IN ACCORDANCE WITH SECTION 1076 OF THE STANDARD SPECIFICATIONS. STAINLESS STEEL THREADED INSERTS MAY BE USED AS AN ALTERNATE.

THE COST OF THE 1/2" Ø THREADED INSERTS SHALL BE INCLUDED IN THE PRICE BID FOR THE PRECAST UNITS.

THE DRAIN OPENING AT THE GUTTERLINE SHALL BE 8" X 4". THE HEIGHT OF THE BLOCKOUT IN THE VERTICAL CONCRETE BARRIER RAIL SHALL EXTEND FROM THE TOP OF THE CORED SLAB UNIT TO THE TOP OF THE DRAIN OPENING.

APPLY EPOXY PROTECTIVE COATING TO EXTERIOR FACE OF THE EXTERIOR CORED SLAB UNITS THAT REQUIRE DRAINS IN THE BARRIER RAIL.



CONCRETE RELEASE STRENGTH


UNIT	PSI
40' UNITS	4,000
50' UNITS	4,900

PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
STATION: 14+61.05 -L-

SHEET 5 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

STANDARD
3'-0" X 1'-9"
PRESTRESSED CONCRETE
CORED SLAB UNIT
90° SKEW



ASSEMBLED BY: N.D'AIUTO DATE: 2/20/15
CHECKED BY: T.R.PETERSON DATE: 3/2/15
DRAWN BY: DGE 5/09
CHECKED BY: BCH 6/09 REV. 11/14 MAA/TMG


REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SHEET NO. S-9
TOTAL SHEETS 20

*****SYSTEM*****
*****DCN*****
*****USERNAME*****




PLAN




SECTION E-E

GUARDRAIL ANCHOR ASSEMBLY DETAILS



ELEVATION




PLAN

LOCATION OF ANCHORS FOR GUARDRAIL

END BENT 1 SHOWN, END BENT 2 SIMILAR.

NOTES


- THE GUARDRAIL ANCHOR ASSEMBLY SHALL CONSIST OF A 1/4" HOLD DOWN PLATE AND 7 - 7/8" Ø BOLTS WITH NUTS AND WASHERS.
- THE HOLD-DOWN PLATE SHALL CONFORM TO AASHTO M270 GRADE 36. AFTER FABRICATION, THE HOLD-DOWN PLATE SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH AASHTO M111.
- BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307 AND NUTS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M291. BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS, NUTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 7/8" Ø GALVANIZED BOLTS, NUTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)
- THE GUARDRAIL ANCHOR ASSEMBLY IS REQUIRED AT ALL POINTS WHERE APPROACH GUARDRAIL IS TO BE ATTACHED TO THE END OF BARRIER RAIL. FOR POINTS OF ATTACHMENT, SEE SKETCH.
- AFTER INSTALLATION, THE EXPOSED THREAD OF THE BOLT SHALL BE BURRED WITH A SHARP POINTED TOOL.
- THE COST OF THE GUARDRAIL ANCHOR ASSEMBLY SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR VERTICAL CONCRETE BARRIER RAIL.
- THE VERTICAL REINFORCING BARS MAY BE SHIFTED SLIGHTLY IN THE VERTICAL CONCRETE BARRIER RAIL TO CLEAR ASSEMBLY BOLTS.
- THE 1/4" Ø HOLES SHALL BE FORMED OR DRILLED WITH A CORE BIT. IMPACT TOOLS WILL NOT BE PERMITTED. ANY CONCRETE DAMAGED BY THIS WORK SHALL BE REPAIRED TO THE SATISFACTION OF THE ENGINEER.



SKETCH SHOWING POINTS OF ATTACHMENT

* DENOTES GUARDRAIL ANCHOR ASSEMBLY

PROJECT NO. 17BP.12.R.43
 CLEVELAND COUNTY
 STATION: 14+61.05 -L-



6/6/2017

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 GUARDRAIL ANCHORAGE
 DETAILS
 FOR VERTICAL CONCRETE
 BARRIER RAIL

ASSEMBLED BY : N.D'AIUTO	DATE : 2/20/15
CHECKED BY : T.R.PETERSON	DATE : 3/2/15
DRAWN BY : MAA 5/10	REV. 12/5/11 MAA/GM
CHECKED BY : GM 5/10	REV. 6/13 MAA/GM
	REV. 1/15 MAA/TMG

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1			3			20
2			4			

STD. NO. GRA3


NOTES

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR DOWELS.


THE CONCRETE IN THE SHADED AREA OF THE WING SHALL BE POURED AFTER THE VERTICAL CONCRETE BARRIER RAIL IS CAST IF SLIP FORMING IS USED.

FOR PILE SPLICE DETAILS, SEE SHEET 4 OF 4.

FOR WING DETAILS, SEE SHEET 3 OF 4.



PLAN



ELEVATION


WINGS NOT SHOWN FOR CLARITY.
FOR SECTION A-A, SEE SHEET 4 OF 4.
CONCRETE COLLARS FOR STEEL PILES NOT SHOWN IN PLAN AND ELEVATION VIEWS FOR CLARITY.
SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL", SHEET 4 OF 4.

PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
STATION: 14+61.05 -L-

SHEET 1 OF 4

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SUBSTRUCTURE
END BENT 1



6/6/2017

ASSEMBLED BY : N.D'AIUTO DATE : 2/20/15
CHECKED BY : T.R.PETERSON DATE : 3/2/15
DRAWN BY : WJH 12/11
CHECKED BY : AAC 12/11
REV. 4/15 MAA/TMG

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-11
1			3			TOTAL SHEETS
2			4			20


NOTES

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR DOWELS.


THE CONCRETE IN THE SHADED AREA OF THE WING SHALL BE POURED AFTER THE VERTICAL CONCRETE BARRIER RAIL IS CAST IF SLIP FORMING IS USED.

FOR PILE SPLICE DETAILS, SEE SHEET 4 OF 4.

FOR WING DETAILS, SEE SHEET 3 OF 4.



PLAN



ELEVATION

WINGS NOT SHOWN FOR CLARITY.
FOR SECTION A-A, SEE SHEET 4 OF 4.
CONCRETE COLLARS FOR STEEL PILES NOT SHOWN IN PLAN AND ELEVATION VIEWS FOR CLARITY.
SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL", SHEET 4 OF 4.

PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
STATION: 14+61.05 -L-

SHEET 2 OF 4

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH


SUBSTRUCTURE
END BENT 2




ASSEMBLED BY : N.D'AIUTO	DATE : 2/20/15
CHECKED BY : T.R.PETERSON	DATE : 3/2/15
DRAWN BY : WJH 12/11	REV. 4/15
CHECKED BY : AAC 12/11	MAA/TMG

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-12
1			3			TOTAL SHEETS
2			4			20


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED




PLAN OF WING (W1)




PLAN OF WING (W2)




ELEVATION OF WING (W1)



ELEVATION OF WING (W2)




SECTION X-X



SECTION Y-Y

PROJECT NO. 17BP.12.R.43
 CLEVELAND COUNTY
 STATION: 14+61.05 -L-

SHEET 3 OF 4



6/6/2017

ASSEMBLED BY : N.D'AIUTO DATE : 2/20/15
 CHECKED BY : T.R.PETERSON DATE : 3/2/15
 DRAWN BY : WJH 12/11
 CHECKED BY : AAC 12/11
 REV. 4/15 MAA/TMG


06-JUN-2017 09:51
 S:\DPC3\Division\17BP12R43\Plans\17BP12R43_SD.E*_.01.dgn
 mcheek

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
SUBSTRUCTURE END BENT WING DETAILS					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

SHEET NO.
S-13
TOTAL SHEETS
20

STD. NO. EB_27_90S4




BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.


BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.


TEMPORARY DRAINAGE AT END BENT




PILE SPLICE DETAILS




BILL OF MATERIAL FOR ONE END BENT					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	#9	1	35'-0"	952
B2	28	#4	STR	17'-7"	329
B3	9	#4	STR	2'-5"	15
D1	18	#6	STR	1'-6"	41
H1	40	#4	2	9'-4"	249
K1	16	#4	STR	2'-11"	31
S1	42	#4	3	10'-5"	292
S2	42	#4	4	3'-2"	89
S3	20	#4	5	6'-6"	87
V1	52	#4	STR	6'-2"	214
REINFORCING STEEL (FOR ONE END BENT)					LBS. 2,299
CLASS A CONCRETE BREAKDOWN (FOR ONE END BENT)					
POUR #1 CAP, LOWER PART OF WINGS & COLLARS					C.Y. 16.7
POUR #2 UPPER PART OF WINGS					C.Y. 2.1
TOTAL CLASS A CONCRETE					C.Y. 18.8



END BENT 1 SHOWN, END BENT 2 SIMILAR BY ROTATION



CONCRETE COLLAR NOT SHOWN FOR CLARITY. SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL."




CORROSION PROTECTION FOR STEEL PILES DETAIL

END BENT 1 SHOWN, END BENT 2 SIMILAR BY ROTATION

PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
STATION: 14+61.05 -L-

SHEET 4 OF 4



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH




SUBSTRUCTURE
END BENT 1 & 2
DETAILS

ASSEMBLED BY : N.D'AIUTO	DATE : 2/20/15
CHECKED BY : T.R.PETERSON	DATE : 3/2/15
DRAWN BY : WJH	12/11
CHECKED BY : AAC	12/11

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-14	
1			3			TOTAL SHEETS	
2			4			20	

NOTES

- STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR DOWELS.
- HOOKS ON "V" BARS MAY BE TURNED AS NECESSARY FOR PLACING REINFORCING STEEL.
- FOR DRILLED PIERS, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.
- ALL STEEL IN THE DRILLED PIERS IS INCLUDED IN THE PAY ITEMS FOR "REINFORCING STEEL" AND "SPIRAL COLUMN REINFORCING STEEL."
- ★ INVERT ALTERNATE STIRRUPS.
- THE LOCATION OF THE CONSTRUCTION JOINT IN THE DRILLED PIERS IS BASED ON AN APPROXIMATE GROUND LINE ELEVATION. IF THE CONSTRUCTION JOINT IS ABOVE THE ACTUAL GROUND LINE ELEVATION, THE CONTRACTOR SHALL PLACE THE CONSTRUCTION JOINT ONE FOOT BELOW THE GROUND LINE.
- THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE LONGITUDINAL REINFORCEMENT FOR DRILLED PIERS IS DETAILED WITH 3 FEET OF EXTRA LENGTH.




ASSEMBLED BY :	N.D.AIUTO	DATE :	5/11/15
CHECKED BY :	T.R.PETERSON	DATE :	5/12/15
DRAWN BY :	DGE	4/10	
CHECKED BY :	MKT	4/10	
REV.	11/14	MAA/TMG	

06-JUN-2017 09:51
 S:\DPC3\Division\et+s\Div12\17BP12R43\Plans\17BP12R43_SD.B1.01.dgn
 mcheek

DIMENSIONS & REINFORCING STEEL ARE TYPICAL FOR EACH COLUMN & DRILLED PIER UNLESS OTHERWISE NOTED.

PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
 STATION: 14+61.05 -L-

SHEET 1 OF 2




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

SUBSTRUCTURE
 BENT 1


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-15
1			3			TOTAL SHEETS
2			4			20

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


STD. NO. DP_BT_27_90S_<50'




PLAN OF DRILLED PIERS & COLUMNS




END ELEVATION



CONSTRUCTION JOINT DETAIL




END OF CAP VIEW
(TYPICAL BOTH ENDS)



BAR TYPES


ALL BAR DIMENSIONS ARE OUT TO OUT.

BILL OF MATERIAL					
BENT 1					
BAR NO.	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	10	#11	1	32'-2"	1709
B2	6	#5	STR	29'-2"	183
D1	36	#6	STR	1'-6"	81
M1	10	#11	STR	36'-7"	1944
M2	20	#11	STR	32'-7"	3462
S1	46	#5	2	9'-0"	432
U1	6	#4	3	5'-8"	23
U2	6	#4	3	5'-6"	22
VI	30	#11	4	12'-8"	2019
REINFORCING STEEL				LBS.	9,875
SP-1	1	*	5	426'-0"	444
SP-2	2	*	5	362'-10"	757
SP-3	3	**	6	257'-3"	516
SPIRAL COLUMN REINFORCING STEEL				LBS.	1,717
* THE SP-1 & SP-2 SPIRAL REINFORCING STEEL SHALL BE W31 OR D-31 COLD DRAWN WIRE OR #5 PLAIN OR DEFORMED BAR					
** THE SP-3 SPIRAL REINFORCING STEEL SHALL BE W20 OR D-20 COLD DRAWN WIRE OR #4 PLAIN OR DEFORMED BAR					
CLASS A CONCRETE BREAKDOWN					
POUR #2 (COLUMNS)				C.Y.	4.9
POUR #3 (CAP)				C.Y.	10.4
TOTAL CLASS A CONCRETE				C.Y.	15.3
DRILLED PIER CONCRETE					
POUR #1 (DRILLED PIERS)				C.Y.	18.7
3'-0" DRILLED PIERS IN SOIL				LIN. FT.	29.50
3'-0" DRILLED PIERS NOT IN SOIL				LIN. FT.	42.00
CSL TUBES				LIN. FT.	304.00
SID INSPECTIONS				EA.	1
SPT TESTING				EA.	2
CSL TESTING				EA.	1



SECTION THROUGH CAP

* INVERT ALTERNATE STIRRUPS






PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
STATION: 14+61.05 -L-

SHEET 2 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
SUBSTRUCTURE					
BENT 1					
REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
TOTAL SHEETS					20

ASSEMBLED BY :	N.D.AIUTO	DATE :	5/11/15
CHECKED BY :	T.R.PETERSON	DATE :	5/12/15
DRAWN BY :	DGE 3/10	REV. 11/14	MAA/TMG
CHECKED BY :	MKT 3/10		

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED




NOTES

- STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR DOWELS.
- HOOKS ON "V" BARS MAY BE TURNED AS NECESSARY FOR PLACING REINFORCING STEEL.
- FOR DRILLED PIERS, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.
- ALL STEEL IN THE DRILLED PIERS IS INCLUDED IN THE PAY ITEMS FOR "REINFORCING STEEL" AND "SPIRAL COLUMN REINFORCING STEEL."
- ★ INVERT ALTERNATE STIRRUPS.
- THE LOCATION OF THE CONSTRUCTION JOINT IN THE DRILLED PIERS IS BASED ON AN APPROXIMATE GROUND LINE ELEVATION. IF THE CONSTRUCTION JOINT IS ABOVE THE ACTUAL GROUND LINE ELEVATION, THE CONTRACTOR SHALL PLACE THE CONSTRUCTION JOINT ONE FOOT BELOW THE GROUND LINE.
- THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE LONGITUDINAL REINFORCEMENT FOR DRILLED PIERS IS DETAILED WITH 3 FEET OF EXTRA LENGTH.

ASSEMBLED BY : N.D.AIUTO DATE : 5/11/15
 CHECKED BY : T.R.PETERSON DATE : 5/12/15
 DRAWN BY : DGE 4/10
 CHECKED BY : MKT 4/10 REV. 11/14 MAA/TMG

ELEVATION
 DIMENSIONS & REINFORCING STEEL ARE TYPICAL FOR EACH COLUMN & DRILLED PIER UNLESS OTHERWISE NOTED.


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED




PROJECT NO. 17BP.12.R.43
 CLEVELAND COUNTY
 STATION: 14+61.05 -L-

SHEET 1 OF 2


STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH				SUBSTRUCTURE BENT 2	
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
SHEET NO. S-17					TOTAL SHEETS 20




PLAN OF DRILLED PIERS & COLUMNS




END ELEVATION




CONSTRUCTION JOINT DETAIL



END OF CAP VIEW (TYPICAL BOTH ENDS)



SECTION THROUGH CAP
★ INVERT ALTERNATE STIRRUPS




ALL BAR DIMENSIONS ARE OUT TO OUT.

BILL OF MATERIAL					
BENT 2					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	10	#11	1	32'-2"	1709
B2	6	#5	STR	29'-2"	183
D1	36	#6	STR	1'-6"	81
M1	30	#11	STR	32'-3"	5140
S1	46	#5	2	9'-0"	432
U1	6	#4	3	5'-8"	23
U2	6	#4	3	5'-6"	22
V1	30	#11	4	11'-2"	1780
REINFORCING STEEL				LBS.	9,370
SP-1	3	*	5	357'-10"	1120
SP-2	3	*	6	217'-2"	435
SPIRAL COLUMN REINFORCING STEEL				LBS.	1,555
* THE SP-1 SPIRAL REINFORCING STEEL SHALL BE W31 OR D-31 COLD DRAWN WIRE OR #5 PLAIN OR DEFORMED BAR					
* THE SP-2 SPIRAL REINFORCING STEEL SHALL BE W20 OR D-20 COLD DRAWN WIRE OR #4 PLAIN OR DEFORMED BAR					
CLASS A CONCRETE BREAKDOWN					
POUR #2 (COLUMNS)				C.Y.	4.1
POUR #3 (CAP)				C.Y.	10.4
TOTAL CLASS A CONCRETE				C.Y.	14.5
DRILLED PIER CONCRETE					
POUR #1 (DRILLED PIERS)				C.Y.	17.4
3'-0" Ø DRILLED PIERS IN SOIL				LIN. FT.	27.50
3'-0" Ø DRILLED PIERS NOT IN SOIL				LIN. FT.	39.00
CSL TUBES				LIN. FT.	284.00
SPT TESTING				EA.	2
CSL TESTING				EA.	1

ASSEMBLED BY :	N.D. AIUTO	DATE :	5/11/15
CHECKED BY :	T.R. PETERSON	DATE :	5/12/15
DRAWN BY :	DGE	3/10	
CHECKED BY :	MKT	3/10	
REV.	11/14	MAA/TMC	

*****SYTIME*****
*****DCN*****
*****USERNAME*****

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED






PROJECT NO. 17BP.12.R.43
CLEVELAND COUNTY
STATION: 14+61.05 -L-


STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
SUBSTRUCTURE					
BENT 2					
SHEET NO. S-18					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
TOTAL SHEETS					20

ESTIMATED QUANTITIES

BRIDGE @ STA. 14+61.05 -L-	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE
	TONS	SQUARE YARDS
END BENT 1	137	152
END BENT 2	125	139
TOTAL	262	291



PROJECT NO. 17BP.12.R.43
 CLEVELAND COUNTY
 STATION: 14+61.05 -L-



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 RIP RAP DETAILS


ASSEMBLED BY : N.D'AIUTO	DATE : 2/25/15
CHECKED BY : T.R. PETERSON	DATE : 3/15
DRAWN BY : FCJ 2/88	REV. 8/16/99 RWW/LES
CHECKED BY : ARB 8/88	REV. 10/17/00 RWW/LES
	REV. 5/1/06R TLA/GM

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

TOTAL SHEETS 20

STD. NO. RR2



NOTES

FOR BRIDGE APPROACH FILL INCLUDING GEOTEXTILE, 4" Ø DRAINAGE PIPE, AND #78M STONE BACKFILL, SEE ROADWAY PLANS.

GEOTEXTILE SHALL BE TYPE 1 IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS SECTION 1056.


#78M STONE BACKFILL (CLASS V SELECT MATERIAL) SHALL BE IN ACCORDANCE WITH STANDARD SPECIFICATIONS SECTION 1016.

#78M STONE BACKFILL IS TO BE CONTINUOUS ALONG FILL FACE OF BACKWALL FROM OUTSIDE EDGE TO OUTSIDE EDGE OF APPROACH SLAB.

FOR THE 4" Ø DRAINAGE PIPE OUTLET(S), SEE ROADWAY STANDARD DRAWINGS.


AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

APPROACH SLAB GROOVING IS NOT REQUIRED.



NOTE: IF THE APPROACH SLAB IS NOT CONSTRUCTED IMMEDIATELY AFTER THE BACKFILLING OF THE END BENT EXCAVATION, GRADE TO DRAIN TO THE BOTTOM OF THE SLOPE AND PROVIDE EROSION RESISTANT MATERIAL, SUCH AS FIBERGLASS ROVING OR AS DIRECTED BY THE ENGINEER TO PREVENT SOIL EROSION AND TO PROTECT THE AREA ADJACENT TO THE STRUCTURE. THE CONTRACTOR WILL BE REQUIRED TO REMOVE THESE MATERIALS PRIOR TO CONSTRUCTION OF THE APPROACH SLAB.

TEMPORARY DRAINAGE DETAIL




NOTE: IMMEDIATELY AFTER THE CONSTRUCTION OF THE APPROACH SLAB, THE CONTRACTOR SHALL PROVIDE TEMPORARY BERM AND SLOPE DRAIN. CONTRACTOR SHALL GRADE TO PIPE INLET AND PROVIDE EROSION RESISTANT MATERIAL AS SHOWN. THE EROSION RESISTANT MATERIAL SHALL BE EITHER 1) ASPHALT PLANT MIX, TYPE 1 OR TYPE 2, MIN. 2" DEPTH, 2) EROSION CONTROL MAT, OR 3) CONCRETE, AS DIRECTED BY THE ENGINEER. THE SLOPE DRAIN SHALL CONSIST OF A NON-PERFORATED TEMPORARY DRAINAGE PIPE, 12 INCHES IN DIAMETER.


PLAN VIEW

TEMPORARY BERM AND SLOPE DRAIN DETAILS

(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)



SECTION THROUGH SLAB



CURB DETAILS

BILL OF MATERIAL

APPROACH SLAB AT EB 1

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
*A1	13	#4	STR	25'-10"	224
A2	13	#4	STR	25'-10"	224
*B1	52	#5	STR	11'-2"	606
B2	52	#6	STR	11'-8"	911

REINFORCING STEEL LBS. 1,135

* EPOXY COATED REINFORCING STEEL LBS. 830

CLASS AA CONCRETE C.Y. 15.1

APPROACH SLAB AT EB 2

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
*A1	13	#4	STR	25'-10"	224
A2	13	#4	STR	25'-10"	224
*B1	52	#5	STR	11'-2"	606
B2	52	#6	STR	11'-8"	911


REINFORCING STEEL LBS. 1,135

* EPOXY COATED REINFORCING STEEL LBS. 830

CLASS AA CONCRETE C.Y. 15.1

ASSEMBLED BY : N.D. AIUTO	DATE : 2/20/15
CHECKED BY : T.R. PETERSON	DATE : 3/2/15
DRAWN BY : SHS/MAA	5-09
CHECKED BY : BCH	5-09
REV. 12-11	MAA/AAC
REV. 8-14	MAA/TMG

06-JUN-2017 09:51
 S:\DPC3\Division\et+s\Div12\17BP12R43\Plans\17BP12R43_SD_AS_01.dgn
 mcheek



6/6/2017

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-20
1			3			TOTAL SHEETS
2			4			20

STD. NO. BAS.27.90S

STANDARD NOTES

DESIGN DATA:

SPECIFICATIONS	-----	A.A.S.H.T.O. (CURRENT)
LIVE LOAD	-----	SEE PLANS
IMPACT ALLOWANCE	-----	SEE A.A.S.H.T.O.
STRESS IN EXTREME FIBER OF		
STRUCTURAL STEEL - AASHTO M270 GRADE 36	- -	20,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50W	- -	27,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50	- -	27,000 LBS. PER SQ. IN.
REINFORCING STEEL IN TENSION		
GRADE 60	- -	24,000 LBS. PER SQ. IN.
CONCRETE IN COMPRESSION	-----	1,200 LBS. PER SQ. IN.
CONCRETE IN SHEAR	-----	SEE A.A.S.H.T.O.
STRUCTURAL TIMBER - TREATED OR		
UNTREATED - EXTREME FIBER STRESS	-----	1,800 LBS. PER SQ. IN.
COMPRESSION PERPENDICULAR TO GRAIN OF TIMBER	-----	375 LBS. PER SQ. IN.
EQUIVALENT FLUID PRESSURE OF EARTH	-----	30 LBS. PER CU. FT.
		(MINIMUM)

MATERIAL AND WORKMANSHIP:

EXCEPT AS MAY OTHERWISE BE SPECIFIED ON PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2012 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N. C. DEPARTMENT OF TRANSPORTATION.

STEEL SHEET PILING FOR PERMANENT OR TEMPORARY APPLICATIONS SHALL BE HOT ROLLED.

CONCRETE:

UNLESS OTHERWISE REQUIRED ON PLANS, CLASS A CONCRETE SHALL BE USED FOR ALL PORTIONS OF ALL STRUCTURES WITH THE EXCEPTION THAT: CLASS AA CONCRETE SHALL BE USED IN BRIDGE SUPERSTRUCTURES, ABUTMENT BACKWALLS, AND APPROACH SLABS; AND CLASS B CONCRETE SHALL BE USED FOR SLOPE PROTECTION AND RIP RAP.

CONCRETE CHAMFERS:

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO 1-1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.

DOWELS:

DOWELS WHEN INDICATED ON PLANS AS FOR CULVERT EXTENSIONS, SHALL BE EMBEDDED AT LEAST 12" INTO THE OLD CONCRETE AND GROUTED INTO PLACE WITH 1:2 CEMENT MORTAR.

ALLOWANCE FOR DEAD LOAD DEFLECTION, SETTLEMENT, ETC. IN CASTING SUPERSTRUCTURES:

BRIDGES SHALL BE BUILT ON THE GRADE OR VERTICAL CURVE SHOWN ON PLANS. SLABS, CURBS AND PARAPETS SHALL CONFORM TO THE GRADE OR CURVE. ALL DIMENSIONS WHICH ARE GIVEN IN SECTION AND ARE AFFECTED BY DEAD LOAD DEFLECTIONS ARE DIMENSIONS AT CENTER LINE OF BEARING UNLESS OTHERWISE NOTED ON PLANS. IN SETTING FORMS FOR STEEL BEAM BRIDGES AND PRESTRESSED CONCRETE GIRDER BRIDGES, ADJUSTMENTS SHALL BE MADE DUE TO THE DEAD LOAD DEFLECTIONS FOR THE ELEVATIONS SHOWN. WHERE BLOCKS ARE SHOWN OVER BEAMS FOR BUILDING UP TO THE SLAB, THE VERTICAL DIMENSIONS OF THE BLOCKS SHALL BE ADJUSTED BETWEEN BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTIONS, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. WHERE BOTTOM OF SLAB IS IN LINE WITH BOTTOM OF TOP FLANGES, DEPTH OF SLAB BETWEEN BEARINGS SHALL BE ADJUSTED TO COMPENSATE FOR DEAD LOAD DEFLECTION, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. IN SETTING FALSEWORK AND FORMS FOR REINFORCED CONCRETE SPANS, AN ALLOWANCE SHALL BE MADE FOR DEAD LOAD DEFLECTIONS, SETTLEMENT OF FALSEWORK, AND PERMANENT CAMBER WHICH SHALL BE PROVIDED FOR IN ADDITION TO THE ELEVATIONS SHOWN. AFTER REMOVAL OF THE FALSEWORK, THE FINISHED STRUCTURES SHALL CONFORM TO THE PROFILE AND ELEVATIONS SHOWN ON THE PLANS AND CONSTRUCTION ELEVATIONS FURNISHED BY THE ENGINEER. DETAILED DRAWINGS FOR FALSEWORK OR FORMS FOR BRIDGE SUPERSTRUCTURE AND ANY STRUCTURE OR PARTS OF A STRUCTURE AS NOTED ON THE PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BEFORE CONSTRUCTION OF THE FALSEWORK OR FORMS IS STARTED.

REINFORCING STEEL:

ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS. WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.

STRUCTURAL STEEL:

AT THE CONTRACTOR'S OPTION, HE MAY SUBSTITUTE 7/8" Ø SHEAR STUDS FOR THE 3/4" Ø STUDS SPECIFIED ON THE PLANS. THIS SUBSTITUTION SHALL BE MADE AT THE RATE OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS, AND STUD SPACING CHANGES SHALL BE MADE AS NECESSARY TO PROVIDE THE SAME EQUIVALENT NUMBER OF 7/8" Ø STUDS ALONG THE BEAM AS SHOWN FOR 3/4" Ø STUDS BASED ON THE RATIO OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS. STUDS OF THE LENGTH SPECIFIED ON THE PLANS MUST BE PROVIDED. THE MAXIMUM SPACING SHALL BE 2'-0". EXCEPT AT THE INTERIOR SUPPORTS OF CONTINUOUS BEAMS WHERE THE COVER PLATE IS IN CONTACT WITH BEARING PLATE, THE CONTRACTOR MAY, AT HIS OPTION, SUBSTITUTE FOR THE COVER PLATES DESIGNATED ON THE PLANS COVER PLATES OF THE EQUIVALENT AREA PROVIDED THESE PLATES ARE AT LEAST 5/16" IN THICKNESS AND DO NOT EXCEED A WIDTH EQUAL TO THE FLANGE WIDTH LESS 2" OR A THICKNESS EQUAL TO 2 TIMES THE FLANGE THICKNESS. THE SIZE OF FILLET WELDS SHALL CONFORM TO THE REQUIREMENTS OF THE CURRENT ANSI/AASHTO/AWS "BRIDGE WELDING CODE". ELECTROSLAG WELDING WILL NOT BE PERMITTED. WITH THE SOLE EXCEPTION OF EDGES AT SURFACES WHICH BEAR ON OTHER SURFACES, ALL SHARP EDGES AND ENDS OF SHAPES AND PLATES SHALL BE SLIGHTLY ROUNDED BY SUITABLE MEANS TO A RADIUS OF APPROXIMATELY 1/16 INCH OR EQUIVALENT FLAT SURFACE AT A SUITABLE ANGLE PRIOR TO PAINTING, GALVANIZING, OR METALLIZING.

HANDRAILS AND POSTS:

METAL STANDARDS AND FACES OF THE CONCRETE END POSTS FOR THE METAL RAIL SHALL BE SET NORMAL TO THE GRADE OF THE CURB, UNLESS OTHERWISE SHOWN ON PLANS. THE METAL RAIL AND TOPS OF CONCRETE POSTS USED WITH THE ALUMINUM RAIL SHALL BE BUILT PARALLEL TO THE GRADE OF THE CURB. METAL HANDRAILS SHALL BE IN ACCORDANCE WITH THE PLANS. RAILS SHALL BE AS MANUFACTURED FOR BRIDGE RAILING. CASTINGS SHALL BE OF A UNIFORM APPEARANCE. FINS AND OTHER DEFORMATIONS RESULTING FROM CASTING OR OTHERWISE SHALL BE REMOVED IN A MANNER SO THAT A UNIFORM COLORING OF THE COMPLETED CASTING SHALL BE OBTAINED. CASTINGS WITH DISCOLORATIONS OR OF NON-UNIFORM COLORING WILL NOT BE ACCEPTED. CERTIFIED MILL REPORTS ARE REQUIRED FOR METAL RAILS AND POSTS.

SPECIAL NOTES:

GENERALLY, IN CASE OF DISCREPANCY, THIS STANDARD SHEET OF NOTES SHALL GOVERN OVER THE SPECIFICATIONS, BUT THE REMAINDER OF THE PLANS SHALL GOVERN OVER NOTES HEREON, AND SPECIAL PROVISIONS SHALL GOVERN OVER ALL. SEE SPECIFICATIONS ARTICLE 105-4.

ENGLISH

JANUARY, 1990