

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.13.R.86	1	13

**STATE OF NORTH CAROLINA**  
**DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF HIGHWAYS**  
**GEOTECHNICAL ENGINEERING UNIT**

**STRUCTURE**  
**SUBSURFACE INVESTIGATION**

PROJ. REFERENCE NO. 17BP.13.R.86 F.A. PROJ. N/A  
COUNTY Yancey  
PROJECT DESCRIPTION Bridge No. 189 on SR 1404 over Roaring Fork Creek

**CONTENTS**

<u>SHEET</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2, 2A	LEGEND
3	SITE PLAN
4	BORING LOCATION PLAN
5-10	BORE LOG AND CORE REPORTS
11-12	ROCK CORE PHOTOS

PERSONNEL

C. Boyce

J. Pickett

M. Hosseini

R. Kral, E.I.

INVESTIGATED BY F&R, Inc.

CHECKED BY M. Walko, P.E.

SUBMITTED BY F&R, Inc.

DATE December 2012

**CAUTION NOTICE**

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.


GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

DRAWN BY: M. Brewer, E.I.



# NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

## DIVISION OF HIGHWAYS

### GEOTECHNICAL ENGINEERING UNIT

## SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

### SOIL DESCRIPTION

SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (AASHTO T206, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE:

*VERY STIFF, GRAY SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6*

### GRADATION

**WELL GRADED** - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE.  
**UNIFORM** - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED)  
**GAP-GRADED** - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.

### ANGULARITY OF GRAINS

THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS **ANGULAR**, **SUBANGULAR**, **SUBROUNDED**, OR **ROUNDED**.

### SOIL LEGEND AND AASHTO CLASSIFICATION

GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)							SILT-CLAY MATERIALS (> 35% PASSING #200)				ORGANIC MATERIALS			
GROUP CLASS.	A-1		A-3		A-2			A-4	A-5	A-6	A-7	A-1, A-2	A-4, A-5		
SYMBOL	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7					A-7-5	A-7-6	A-3	A-6, A-7	
% PASSING	50 MX 30 MX 50 MX 15 MX 25 MX		51 MN	35 MX	35 MX	35 MX	35 MX	36 MN	36 MN	36 MN	36 MN				
LIQUID LIMIT	6 MX		NP	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN				
PLASTIC INDEX	6 MX		NP	10 MX	10 MX	11 MN	11 MN	10 MX	10 MX	11 MN	11 MN				
GROUP INDEX	0		0	0	0	4 MX	8 MX	12 MX	16 MX	No MX					
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND		FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND			SILTY SOILS	CLAYEY SOILS		SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER			HIGHLY ORGANIC SOILS		
GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD							FAIR TO POOR			FAIR TO POOR	POOR	UNSATURABLE		

### MINERALOGICAL COMPOSITION

MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.

### COMPRESSIBILITY

**SLIGHTLY COMPRESSIBLE**      LIQUID LIMIT LESS THAN 31  
**MODERATELY COMPRESSIBLE**      LIQUID LIMIT EQUAL TO 31-50  
**HIGHLY COMPRESSIBLE**      LIQUID LIMIT GREATER THAN 50

### PERCENTAGE OF MATERIAL

ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME
HIGHLY ORGANIC	>10%	>20%	HIGHLY

### GROUND WATER

- WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING
- STATIC WATER LEVEL AFTER 24 HOURS
- PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA
- SPRING OR SEEP

### CONSISTENCY OR DENSENESS

PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT <sup>2</sup> )
GENERALLY GRANULAR MATERIAL (NON-COHESSIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	<4 4 TO 10 10 TO 30 30 TO 50 >50	N/A
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	<2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30	<0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 >4

### MISCELLANEOUS SYMBOLS

- ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION
- SOIL SYMBOL
- ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT
- INFERRED SOIL BOUNDARY
- INFERRED ROCK LINE
- ALLUVIAL SOIL BOUNDARY
- DIP & DIP DIRECTION OF ROCK STRUCTURES
- SPT DMT VST PMT TEST BORING
- AUGER BORING
- CORE BORING
- MONITORING WELL
- PIEZOMETER INSTALLATION
- SLOPE INDICATOR INSTALLATION
- CONE PENETROMETER TEST
- SOUNDING ROD
- TEST BORING W/ CORE
- SPT N-VALUE
- SPT REFUSAL

### TEXTURE OR GRAIN SIZE

U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270
	4.76	2.00	0.42	0.25	0.075	0.053

BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)
GRAIN SIZE	MM 305 IN. 12	75 3	2.0	0.25	0.05	0.005

### SOIL MOISTURE - CORRELATION OF TERMS

SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE
PLASTIC RANGE (PI)	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE
OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE
SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE

### PLASTICITY

NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH
LOW PLASTICITY	0-5	VERY LOW
MED. PLASTICITY	6-15	SLIGHT
HIGH PLASTICITY	16-25	MEDIUM
	26 OR MORE	HIGH

### COLOR

DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.

### ABBREVIATIONS


- AR - AUGER REFUSAL
  - BT - BORING TERMINATED
  - CL - CLAY
  - CPT - CONE PENETRATION TEST
  - CSE. - COARSE
  - CT - CORING TERMINATED
  - DMT - DILATOMETER TEST
  - DPT - DYNAMIC PENETRATION TEST
  - e - VOID RATIO
  - EMBANK. - EMBANKMENT
  - F - FINE
  - FOSS. - FOSSILIFEROUS
  - FRAC. - FRACTURED, FRACTURES
  - FRAGS. - FRAGMENTS
  - HI. - HIGHLY
  - MED. - MEDIUM
  - MICA. - MICACEOUS
  - MOD. - MODERATELY
  - NP - NON PLASTIC
  - ORG. - ORGANIC
  - PMT - PRESSUREMETER TEST
  - SAP. - SAPROLITIC
  - SDY. - SANDY
  - SL. - SILT, SILTY
  - SLI. - SLIGHTLY
  - TCR - TRICONE REFUSAL
  - w - MOISTURE CONTENT
  - v - VERY
  - WEA. - WEATHERED
  - γ<sub>u</sub> - UNIT WEIGHT
  - γ<sub>d</sub> - DRY UNIT WEIGHT
- SAMPLE ABBREVIATIONS**
- S - BULK
  - SS - SPLIT SPOON
  - ST - SHELBY TUBE
  - RS - ROCK
  - RT - RECOMPACTED TRIAXIAL
  - CBR - CALIFORNIA BEARING RATIO

### EQUIPMENT USED ON SUBJECT PROJECT

DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:
<input type="checkbox"/> MOBILE B- _____	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL
<input type="checkbox"/> BK-51	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE:
<input checked="" type="checkbox"/> CME-550X	<input checked="" type="checkbox"/> 8" HOLLOW AUGERS	<input type="checkbox"/> -B _____
<input type="checkbox"/> CME-75	<input type="checkbox"/> HARD FACED FINGER BITS	<input checked="" type="checkbox"/> -N 02
<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG.-CARBIDE INSERTS	<input type="checkbox"/> -H _____
<input type="checkbox"/> _____	<input type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER	HAND TOOLS:
<input type="checkbox"/> _____	<input type="checkbox"/> TRICONE _____ * STEEL TEETH	<input type="checkbox"/> POST HOLE DIGGER
<input type="checkbox"/> _____	<input type="checkbox"/> TRICONE _____ * TUNG.-CARB.	<input type="checkbox"/> HAND AUGER
<input type="checkbox"/> _____	<input checked="" type="checkbox"/> CORE BIT	<input type="checkbox"/> SOUNDING ROD
<input type="checkbox"/> _____	<input type="checkbox"/> _____	<input type="checkbox"/> VANE SHEAR TEST

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
GEOTECHNICAL ENGINEERING UNIT  
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**

ROCK DESCRIPTION		TERMS AND DEFINITIONS	
<p>HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:</p>		<p>ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER.  <b>AQUIFER</b> - A WATER BEARING FORMATION OR STRATA.  <b>ARENACEOUS</b> - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND.  <b>ARGILLACEOUS</b> - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC.  <b>ARTESIAN</b> - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE.  <b>CALCAREOUS (CALC.)</b> - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE.  <b>COLLUVIUM</b> - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE.  <b>CORE RECOVERY (REC.)</b> - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.  <b>DIKE</b> - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK.  <b>DIP</b> - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL.  <b>DIP DIRECTION (DIP AZIMUTH)</b> - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH.  <b>FAULT</b> - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE.  <b>FISSILE</b> - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES.  <b>FLOAT</b> - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL.  <b>FLOOD PLAIN (FP)</b> - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM.  <b>FORMATION (FM.)</b> - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD.  <b>JOINT</b> - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED.  <b>LEDGE</b> - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT.  <b>LENS</b> - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS.  <b>MOTTLED (MOT.)</b> - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE.  <b>PERCHED WATER</b> - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM.  <b>RESIDUAL (RES.) SOIL</b> - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK.  <b>ROCK QUALITY DESIGNATION (RQD)</b> - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.  <b>SAPROLITE (SAP.)</b> - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK.  <b>SILL</b> - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS.  <b>SLICKENSIDE</b> - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE.  <b>STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT)</b> - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS.  <b>STRATA CORE RECOVERY (SREC.)</b> - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE.  <b>STRATA ROCK QUALITY DESIGNATION (SRQD)</b> - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE.  <b>TOPSOIL (TS.)</b> - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.</p>	
<p><b>WEATHERED ROCK (WR)</b></p> 	<p>NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES &gt; 100 BLOWS PER FOOT IF TESTED.</p>		
<p><b>CRYSTALLINE ROCK (CR)</b></p> 	<p>FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.</p>		
<p><b>NON-CRYSTALLINE ROCK (NCR)</b></p> 	<p>FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.</p>		
<p><b>COASTAL PLAIN SEDIMENTARY ROCK (CP)</b></p> 	<p>COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.</p>		
WEATHERING			
<p><b>FRESH</b></p>	<p>ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE.</p>		
<p><b>VERY SLIGHT (V SL.)</b></p>	<p>ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.</p>		
<p><b>SLIGHT (SL.)</b></p>	<p>ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.</p>		
<p><b>MODERATE (MOD.)</b></p>	<p>SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.</p>		
<p><b>MODERATELY SEVERE (MOD. SEV.)</b></p>	<p>ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. <i>IF TESTED, WOULD YIELD SPT REFUSAL</i></p>		
<p><b>SEVERE (SEV.)</b></p>	<p>ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <i>IF TESTED, YIELDS SPT N VALUES &gt; 100 BPF</i></p>		
<p><b>VERY SEVERE (V SEV.)</b></p>	<p>ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. <i>IF TESTED, YIELDS SPT N VALUES &lt; 100 BPF</i></p>		
<p><b>COMPLETE</b></p>	<p>ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.</p>		
ROCK HARDNESS			
<p><b>VERY HARD</b></p>	<p>CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.</p>		
<p><b>HARD</b></p>	<p>CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.</p>		
<p><b>MODERATELY HARD</b></p>	<p>CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.</p>		
<p><b>MEDIUM HARD</b></p>	<p>CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.</p>		
<p><b>SOFT</b></p>	<p>CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.</p>		
<p><b>VERY SOFT</b></p>	<p>CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGERNAIL.</p>		
FRACTURE SPACING		BEDDING	
<p><b>TERM</b></p>	<p><b>SPACING</b></p>	<p><b>TERM</b></p>	<p><b>THICKNESS</b></p>
<p>VERY WIDE</p>	<p>MORE THAN 10 FEET</p>	<p>VERY THICKLY BEDDED</p>	<p>&gt; 4 FEET</p>
<p>WIDE</p>	<p>3 TO 10 FEET</p>	<p>THICKLY BEDDED</p>	<p>1.5 - 4 FEET</p>
<p>MODERATELY CLOSE</p>	<p>1 TO 3 FEET</p>	<p>THINLY BEDDED</p>	<p>0.16 - 1.5 FEET</p>
<p>CLOSE</p>	<p>0.16 TO 1 FEET</p>	<p>VERY THINLY BEDDED</p>	<p>0.03 - 0.16 FEET</p>
<p>VERY CLOSE</p>	<p>LESS THAN 0.16 FEET</p>	<p>THICKLY LAMINATED</p>	<p>0.008 - 0.03 FEET</p>
		<p>THINLY LAMINATED</p>	<p>&lt; 0.008 FEET</p>
INDURATION			
<p>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</p>			
<p><b>FRIABLE</b></p>	<p>RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</p>		
<p><b>MODERATELY INDURATED</b></p>	<p>GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</p>		
<p><b>INDURATED</b></p>	<p>GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</p>		
<p><b>EXTREMELY INDURATED</b></p>	<p>SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</p>		
<p><b>BENCH MARK:</b> Survey information provided by KCI Associates of NC.</p>			
<p><b>ELEVATION:</b></p>			<p><b>FT.</b></p>
<p><b>NOTES:</b></p>			



**SITE**

Roaring Fork Rd




**SINCE FROEHLING & ROBERTSON, INC.**

*Engineering Stability Since 1881*

2505 Hutchison-McDonald Road  
 Charlotte, North Carolina 28269 | USA  
 T 704.596.2889 | F 704.596.3784  
 www.fandr.com


**SITE LOCATION PLAN**

PROJECT REFERENCE NO.: 17BP.13.R.86		F&R PROJECT NO.: 63N-0266
I.D. NO.: N/A	F.A. PROJECT NO.: N/A	COUNTY: Yancey
PROJECT DESCRIPTION: Bridge #189 on SR 1404 over Roaring Fork Creek		
SITE DESCRIPTION: Bridge #189 on SR 1404 over Roaring Fork Creek		
DRAWN BY: R. Kral	CHECKED BY: M. Walko, P.E.	
DATE: November 2012	SCALE: NOT TO SCALE	
		<b>DRAWING No.: 1</b>



**PLAN**

(PILES NOT SHOWN IN PLAN VIEW)



**FROEHLING & ROBERTSON, INC.**

*Engineering Stability Since 1881*

2505 Hutchison-McDonald Road  
 Charlotte, North Carolina 28269 | USA  
 T 704.596.2889 | F 704.596.3784  
 www.fandr.com

**BORING LOCATION PLAN**

PROJECT REFERENCE NO.: 17BP.13.R.86		F&R PROJECT NO.: 63N-0266
I.D. NO.: N/A	F.A. PROJECT NO.: N/A	COUNTY: Yancey
PROJECT DESCRIPTION: Bridge #189 on SR 1404 over Roaring Fork Creek		
SITE DESCRIPTION: Bridge #189 on SR 1404 over Roaring Fork Creek		
DRAWN BY: R. Kral	CHECKED BY: M. Walko, P.E.	
DATE: November 2012	SCALE: 1"=15'	

DRAWING No.: **2**



# NCDOT GEOTECHNICAL ENGINEERING UNIT

## BORELOG REPORT

WBS 17BP.13.R.86		TIP N/A		COUNTY Yancey		GEOLOGIST R. Kral										
SITE DESCRIPTION Bridge 189 on SR 1404 over Roaring Fork Creek							GROUND WTR (ft)									
BORING NO. EB1-A		STATION 12+89		OFFSET 12 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 3,010.1 ft		TOTAL DEPTH 20.0 ft		NORTHING 830,989		EASTING 979,748										
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic										
DRILLER C. Boyce		START DATE 08/09/12		COMP. DATE 08/10/12		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
3015																
3010	3,010.1	0.0	1	3	4										3,010.1	0.0
3005	3,006.6	3.5	11	9	12										3,007.1	3.0
3000	3,002.1	8.0	60/0.0												3,002.1	8.0
2995															3,000.1	10.0
															2,990.1	20.0
Boring Terminated at Elevation 2,990.1 ft in Crystalline Rock (Biotite Gneiss)																

NCDOT BORE SINGLE 63N-0266-0009 - GROUP R BRIDGE 189.GPJ NC\_DOT.GDT 11/13/13



# NCDOT GEOTECHNICAL ENGINEERING UNIT CORE BORING REPORT

WBS 17BP.13.R.86		TIP N/A		COUNTY Yancey		GEOLOGIST R. Kral						
SITE DESCRIPTION Bridge 189 on SR 1404 over Roaring Fork Creek							GROUND WTR (ft)					
BORING NO. EB1-A		STATION 12+89		OFFSET 12 ft LT		ALIGNMENT -L-						
COLLAR ELEV. 3,010.1 ft		TOTAL DEPTH 20.0 ft		NORTHING 830,989		EASTING 979,748						
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic						
DRILLER C. Boyce		START DATE 08/09/12		COMP. DATE 08/10/12		SURFACE WATER DEPTH N/A						
CORE SIZE NQ-2		TOTAL RUN 12.0 ft										
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		L O G	DESCRIPTION AND REMARKS	DEPTH (ft)	
					REC. (ft) %	RQD (ft) %	REC. (ft) %	RQD (ft) %				
3002.1										Begin Coring @ 8.0 ft		
3000	3,002.1	8.0	5.0	N=60/0.0 1:20/1.0 1:28/1.0 3:35/1.0 6:29/1.0 7:26/1.0	(4.0) 80%	(2.6) 52%	(1.7) 84%	(0.5) 25%		3,002.1 3,000.1	8.0 10.0	
	2,997.1	13.0					(9.3) 93%	(8.6) 86%		CRYSTALLINE ROCK Gray and white moderately hard to hard, slightly weathered, very close to closely spaced fractured hornblende MUSCOVITE GNEISS		
2995			5.0	9:10/1.0 14:12/1.0 4:38/1.0 4:34/1.0 4:12/1.0	(4.9) 98%	(4.7) 93%				CRYSTALLINE ROCK Gray and white hard to very hard, fresh to very slightly weathered, very close to moderately closely spaced fractured muscovite BIOTITE GNEISS		
	2,992.1	18.0										
	2,990.1	20.0	2.0	4:02/1.0 7:02/1.0	(2.0) 100%	(1.9) 96%				2,990.1	20.0	
Boring Terminated at Elevation 2,990.1 ft in Crystalline Rock (Biotite Gneiss)												

NCDOT CORE SINGLE 63N-0266-0009 - GROUP R BRIDGE 189.GPJ NC\_DOT.GDT 11/13/13



# NCDOT GEOTECHNICAL ENGINEERING UNIT BORELOG REPORT

WBS 17BP.13.R.86	TIP N/A	COUNTY Yancey	GEOLOGIST R. Kral
SITE DESCRIPTION Bridge 189 on SR 1404 over Roaring Fork Creek			GROUND WTR (ft)
BORING NO. EB1-B	STATION 12+79	OFFSET 15 ft RT	ALIGNMENT -L-
COLLAR ELEV. 3,008.0 ft	TOTAL DEPTH 6.0 ft	NORTHING 830,992	EASTING 979,777
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011		DRILL METHOD H.S. Augers	HAMMER TYPE Automatic
DRILLER C. Boyce	START DATE 08/16/12	COMP. DATE 08/16/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)
3010														
	3,008.0	0.0	2	4	5									GROUND SURFACE 0.0
3005	3,004.5	3.5	4	5	95							M		<b>ROADWAY EMBANKMENT</b> Brown clayey fine to coarse SAND (A-2-6), trace to some rock fragments 4.0
	3,002.0	6.0	60	0	0							W		<b>WEATHERED ROCK</b> Brown and tan biotite gneiss 6.0
														Boring Terminated with Standard Penetration Test Refusal at Elevation 3,002.0 ft on Crystalline Rock (Biotite Gneiss)

NCDOT BORE SINGLE 63N-0266-0009 - GROUP R BRIDGE 189.GPJ NC\_DOT.GDT 11/13/13





# NCDOT GEOTECHNICAL ENGINEERING UNIT BORELOG REPORT

WBS 17BP.13.R.86		TIP N/A		COUNTY Yancey		GEOLOGIST R. Kral											
SITE DESCRIPTION Bridge 189 on SR 1404 over Roaring Fork Creek							GROUND WTR (ft)										
BORING NO. EB2-A		STATION 13+32		OFFSET 10 ft LT		ALIGNMENT -L-											
COLLAR ELEV. 3,014.0 ft		TOTAL DEPTH 15.0 ft		NORTHING 831,026		EASTING 979,728											
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic											
DRILLER C. Boyce		START DATE 08/09/12		COMP. DATE 08/09/12		SURFACE WATER DEPTH N/A											
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	LOG G	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
3015	3,014.0	0.0													3,014.0	0.0	GROUND SURFACE
			2	4	22								M		3,012.5	1.5	<b>ROADWAY EMBANKMENT</b> Brown clayey fine to coarse SAND (A-2-6), trace rock fragments
3010	3,010.5	3.5	4	5	10								W				<b>ALLUVIAL</b> Brown, black and tan clayey fine to coarse SAND (A-2-6), some rock fragments
3005	3,005.5	8.5	29	22	27								W		3,005.5	8.5	<b>RESIDUAL</b> Brown and tan clayey fine to coarse SAND (A-2-6), some rock fragments
3000	3,000.5	13.5													3,000.5	13.5	
	2,999.0	15.0	31	69/0.2											2,999.0	15.0	<b>WEATHERED ROCK</b> Orange, brown and black biotite gneiss Boring Terminated with Standard Penetration Test Refusal at Elevation 2,999.0 ft on Crystalline Rock (Biotite Gneiss)
			60/0.0														

NCDOT BORE SINGLE 63N-0266-0009 - GROUP R BRIDGE 189.GPJ NC\_DOT.GDT 11/13/13



# NCDOT GEOTECHNICAL ENGINEERING UNIT

## BORELOG REPORT

WBS 17BP.13.R.86		TIP N/A		COUNTY Yancey		GEOLOGIST R. Kral										
SITE DESCRIPTION Bridge 189 on SR 1404 over Roaring Fork Creek								GROUND WTR (ft)								
BORING NO. EB2-B		STATION 13+14		OFFSET 5 ft RT		ALIGNMENT -L-		0 HR. 5.0								
COLLAR ELEV. 3,012.5 ft		TOTAL DEPTH 26.0 ft		NORTHING 831,019		EASTING 979,749		24 HR. FIAD								
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic										
DRILLER C. Boyce		START DATE 08/16/12		COMP. DATE 08/16/12		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
3015																
	3,012.5	0.0													3,012.5	0.0
3010			1	3	6							M		3,009.5	3.0	GROUND SURFACE ROADWAY EMBANKMENT Brown clayey fine to coarse SAND (A-2-6), trace rock fragments Boulder Fill
3005														3,005.5	7.0	RESIDUAL Brown and tan silty fine to coarse SAND (A-2-4(0)), some rock fragments
	3,004.0	8.5												3,001.5	11.0	
			51	9	16							SS-2	15%			
3000	3,001.5	11.0												2,999.5	13.0	CRYSTALLINE ROCK Gray and white hornblende muscovite gneiss
			60/0.0											2,996.5	16.0	CRYSTALLINE ROCK Gray and brown biotite schist
2995																CRYSTALLINE ROCK Gray and white muscovite gneiss
2990																
														2,986.5	26.0	Boring Terminated at Elevation 2,986.5 ft in Crystalline Rock (Muscovite Gneiss)  1) Drillers used coring equipment (NQ-2) and roller cone to penetrate boulder fill layer.

NCDOT BORE SINGLE 63N-0266-0009 - GROUP P BRIDGE 189.GPJ NC\_DOT.GDT 11/13/13



# NCDOT GEOTECHNICAL ENGINEERING UNIT CORE BORING REPORT


WBS 17BP.13.R.86		TIP N/A		COUNTY Yancey			GEOLOGIST R. Kral				
SITE DESCRIPTION Bridge 189 on SR 1404 over Roaring Fork Creek									GROUND WTR (ft)		
BORING NO. EB2-B		STATION 13+14		OFFSET 5 ft RT		ALIGNMENT -L-		0 HR. 5.0			
COLLAR ELEV. 3,012.5 ft		TOTAL DEPTH 26.0 ft		NORTHING 831,019		EASTING 979,749		24 HR. FIAD			
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011						DRILL METHOD H.S. Augers		HAMMER TYPE Automatic			
DRILLER C. Boyce			START DATE 08/16/12		COMP. DATE 08/16/12		SURFACE WATER DEPTH N/A				
CORE SIZE NQ-2			TOTAL RUN 15.0 ft								
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		L O G	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (ft) %	RQD (ft) %	REC. (ft) %	RQD (ft) %			
3001.54											
3000	3,001.5	11.0	5.0	N=60/0.0 2:16/1.0 2:33/1.0 6:12/1.0 2:01/1.0 2:16/1.0	(3.3) 67%	(0.3) 7%	(2.0) 100%	(0.3) 17%		Begin Coring @ 11.0 ft	11.0
										Gray and white hard, slightly weathered, very close to closely spaced fractured hornblende MUSCOVITE GNEISS	13.0
2995	2,996.5	16.0	5.0	3:25/1.0 4:40/1.0 4:58/1.0 6:37/1.0 8:13/1.0	(4.6) 92%	(4.6) 92%	(1.3) 44%	(0.0) 0%		Gray and brown moderately hard to hard, slightly to moderately weathered, very closely spaced fractured BIOTITE SCHIST	16.0
										Gray and white hard to very hard, fresh to very slightly weathered, close to moderately spaced fractured MUSCOVITE GNEISS	
2990	2,991.5	21.0	5.0	9:42/1.0 13:29/1.0 20:23/1.0 3:45/1.0 4:26/1.0	(4.8) 97%	(4.8) 97%					
	2,986.5	26.0								Boring Terminated at Elevation 2,986.5 ft in Crystalline Rock (Muscovite Gneiss)	26.0
1) Drillers used coring equipment (NQ-2) and roller cone to penetrate boulder fill layer.											

NCDOT CORE SINGLE 63N-0266-0009 - GROUP R BRIDGE 189.GPJ NC\_DOT.GDT 11/13/13




**Bridge 990189 – SR 1404 across Roaring Fork Creek  
CORE PHOTOGRAPHS: EB1-A: Station 12+89**

**8.0 feet**





**18.0 feet**






**Bridge 990189 – SR 1404 across Roaring Fork Creek  
CORE PHOTOGRAPHS: EB2-B: Station 13+14**

**11.0 feet**



**21.0 feet**



STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.13.R.81	1	13

**STATE OF NORTH CAROLINA**  
**DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF HIGHWAYS**  
**GEOTECHNICAL ENGINEERING UNIT**

**STRUCTURE**  
**SUBSURFACE INVESTIGATION**

PROJ. REFERENCE NO. 17BP.13.R.81 F.A. PROJ. NA  
COUNTY Yancey  
PROJECT DESCRIPTION Bridge No. 990149 on SR 1403 over Roaring Fork Creek

**CONTENTS**

<u>SHEET</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2, 2A	LEGEND
3	SITE PLAN
4	BORING LOCATION PLAN
5-10	BORE LOG AND CORE REPORTS
11-12	ROCK CORE PHOTOS

PERSONNEL

- C. Boyce
- J. Pickett
- M. Hosseini
- R. Kral, E.I.
- J. Harris

INVESTIGATED BY F&R, Inc.  
CHECKED BY M. Walko, P.E.  
SUBMITTED BY F&R, Inc.  
DATE January 2013

**CAUTION NOTICE**

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.


GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

DRAWN BY: M. Brewer, E.I.



# NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

## DIVISION OF HIGHWAYS

### GEOTECHNICAL ENGINEERING UNIT

## SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

### SOIL DESCRIPTION

SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (AASHTO T206, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE:

*VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6*

### GRADATION

**WELL GRADED** - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE.  
**UNIFORM** - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED)  
**GAP-GRADED** - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.

### ANGULARITY OF GRAINS

THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS **ANGULAR**, **SUBANGULAR**, **SUBROUNDED**, OR **ROUNDED**.

### SOIL LEGEND AND AASHTO CLASSIFICATION

GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)							SILT-CLAY MATERIALS (> 35% PASSING #200)				ORGANIC MATERIALS		
GROUP CLASS.	A-1	A-3	A-2		A-4	A-5	A-6	A-7	A-1, A-2	A-4, A-5				
SYMBOL														
% PASSING	# 10 # 40 # 200													
LIQUID LIMIT	50 MX 30 MX 15 MX	50 MX 25 MX	51 MN											
PLASTIC INDEX	6 MX	NP	40 MX 10 MX	41 MN 10 MN	40 MX 11 MN	41 MN 11 MN	40 MX 10 MX	41 MN 11 MN	40 MX 10 MX	41 MN 11 MN	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER		HIGHLY ORGANIC SOILS	
GROUP INDEX	0	0	0	4 MX	8 MX	12 MX	16 MX	No MX						
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND	FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS	CLAYEY SOILS								
GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD				FAIR TO POOR		FAIR TO POOR	POOR	UNSATURABLE					

### MINERALOGICAL COMPOSITION

MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.

### COMPRESSIBILITY

SLIGHTLY COMPRESSIBLE  
 MODERATELY COMPRESSIBLE  
 HIGHLY COMPRESSIBLE

LIQUID LIMIT LESS THAN 31  
 LIQUID LIMIT EQUAL TO 31-50  
 LIQUID LIMIT GREATER THAN 50

### PERCENTAGE OF MATERIAL

ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME
HIGHLY ORGANIC	>10%	>20%	HIGHLY
			1 - 10% 10 - 20% 20 - 35% 35% AND ABOVE

### GROUND WATER

- WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING
- STATIC WATER LEVEL AFTER 24 HOURS
- PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA
- SPRING OR SEEP

### CONSISTENCY OR DENSENESS

PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT <sup>2</sup> )
GENERALLY GRANULAR MATERIAL (NON-COHESSIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	<4 4 TO 10 10 TO 30 30 TO 50 >50	N/A
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	<2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30	<0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 >4

### MISCELLANEOUS SYMBOLS

- ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION
- SOIL SYMBOL
- ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT
- INFERRED SOIL BOUNDARY
- INFERRED ROCK LINE
- ALLUVIAL SOIL BOUNDARY
- DIP & DIP DIRECTION OF ROCK STRUCTURES
- SPT DMT VST PMT TEST BORING
- AUGER BORING
- CORE BORING
- MONITORING WELL
- PIEZOMETER INSTALLATION
- SLOPE INDICATOR INSTALLATION
- CONE PENETROMETER TEST
- SOUNDING ROD
- TEST BORING W/ CORE
- SPT N-VALUE
- SPT REFUSAL

### TEXTURE OR GRAIN SIZE

U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270
	4.76	2.00	0.42	0.25	0.075	0.053

BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)
GRAIN SIZE	MM 305 IN. 12	75 3	2.0	0.25	0.05	0.005

### SOIL MOISTURE - CORRELATION OF TERMS

SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE
PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE
OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE
SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE

### PLASTICITY

NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH
LOW PLASTICITY	0-5	VERY LOW
MED. PLASTICITY	6-15	SLIGHT
HIGH PLASTICITY	16-25	MEDIUM
	26 OR MORE	HIGH

### COLOR

DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.

### ABBREVIATIONS

- AR - AUGER REFUSAL
  - BT - BORING TERMINATED
  - CL - CLAY
  - CPT - CONE PENETRATION TEST
  - CSE. - COARSE
  - CT - CORING TERMINATED
  - DMT - DILATOMETER TEST
  - DPT - DYNAMIC PENETRATION TEST
  - e - VOID RATIO
  - EMBANK. - EMBANKMENT
  - F - FINE
  - FOSS. - FOSSILIFEROUS
  - FRAC. - FRACTURED, FRACTURES
  - FRAGS. - FRAGMENTS
  - HI. - HIGHLY
  - MED. - MEDIUM
  - MICA. - MICACEOUS
  - MOD. - MODERATELY
  - NP - NON PLASTIC
  - ORG. - ORGANIC
  - PMT - PRESSUREMETER TEST
  - SAP. - SAPROLITIC
  - SDY. - SANDY
  - SL. - SILT, SILTY
  - SLI. - SLIGHTLY
  - TCR - TRICONE REFUSAL
  - w - MOISTURE CONTENT
  - v - VERY
  - WEA. - WEATHERED
  - γ<sub>u</sub> - UNIT WEIGHT
  - γ<sub>d</sub> - DRY UNIT WEIGHT
- SAMPLE ABBREVIATIONS**
- S - BULK
  - SS - SPLIT SPOON
  - ST - SHELBY TUBE
  - RS - ROCK
  - RT - RECOMPACTED TRIAXIAL
  - CBR - CALIFORNIA BEARING RATIO

### EQUIPMENT USED ON SUBJECT PROJECT

DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:
<input type="checkbox"/> MOBILE B- _____	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL
<input type="checkbox"/> BK-51	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	<b>CORE SIZE:</b>
<input checked="" type="checkbox"/> CME-550X	<input checked="" type="checkbox"/> 8" HOLLOW AUGERS	<input type="checkbox"/> -B _____
<input type="checkbox"/> CME-75	<input type="checkbox"/> HARD FACED FINGER BITS	<input type="checkbox"/> -N _____
<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG.-CARBIDE INSERTS	<input type="checkbox"/> -H _____
<input type="checkbox"/> _____	<input type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER	<b>HAND TOOLS:</b>
<input type="checkbox"/> _____	<input type="checkbox"/> TRICONE _____ * STEEL TEETH	<input type="checkbox"/> POST HOLE DIGGER
<input type="checkbox"/> _____	<input type="checkbox"/> TRICONE _____ * TUNG.-CARB.	<input type="checkbox"/> HAND AUGER
<input type="checkbox"/> _____	<input type="checkbox"/> CORE BIT	<input type="checkbox"/> SOUNDING ROD
<input type="checkbox"/> _____	<input type="checkbox"/> _____	<input type="checkbox"/> VANE SHEAR TEST
<input type="checkbox"/> _____	<input type="checkbox"/> _____	<input type="checkbox"/> _____

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF HIGHWAYS**  
**GEOTECHNICAL ENGINEERING UNIT**  
**SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**

ROCK DESCRIPTION		TERMS AND DEFINITIONS	
<p>HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:</p>		<p>ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER.</p> <p>AQUIFER - A WATER BEARING FORMATION OR STRATA.</p> <p>ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND.</p> <p>ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC.</p> <p>ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE.</p> <p>CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE.</p> <p>COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE.</p> <p>CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.</p> <p>DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK.</p> <p>DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL.</p> <p>DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH.</p> <p>FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE.</p> <p>FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES.</p> <p>FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL.</p> <p>FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM.</p> <p>FORMATION (FM.) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD.</p> <p>JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED.</p> <p>LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT.</p> <p>LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS.</p> <p>MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE.</p> <p>PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM.</p> <p>RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK.</p> <p>ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.</p> <p>SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK.</p> <p>SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS.</p> <p>SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE.</p> <p>STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS.</p> <p>STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE.</p> <p>STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE.</p> <p>TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.</p>	
<p>WEATHERED ROCK (WR)  NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES &gt; 100 BLOWS PER FOOT IF TESTED.</p> <p>CRYSTALLINE ROCK (CR)  FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.</p> <p>NON-CRYSTALLINE ROCK (NCR)  FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.</p> <p>COASTAL PLAIN SEDIMENTARY ROCK (CP)  COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.</p>			
<b>WEATHERING</b>			
FRESH	ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING, ROCK RINGS UNDER HAMMER IF CRYSTALLINE.		
VERY SLIGHT (V SLI.)	ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN, CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.		
SLIGHT (SLI.)	ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH, OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.		
MODERATE (MOD.)	SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.		
MODERATELY SEVERE (MOD. SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. <i>IF TESTED, WOULD YIELD SPT REFUSAL</i>		
SEVERE (SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <i>IF TESTED, YIELDS SPT N VALUES &gt; 100 BPF</i>		
VERY SEVERE (V SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. <i>IF TESTED, YIELDS SPT N VALUES &lt; 100 BPF</i>		
COMPLETE	ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.		
<b>ROCK HARDNESS</b>			
VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.		
HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.		
MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.		
MEDIUM HARD	CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.		
SOFT	CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.		
VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGERNAIL.		
<b>FRACTURE SPACING</b>		<b>BEDDING</b>	
<b>TERM</b>	<b>SPACING</b>	<b>TERM</b>	<b>THICKNESS</b>
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	> 4 FEET
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET
CLOSE	0.16 TO 1 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET
		THINLY LAMINATED	< 0.008 FEET
<b>INDURATION</b>			
FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.			
FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.		
MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.		
INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.		
EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.		
		BENCH MARK: Survey information provided by KCI Associates of NC.	
		ELEVATION: _____ FT.	
NOTES:			





**SITE**

**SITE LOCATION PLAN**




**FROEHLING & ROBERTSON, INC.**

*Engineering Stability Since 1881*


2505 Hutchison-McDonald Road  
 Charlotte, North Carolina 28269 | USA  
 T 704.596.2889 | F 704.596.3784  
 www.fandr.com


PROJECT REFERENCE NO.: 17BP.13.R.81		F&R PROJECT NO.: 63N-0266
I.D. NO.: N/A	F.A. PROJECT NO.: N/A	COUNTY: Yancey
PROJECT DESCRIPTION: Bridge #149 on SR 1403 over Roaring Fork Creek		
SITE DESCRIPTION: Bridge #149 on SR 1403 over Roaring Fork Creek		
DRAWN BY: R. Kral	CHECKED BY: M. Walko, P.E.	
DATE: January 2013		
		<b>DRAWING No.: 1</b>



**PLAN**

(PILES NOT SHOWN IN PLAN VIEW)



<p>SINCE 1881</p>  <p><b>FROEHLING &amp; ROBERTSON, INC.</b></p> <p>Engineering Stability Since 1881</p> <p>2505 Hutchison-McDonald Road Charlotte, North Carolina 28269   USA T 704.596.2889   F 704.596.3784 www.fandr.com</p>	<b>BORING LOCATION PLAN</b>		<p><b>DRAWING</b> No.: <b>2</b></p>	
	PROJECT REFERENCE NO.: 17BP.13.R.81			F&R PROJECT NO.: 63N-0266
	I.D. NO.: N/A	F.A. PROJECT NO.: N/A		COUNTY: Yancey
	PROJECT DESCRIPTION: Bridge #149 on SR 1403 over Roaring Fork Creek			
	SITE DESCRIPTION: Bridge #149 on SR 1403 over Roaring Fork Creek			
DRAWN BY: R. Kral	CHECKED BY: M. Walko, P.E.			
DATE: January 2013	SCALE: 1"=15'			



# NCDOT GEOTECHNICAL ENGINEERING UNIT

## BORELOG REPORT

WBS 17BP.13.R.81	TIP N/A	COUNTY Yancey	GEOLOGIST R. Kral
SITE DESCRIPTION Bridge 149 on SR 1403 over Roaring Fork Creek			GROUND WTR (ft)
BORING NO. EB1-A	STATION 12+68	OFFSET 12 ft LT	ALIGNMENT -L-
COLLAR ELEV. 3,036.4 ft	TOTAL DEPTH 9.5 ft	NORTHING 831,088	EASTING 979,507
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011		DRILL METHOD H.S. Augers	HAMMER TYPE Automatic
DRILLER C. Boyce	START DATE 08/07/12	COMP. DATE 08/08/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
3040																
	3,036.4	0.0													3,036.4	0.0
3035			2	4	9											
	3,032.9	3.5	12	14	8											
3030																
	3,027.9	8.5	60/0.1												3,027.9	8.5
	3,026.9	9.5	60/0.1												3,026.9	9.5

GROUND SURFACE

**ROADWAY EMBANKMENT**  
Brown and tan sandy fine to coarse SAND (A-2-4(0)), trace to some rock fragments  
(Soil and Cobble Fill)

SS-1 11%

**CRYSTALLINE ROCK**  
Yellow, white and brown muscovite schist  
Boring Terminated with Standard Penetration Test Refusal at Elevation 3,026.9 ft in Crystalline Rock (Muscovite Schist)

NCDOT BORE SINGLE 63N-0266-0006 - GROUP R BRIDGE 149.GPJ NC\_DOT.GDT 11/13/13



# NCDOT GEOTECHNICAL ENGINEERING UNIT BORELOG REPORT

WBS 17BP.13.R.81	TIP N/A	COUNTY Yancey	GEOLOGIST R. Kral / J. Harris
SITE DESCRIPTION Bridge 149 on SR 1403 over Roaring Fork Creek			GROUND WTR (ft)
BORING NO. EB1-B	STATION 12+78	OFFSET 8 ft RT	ALIGNMENT -L-
COLLAR ELEV. 3,035.2 ft	TOTAL DEPTH 24.5 ft	NORTHING 831,072	EASTING 979,524
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011		DRILL METHOD H.S. Augers	HAMMER TYPE Automatic
DRILLER C. Boyce	START DATE 08/07/12	COMP. DATE 08/08/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	L O G	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						ELEV. (ft)
3040																
3035	3,035.2	0.0	3	2	7									3,035.2	GROUND SURFACE	0.0
3030	3,031.7	3.5	5	13	12									3,033.7	<b>ROADWAY EMBANKMENT</b> Brown and tan silty CLAY (A-7-5), trace rock fragments	1.5
3025	3,026.7 3,025.7	8.5 9.5	82 60/0.0	18/0.0										3,026.7 3,025.7	(Soil and Cobble Fill) <b>WEATHERED ROCK</b> Brown and tan muscovite schist <b>CRYSTALLINE ROCK</b> Gray, white and black muscovite schist	8.5 9.5
3020														3,019.2 3,018.2	<b>CRYSTALLINE ROCK</b> Gray and black biotite schist <b>CRYSTALLINE ROCK</b> Gray and white muscovite gneiss	16.0 17.0
3015														3,010.7	Boring Terminated at Elevation 3,010.7 ft in Crystalline Rock (Muscovite Gneiss)	24.5

NCDOT BORE SINGLE 63N-0266-0006 - GROUP R BRIDGE 149.GPJ NC\_DOT.GDT 11/13/13



# NCDOT GEOTECHNICAL ENGINEERING UNIT CORE BORING REPORT

WBS 17BP.13.R.81		TIP N/A		COUNTY Yancey		GEOLOGIST R. Kral / J. Harris					
SITE DESCRIPTION Bridge 149 on SR 1403 over Roaring Fork Creek									GROUND WTR (ft)		
BORING NO. EB1-B		STATION 12+78		OFFSET 8 ft RT		ALIGNMENT -L-		0 HR. 8.0			
COLLAR ELEV. 3,035.2 ft		TOTAL DEPTH 24.5 ft		NORTHING 831,072		EASTING 979,524		24 HR. 7.5			
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic					
DRILLER C. Boyce		START DATE 08/07/12		COMP. DATE 08/08/12		SURFACE WATER DEPTH N/A					
CORE SIZE NQ-2		TOTAL RUN 15.0 ft									
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		L O G	DESCRIPTION AND REMARKS	DEPTH (ft)
					REC. (ft) %	RQD (ft) %	REC. (ft) %	RQD (ft) %			
3025.7											
3025	3,025.7	9.5	5.0	N=60/0.0 1:29/1.0 2:15/1.0 2:00/1.0 2:29/1.0 2:10/1.0	(3.9) 78%	(1.7) 33%	(5.3) 81%	(2.8) 42%		Begin Coring @ 9.5 ft	
										CRSTALLINE ROCK	9.5
										Gray, white and black moderately hard to hard, slightly weathered, very close to closely spaced fractured MUSCOVITE SCHIST	
3020	3,020.7	14.5	5.0	2:24/1.0 3:13/1.0 2:21/1.0 4:22/1.0 5:39/1.0	(4.8) 95%	(3.0) 60%					
										CRSTALLINE ROCK	16.0
										Gray and black, hard, slightly weathered, very closely spaced fractured BIOTITE SCHIST	17.0
3015	3,015.7	19.5	5.0	4:15/1.0 3:21/1.0 6:09/1.0 7:39/1.0 6:50/1.0	(5.0) 100%	(4.7) 93%	(1.0) 100%	(0.0) 0%			
										CRSTALLINE ROCK	
										Gray and white, hard, slightly weathered, very close to moderately closely spaced fractured MUSCOVITE GNEISS	
	3,010.7	24.5								Boring Terminated at Elevation 3,010.7 ft in Crystalline Rock (Muscovite Gneiss)	24.5

NCDOT CORE SINGLE 63N-0266-0006 - GROUP R BRIDGE 149.GPJ NC\_DOT.GDT 11/13/13



# NCDOT GEOTECHNICAL ENGINEERING UNIT

## BORELOG REPORT

WBS 17BP.13.R.81		TIP N/A		COUNTY Yancey		GEOLOGIST R. Kral / J. Harris											
SITE DESCRIPTION Bridge 149 on SR 1403 over Roaring Fork Creek							GROUND WTR (ft)										
BORING NO. EB2-A		STATION 13+10		OFFSET 9 ft LT		ALIGNMENT -L-											
COLLAR ELEV. 3,033.4 ft		TOTAL DEPTH 22.5 ft		NORTHING 831,096		EASTING 979,551											
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic											
DRILLER C. Boyce		START DATE 08/07/12		COMP. DATE 08/08/12		SURFACE WATER DEPTH N/A											
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
3035	3,033.4	0.0	2	4	3	7								3,033.4	0.0	GROUND SURFACE	
3030	3,029.9	3.5	24	32	22									3,025.9	7.5	ROADWAY EMBANKMENT Brown and tan clayey fine to coarse SAND (A-2-6), trace to some rock fragments  (Soil and Cobble Fill)	
3025	3,025.9	7.5	60/0.0											3,025.9		CRYSTALLINE ROCK Gray and white muscovite gneiss	
3020																	
3015																	
														3,010.9	22.5	Boring Terminated at Elevation 3,010.9 ft in Crystalline Rock (Biotite Gneiss)	



# NCDOT GEOTECHNICAL ENGINEERING UNIT CORE BORING REPORT

WBS 17BP.13.R.81		TIP N/A		COUNTY Yancey			GEOLOGIST R. Kral / J. Harris					
SITE DESCRIPTION Bridge 149 on SR 1403 over Roaring Fork Creek									GROUND WTR (ft)			
BORING NO. EB2-A		STATION 13+10		OFFSET 9 ft LT		ALIGNMENT -L-		0 HR. 3.5				
COLLAR ELEV. 3,033.4 ft		TOTAL DEPTH 22.5 ft		NORTHING 831,096		EASTING 979,551		24 HR. 4.0				
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011					DRILL METHOD H.S. Augers		HAMMER TYPE Automatic					
DRILLER C. Boyce		START DATE 08/07/12		COMP. DATE 08/08/12		SURFACE WATER DEPTH N/A						
CORE SIZE NQ-2		TOTAL RUN 15.0 ft										
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		L O G	DESCRIPTION AND REMARKS	DEPTH (ft)	
					REC. (ft)	RQD (%)	REC. (ft)	RQD (%)				
3025.9												
3025	3,025.9	7.5	5.0	N=60/0.0 1:05/1.0 2:04/1.0 2:59/1.0 2:52/1.0 1:11/1.0	(4.1) 82%	(2.3) 45%	(12.7) 84%	(8.3) 56%		3,025.9	7.5	
3020	3,020.9	12.5	5.0	1:27/1.0 2:41/1.0 1:23/1.0 3:49/1.0 2:40/1.0	(3.8) 75%	(2.0) 40%						
3015	3,015.9	17.5	5.0	2:55/1.0 5:39/1.0 6:35/1.0 9:15/1.0 11:05/1.0	(4.8) 97%	(4.1) 82%						
	3,010.9	22.5								3,010.9	22.5	
Boring Terminated at Elevation 3,010.9 ft in Crystalline Rock (Biotite Gneiss)												

NCDOT CORE SINGLE 63N-0266-0006 - GROUP R BRIDGE 149.GPJ NC\_DOT.GDT 11/13/13



# NCDOT GEOTECHNICAL ENGINEERING UNIT

## BORELOG REPORT

WBS 17BP.13.R.81		TIP N/A		COUNTY Yancey		GEOLOGIST R. Kral											
SITE DESCRIPTION Bridge 149 on SR 1403 over Roaring Fork Creek							GROUND WTR (ft)										
BORING NO. EB2-B		STATION 13+32		OFFSET 12 ft RT		ALIGNMENT -L-											
COLLAR ELEV. 3,031.0 ft		TOTAL DEPTH 8.5 ft		NORTHING 831,080		EASTING 979,577											
DRILL RIG/HAMMER EFF./DATE F&R3763 CME-550X 81% 12/15/2011				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic											
DRILLER C. Boyce		START DATE 08/08/12		COMP. DATE 08/08/12		SURFACE WATER DEPTH N/A											
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
3035																	
3030	3,031.0	0.0	2	3	3	6						M		3,031.0	0.0	GROUND SURFACE	
3025	3,027.5	3.5	11	9	17	26						SS-2	22%			<b>ROADWAY EMBANKMENT</b> Brown, tan and black silty fine to coarse SAND (A-2-4(0)), trace to some rock fragments  (Soil and Cobble Fill)	
	3,022.5	8.5	60/0.0			60/0.0									3,022.5	8.5	Boring Terminated with Standard Penetration Test Refusal at Elevation 3,022.5 ft on Crystalline Rock (Muscovite Gneiss)

NCDOT BORE SINGLE 63N-0266-0006 - GROUP R BRIDGE 149.GPJ NC\_DOT.GDT 11/13/13







# Bridge 990149 – SR 1403 across Roaring Fork Creek

## CORE PHOTOGRAPHS: EB1-B: Station 12+78

9.5 feet



19.5 feet






# Bridge 990149 – SR 1403 across Roaring Fork Creek

## CORE PHOTOGRAPHS: EB2-A: Station 13+10

7.5 feet



17.5 feet

