

Site 100-01-00205

Sweet Birch Lane – Yancey County


6/2/99

REVISIONS

PLOT DRIVER: NCDOT.pdf_color_eng_50uplt
 USER: ERBROOKS
 DATE: 3/20/2026
 TIME: 4:32:36 PM
 FILE: NorthCarolinaDepartmentofPublicSafety\NCDPS-growth\Prof.Design_Services\6.0_CAD_BITMAP\6.2_WIP\Site_100-01-00217a_Roadway\Proj\100-01-00205_Typ.dgn


PAVEMENT SCHEDULE	
C1	PROPOSED 2" ASPHALT SURFACE COURSE, TYPE S4.75A, AT AN AVERAGE RATE OF 220 LBS PER SQ YD
C2	PROPOSED ASPHALT SURFACE COURSE, TYPE S4.75A, AT AN AVERAGE RATE OF 110 LBS PER SQ YD PER INCH
J	6" AGGREGATE BASE COURSE
T	EARTH MATERIAL

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




TYPICAL SECTION NO. 1
ASPHALT SURFACE

- L- STA 10+11.05 TO 10+69.00 +/- (BEGIN BRIDGE)
- L- STA 11+71.79 +/- (END BRIDGE) TO 12+08.91
- Y6B- STA 10+07.62 TO 10+22.00 (MIRRORED)
- DRI- STA 10+00.00 TO 10+39.00 (MIRRORED)




TYPICAL SECTION NO. 2
ABC SURFACE

- Y6B- STA 10+22.00 TO 13+73.00
- Y6B- STA 14+07.00 TO 14+25.00
- Y1A- STA 10+47.82 TO 10+78.00
- Y1A- STA 11+12.00 TO 21+19.00
- Y1A- STA 21+67.00 TO 22+34.29
- Y1- STA 11+33.56 TO 19+00.00




TYPICAL SECTION NO. 3


- L- STA 10+69.00 +/- (BEGIN BRIDGE) TO 11+71.79 +/- (END BRIDGE)
- (SEE STRUCTURE PLANS)




TYPICAL SECTION NO. 4A
 -Y1A- STA 10+78.00 TO 11+12.00
 -Y1A- STA 21+19.00 TO 21+67.00



TYPICAL SECTION NO. 4B
 -Y6B- STA 13+73.00 TO 14+07.00
 -DRI- STA 10+39.00 TO 10+98.79 *
 *USE (C1) FROM PAVEMENT SCHEDULE



INSET
DITCH SECTIONS



INSET
GUARDRAIL SECTIONS

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 1
ROADWAY DESIGN ENGINEER	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St, Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-01116	

NCDOT 2024 ROADWAY ENGLISH STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" CONTRACTS STANDARDS AND DEVELOPMENT UNIT - N. C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N. C., DATED JANUARY 16, 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS.

STD. NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	METHOD OF CLEARING - METHOD II
225.02	GUIDE FOR GRADING SURGRADE - SECONDARY AND LOCAL
225.04	METHOD OF OBTAINING SUPERELEVATION - TWO LANE PAVEMENT
DIVISION 5 - SUBGRADE BASES AND SHOULDERS	
560.01	METHOD OF SHOULDER CONSTRUCTION - HIGH SIDE OF SUPERELEVATED CURVE - METHOD I
DIVISION 8 - INCIDENTALS	
862.01	GUARDRAIL PLACEMENT (USE DETAILS IN LIEU OF STANDARDS FOR SHEETS 4, 6, 11, 12, AND 14 OF 15)
862.02	GUARDRAIL INSTALLATION (USE DETAIL IN LIEU OF STANDARD FOR SHEET 5 OF 9)
862.03	STRUCTURE ANCHOR UNITS (USE DETAIL IN LIEU OF STANDARDS FOR SHEET 6 AND 8 OF 9)
876.01	RIP RAP IN CHANNELS AND DITCHES

IF GUARDRAIL ON US 19W IS NOT EXISTING OR IN PLACE BY COMPLETION OF CONSTRUCTION OF BRIDGE 001-01-00205, TERMINATE -L- GUARDRAIL 15' FROM US 19W EDGE OF PAVEMENT AND PLACE A TEMPORARY AT-1 END UNIT ON THE END OF EACH GUARDRAIL.

NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 2
RW SHEET NO.	
ROADWAY DESIGN ENGINEER 2. Erskine Brooks	HYDRAULICS ENGINEER 3. Devin Harrison
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St., Suite 900, Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	
SCALE (HORIZONTAL)	

GENERAL NOTES: NCDOT 2024 STANDARD SPECIFICATIONS

GRADING AND SURFACING: THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.


CLEARING: CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION: ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION: ASPHALT AND EARTH SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

GUARDRAIL: THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

EXCAVATION: LOCALIZED BLASTING MAY BE REQUIRED FOR EXCAVATION AND INSTALLATION OF DRAINAGE STRUCTURE AND PIPES. BLASTING WILL BE CONSIDERED INCIDENTAL TO THE OVERALL GRADING, AND SHALL BE COMPLETED IN ACCORDANCE WITH STANDARD SPECIFICATION SECTION 220



PLOT DRIVER: NCDOT.pdf_color_eng_50.dpt
 USER: BPHELLIPS
 FILE: \

PENTABLE: NCDOT.dshp1.tbi
 TIME: 10:28:56 AM
 DATE: 3/20/2026

REVISIONS

NCDOT 2024 ROADWAY ENGLISH STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" CONTRACTS STANDARDS AND DEVELOPMENT UNIT - N. C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N. C., DATED JANUARY 16, 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS.

STD. NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	METHOD OF CLEARING - METHOD II
225.02	GUIDE FOR GRADING - SUBGRADE - SECONDARY AND LOCAL
225.04	METHOD OF OBTAINING SUPERELEVATION - TWO LANE PAVEMENT
DIVISION 5 - SUBGRADE BASES AND SHOULDERS	
560.01	METHOD OF SHOULDER CONSTRUCTION - HIGH SIDE OF SUPERELEVATED CURVE - METHOD I
DIVISION 8 - INCIDENTALS	
862.01	GUARDRAIL PLACEMENT (USE DETAILS IN LIEU OF STANDARDS FOR SHEETS 4, 6, 11, 12, AND 14 OF 15)
862.02	GUARDRAIL INSTALLATION (USE DETAIL IN LIEU OF STANDARD FOR SHEET 5 OF 9)
862.03	STRUCTURE ANCHOR UNITS (USE DETAIL IN LIEU OF STANDARDS FOR SHEET 6 AND 8 OF 9)
874.01	RIP RAP IN CHANNELS AND DITCHES

IF GUARDRAIL ON US 19W IS NOT EXISTING OR IN PLACE BY COMPLETION OF CONSTRUCTION OF BRIDGE 100-01-00205, TERMINATE -L- GUARDRAIL 15' FROM US 19W EDGE OF PAVEMENT AND PLACE A TEMPORARY AT-1 END UNIT ON THE END OF EACH GUARDRAIL.

GENERAL NOTES: NCDOT 2024 STANDARD SPECIFICATIONS

GRADING AND SURFACING: THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING: CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION: ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION: ASPHALT AND EARTH SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

GUARDRAIL: THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

EXCAVATION: LOCALIZED BLASTING MAY BE REQUIRED FOR EXCAVATION AND INSTALLATION OF DRAINAGE STRUCTURE AND PIPES. BLASTING WILL BE CONSIDERED INCIDENTAL TO THE OVERALL GRADING, AND SHALL BE COMPLETED IN ACCORDANCE WITH STANDARD SPECIFICATION SECTION 220

MORROW BENJAMIN KEVIN
PARCEL NO.: 989100588286000

BEGIN PROJECT 100-01-00205
BEGIN CONSTRUCTION
100-01-00205 -L- STA. 10+11.05 =
US 19W SOUTH PDB -L- STA. 240+73.85


-Y6B-

PI Sta. 10+19.24	PI Sta. 11+37.95
$\Delta = 35^{\circ} 33' 23.6''$ (LT)	$\Delta = 37^{\circ} 07' 01.8''$ (RT)
$D = 95^{\circ} 29' 34.7''$	$D = 19^{\circ} 05' 54.9''$
$L = 37.23'$	$L = 194.35'$
$T = 19.24'$	$T = 100.72'$
$R = 60.00'$	$R = 300.00'$

PROJECT REFERENCE NO.	SHEET NO.
	2A
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
3/20/2026	3/20/2026
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

REVISIONS

PLOT DRIVER: NCDOT.pdf_color_eng_50.dpt
USER: BPHILLIPS
DATE: 3/20/2026
TIME: 10:29:08 AM
FILE: \




WEBB BOBBY
PARCEL NO.: 989100679835000

CONTRACTOR TO EXCAVATE NO STEEPER THAN 2H:1V SLOPE AT EACH OPEN END PIPE TO MAINTAIN AT LEAST 1' OF COVER BETWEEN THE ROAD SURFACE AND TOP OF PIPE.

FOR -L- PROFILE, SEE SHEET 7
FOR -Y6A- PROFILE, SEE SHEET 7
FOR -Y6B- PROFILE, SEE SHEET 7

NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 3
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER 2. Erskine Brooks	HYDRAULICS ENGINEER David Harrison
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	



MATCHLINE -Y6B- STA. 12+00.00, SEE SHEET 2

MATCHLINE -Y1A- STA. 14+35.00, SEE SHEET 4

PLOT DRIVER: NCDOT.pdf_color_eng_50.dwt
 USER: BPHELLIPS
 FILE: \

PENTABLE: NCDOT.dshp1.tbi
 USER: BPHELLIPS
 FILE: \


REVISIONS

-Y6B-			
PI Sta 11+37.95	PI Sta 13+58.54	PI Sta 14+34.40	PI Sta 15+03.77
$\Delta = 37^{\circ} 07' 01.8''$ (RT)	$\Delta = 10^{\circ} 12' 09.2''$ (RT)	$\Delta = 7^{\circ} 50' 12.0''$ (RT)	$\Delta = 12^{\circ} 16' 17.8''$ (RT)
D = 19' 05" 54.9"	D = 8' 11" 06.4"	D = 28' 38" 52.4"	D = 57' 17" 44.8"
L = 194.35'	L = 124.65'	L = 27.36'	L = 21.42'
T = 100.72'	T = 62.49'	T = 13.70'	T = 10.75'
R = 300.00'	R = 700.00'	R = 200.00'	R = 100.00'

-Y1A-			
PI Sta 10+34.66	PI Sta 11+21.41	PI Sta 12+73.88	PI Sta 15+50.37
$\Delta = 11^{\circ} 59' 35.0''$ (LT)	$\Delta = 14^{\circ} 54' 25.9''$ (RT)	$\Delta = 7^{\circ} 12' 17.2''$ (RT)	$\Delta = 16^{\circ} 41' 25.6''$ (LT)
D = 17' 21" 44.5"	D = 14' 19" 26.2"	D = 3' 34" 51.6"	D = 4' 46" 28.7"
L = 69.08'	L = 104.07'	L = 20.20'	L = 349.56'
T = 34.66'	T = 52.33'	T = 100.73'	T = 176.03'
R = 330.00'	R = 400.00'	R = 1600.00'	R = 1200.00'

FOR -Y1A- PROFILE, SEE SHEET 8
 FOR -Y6B- PROFILE, SEE SHEET 7

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 3A
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER 2. Erskine Brooks	HYDRAULICS ENGINEER 3. Devin Harrison
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St., Suite 900, Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	



MATCHLINE -Y6B- STA. 12+00.00, SEE SHEET 2A

MATCHLINE -Y1A- STA. 14+35.00, SEE SHEET 4A

PLOT DRIVER: NCDOT.pdf_color_eng_50.dpt
 USER: BPHELLIPS
 FILE: \

REVISIONS
 PENTABLE: NCDOT.dshp1.tbi
 TIME: 10:29:24 AM
 DATE: 3/20/2026

-Y6B-			
PI Sta 11+37.95	PI Sta 13+58.54	PI Sta 14+34.40	PI Sta 15+03.77
$\Delta = 37^{\circ} 07' 01.8''$ (RT)	$\Delta = 10^{\circ} 12' 09.2''$ (RT)	$\Delta = 7^{\circ} 50' 12.0''$ (RT)	$\Delta = 12^{\circ} 16' 17.8''$ (RT)
D = 19' 05" 54.9"	D = 8' 11" 06.4"	D = 28' 38" 52.4"	D = 57' 17" 44.8"
L = 194.35'	L = 124.65'	L = 27.36'	L = 21.42'
T = 100.72'	T = 62.49'	T = 13.70'	T = 10.75'
R = 300.00'	R = 700.00'	R = 200.00'	R = 100.00'


-Y1A-			
PI Sta 10+34.66	PI Sta 11+21.41	PI Sta 12+73.88	PI Sta 15+50.37
$\Delta = 11^{\circ} 59' 35.0''$ (LT)	$\Delta = 14^{\circ} 54' 25.9''$ (RT)	$\Delta = 7^{\circ} 12' 17.2''$ (RT)	$\Delta = 16^{\circ} 41' 25.6''$ (LT)
D = 17' 21" 44.5"	D = 14' 19" 26.2"	D = 3' 34" 51.6"	D = 4' 46" 28.7"
L = 69.08'	L = 104.07'	L = 20.20'	L = 349.56'
T = 34.66'	T = 52.33'	T = 100.73'	T = 176.03'
R = 330.00'	R = 400.00'	R = 1600.00'	R = 1200.00'

FOR -Y1A- PROFILE, SEE SHEET 8
 FOR -Y6B- PROFILE, SEE SHEET 7

PLOT DRIVER: NCDOT.pdf_color_eng_50.plt
 USER: BPHELLIPS
 FILE: \

REVISIONS

PENTABLE: NCDOT.dshp1.tbi
 TIME: 10:29:29 AM
 DATE: 3/20/2026




NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 4
ROADWAY DESIGN ENGINEER 2. Erskine Brooks	HYDRAULICS ENGINEER David Harrison
3/20/2026	3/20/2026
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

MATCHLINE -YIA- STA. 14 + 35.00, SEE SHEET 3

MATCHLINE -YIA- STA. 19 + 85.00, SEE SHEET 5

-YIA-			
PI Sta 15+50.37 Δ = 16° 41' 25.6" (LT) D = 4° 46' 28.7" L = 349.56' T = 176.03' R = 1,200.00'	PI Sta 17+75.60 Δ = 3° 56' 52.4" (RT) D = 3° 49' 11.0" L = 103.36' T = 51.70' R = 1,500.00'	PI Sta 18+80.75 Δ = 15° 13' 55.8" (LT) D = 14° 19' 26.2" L = 106.34' T = 53.49' R = 400.00'	PI Sta 19+72.14 Δ = 21° 48' 41.7" (RT) D = 28° 38' 52.4" L = 76.14' T = 38.53' R = 200.00'




FROM STA. 16+00 TO STA. 18+00 -YIA- RT

FOR -YIA- PROFILE, SEE SHEET 8

REVISIONS


PLOT DRIVER: NCDOT.pdf_color_eng_50.dpt
 USER: BPILLIPS
 FILE: \

PENTABLE: NCDOT.dshp1.tbi
 TIME: 10:28:43 AM
 DATE: 3/20/2026






PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 4A
ROADWAY DESIGN ENGINEER 2. Erskine Brooks NORTH CAROLINA PROFESSIONAL ENGINEER 3/20/2026	HYDRAULICS ENGINEER David Harrison NORTH CAROLINA PROFESSIONAL ENGINEER 3/20/2026
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St, Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	


-Y1A-			
PI Sta 15+50.37	PI Sta 17+75.60	PI Sta 18+80.75	PI Sta 19+72.14
$\Delta = 16' 41" 25.6" (LT)$	$\Delta = 3' 56" 52.4" (RT)$	$\Delta = 15' 13" 55.8" (LT)$	$\Delta = 21' 48" 41.7" (RT)$
$D = 4' 46" 28.7"$	$D = 3' 49" 11.0"$	$D = 14' 19" 26.2"$	$D = 28' 38" 52.4"$
$L = 349.56'$	$L = 103.36'$	$L = 106.34'$	$L = 76.14'$
$T = 176.03'$	$T = 51.70'$	$T = 53.49'$	$T = 38.53'$
$R = 1,200.00'$	$R = 1,500.00'$	$R = 400.00'$	$R = 200.00'$



FOR -Y1A- PROFILE, SEE SHEET 8

NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 5
RW SHEET NO.	
ROADWAY DESIGN ENGINEER 	HYDRAULICS ENGINEER 
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
 HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	




REVISIONS


PLOT DRIVER: NCDOT.pdf_color_eng_50.dpt
 USER: BPHELLIPS
 FILE: \

PENTABLE: NCDOT.pshp1.tbi
 TIME: 10:29:48 AM
 DATE: 3/20/2026

-YIA-			-YI-		-DRI-	
PI Sta 19+72.14	PI Sta 21+72.71	PI Sta 22+16.27	PI Sta 12+10.99	PI Sta 14+18.09	PI Sta 10+84.17	
$\Delta = 21^{\circ} 48' 41.7" (RT)$	$\Delta = 40^{\circ} 07' 12.9" (RT)$	$\Delta = 20^{\circ} 52' 54.4" (LT)$	$\Delta = 14^{\circ} 14' 09.6" (LT)$	$\Delta = 27^{\circ} 05' 50.6" (RT)$	$\Delta = 56^{\circ} 51' 01.3" (LT)$	
$D = 28^{\circ} 38' 52.4"$	$D = 76^{\circ} 23' 39.7"$	$D = 57^{\circ} 17' 44.8"$	$D = 9^{\circ} 14' 28.5"$	$D = 19^{\circ} 05' 54.9"$	$D = 286^{\circ} 28' 44.0"$	
$L = 76.14'$	$L = 52.52'$	$L = 36.45'$	$L = 154.05'$	$L = 141.68'$	$L = 19.84'$	
$T = 38.53'$	$T = 27.39'$	$T = 18.43'$	$T = 77.42'$	$T = 72.29'$	$T = 10.83'$	
$R = 200.00'$	$R = 75.00'$	$R = 100.00'$	$R = 620.00'$	$R = 300.00'$	$R = 20.00'$	

FOR -YI- PROFILE, SEE SHEET 8
 FOR -YIA- PROFILE, SEE SHEET 8
 FOR -DRI- PROFILE, SEE SHEET 8

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 5A
ROADWAY DESIGN ENGINEER 2. Erskine Brooks	HYDRAULICS ENGINEER 3. Devin Harrison
3/20/2026	3/20/2026
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
 HDR Engineering, Inc. of the Carolinas 555 Fayetteville St, Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	




REVISIONS

PLOT DRIVER: NCDOT.pdf,color_eng_50.dpt
 USER: BPHELLIPS
 FILE: \

PENTABLE: NCDOT.dshp1.tbi
 DATE: 3/20/2026
 TIME: 10:30:01 AM

-Y1A-			-Y1-		-DRI-	
PI Sta 19+72.14	PI Sta 21+72.71	PI Sta 22+16.27	PI Sta 12+10.99	PI Sta 14+18.09	PI Sta 10+84.17	
$\Delta = 21^{\circ} 48' 41.7" (RT)$	$\Delta = 40^{\circ} 07' 12.9" (RT)$	$\Delta = 20^{\circ} 52' 54.4" (LT)$	$\Delta = 14^{\circ} 14' 09.6" (LT)$	$\Delta = 27^{\circ} 05' 50.6" (RT)$	$\Delta = 56^{\circ} 51' 01.3" (LT)$	
$D = 28^{\circ} 38' 52.4"$	$D = 76^{\circ} 23' 39.7"$	$D = 57^{\circ} 17' 44.8"$	$D = 91^{\circ} 14' 28.5"$	$D = 19^{\circ} 05' 54.9"$	$D = 286^{\circ} 28' 44.0"$	
$L = 76.14'$	$L = 52.52'$	$L = 36.45'$	$L = 154.05'$	$L = 141.88'$	$L = 19.84'$	
$T = 38.53'$	$T = 27.39'$	$T = 18.43'$	$T = 77.42'$	$T = 72.29'$	$T = 10.83'$	
$R = 200.00'$	$R = 75.00'$	$R = 100.00'$	$R = 620.00'$	$R = 300.00'$	$R = 20.00'$	

FOR -Y1- PROFILE, SEE SHEET 8
 FOR -Y1A- PROFILE, SEE SHEET 8
 FOR -DRI- PROFILE, SEE SHEET 8



NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 6
ROADWAY DESIGN ENGINEER 2. Erskine Brooks	HYDRAULICS ENGINEER 3. Devin Harrison
3/20/2026	3/20/2026
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

MATCHLINE -Y1- STA. 14 + 00.00, SEE SHEET 5

REVISIONS




PLOT DRIVER: NCDOT.pdf_color_eng_50dpi
 USER: BPHILLIPS
 FILE: \


PENTABLE: NCDOT.dshp\fl.tbl
 TIME: 10:30:06 AM
 DATE: 3/20/2026

-Y1-		
PI Sta 14+18.09 Δ = 27° 05' 50.6" (RT) D = 19' 05" 54.9" L = 141.88' T = 72.29' R = 300.00'	PI Sta 15+26.69 Δ = 14° 49' 03.1" (LT) D = 19' 05" 54.9" L = 77.58' T = 39.01' R = 300.00'	PI Sta 16+64.75 Δ = 4° 14' 25.9" (RT) D = 10' 25" 02.7" L = 40.71' T = 20.36' R = 550.00'
PI Sta 17+87.39 Δ = 13° 40' 09.1" (RT) D = 28° 38' 52.4" L = 47.71' T = 23.97' R = 200.00'	PI Sta 18+67.80 Δ = 27° 09' 33.5" (LT) D = 57' 17" 44.8" L = 47.40' T = 24.15' R = 100.00'	PI Sta 19+73.58 Δ = 44° 49' 52.5" (RT) D = 49' 49" 20.7" L = 89.98' T = 47.44' R = 115.00'

CONTRACTOR TO EXCAVATE NO STEEPER THAN 2H:1V SLOPE AT EACH OPEN END PIPE TO MAINTAIN AT LEAST 1' OF COVER BETWEEN THE ROAD SURFACE AND TOP OF PIPE.

FOR -Y1- PROFILE, SEE SHEET 8

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 6A
RDW SHEET NO.	
ROADWAY DESIGN ENGINEER 	HYDRAULICS ENGINEER 
<p>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</p>  HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	



MATCHLINE -YI- STA. 14+00.00, SEE SHEET 5A

REVISIONS

PLOT DRIVER: NCDOT.pdf_color_eng_50dpi
 USER: BPHILLIPS
 FILE: \

PENTABLE: NCDOT.dshp\fl.tbl
 TIME: 10:30:18 AM
 DATE: 3/20/2026

-YI-		
PI Sta 14+18.09 Δ = 27° 05' 50.6" (RT) D = 19' 05" 54.9" L = 141.88' T = 72.29' R = 300.00'	PI Sta 15+26.69 Δ = 14° 49' 03.1" (LT) D = 19' 05" 54.9" L = 77.58' T = 39.01' R = 300.00'	PI Sta 16+64.75 Δ = 4° 14' 25.9" (RT) D = 10' 25" 02.7" L = 40.71' T = 20.36' R = 550.00'
PI Sta 17+87.39 Δ = 13° 40' 09.1" (RT) D = 28° 38' 52.4" L = 47.71' T = 23.97' R = 200.00'	PI Sta 18+67.80 Δ = 27° 09' 33.5" (LT) D = 57' 17" 44.8" L = 47.40' T = 24.15' R = 100.00'	PI Sta 19+73.58 Δ = 44° 49' 52.5" (RT) D = 49' 49" 20.7" L = 89.98' T = 47.44' R = 115.00'

HYDE, PETER E & SARAH K
PARCEL NO.: 989100778561000

BAKER, TED H & EVELYN
PARCEL NO.: 989100960124000


CONTRACTOR TO EXCAVATE NO STEEPER THAN 2H:1V SLOPE AT EACH OPEN END PIPE TO MAINTAIN AT LEAST 1' OF COVER BETWEEN THE ROAD SURFACE AND TOP OF PIPE.

FOR -YI- PROFILE, SEE SHEET 8




HDR Engineering, Inc. of the Carolinas
555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 7
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	



PLOT DRIVER: NCDOT.pdf_color_eng_50.pdf
 USER: ERBROOKS
 FILE: NorthCarolinaDepartmentofPublicSafety\NCDPS-GROW\NC_Prof.Design_Services\6.0_CAD_BITMAP\6.2_WIP\Site_100-01-00217a\Roadway\Proj\100-01-00205_rdy.plt07.dgn
 PENTABLE: NCDOT.pshp.plt
 TIME: 4:04:49 PM
 DATE: 3/20/2026

REVISIONS






FOR -L- PLAN, SEE SHEET 2

FOR -Y6B- PLAN, SEE SHEETS 2 AND 3




HDR Engineering, Inc. of the Carolinas
555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. 8
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	



PLOT DRIVER: NCDOT.pdf, color, eng, 50upf
 USER: ERBROOKS
 FILE: North Carolina Department of Public Safety\NCDPS-GROW, NC_Prof_Design_Services\6.0_CAD_BITMAP\6.2_WIP_Site_100-01-00217a_Roadway\Proj\100-01-00205_rdy.dwg, p108.dgn
 DATE: 3/20/2026
 TIME: 4:05:38 PM
 REVISIONS

PROJ. REFERENCE NO.	SHEET NO.
100-01-00205	TMP-1
 HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS, AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS OR RESULT IN DUPLICATE OR UNDESIRED OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING, OR REMOVAL OF DEVICES AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

TIME RESTRICTIONS

A) DO NOT CLOSE OR NARROW TRAVEL LANES AS FOLLOWS:

<u>ROAD NAME</u>	<u>DAY AND TIME RESTRICTIONS</u>
US 19W	MON-FRI: 7:00 AM TO 9:00 AM 4:00 PM TO 6:00 PM

B) DO NOT CLOSE OR NARROW TRAVEL LANES DURING HOLIDAYS AND SPECIAL EVENTS AS FOLLOWS:

- | <u>ROAD NAME</u> |
|------------------|
| US 19W |
- FOR ANY UNEXPECTED OCCURRENCE THAT CREATES UNUSUALLY HIGH TRAFFIC VOLUMES, AS DIRECTED BY THE ENGINEER.
 - FOR NEW YEAR'S, BETWEEN THE HOURS OF 4:00 PM DECEMBER 31ST TO 9:00 AM JANUARY 2ND. IF NEW YEAR'S DAY IS ON A FRIDAY, SATURDAY, SUNDAY, OR MONDAY THEN UNTIL 9:00 AM THE FOLLOWING TUESDAY.
 - FOR EASTER, BETWEEN THE HOURS OF 4:00 PM THURSDAY AND 9:00 AM MONDAY.
 - FOR MEMORIAL DAY, BETWEEN THE HOURS OF 4:00 PM FRIDAY TO 9:00 AM TUESDAY.
 - FOR INDEPENDENCE DAY, BETWEEN THE HOURS OF 4:00 PM THE DAY BEFORE INDEPENDENCE DAY AND 9:00 AM THE DAY AFTER INDEPENDENCE DAY.

IF INDEPENDENCE DAY IS ON A FRIDAY, SATURDAY, SUNDAY OR MONDAY THEN BETWEEN THE HOURS OF 4:00 PM THE THURSDAY BEFORE INDEPENDENCE DAY AND 9:00 AM THE TUESDAY AFTER INDEPENDENCE DAY.
 - FOR LABOR DAY, BETWEEN THE HOURS OF 4:00 PM FRIDAY AND 9:00 AM TUESDAY.
 - FOR THANKSGIVING DAY, BETWEEN THE HOURS OF 4:00 PM TUESDAY TO 9:00 AM MONDAY.
 - FOR CHRISTMAS, BETWEEN THE HOURS OF 4:00 PM THE FRIDAY BEFORE THE WEEK OF CHRISTMAS DAY AND 9:00 AM THE FOLLOWING TUESDAY AFTER THE WEEK OF CHRISTMAS.

C) DO NOT CLOSE ROAD AS FOLLOWS:

<u>ROAD NAME</u>	<u>DAY AND TIME RESTRICTIONS</u>
US 19W	ANYTIME

D) DO NOT STOP TRAFFIC AS FOLLOWS:

<u>ROAD NAME</u>	<u>DAY AND TIME RESTRICTIONS</u>	<u>DURATION AND OPERATION</u>
US 19W	MONDAY - SUNDAY 7:00 AM TO 9:00 AM 4:00 PM TO 6:00 PM	30 MINUTES FOR GIRDER/MATERIAL DELIVERY

E) DO NOT CONDUCT ANY HAULING OPERATIONS AGAINST THE FLOW OF TRAFFIC OF AN OPEN TRAVELWAY UNLESS THE HAULING OPERATION IS PROTECTED BY BARRIER OR GUARDRAIL OR AS DIRECTED BY THE ENGINEER.

LANE AND SHOULDER CLOSURE REQUIREMENTS

- F) REMOVE LANE CLOSURE DEVICES FROM THE LANE WHEN WORK IS NOT BEING PERFORMED BEHIND THE LANE CLOSURE OR WHEN A LANE CLOSURE IS NO LONGER NEEDED OR AS DIRECTED BY THE ENGINEER.
- G) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN 15 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN SHOULDER USING ROADWAY STANDARD DRAWING NO. 1101.04 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL OR A LANE CLOSURE IS INSTALLED.
- H) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN A LANE OF TRAVEL, CLOSE THE LANE ACCORDING TO THE TRAFFIC CONTROL PLANS, ROADWAY STANDARD DRAWINGS, OR AS DIRECTED BY THE ENGINEER. CONDUCT THE WORK SO THAT ALL PERSONNEL AND/OR EQUIPMENT REMAIN WITHIN THE CLOSED TRAVEL LANE.
- I) NOTIFY THE NCDOT STATEWIDE TRANSPORTATION OPERATIONS CENTER (STOC) AT 877-627-7862 APPROXIMATELY 30 MINUTES PRIOR TO INSTALLING AND WITHIN 15 MINUTES AFTER REMOVING THE LANE CLOSURE.

PAVEMENT EDGE DROP OFF REQUIREMENTS

- J) BACKFILL AT A 6:1 SLOPE UP TO THE EDGE AND ELEVATION OF EXISTING PAVEMENT IN AREAS ADJACENT TO AN OPENED TRAVEL LANE THAT HAS AN EDGE OF PAVEMENT DROP-OFF THAT EXCEEDS 2 INCHES.

BACKFILL WITH SUITABLE COMPACTED MATERIAL, AS APPROVED BY THE ENGINEER, AT NO EXPENSE TO THE DEPARTMENT.

TRAFFIC PATTERN ALTERATIONS

- K) NOTIFY THE ENGINEER THIRTY (30) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.
- ### SIGNING
- L) INSTALL ADVANCE WORK ZONE WARNING SIGNS WHEN WORK IS WITHIN 40 FT FROM THE EDGE OF TRAVEL LANE AND NO MORE THAN THREE (3) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- M) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

TRAFFIC CONTROL DEVICES

- N) WHEN LANE CLOSURES ARE NOT IN EFFECT SPACE CHANNELIZING DEVICES IN WORK AREAS NO GREATER IN FEET THAN TWICE THE POSTED SPEED LIMIT (MPH) EXCEPT, 10 FT ON-CENTER IN RADII, AND 3 FT OFF THE EDGE OF AN OPEN TRAVELWAY. REFER TO STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES SECTIONS 1130 (DRUMS), 1135 (CONES) AND 1180 (SKINNY DRUMS) FOR ADDITIONAL REQUIREMENTS.
- O) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.

PAVEMENT MARKINGS AND MARKERS

- P) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS BY THE END OF EACH DAY'S OPERATION.

MISCELLANEOUS



- Q) LAW ENFORCEMENT MAY BE USED TO MAINTAIN TRAFFIC THROUGH THE WORK AREA AND/OR INTERSECTIONS AS DIRECTED BY THE ENGINEER.




ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

<u>STD. NO.</u>	<u>TITLE</u>
1101.01	WORK ZONE ADVANCE WARNING SIGNS
1101.02	TEMPORARY LANE CLOSURES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1110.02	PORTABLE WORK ZONE SIGNS
1130.01	DRUMS
1135.01	CONES
1145.01	BARRICADES
1150.01	FLAGGERS
1180.01	SKINNY-DRUMS
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTI-LANE ROADWAYS
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING

PLOT DRIVER: NCDOT_pdf_color_eng_50.ppt
 USER: ERBROOKS
 FILE: pwt\pwtfor-used010a\tr\ome\hdf\hdf\US_East_01A\Documents\2540098\104\34317\6.0_CAD\BIM\6.2.WIP\Site 100-01-00210a\TrafficControl\TCP\100-01-00205_TMP_TMP01.dgn
 PENTABLE: NCDOT_tcp.tbl
 TIME: 5:28:51 PM
 DATE: 3/20/2026
 REVISIONS

APPROVED: <i>R. Erskine Brooks</i> DATE: 3/20/2026 SEAL			TRANSPORTATION MANAGEMENT PLAN
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED			



I HEREBY CERTIFY THESE PLANS ARE THE AS-BUILT PLANS

GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-
SHEET 1 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

GENERAL DRAWING
BRIDGE ON -L- (SWEETBIRCH RD.)
OVER CANE RIVER SOUTH OF US 19W

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-01
1	--	--	3	--	--	TOTAL SHEETS 21
2	--	--	4	--	--	


DES BY: G. MYERS	DATE: 11/25	DWG BY: B. PETERSON	DATE: 10/25
DES CHK: G. CASTREJON	DATE: 11/25	CHK BY: J. PATT	DATE: 12/25

HDR HDR Engineering, Inc. of the Carolinas
517 Fayetteville Rd., Suite 100 Raleigh, NC 27601
N.C.B.E.L.S. License Number F-0116


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Gregory F. Myers 3/5/2026

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.DP
 USER: MSHELLS DATE: 3/4/2026 TIME: 7:50:52 AM
 FILE: ...\\CAD\\Pion Production Set\\1




END BENT 1



BENT 1

FOUNDATION LAYOUT

NOTES
FOR GEOTECHNICAL FOUNDATION TABLES, SEE SHEET S-03.



END BENT 2

PENTABLE: NCDOT STRUCTURES DEFAULT PEN.tbl
TIME: 10:05:56 AM

PLOT DRIVER: NCDOT STRUCTURES DEFAULT PLOTTER.ppt
USER: DCARTER DATE: 12/23/2025
FILE: ...CAD\Plan Production_Set1\2

DES BY: G. MYERS	DATE: 10/25	DWG BY: B. PETERSON	DATE: 10/25
DES CHK: G. CASTREJON	DATE: 10/25	CHK BY: G. MYERS	DATE: 12/25



GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-
SHEET 2 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

GENERAL DRAWING
FOUNDATION LAYOUT

REVISIONS						SHEET NO. S-02
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1	--	--	3	--	--	21
2	--	--	4	--	--	

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

End Bt Pk (e.g., "Bent 1")	No.	Faction Reader per Pk KIPS	Required Drilled Pier Tip Elevation	Y OF L		ED PII	NFORM	N/IN	LATION	SU	ARY OJ	LLED	TESTING
				Blank	er								
End Be	1-4	395	2389.50										
Bent	2	615	2389.50		239								
End Be	1-4	400	2389.50										

* Drilled P Soil in r
 ** Permanent records
 *** Drilled p
 h, Drilled Pils
 se with Ardc
 casing Leng
 Article 411-7
 a are based
 Not in Soil at
 f the NCDOT
 the different
 DOT Stande
 upon that re
 Pier Length
 I Specificat
 in the groun
 cations.
 ion is approx
 t Elevation 2
 present esin
 ents with a r
 xp of drilled
 ed pier quan
 pay item, dri
 tion, witho
 are measur
 through air
 ver, and the
 nditions are
 id for as eith
 ill be paid at
 it casing tip
 a, Drilled Pils
 not until prio
 and is meas
 Dis. Drilled
 Dis. Drilled
 paid for as "I
 it in Soil" an
 ill."
 it Steel Cask
 Dis. Drilled Pils
 in

NOTES:

- The Dri r Foundati es are bas he bridge s xture desig oundation i tendations by a North na Profess ngineer (S bra, #053/ i 03-17-20. levations may
- The de ssented he based on s face inform obtained fr rgs perfor Site-0217 s been ass hat similar face condi det at the c site. Actua
- var fr se indicate nificant va in rock ele are encou during cons n, the Engi ust be conti mediate) ew and ve design.
- For en ns, see Ce r, as per C L. testing r required for s. The engi er will det he need fo esting. For esting, see n 411 of th ard Specil s.
- CSL tu s required d for drillec The engine . Do not e . below ele 2398 ft with or appro he Engine : Standard cations.
- SID Ins rs may be d for drillec . Do not e . below ele 2398 ft with or appro he Engine : Standard cations.
- Perma sel casings quired for (ers at Ber . Do not e . below ele 2398 ft with or appro he Engine : Standard cations.
- Test H s required ed pils at ant No. 1, l nt No.2 an No. 1 to cc ntinuous rc . Test hole:

DES BY: J. PATT DATE: 10/25
 DES CHK: S. DICKENS DATE: 10/25
 DWG BY: B. PETERSON DATE: 10/25
 CHK BY: G. MYERS DATE: 12/25

PROJECT NO. GROW NC 100-01-00205
 YANCEY COUNTY
 STATION: 11+20.40 -L-

SHEET 3 OF 5

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**GENERAL DRAWING
 GEOTECHNICAL
 FOUNDATION TABLES**



Gregory E. Myers


REVISIONS						SHEET NO. S-03
NO.	BY:	DATE:	NO.	BY:	DATE:	
1	MJS	03/26	3	--	--	TOTAL SHEETS 21
2	--	--	4	--	--	

HDR HDR Engineering, Inc. of the Carolinas
 511 Fayetteville Rd., Suite 400 Raleigh, NC 27601
 N.C.B.E.L.S. License Number F-0116

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

PENTABLE: NCDOT STRUCTURES DEFAULT PEN.tbl
 TIME: 8:29:03 AM

PLOT DRIVER: NCDOT STRUCTURES DEFAULT PLOTTER.dpf
 USER: GMYERS DATE: 3/18/2026
 FILE: ...CAD\N\pion Production Set\3



LOCATION SKETCH

HYDRAULIC DATA

0100 PRELIM. SRH-20 DISCHARGE	= 36,320 CFS
BASE FLOOD ELEVATION	= 2423.9 FT.
DRAINAGE AREA	= 112.0 SQ. MI.
0100 PRELIM. SRH-20 WATER ELEVATION	= 2428.5 FT.

TOTAL BILL OF MATERIAL

	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA. 11+20.40 -L-	REMOVAL OF EXISTING STRUCTURE AT STATION 11+20.40 -L-	ASBESTOS ASSESSMENT	3'-0" DIA DRILLED PIERS IN SOIL	3'-0" DIA DRILLED PIERS NOT IN SOIL	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	CSL TESTING
	LUMP SUM	LUMP SUM	LUMP SUM	LIN. FT.	LIN. FT.	LIN. FT.	EA.
SUPERSTRUCTURE							
END BENT 1				19.6	34.4		1
BENT 1				9.8	17.2	15.8	1
END BENT 2				19.6	34.4		1
TOTAL	LUMP SUM	LUMP SUM	LUMP SUM	49.0	86.0	15.8	3

	CLASS A CONCRETE (BRIDGE)	REINFORCING STEEL (BRIDGE)	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE	ELASTOMERIC BEARINGS	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS
	CU. YDS.	LBS.	LBS.	TONS	SO. YDS.	LUMP SUM	NO. LIN. FT.
SUPERSTRUCTURE						LUMP SUM	12 600.0
END BENT 1	94.7	25,896	2,382	315	350		
BENT 1	12.9	7,013	1,143				
END BENT 2	73.1	18,534	2,166	205	230		
TOTAL	180.7	51,443	5,691	520	580	LUMP SUM	12 600.0

NOTES

- ASSUMED LIVE LOAD = HS-20 OR ALTERNATE LOADING
- THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.
- THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.
- FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.
- FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
- FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- NEEDLE BEAMS WILL NOT BE ALLOWED UNLESS OTHERWISE CALLED FOR ON THE PLANS OR APPROVED BY THE ENGINEER.
- THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF PUBLIC SAFETY FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.
- REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED IN A MANNER THAT PREVENTS DEBRIS FROM FALLING INTO THE WATER. THE CONTRACTOR SHALL SUBMIT DEMOLITION PLANS FOR REVIEW AND REMOVE THE BRIDGE IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.
- THE SCOUR CRITICAL ELEVATION FOR BENT NO. 1 IS ELEVATION 2398.10 SCOUR CRITICAL ELEVATIONS ARE USED TO MONITOR POSSIBLE SCOUR PROBLEMS DURING THE LIFE OF THE STRUCTURE.
- FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.
- THE LOCATION OF THE CONSTRUCTION JOINT IN THE DRILLED PIERS IS BASED ON AN APPROXIMATE GROUND LINE ELEVATION. IF THE CONSTRUCTION JOINT IS ABOVE THE ACTUAL GROUND ELEVATION, THE CONTRACTOR SHALL PLACE THE CONSTRUCTION JOINT 1 FT. BELOW THE GROUND LINE.
- ASPHALT WEARING SURFACE IS INCLUDED IN ROADWAY QUANTITY ON ROADWAY PLANS.
- GUARDRAIL IS INCLUDED IN ROADWAY QUANTITY ON ROADWAY PLANS.
- FOR ASBESTOS ASSESSMENT FOR BRIDGE DEMOLITION AND RENOVATION ACTIVITIES, SEE SPECIAL PROVISIONS.
- THE FUNCTION OF GUARDRAIL PROVIDED ON STRUCTURE IS TO GUIDE DRIVERS ACROSS THE BRIDGE RATHER THAN MEET CRASH DESIGN REQUIREMENTS.
- AT THE CONTRACTOR'S OPTION, AND UPON REMOVAL OF THE CAUSEWAY, THE CLASS II RIP RAP USED IN THE CAUSEWAY MAY BE PLACED AS RIP RAP SLOPE PROTECTION. SEE SPECIAL PROVISIONS FOR CONSTRUCTION, MAINTENANCE AND REMOVAL OF TEMPORARY ACCESS AT STATION 11+20.40 -L-.

GROW NC
PROJECT NO. 100-01-00205

YANCEY COUNTY

STATION: 11+20.40 -L-

SHEET 4 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
GENERAL DRAWING
BRIDGE ON -L- (SWEETBIRCH RD.)
OVER CANE RIVER SOUTH OF US 19W



Gregory E. Myers

DES BY: G. MYERS	DATE: 11/25	DWG BY: B. PETERSON	DATE: 10/25
DES CHK: G. CASTREJON	DATE: 11/25	CHK BY: K. DICKENS	DATE: 12/25



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO. S-04
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1	--	--	3	--	--	21
2	--	--	4	--	--	

PENTABLE: NDDOT STRUCTURES DEFAULT PEN.tbl
TIME: 9:16:17 AM

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.dpt
USER: GMYERS DATE: 3/18/2026
FILE: ...CAD\Plan Production Set1.v4

LOAD AND RESISTANCE FACTOR RATING (LRFR) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS																								
LOAD TYPE	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING #	MINIMUM RATING FACTORS (RF)	TONS = W x RF	STRENGTH I LIMIT STATE								SERVICE III LIMIT STATE								COMMENT NUMBER		
						MOMENT				SHEAR				MOMENT										
						LIVE-LOAD FACTORS (γ _{LL})	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	LIVE-LOAD FACTORS (γ _{LL})	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION		DISTANCE FROM LEFT END OF SPAN (ft)	
DESIGN LOAD	HL-93 (INVENTORY)	N/A	①	1.394	--	1.75	0.276	1.57	50'	EL	24.5	0.531	1.39	50'	EL	2.45	0.80	0.276	1.44	50'	EL	24.5		
	HL-93 (OPERATING)	N/A		1.807	--	1.35	0.276	2.03	50'	EL	24.5	0.531	1.81	50'	EL	2.45	N/A	--	--	--	--	--		
	HS-20 (INVENTORY)	36.000	②	1.667	60.007	1.75	0.276	1.95	50'	EL	24.5	0.531	1.67	50'	EL	2.45	0.80	0.276	1.79	50'	EL	24.5		
	HS-20 (OPERATING)	36.000		2.161	77.787	1.35	0.276	2.52	50'	EL	24.5	0.531	2.16	50'	EL	2.45	N/A	--	--	--	--	--		
LEGAL LOAD	SINGLE VEHICLE (SV)	SNSH	13.500		3.635	49.079	1.4	0.276	4.95	50'	EL	24.5	0.531	4.70	50'	EL	2.45	0.80	0.276	3.64	50'	EL	24.5	
		SNGARBS2	20.000		2.871	57.420	1.4	0.276	3.91	50'	EL	24.5	0.531	3.42	50'	EL	2.45	0.80	0.276	2.87	50'	EL	24.5	
		SNAGRIS2	22.000		2.778	61.109	1.4	0.276	3.78	50'	EL	19.6	0.531	3.21	50'	EL	2.45	0.80	0.276	2.78	50'	EL	24.5	
		SNCOTTS3	27.250		1.814	49.418	1.4	0.276	2.47	50'	EL	24.5	0.531	2.36	50'	EL	2.45	0.80	0.276	1.81	50'	EL	24.5	
		SNAGGRS4	34.925		1.577	55.063	1.4	0.276	2.15	50'	EL	24.5	0.531	2.01	50'	EL	2.45	0.80	0.276	1.58	50'	EL	24.5	
		SNS5A	35.550		1.537	54.657	1.4	0.276	2.09	50'	EL	24.5	0.531	2.07	50'	EL	2.45	0.80	0.276	1.54	50'	EL	24.5	
		SNS6A	39.950		1.438	57.430	1.4	0.276	1.96	50'	EL	24.5	0.531	1.91	50'	EL	2.45	0.80	0.276	1.44	50'	EL	24.5	
	SNS7B	42.000		1.370	57.540	1.4	0.276	1.87	50'	EL	24.5	0.531	1.91	50'	EL	2.45	0.80	0.276	1.37	50'	EL	24.5		
	TRUCK TRACTOR SEMI-TRAILER (TTST)	TNAGRIT3	33.000		1.761	58.118	1.4	0.276	2.40	50'	EL	24.5	0.531	2.25	50'	EL	2.45	0.80	0.276	1.76	50'	EL	24.5	
		TNT4A	33.075		1.777	58.759	1.4	0.276	2.42	50'	EL	24.5	0.531	2.17	50'	EL	2.45	0.80	0.276	1.78	50'	EL	24.5	
		TNT6A	41.600		1.480	61.558	1.4	0.276	2.01	50'	EL	24.5	0.531	2.08	50'	EL	2.45	0.80	0.276	1.48	50'	EL	24.5	
		TNT7A	42.000		1.502	63.087	1.4	0.276	2.05	50'	EL	24.5	0.531	1.94	50'	EL	2.45	0.80	0.276	1.50	50'	EL	24.5	
		TNT7B	42.000		1.566	65.773	1.4	0.276	2.13	50'	EL	24.5	0.531	1.84	50'	EL	2.45	0.80	0.276	1.57	50'	EL	24.5	
		TNAGRIT4	43.000		1.486	63.902	1.4	0.276	2.02	50'	EL	24.5	0.531	1.77	50'	EL	2.45	0.80	0.276	1.49	50'	EL	24.5	
TNAGT5A		45.000		1.388	62.470	1.4	0.276	1.89	50'	EL	24.5	0.531	1.80	50'	EL	2.45	0.80	0.276	1.39	50'	EL	24.5		
TNAGT5B	45.000		③	1.360	61.206	1.4	0.276	1.85	50'	EL	24.5	0.531	1.68	50'	EL	2.45	0.80	0.276	1.36	50'	EL	24.5		
EMERGENCY VEHICLE (EV)	EV2	28.750		2.154	61.929	1.3	0.276	2.97	50'	EL	24.5	0.531	2.50	50'	EL	5.50	0.80	0.276	2.15	50'	EL	24.5		
	EV3	43.000	④	1.392	59.852	1.3	0.276	1.92	50'	EL	24.5	0.531	1.69	50'	EL	5.50	0.80	0.276	1.39	50'	EL	24.5		

LOAD FACTORS:

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ _{DC}	γ _{DW}
		STRENGTH I	1.25
	SERVICE III	1.00	1.00

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.

ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

COMMENTS:

-
-
-
-

CONTROLLING LOAD RATING

① DESIGN LOAD RATING (HL-93)

② DESIGN LOAD RATING (HS-20)


③ LEGAL LOAD RATING **

④ EMERGENCY VEHICLE LOAD RATING **

** SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION

I - INTERIOR GIRDER
EL - EXTERIOR LEFT GIRDER
ER - EXTERIOR RIGHT GIRDER



GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-


SHEET 5 OF 5



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

STANDARD
LRFR SUMMARY FOR
50' CORED SLAB UNIT
90° SKEW
(NON-INTERSTATE TRAFFIC)

REVISIONS						SHEET NO. S-05
NO.	BY:	DATE:	NO.	BY:	DATE:	
1	--	--	3	--	--	TOTAL SHEETS 21
2	--	--	4	--	--	




DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

STD. NO. 21LRFR1-90S_50L


PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.plt
 USER: DCARTER DATE: 12/23/2025
 FILE: ...CAD\Plot Production_Set1\5

DES BY: G. MYERS DATE: 10/25
 DES CHK: G. MARTINEZ DATE: 10/25
 DWG BY: D. CARTER DATE: 11/25
 CHK BY: A. AMBROSI DATE: 11/25




TYPICAL SECTION

* - THE MAXIMUM GUARDRAIL HEIGHT AND ASPHALT THICKNESS IS SHOWN. THE HEIGHT OF THE GUARDRAIL AND ASPHALT THICKNESS VARIES WHILE THE TOP OF THE GUARDRAIL FOLLOWS THE PROFILE OF THE GUTTERLINE.



TYPICAL PLAN (TYP. EA. CORED SLAB UNIT)



SECTION A-A

BLOCKOUT DETAIL FOR ANCHOR BOLTS






PLATE DETAILS




EXT. SLAB SECTION


(FOR PRESTRESSED STRAND LAYOUT, SEE INTERIOR SLAB SECTION.)
(GUARDRAIL ANCHORAGE ASSEMBLY NOT SHOWN. FOR GUARDRAIL ANCHOR ASSEMBLY, SEE SHEET 3 OF 3)



SECTION AT END BENT



SECTION AT BENT




INTERIOR SLAB SECTION (50' UNIT) (19 STRANDS REQUIRED)

0.6" Ø LOW RELAXATION STRAND LAYOUT


▲ BOND SHALL BE BROKEN ON THESE STRANDS FOR A DISTANCE OF 6'-0" FROM END OF CORED SLAB UNIT. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.

DEBONDING LEGEND



SHEAR KEY DETAIL


NOTE: OMIT SHEAR KEY ON OUTSIDE FACE OF EXTERIOR CORED SLABS.



ELEVATION VIEW


SECTION B-B

GRAUTED RECESS AT END OF POST-TENSIONED STRAND OF CORED SLABS



END ELEVATION

SHOWING PLACEMENT OF DOUBLE STIRRUPS AND LOCATION OF ANCHOR BOLT HOLES. (STRAND LAYOUT NOT SHOWN.)
INTERIOR SLAB UNIT SHOWN-EXTERIOR SLAB UNIT SIMILAR EXCEPT SHEAR KEY LOCATION.



THREADED INSERT DETAIL

GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-

SHEET 1 OF 3

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
3'-0" x 1'-9"
PRESTRESSED CONCRETE
CORED SLAB UNIT
90° SKEW

REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1	--	--	3	--
2	--	--	4	--

TOTAL SHEETS 21

STD. NO. 21" PCS2-27.90S



PENTABLE: NCDOT STRUCTURES DEFAULT PEN.tbl
TIME: 10:59:23 AM

PLOT DRIVER: NCDOT STRUCTURES DEFAULT PLOTTER.dpf
USER: DCARTER DATE: 12/23/2025
DES: G. MYERS DATE: 10/25
FILE: ...CAD\Plan Production Set1.vg


DES BY: G. MARTINEZ	DATE: 10/25	DWG BY: D. CARTER	DATE: 11/25
DES CHK: G. MYERS	DATE: 10/25	CHK BY: A. AMBROSI	DATE: 11/25

HDR HDR Engineering, Inc. of the Carolinas
551 Fayetteville Rd., Suite 100 Raleigh, NC 27601
N.C.B.E.L.S. License Number F-0116
12/23/2025
Gregory E. Myers
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED





PLAN OF UNIT
SPAN A SHOWN, SPAN B SIMILAR



GUTTERLINE ASPHALT THICKNESS AND GUARDRAIL HEIGHT	ASPHALT OVERLAY THICKNESS		GUARDRAIL HEIGHT	
	@ MIDSPAN		@ MIDSPAN	
50' UNIT	1 3/8"		2'-8 3/8"	

GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-
SHEET 2 OF 3

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
PLAN OF 50' UNIT
13'-9" CLEAR ROADWAY
90° SKEW



DES BY: G. MYERS	DATE: 10/25	DWG BY: D. CARTER	DATE: 11/25
DES CHK: G. MARTINEZ	DATE: 10/25	CHK BY: A. AMBROSI	DATE: 11/25





DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO. S-07 TOTAL SHEETS 21
NO.	BY:	DATE:	NO.	BY:	DATE:	
1	--	--	3	--	--	
2	--	--	4	--	--	

STD. NO. 21" PCS_27_90S_50L

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.plt
 USER: GMYERS DATE: 12/23/2025
 FILE: ...ACAD\Plot Production_Set17
 PENTABLE: NDDOT STRUCTURES DEFAULT PEN.tbl
 TIME: 3:16:11 PM



GUARDRAIL ANCHOR ASSEMBLY FOR PRESTRESSED CONCRETE CORED SLAB UNIT

DEAD LOAD DEFLECTION AND CAMBER	
	3'-0" x 1'-9"
50' CORED SLAB UNIT	0.6" Ø L.R. STRAND
CAMBER (SLAB ALONE IN PLACE)	1/2" ↑
DEFLECTION DUE TO SUPERIMPOSED DEAD LOAD **	3/8" ↓
FINAL CAMBER	1/8" ↑

** INCLUDES FUTURE WEARING SURFACE

GRADE 270 STRANDS	
	0.6" Ø L.R.
AREA (SQUARE INCHES)	0.217
ULTIMATE STRENGTH (LBS. PER STRAND)	58,600
APPLIED PRESTRESS (LBS. PER STRAND)	43,950

CORED SLAB REQUIRED			
	NUMBER	LENGTH	TOTAL LENGTH
50' UNIT			
EXTERIOR C.S.	4	50'-0"	200'
INTERIOR C.S.	8	50'-0"	400'
TOTAL	12	50'-0"	600'

BILL OF MATERIAL FOR ONE 50' CORED SLAB UNIT							
				EXTERIOR UNIT		INTERIOR UNIT	
BAR	NUMBER	SIZE	TYPE	LENGTH	WEIGHT	LENGTH	WEIGHT
B6	4	#4	STR	25'-9"	69	25'-9"	69
S1	8	#5	3	4'-3"	35	4'-3"	35
S2	104	#4	3	5'-4"	371	5'-4"	371
REINFORCING STEEL				LBS.	475		475
6500 P.S.I. CONCRETE				LBS.	7.1		7.1
0.6" Ø L.R. STRANDS				NO.	19		19

NOTES

ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW RELAXATION GRADE 270 STRANDS AND SHALL CONFORM TO AASHTO M203 EXCEPT FOR SAMPLING REQUIREMENTS WHICH SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

ALL REINFORCING STEEL CAST WITH THE CORED SLAB SECTIONS SHALL BE GRADE 60 AND SHALL BE INCLUDED IN THE UNIT PRICE BID FOR PRESTRESSED CONCRETE CORED SLABS.

RECESSES FOR TRANSVERSE STRANDS SHALL BE GROUTED AFTER THE TENSIONING OF THE STRANDS.

THE 2 1/2" Ø ANCHOR BOLT HOLES AND BLOCKOUTS AT FIXED ENDS OF SLAB SECTIONS SHALL BE FILLED WITH NON-SHRINK GROUT.

THE BACKER RODS SHALL CONFORM TO THE REQUIREMENTS OF TYPE M BOND BREAKER. SEE SECTION 1028 OF THE STANDARD SPECIFICATIONS.

WHEN CORED SLABS ARE CAST, AN INTERNAL HOLD-DOWN SYSTEM SHALL BE EMPLOYED TO PREVENT VOIDS FROM RISING OR MOVING SIDWAYS. AT LEAST SIX WEEKS PRIOR TO CASTING CORED SLABS, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER FOR REVIEW AND COMMENT, DETAILED DRAWINGS OF THE PROPOSED HOLD-DOWN SYSTEM, IN ADDITION TO STRUCTURAL DETAILS, LOCATION AND SPACING OF THE HOLD-DOWNS SHALL BE INDICATED.

APPLY EPOXY PROTECTIVE COATING TO CORED SLAB UNIT ENDS.

PRESTRESSING STRANDS SHALL BE CUT FLUSH WITH THE CORED SLAB UNITS ENDS.

FLAME CUTTING OF THE TRANSVERSE POST-TENSIONING STRAND IS NOT ALLOWED.

THE TRANSFER OF LOAD FROM THE ANCHORAGES TO THE CORED SLAB UNIT SHALL BE DONE WHEN THE CONCRETE HAS REACHED A COMPRESSIVE STRENGTH OF NOT LESS THAN THE REQUIRED STRENGTH SHOWN IN THE "CONCRETE RELEASE STRENGTH" TABLE.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

THE PERMITTED THREADED INSERTS ARE DETAILED AS AN OPTION FOR THE CONTRACTOR TO ATTACH FALSEWORK AND FORMWORK DURING CONSTRUCTION.

THE PERMITTED THREADED INSERTS IN THE EXTERIOR UNITS SHALL BE SIZED BY THE CONTRACTOR, SPACED AT 4'-0" CENTERS AND GALVANIZED IN ACCORDANCE WITH SECTION 1076 OF THE STANDARD SPECIFICATIONS. STAINLESS STEEL THREADED INSERTS MAY BE USED AS AN ALTERNATE.

THE PERMITTED THREADED INSERTS SHALL BE GROUTED BY THE CONTRACTOR IMMEDIATELY FOLLOWING REMOVAL OF THE FALSEWORK.

THE COST OF THE PERMITTED THREADED INSERTS SHALL BE INCLUDED IN THE PRICE BID FOR THE PRECAST UNITS.

POST-TENSIONING SHALL BE DONE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

THE GUARDRAIL ANCHOR ASSEMBLY FOR CORED SLABS SHALL CONSIST OF THE FOLLOWING COMPONENTS:

- A. FERRULES SHALL BE MADE FROM STEEL MEETING THE REQUIREMENTS OF AASHTO M169, GRADE 12L14 AND SHALL HAVE A MINIMUM LENGTH OF THREADS OF 2 1/2".
- B. 4 - 1" Ø X 2 1/4" BOLTS WITH WASHERS, BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307. BOLTS AND WASHERS SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 1" Ø X 2 1/4" GALVANIZED BOLTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)
- C. WIRE STRUTS SHOWN IN THE GUARDRAIL ANCHOR ASSEMBLY FOR CORED SLABS DETAIL ARE MINIMUM ALLOWABLE SIZE AND SHALL HAVE A MINIMUM TENSILE STRENGTH OF 100,000 P.S.I. AS AN OPTION, A 1/16" Ø WIRE STRUT WITH A MINIMUM TENSILE STRENGTH OF 90,000 PSI IS ACCEPTABLE.

GUARDRAIL ANCHOR ASSEMBLY WITH BOLTS SHALL BE ASSEMBLED IN THE SHOP. BOLT THREADS MAY BE RECUT AS NECESSARY TO INSURE FIT.


THE COST OF THE GUARDRAIL ANCHOR ASSEMBLY COMPLETE IN PLACE, SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR PRESTRESSED CORED SLAB UNITS.

FERRULES TO BE PLUGGED DURING CASTING OF PRESTRESSED CONCRETE CORED SLAB UNITS AS RECOMMENDED BY THE MANUFACTURER.

AT THE CONTRACTOR'S OPTION, FERRULES WITH OPEN OR CLOSED ENDS MAY BE USED.

PAYMENT FOR GUARDRAIL, POSTS, AND POST BASE PLATES IS INCLUDED IN ROADWAY PAY ITEMS.

PRESTRESSED CONCRETE CORED SLAB UNITS REINFORCING STEEL MAY BE SHIFTED AS NECESSARY TO CLEAR GUARDRAIL ANCHOR ASSEMBLY. CARE SHOULD BE TAKEN TO KEEP THE SHIFTING OF REINFORCING STEEL TO A MINIMUM.



ELASTOMERIC BEARING DETAILS
ELASTOMER IN ALL BEARING SHALL BE 50 DUROMETER HARDNESS.

CONCRETE RELEASE STRENGTH	
UNIT	PSI
50' UNITS	4900

PROJECT NO. GROW NC 100-01-00205

YANCEY COUNTY

STATION: 11+20.40 -L-

SHEET 3 OF 3



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
3'-0" x 1'-9"
PRESTRESSED CONCRETE
CORED SLAB UNIT
90° SKEW

REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1	--	--	3	--	--
2	--	--	4	--	--

SHEET NO.
S-08
TOTAL SHEETS
21

DES BY: G. MYERS DATE: 10/25 DWG BY: D. CARTER DATE: 11/25
DES CHK: G. MARTINEZ DATE: 10/25 CHK BY: A. AMBROSI DATE: 11/25


HDR HDR Engineering, Inc. of the Carolinas
251 Fayetteville Rd., Suite 100 Raleigh, NC 27601
N.C.B.E.L.S. License Number F-0116

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STD. NO. 21" PCS3.27.90S

PENTABLE: NDDOT STRUCTURES DEFAULT PEN.tbl
TIME: 11:39:28 AM

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.dpt
USER: DCARTER DATE: 12/23/2025
FILE: ...CAD\Plan Production_Set18



TOP OF COLUMN ELEVATIONS	
COLUMN NO.	ELEVATION
1	2423.49
2	2423.36
3	2423.10
4	2422.96

NOTES

FOR SECTION A-A AND CONSTRUCTION JOINT DETAIL AT BASE OF WALL, SEE SHEET 5 OF 5.

FOR SECTIONS C-C AND D-D, SEE SHEET 4 OF 5.

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR ANCHOR BOLTS.

HOOKS ON "V" BARS MAY BE TURNED AS NECESSARY FOR PLACING REINFORCING STEEL.

FOR DRILLED PIERS, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.

ALL STEEL IN THE DRILLED PIERS IS INCLUDED IN THE PAY ITEMS FOR "REINFORCING STEEL" AND "SPIRAL COLUMN REINFORCING STEEL."



* INVERT ALTERNATE STIRRUPS.

THE CONTRACTOR SHALL FIELD VERIFY THE DRILLED PIER TIP ELEVATION AT EACH DRILLED PIER, PRIOR TO ORDERING REINFORCEMENT FOR DRILLED PIERS. DRILLED PIER LONGITUDINAL REINFORCEMENT AND SPIRAL LENGTHS ARE BASED ON THE ASSUMED DRILLED PIER TIP ELEVATION AND SHALL BE ADJUSTED AS NECESSARY TO MEET THE MINIMUM DRILLED PIER PENETRATION INTO ROCK.

REINFORCING STRAPS SHALL BE ATTACHED TO THE END BENT 1 RETAINING WALL. DESIGN REINFORCING STRAPS ON END BENT 1 RETAINING WALL AS SHOWN IN TIE BACK DETAIL ON SHEET 4 OF 5.

REINFORCING STRAPS SHALL NOT BE SPACED GREATER THAN 7 FEET ALONG THE FACE OF THE RETAINING WALL.

DESIGN REINFORCEMENT CONNECTED TO END BENT 1 RETAINING WALL FOR FACTORED LOAD AND LENGTH OF REINFORCEMENT IN ACTIVE ZONE, CAST REINFORCEMENT OR CONNECTORS INTO RETAINING WALL FOR END BENT NO. 1 LOCATED AT STA. 10+69.00 -L-. MAINTAIN A CLEARANCE OF AT LEAST 3" BETWEEN REINFORCEMENT OR CONNECTORS AND REINFORCING STEEL IN RETAINING WALL.



GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-
SHEET 1 OF 5



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

**SUBSTRUCTURE
END BENT 1
PLAN AND ELEVATION**


DES BY: J. PATT	DATE: 11/25	DWG BY: B. PETERSON	DATE: 11/25
DES CHK: K. DICKENS	DATE: 12/25	CHK BY: G. MYERS	DATE: 12/25

HDR HDR Engineering, Inc. of the Carolinas
551 Fayetteville Rd., Suite 100 Raleigh, NC 27601
N.C. B.E.L.S. License Number F-0116


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

REVISIONS				SHEET NO. 5-09
NO.	BY:	DATE:	DATE:	
1	--	--	--	TOTAL SHEETS 21
2	--	--	--	

PLOT DRIVER: NODOT STRUCTURES DEFAULT PLOTTER.DPT
 USER: MSHELLS DATE: 1/6/2026
 FILE: ...\\CAD\\Pion Production Set19



PLAN OF RETAINING WALL
(DRILLED PIERS AND MAIN REINFORCEMENT FOR DRILLED PIERS AND COLUMNS NOT SHOWN FOR CLARITY)



ELEVATION OF RETAINING WALL

NOTES
FOR SECTIONS E-E, F-F & G-G, SEE SHEET 4 OF 5.
FOR DETAIL "B", SEE SHEET 5 OF 5.
FOR ELEVATION OF WEEPHOLE, SEE SECTION F-F ON SHEET 4 OF 5.
⊕ = 4-#6V105 @ 9" CTS. (FRONT FACE) (TYP. COL. 2 & 3)

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.ppt
 USER: MSELLS DATE: 1/6/2026
 FILE: ...\\CAD\\Pilot Production Set\\10
 PENTABLE: NDDOT STRUCTURES DEFAULT PEN.tbl
 TIME: 12:03:50 PM

DES BY: J. PATT	DATE: 11/25	DWG BY: B. PETERSON	DATE: 11/25
DES CHK: G. MYERS	DATE: 12/25	CHK BY: G. MYERS	DATE: 12/25

HDR HDR Engineering, Inc. of the Carolinas
 551 Fayetteville Rd., Suite 100 Raleigh, NC 27601
 N.C.B.E.L.S. License Number F-01116




PROJECT NO. 100-01-00205
 YANCEY COUNTY
 STATION: 11+20.40 -L-
 SHEET 2 OF 5

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH


**SUBSTRUCTURE
 END BENT 1
 RETAINING WALL LAYOUT**

REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	5-10	TOTAL SHEETS
1	--	--	3	--	--		21
2	--	--	4	--	--		

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**




PLAN OF WING
(WING W1 SHOWN, WING W2 OPPOSITE HAND)
(DRILLED PIER AND COLUMN NOT SHOWN FOR CLARITY)




ELEVATION OF WING
(WING W1 SHOWN, WING W2 OPPOSITE HAND)
(COLUMN NOT SHOWN FOR CLARITY)

WINGWALL "V" BAR TABLE		
LOCATION	FRONT FACE	FILL FACE
WINGWALL 1	18-#6V110 @ 9"CTS.	20-#6V110 @ 9"CTS.
WINGWALL 2	18-#6V111 @ 9"CTS.	20-#6V111 @ 9"CTS.



SECTION B-B



SECTION H-H

GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-

SHEET 3 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

**SUBSTRUCTURE
END BENT 1
WINGWALL DETAILS**




REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	5-11
1	--	--	3	--	--	TOTAL SHEETS
2	--	--	4	--	--	21

DES BY: J. PATT	DATE: 11/25	DWG BY: B. PETERSON	DATE: 11/25
DES CHK: G. MYERS	DATE: 12/25	CHK BY: G. MYERS	DATE: 12/25




DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.DIF
 USER: DCARTER DATE: 12/23/2025
 PENTABLE: NDDOT STRUCTURES DEFAULT PEN.tbl
 TIME: 2:17:36 PM
 FILE: ...\\CAD\\Pion Production Set\\11




PLAN OF DRILLED PIERS




SECTION F-F


SECTION G-G




SECTION C-C



SECTION D-D



SECTION E-E



TIE BACK DETAIL
(SEE "SUBSTRUCTURE END BENT 1 PLAN AND ELEVATION" SHEET FOR NOTES)

COLUMN NO.	HEIGHT
1	20'-5 7/8"
2	20'-4 5/16"
3	20'-1 1/16"
4	19'-11 1/2"

GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-
SHEET 4 OF 5

FOR STEEL OR HDPE REINFORCEMENT CONNECTED TO RETAINING WALL OF END BENT, SUBMIT PROPOSED CONNECTION DETAILS FOR APPROVAL



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
SUBSTRUCTURE
END BENT 1 DETAILS

REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1	--	--	3	--	--
2	--	--	4	--	--

SHEET NO. S-12
TOTAL SHEETS 21

DES BY: J. PATT DATE: 11/25 DWG BY: B. PETERSON DATE: 11/25
DES CHK: G. MYERS DATE: 12/25 CHK BY: G. MYERS DATE: 12/25




DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.DPT
USER: MSHELLS DATE: 1/6/2026
FILE: ...CAD\Plan Production Set\12


+

+

+




SECTION A-A




CONSTRUCTION JOINT DETAIL

(WALL REINFORCEMENT NOT SHOWN FOR CLARITY)



SECTION THRU DRILLED PIER

DES BY: J. PATT	DATE: 11/25	DWG BY: D. CARTER	DATE: 11/25
DES CHK: K. DICKENS	DATE: 12/25	CHK BY: G. MYERS	DATE: 12/25




TEMPORARY DRAINAGE AT END BENT


BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.



ALL BAR DIMENSIONS ARE OUT TO OUT



DETAIL "B"

* THE SP-101 SPIRAL REINFORCING STEEL SHALL BE #31 OR D-31 COLD DRAWN WIRE OR #5 PLAIN OR DEFORMED BAR
 * THE SP-102 THRU SP-104 SPIRAL REINFORCING STEEL SHALL BE W20 OR D-20 COLD DRAWN WIRE OR #4 PLAIN OR DEFORMED BAR



Gregory E. Myers

BILL OF MATERIAL

END BENT 1				
BAR NO.	SIZE	TYPE	LENGTH	WEIGHT
B101	#9	1	27'-10"	189
B102	#9	1	26'-4"	179
B103	#9	1	25'-3"	172
B104	#9	1	24'-2"	164
B105	#9	1	23'-1"	157
B106	#9	1	21'-7"	147
B107	#5	STR	25'-4"	106
B108	#5	STR	19'-2"	80
H101	#6	STR	19'-7"	1647
H102	#6	4	20'-10"	1752
H103	#6	4	21'-4"	1794
H104	#6	4	20'-4"	305
H105	#6	4	19'-2"	288
H106	#6	4	16'-4"	147
H107	#6	4	15'-4"	138
K101	#6	STR	2'-7"	23
K102	#6	STR	3'-5"	31
S101	#5	3	9'-6"	208
U101	#6	5	10'-0"	1682
V101	#14	2	35'-5"	2709
V102	#14	2	38'-4"	5865
V103	#14	2	34'-11"	2671
V104	#6	STR	23'-3"	2654
V105	#6	STR	22'-4"	1879
V106	#6	STR	20'-2"	61
V107	#6	STR	22'-3"	134
V108	#6	STR	19'-7"	59
V109	#6	STR	4'-0"	108
V110	#6	STR	4'-8"	266
V111	#6	STR	4'-11"	281
TOTAL			25,896 LBS.	
SPIRAL COLUMN REINFORCING STEEL				
BAR NO.	SIZE	TYPE	LENGTH	WEIGHT
SP-101	#5	7	217'-8"	908
SP-102	#5	6	551'-2"	368
SP-103	#5	6	560'-1"	748
SP-104	#5	6	535'-7"	358
TOTAL			2,382 LBS.	
CLASS A CONCRETE BREAKDOWN				
POUR #2 (COLUMNS & RETAINING WALL)			76.2 C.Y.	
POUR #3 (CAP & UPPER WINGS)			18.5 C.Y.	
TOTAL CLASS A CONCRETE			94.7 C.Y.	
DRILLED PIERS				
DRILLED PIER CONCRETE			14.0 C.Y.	
POUR #1 (DRILLED PIERS)				



GROW NC
 PROJECT NO. 100-01-00205
 YANCEY COUNTY
 STATION: 11+20.40 -L-

SHEET 5 OF 5

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE
 END BENT 1
 DETAILS AND
 BILL OF MATERIALS

REVISIONS			
NO.	BY:	DATE:	DATE:
1	--	--	--
2	--	--	--

SHEET NO. S-13
TOTAL SHEETS 21



DIMENSIONS & REINFORCING STEEL ARE TYPICAL FOR EACH COLUMN & DRILLED PIER UNLESS OTHERWISE NOTED.

NOTES

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR ANCHOR BOLTS.

HOOKS ON "V" BARS MAY BE TURNED AS NECESSARY FOR PLACING REINFORCING STEEL.

FOR DRILLED PIERS, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.


ALL STEEL IN THE DRILLED PIERS IS INCLUDED IN THE PAY ITEMS FOR "REINFORCING STEEL" AND "SPIRAL COLUMN REINFORCING STEEL."

* INVERT ALTERNATE STIRRUPS.

THE LOCATION OF THE CONSTRUCTION JOINT IN THE DRILLED PIERS IS BASED ON AN APPROXIMATE GROUND LINE ELEVATION. IF THE CONSTRUCTION JOINT IS ABOVE THE ACTUAL GROUND LINE ELEVATION, THE CONTRACTOR SHALL PLACE THE CONSTRUCTION JOINT ONE FOOT BELOW THE GROUND LINE.

DRILLED PIERS SHALL BE TERMINATED ONE FOOT ± ABOVE NORMAL WATER SURFACE ELEVATION FOR SHAFTS LOCATED IN WATER.

THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE LONGITUDINAL REINFORCEMENT FOR DRILLED PIERS IS DETAILED WITH 3 FEET OF EXTRA LENGTH.



GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-

SHEET 1 OF 2

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SUBSTRUCTURE
BENT No. 1



Gregory E. Myers

REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1	--	--	3	--
2	--	--	4	--

TOTAL SHEETS
21


DES BY: A. AMBROSI	DATE: 11/25	DWG BY: B. PETERSON	DATE: 09/25
DES CHK: K. DICKENS	DATE: 12/25	CHK BY: K. DICKENS	DATE: 12/25




DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PENTABLE: NCDOT STRUCTURES DEFAULT PEN.tbl
TIME: 3:19:50 PM


PLOT DRIVER: NCDOT STRUCTURES DEFAULT PLOTTER.dpt
USER: OMVERS DATE: 12/23/2025
FILE: ...CAD\Plan Production Set\14




PLAN OF DRILLED PIERS & COLUMNS




END ELEVATION



CONSTRUCTION JOINT DETAIL




END OF CAP VIEW (TYPICAL BOTH ENDS)



ALL BAR DIMENSIONS ARE OUT TO OUT

COLUMN HEIGHTS	
COLUMN NO.	HEIGHT (FT.)
1	15'-9 1/8"
2	15'-6 3/4"



SECTION THRU CAP

BILL OF MATERIAL FOR ONE BENT

BAR NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	#11	1	23'-2"	1478
B2	#5	STR	20'-2"	169
M1	#11	STR	26'-4"	2799
S1	#5	2	9'-0"	423
U1	#5	3	5'-8"	36
U2	#5	3	5'-6"	35
V1	#11	4	19'-6"	2073

REINFORCING STEEL (FOR ONE BENT) 7,013 LBS.

BAR NO.	SIZE	TYPE	LENGTH	WEIGHT
SP-1	2	*	265'-7"	555
SP-2	2	**	439'-10"	588

SPIRAL COLUMN REINFORCING STEEL (FOR ONE BENT) 1,143 LBS.

* THE SP-1 SPIRAL REINFORCING STEEL SHALL BE W31 OR D-31 COLD DRAWN WIRE OR #5 PLAIN OR DEFORMED BAR
 ** THE SP-2 SPIRAL REINFORCING STEEL SHALL BE W20 OR D-20 COLD DRAWN WIRE OR #4 PLAIN OR DEFORMED BAR

CLASS A CONCRETE BREAKDOWN (FOR ONE BENT)	
POUR #2 (COLUMNS)	5.7 C.Y.
POUR #3 (CAP)	7.2 C.Y.
TOTAL CLASS A CONCRETE	12.9 C.Y.

DRILLED PIERS: (FOR ONE BENT)	
DRILLED PIER CONCRETE	
POUR #1 (DRILLED PIERS)	8.6 C.Y.

GROW NC
 PROJECT NO. 100-01-00205
 YANCEY COUNTY
 STATION: 11+20.40 -L-

SHEET 2 OF 2

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
SUBSTRUCTURE BENT No. 1



REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1	--	--	3	--
2	--	--	4	--


TOTAL SHEETS 21

DES BY: A. AMBROSI	DATE: 11/25	DWG BY: B. PETERSON	DATE: 09/25
DES CHK: K. DICKENS	DATE: 12/25	CHK BY: K. DICKENS	DATE: 12/25




DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.DP
 USER: DCARTER DATE: 12/23/2025
 PENTABLE: NDDOT STRUCTURES DEFAULT PEN.tbl
 TIME: 2:07:23 PM
 FILE: ...CAD\Pion Production Set\15



TOP OF COLUMN ELEVATIONS	
COLUMN NO.	ELEVATION
1	2420.41
2	2420.29
3	2420.14
4	2419.88



NOTES

FOR DETAIL "A", SEE "SUBSTRUCTURE END BENT 1 PLAN AND ELEVATION" SHEET.

FOR SECTION A-A AND CONSTRUCTION JOINT DETAIL AT BASE OF WALL, SEE SHEET 5 OF 5.

FOR SECTION C-C AND D-D, SEE SHEET 4 OF 5.

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR ANCHOR BOLTS.

HOOKS ON "V" BARS MAY BE TURNED AS NECESSARY FOR PLACING REINFORCING STEEL.

FOR DRILLED PIERS, SEE SECTION 411 OF THE STANDARD SPECIFICATIONS.

ALL STEEL IN THE DRILLED PIERS IS INCLUDED IN THE PAY ITEMS FOR "REINFORCING STEEL" AND "SPIRAL COLUMN REINFORCING STEEL."

* INVERT ALTERNATE STIRRUPS.

THE CONTRACTOR SHALL FIELD VERIFY THE DRILLED PIER TIP ELEVATION AT EACH DRILLED PIER, PRIOR TO ORDERING REINFORCEMENT FOR DRILLED PIERS. DRILLED PIER LONGITUDINAL REINFORCEMENT AND SPIRAL LENGTHS ARE BASED ON THE ASSUMED DRILLED PIER TIP ELEVATION AND SHALL BE ADJUSTED AS NECESSARY TO MEET THE MINIMUM DRILLED PIER PENETRATION INTO ROCK.

GROW NC
 PROJECT NO. 100-01-00205
 YANCEY COUNTY
 STATION: 11+20.40 -L-

SHEET 1 OF 5



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**SUBSTRUCTURE
 END BENT 2
 PLAN AND ELEVATION**



REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	DATE:	5-16
1	--	--	3	--	TOTAL SHEETS
2	--	--	4	--	21

DES BY: J. PATT DATE: 11/25 DWG BY: M. SELLS DATE: 12/25
 DES CHK: K. DICKENS DATE: 11/25 CHK BY: G. MYERS DATE: 12/25

HDR HDR Engineering, Inc. of the Carolinas
 515 Fayetteville Rd., Suite 100 Raleigh, NC 27601
 N.C.B.E.L.S. License Number F-0116

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.plt
 USER: OMVERS DATE: 12/23/2025
 TIME: 3:26:08 PM
 FILE: ...\\CAD\\Pilot Production Set\\16



NOTES
 FOR SECTIONS E-E, F-F & G-G, SEE SHEET 4 OF 5.
 FOR DETAIL "B", SEE SHEET 5 OF 5.
 FOR ELEVATION OF WEEPHOLE, SEE SECTION F-F ON SHEET 4 OF 5.
 # = 4-#5V205 @ 9" CTS. (FRONT FACE) (TYP. COL. 2 & 3)

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.ppt
 USER: MSSELLS DATE: 1/6/2026
 FILE: ...CAD\Nion Production Set\17
 PENTABLE: NDDOT STRUCTURES DEFAULT PEN.tbl
 TIME: 12:24:20 PM

DES BY: J. PATT	DATE: 11/25	DWG BY: M. SELLS	DATE: 12/25
DES CHK: G. MYERS	DATE: 12/25	CHK BY: G. MYERS	DATE: 12/25




GROW NC
 PROJECT NO. 100-01-00205
 YANCEY COUNTY
 STATION: 11+20.40 -L-
 SHEET 2 OF 5

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH


**SUBSTRUCTURE
 END BENT 2
 RETAINING WALL LAYOUT**

REVISIONS						SHEET NO. S-17
NO.	BY:	DATE:	NO.	BY:	DATE:	
1	--	--	3	--	--	TOTAL SHEETS 21
2	--	--	4	--	--	


DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED




PLAN OF WING
(WING W4 SHOWN, WING W3 OPPOSITE HAND)
(DRILLED PIER AND COLUMN NOT SHOWN FOR CLARITY)



ELEVATION OF WING
(WING W4 SHOWN, WING W3 OPPOSITE HAND)
(COLUMN NOT SHOWN FOR CLARITY)



SECTION H-H



SECTION B-B

WINGWALL "V" BAR TABLE		
LOCATION	FRONT FACE	FILL FACE
WINGWALL 3	10-#5V210 @ 1'-0" CTS.	11-#5V210 @ 1'-0" CTS.
WINGWALL 4	10-#5V211 @ 1'-0" CTS.	11-#5V211 @ 1'-0" CTS.

GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-
SHEET 3 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
**SUBSTRUCTURE
END BENT 2
WINGWALL DETAILS**




REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1	--	--	3	--	--
2	--	--	4	--	--

SHEET NO. S-18
TOTAL SHEETS 21


DES BY: J. PATT	DATE: 11/25	DWG BY: M. SELLS	DATE: 12/25
DES CHK: G. MYERS	DATE: 12/25	CHK BY: G. MYERS	DATE: 12/25

HDR HDR Engineering, Inc. of the Carolinas
551 Fayetteville Rd., Suite 100 Raleigh, NC 27601
N.C.B.E.L.S. License Number F-0116
**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.DIF
 USER: DCARTER DATE: 12/23/2025
 PENTABLE: NDDOT STRUCTURES DEFAULT PEN.TBI
 TIME: 1:39:32 PM
 FILE: ...\\CAD\\Pion Production_Ser1\18




PLAN OF DRILLED PIERS



SECTION F-F


SECTION E-E

SECTION G-G



SECTION C-C

SECTION D-D



BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

TEMPORARY DRAINAGE AT END BENT

COLUMN HEIGHTS	
COLUMN NO.	HEIGHT
1	17'-4 ¹⁵ / ₁₆ "
2	17'-3 ¹ / ₂ "
3	17'-1 ¹¹ / ₁₆ "
4	16'-10 ⁹ / ₁₆ "

GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-

SHEET 4 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SUBSTRUCTURE
END BENT 2 DETAILS



REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1	--	--	3	--	--
2	--	--	4	--	--

SHEET NO. S-19
TOTAL SHEETS 21


DES BY: J. PATT	DATE: 10/25	DWG BY: M. SELLS	DATE: 12/25
DES CHK: K. DICKENS	DATE: 11/25	CHK BY: G. MYERS	DATE: 12/25

HDR Engineering, Inc. of the Carolinas
551 Fayetteville Rd., Suite 100 Raleigh, NC 27601
N.C.B.E.L.S. License Number F-0116


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

PENTABLE: NDDOT STRUCTURES DEFAULT PEN.tbl
TIME: 11:44:19 PM


PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.plt
USER: DCARTER DATE: 12/23/2025
FILE: ...CAD\Plan Production Set\19




SECTION A-A




CONSTRUCTION JOINT DETAIL
(WALL REINFORCEMENT NOT SHOWN FOR CLARITY)



SECTION THRU DRILLED PIER



DETAIL "B"



ALL BAR DIMENSIONS ARE OUT TO OUT

- * THE SP-201 SPIRAL REINFORCING STEEL SHALL BE W31 OR D-31 COLD DRAWN WIRE OR #5 PLAIN OR DEFORMED BAR
- * THE SP-202 THRU SP-204 SPIRAL REINFORCING STEEL SHALL BE W20 OR D-20 COLD DRAWN WIRE OR #4 PLAIN OR DEFORMED BAR

BILL OF MATERIAL

END BENT 2						
BAR NO.	SIZE	TYPE	LENGTH	WEIGHT		
B201	#9	1	27'-10"	189		
B202	#9	1	26'-4"	179		
B203	#9	1	25'-3"	172		
B204	#9	1	24'-2"	164		
B205	#9	1	23'-1"	157		
B206	#9	1	21'-7"	147		
B207	#5	STR	25'-4"	106		
B208	#5	STR	19'-2"	80		
H201	#6	STR	19'-7"	1059		
H202	#6	4	16'-10"	910		
H203	#6	4	17'-4"	937		
H204	#6	4	16'-4"	196		
H205	#6	4	15'-2"	182		
H206	#6	4	12'-4"	111		
H207	#6	4	11'-4"	102		
K201	#6	STR	2'-7"	23		
K202	#6	STR	3'-5"	31		
S201	#5	3	9'-6"	208		
U201	#6	5	10'-0"	1081		
V201	#14	2	32'-4"	2474		
V202	#14	2	35'-3"	5393		
V203	#14	2	31'-10"	2435		
V204	#5	STR	19'-9"	865		
V205	#5	STR	19'-2"	920		
V206	#5	STR	17'-1"	36		
V207	#5	STR	18'-9"	78		
V208	#5	STR	16'-7"	35		
V209	#5	STR	4'-0"	58		
V210	#5	STR	4'-7"	100		
V211	#5	STR	4'-10"	106		
TOTAL					18,534 LBS.	
SPIRAL COLUMN REINFORCING STEEL						
BAR NO.	SIZE	TYPE	LENGTH	WEIGHT		
SP-201	#	7	217'-8"	908		
SP-202	**	6	468'-10"	313		
SP-203	**	6	479'-11"	641		
SP-204	**	6	455'-5"	304		
TOTAL					2,166 LBS.	
CLASS A CONCRETE BREAKDOWN						
POUR #2 (COLUMNS & RETAINING WALL)						57.0 C.Y.
POUR #3 (CAP & UPPER WINGS)						16.1 C.Y.
TOTAL CLASS A CONCRETE						73.1 C.Y.
DRILLED PIERS						
DRILLED PIER CONCRETE						14.0 C.Y.
POUR #1 (DRILLED PIERS)						

GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-
SHEET 5 OF 5

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
SUBSTRUCTURE
END BENT 2
DETAILS AND
BILL OF MATERIAL




Gregory E. Myers

DES BY: J. PATT	DATE: 11/25	DWG BY: M. SELLS	DATE: 12/25
DES CHK: K. DICKENS	DATE: 11/25	CHK BY: G. MYERS	DATE: 12/25

HDR Engineering, Inc. of the Carolinas
551 Fayetteville Rd., Suite 100 Raleigh, NC 27601
N.C.B.E.L.S. License Number F-0116
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1	--	--	3	--
2	--	--	4	--



TOTAL SHEETS 21



ESTIMATED QUANTITIES		
BRIDGE @ 11+20.40 -L-	RIP RAP CLASS II (2'-0\"	GEOTEXTILE FOR DRAINAGE
	TONS	SQUARE YARDS
END BENT 1	315	350
END BENT 2	205	230

RIP RAP AT END BENT 1

RIP RAP AT END BENT 2



GROW NC
PROJECT NO. 100-01-00205
YANCEY COUNTY
STATION: 11+20.40 -L-

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

RIP RAP DETAILS



REVISIONS						SHEET NO. 5-21
NO.	BY:	DATE:	NO.	BY:	DATE:	
1	--	--	3	--	--	TOTAL SHEETS 21
2	--	--	4	--	--	

DES BY: A. AMBROSI	DATE: 12/25	DWG BY: D. CARTER	DATE: 12/25
DES CHK: G. MYERS	DATE: 12/25	CHK BY: G. MYERS	DATE: 12/25

HDR HDR Engineering, Inc. of the Carolinas
551 Fayetteville Rd., Suite 100 Raleigh, NC 27601
N.C.B.E.L.S. License Number F-01116

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

PENTABLE: NDDOT STRUCTURES DEFAULT PEN.tbl
TIME: 2:01:09 PM

PLOT DRIVER: NDDOT STRUCTURES DEFAULT PLOTTER.dpf
USER: DCARTER DATE: 12/23/2025
FILE: ...CAD\Plan Production Set\21

ENGINEER:
 HDR Engineering Inc. of the Carolinas
 440 S. Church St. Suite 1200
 Charlotte, NC 28202-2075
 704.338.8700
 NCBELS License Number F-0116

RESPONSIBLE FOR MAINTENANCE:
 NAME:
 PH:
 FAX:
 EMAIL:



HDR Engineering Inc.
 of the Carolinas
 440 S. Church St. Suite 1200
 Charlotte, NC 28202-2075
 704.338.8700

NCBELS License Number F-0116

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-01
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

Bid Drawings For

NORTH CAROLINA DPS

ROADWAY IMPROVEMENTS

Roadway Erosion Control Plans



Project No.
100-01-00205

35.952849, -82.389463

ISSUED FOR PERMITTING - 03-20-2026

LIMITS OF DISTURBANCE = 2.74 ACRES

RIVER BASIN: FRENCH BROAD



2024 NCDOT STANDARD SPECIFICATIONS

GRAPHIC SCALE



THESE EROSION AND SEDIMENT CONTROL PLANS
 COMPLY WITH THE REGULATIONS SET FORTH
 BY THE NCG-010000 GENERAL STORMWATER
 CONSTRUCTION PERMIT ISSUED BY THE NORTH
 CAROLINA DEPARTMENT OF ENVIRONMENTAL
 QUALITY DIVISION OF ENERGY, MINERAL AND LAND RESOURCES

REVISIONS

PLOT DRIVER: NCDOT.pdf_color_eng_100.ppt
 USER: PRECMT
 FILE: \

DATE: 3/20/2026
 TIME: 11:25:15 AM

NORTH CAROLINA STATE PORTS AUTHORITY

EROSION & SEDIMENT CONTROL LEGEND

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-02
RW SHEET NO. ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

Std. #	Description	Symbol	Std. #	Description	Symbol
1605.01	Temporary Silt Fence		1633.01	Temporary Rock Silt Check Type A	
1606.01	Special Sediment Control Fence		1633.02	Temporary Rock Silt Check Type B	
1607.01	Gravel Construction Entrance		1633.03	Temporary Rock Silt Check Type A with Excelsior Matting and Flocculant	
1622.01	Temporary Berms and Slope Drains		1634.01	Temporary Rock Sediment Dam Type A	
1630.02	Silt Basin Type B		1634.02	Temporary Rock Sediment Dam Type B	
1630.03	Temporary Silt Ditch		1635.01	Rock Pipe Inlet Sediment Trap Type A	
1630.04	Stilling Basin		1635.02	Rock Pipe Inlet Sediment Trap Type B	
1630.05	Temporary Diversion		1636.01	Excelsior Wattle Check	
1630.06	Special Stilling Basin		1636.01	Excelsior Wattle Check with Flocculant	
1630.07	Skimmer Basin		1636.01	Coir Fiber Wattle Check	
1630.08	Tiered Skimmer Basin		1636.01	Coir Fiber Wattle Check with Flocculant	
1630.09	Earthen Dam with Skimmer		1636.02	Silt Fence Excelsior Wattle Break	
	Infiltration Basin			Silt Fence Coir Fiber Wattle Break	
	Rock Inlet Sediment Trap:				
1632.01	Type A		1636.03	Excelsior Wattle Barrier	
1632.02	Type B		1636.03	Coir Fiber Wattle Barrier	
1632.03	Type C				

REVISIONS

PLOT DRIVER: NCDOT_pdf_color_eng_100up.plt
 USER: PRECMT
 FILE: \

PENTABLE: NCDOT_TSH.tbl
 DATE: 3/20/2026
 TIME: 11:25:16 AM

PLOT DRIVER: NCDOT_pdf_color_anq_100.ppt
 USER: PRECMI
 FILE: \

DATE: 3/20/2026
 TIME: 11:25:19 AM

REVISIONS

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT
 Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes		
Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQW) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d) Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e) Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION
 Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

<ul style="list-style-type: none"> Temporary grass seed covered with straw or other mulches and tackifiers Hydroseeding Rolled erosion control products with or without temporary grass seed Appropriately applied straw or other mulch Plastic sheeting 	<ul style="list-style-type: none"> Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed
---	--

- POLYACRYLAMIDES (PAMS) AND FLOCCULANTS**
- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the *NC DWR List of Approved PAMS/Flocculants*.
 - Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
 - Apply flocculants at the concentrations specified in the *NC DWR List of Approved PAMS/Flocculants* and in accordance with the manufacturer's instructions.
 - Provide ponding area for containment of treated Stormwater before discharging offsite.
 - Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

- EQUIPMENT AND VEHICLE MAINTENANCE**
- Maintain vehicles and equipment to prevent discharge of fluids.
 - Provide drip pans under any stored equipment.
 - Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
 - Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
 - Remove leaking vehicles and construction equipment from service until the problem has been corrected.
 - Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.


- LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE**
- Never bury or burn waste. Place litter and debris in approved waste containers.
 - Provide a sufficient number and size of waste containers (e.g. dumpster, trash receptacle) on site to contain construction and domestic wastes.
 - Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
 - Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
 - Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
 - Anchor all lightweight items in waste containers during times of high winds.
 - Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
 - Dispose waste off-site at an approved disposal facility.
 - On business days, clean up and dispose of waste in designated waste containers.

- PAINT AND OTHER LIQUID WASTE**
- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
 - Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
 - Contain liquid wastes in a controlled area.
 - Containment must be labeled, sized and placed appropriately for the needs of site.
 - Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

- PORTABLE TOILETS**
- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
 - Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
 - Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

- EARTHEN STOCKPILE MANAGEMENT**
- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
 - Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
 - Provide stable stone access point when feasible.
 - Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.

- HAZARDOUS AND TOXIC WASTE**
- Create designated hazardous waste collection areas on-site.
 - Place hazardous waste containers under cover or in secondary containment.
 - Do not store hazardous chemicals, drums or bagged materials directly on the ground.



- CONCRETE WASHOUTS**
- Do not discharge concrete or cement slurry from the site.
 - Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
 - Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
 - Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
 - Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
 - Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
 - Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
 - Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
 - Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
 - At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

- HERBICIDES, PESTICIDES AND RODENTICIDES**
- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
 - Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
 - Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
 - Do not stockpile these materials onsite.

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-02A
RAW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

PLOT DRIVER: NCG01.pdf_color_eng_100.ppt
 USER: PRECMI
 DATE: 3/20/2026
 TIME: 11:25:20 AM
 FILE: \

REVISIONS

**PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING**

SECTION A: SELF-INSPECTION
Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

**PART II, SECTION G, ITEM (4)
DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT**

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items,
- The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit,
- Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,
- Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,
- Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
- Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

**PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING**

SECTION B: RECORDKEEPING
1. E&SC Plan Documentation
The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

Item to Document	Documentation Requirements
(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.	Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC plan.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC measures.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation to be Kept on Site
In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- This General Permit as well as the Certificate of Coverage, after it is received.
- Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years
All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]


**PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING**

SECTION C: REPORTING
1. Occurrences that Must be Reported
Permittees shall report the following occurrences:

- Visible sediment deposition in a stream or wetland.
- Oil spills if:
 - They are 25 gallons or more,
 - They are less than 25 gallons but cannot be cleaned up within 24 hours,
 - They cause sheen on surface waters (regardless of volume), or
 - They are within 100 feet of surface waters (regardless of volume).
- Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- Anticipated bypasses and unanticipated bypasses.
- Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements
After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.






Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment deposition in a stream or wetland	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions.
(b) Oil spills and release of hazardous substances per Item l(b)-(c) above	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(c) Anticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass.
(d) Unanticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the quality and effect of the bypass.
(e) Noncompliance with the conditions of this permit that may endanger health or the environment [40 CFR 122.41(l)(7)]	<ul style="list-style-type: none"> Within 24 hours, an oral or electronic notification. Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(l)(6). Division staff may waive the requirement for a written report on a case-by-case basis.

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-02B
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
 HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

REVISIONS


PLOT DRIVER: NCDOT_pdf_color_eng_100.plt
 USER: PRECMI
 DATE: 3/20/2026
 TIME: 11:25:22 AM
 FILE: \




PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-02C
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

PLOT DRIVER: NCDOT_pdf_color_eng_100.plt
 USER: PRECMI
 FILE: \


REVISIONS




1633.01
 ROADWAY STANDARD DRAWING FOR
 TEMPORARY ROCK SILT CHECK TYPE A
 STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.




1606.01
 ROADWAY STANDARD DRAWING FOR
 SPECIAL SEDIMENT CONTROL FENCE
 STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.




1622.01
 ROADWAY STANDARD DRAWING FOR
 GUIDE FOR TEMPORARY BERMS AND SLOPE DRAIN
 STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.



1632.02
 ROADWAY STANDARD DRAWING FOR
 ROCK INLET SEDIMENT TRAP TYPE B
 STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.



1630.08
 ROADWAY STANDARD DRAWING FOR
 SPECIAL STILLING BASIN
 STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.




1631.01
 ROADWAY STANDARD DRAWING FOR
 MATTING INSTALLATION
 STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-02D
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.B.E.L.S. License Number: F-0116	

NORTH CAROLINA
STATE PORTS AUTHORITY

SOIL STABILIZATION TIMEFRAMES

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-03A
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
 HDR Engineering, Inc. of the Carolinas 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601 N.C.E.L.S. License Number: F-0116	


REVISIONS

PLOT DRIVER: NCDOT_pdf_color_eng_100.plt
PENTABLE: NCDOT_TSh.tbl
USER: PRECMI
DATE: 3/20/2026
TIME: 11:25:28 AM
FILE: \

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 TO 4:1	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH WITH SLOPES STEEPER THAN 4:1. 7 DAYS FOR PERIMETER DIKES, SWALES, DITCHES PERIMETER SLOPES, AND HQW ZONES
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	7 DAYS FOR PERIMETER DIKES, SWALES, DITCHES PERIMETER SLOPES, AND HQW ZONES

PROJECT REFERENCE NO.	SHEET NO.
100-01-00205	EC-04/CONST.04
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

HDR HDR Engineering, Inc. of the Carolinas
 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
 N.C.B.E.L.S. License Number: F-0116



ENVIRONMENTALLY SENSITIVE AREA
 SEE PROJECT SPECIAL PROVISIONS

NOTE:
 PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B
 AND TEMPORARY ROCK SILT CHECKS TYPE - A AT
 DRAINAGE OUTLETS.

CLEARING AND GRUBBING
 EROSION CONTROL FOR
 CONSTRUCTION SHEET 4

REVISIONS

PLOT DRIVER: NCDOT.pdf_color_eng_100.ppt
 USER: PREGMI
 FILE: \

PENTABLE: NCDOT_EC_C&G.tbl
 DATE: 3/20/2026
 TIME: 11:25:33 AM

CONTRACTOR TO EXCAVATE NO STEEPER THAN
 2H:1V SLOPE AT EACH OPEN END PIPE TO
 MAINTAIN AT LEAST 1' OF COVER BETWEEN
 THE ROAD SURFACE AND TOP OF PIPE.


MATCHLINE -Y6B- STA. 12+00.00
 SEE SHEET 3A

FOR -L- PROFILE, SEE SHEET 7
 FOR -Y6A- PROFILE, SEE SHEET 7
 FOR -Y6B- PROFILE, SEE SHEET 7

NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-05/CONST.05
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

HDR HDR Engineering, Inc. of the Carolinas
555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116



MATCHLINE -Y6B- STA. 12+00.00, SEE SHEET 2

MATCHLINE -Y1A- STA. 14+35.00, SEE SHEET 4

PLOT DRIVER: NCDOT.pdf_color_eng_100.pit
 USER: PRECMI
 FILE: \

REVISIONS


PENTABLE: NCDOT_EC_C&G.tbl
 DATE: 3/20/2026
 TIME: 11:25:35 AM

FOR -Y1A- PROFILE, SEE SHEET 8
FOR -Y6B- PROFILE, SEE SHEET 7

PLOT DRIVER: NCDOT.pdf_color_eng_100.plt
 USER: PRECMI
 FILE: \

PENTABLE: NCDOT_EC_C&G.tbl
 DATE: 3/20/2026
 TIME: 11:25:36 AM


REVISIONS



NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-06/CONST.06
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

HDR HDR Engineering, Inc. of the Carolinas
 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
 N.C.B.E.L.S. License Number: F-0116




FOR -Y1A- PROFILE, SEE SHEET 8

REVISIONS

PLOT DRIVER: NCDOT.ec_color_eng_100.plt
USER: PRECMI
FILE: \

PENTABLE: NCDOT.ec_color_eng_100.plt
DATE: 3/20/2026
TIME: 11:25:40 AM




PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-08/CONST.08
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

HDR HDR Engineering, Inc. of the Carolinas
555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116

FOR -Y1- PROFILE, SEE SHEET 8

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-09/CONST.04
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

HDR HDR Engineering, Inc. of the Carolinas
555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116



REVISIONS

PLOT DRIVER: NCDOT.pdf_color_eng_100.ppt
 USER: PREGMI
 FILE: \
 PENTABLE: NCDOT_EC_FINAL.tbl
 DATE: 3/20/2026
 TIME: 11:25:43 AM


CONTRACTOR TO EXCAVATE NO STEEPER THAN 2H:1V SLOPE AT EACH OPEN END PIPE TO MAINTAIN AT LEAST 1' OF COVER BETWEEN THE ROAD SURFACE AND TOP OF PIPE.

FOR -L- PROFILE, SEE SHEET 7
 FOR -Y6A- PROFILE, SEE SHEET 7
 FOR -Y6B- PROFILE, SEE SHEET 7

NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-10/CONST.05
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

HDR HDR Engineering, Inc. of the Carolinas
555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116



REVISIONS

PLOT DRIVER: NCDOT.pdf_color_eng_100.pit
USER: PRECMI
FILE: \


PENTABLE: NCDOT.ec.FINAL.tbl
DATE: 3/20/2026
TIME: 11:25:44 AM

FOR -Y1A- PROFILE, SEE SHEET 8
FOR -Y6B- PROFILE, SEE SHEET 7

PLOT DRIVER: NCDOT.pdf_color_eng_100.pit
 USER: PRECMI
 FILE: \

PENTABLE: NCDOT.ec.FINAL.tbl
 DATE: 3/20/2026
 TIME: 11:25:46 AM

REVISIONS




NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-11CONST.06
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

HDR HDR Engineering, Inc. of the Carolinas
 555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
 N.C.B.E.L.S. License Number: F-0116

MATCHLINE -Y1A- STA. 14 + 35.00, SEE SHEET 3

MATCHLINE -Y1A- STA. 19 + 85.00, SEE SHEET 5




FROM STA. 16 + 00 TO STA. 18 + 00 -Y1A- RT

FOR -Y1A- PROFILE, SEE SHEET 8

NOTE: THIS SHEET DEPICTS THE POST-STORM AERIAL

PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-12/CONST.07
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER


HDR HDR Engineering, Inc. of the Carolinas
555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116



REVISIONS

PLOT DRIVER: NCDOT.pdf_color_eng_100.pit
 USER: PRECMI
 FILE: \\\n
 PENTABLE: NCDOT_EC_FINAL.tbl
 DATE: 3/20/2026
 TIME: 11:25:47 AM

FOR -Y1- PROFILE, SEE SHEET 8
 FOR -YIA- PROFILE, SEE SHEET 8
 FOR -DRI- PROFILE, SEE SHEET 8



PROJECT REFERENCE NO. 100-01-00205	SHEET NO. EC-13CONST.08
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

HDR HDR Engineering, Inc. of the Carolinas
555 Fayetteville St. Suite 900 Raleigh, N.C. 27601
N.C.B.E.L.S. License Number: F-0116

REVISIONS

PLOT DRIVER: NCDOT.pdf_color_eng_100.pit
USER: PRCM1
FILE: \

PENTABLE: NCDOT_EC_FINAL.tbl
TIME: 11:25:48 AM
DATE: 3/20/2026

END GRADE 100-01-00205
-Y1- STA. 19 + 00.00

END PROJECT 100-01-00205
END CONSTRUCTION
100-01-00205 -Y1- STA. 19 + 10.00

CONTRACTOR TO EXCAVATE NO STEEPER THAN 2H:1V SLOPE AT EACH OPEN END PIPE TO MAINTAIN AT LEAST 1' OF COVER BETWEEN THE ROAD SURFACE AND TOP OF PIPE.

FOR -Y1- PROFILE, SEE SHEET 8


STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	100-01-0205	RF-1	
STATE PROJ. NO.	F. A. PROJ. NO.	DESCRIPTION	

PLANTING DETAILS


SEEDLING / LINER BAREROOT PLANTING DETAIL

HEALING IN


1. Locate a healing-in site in a shady, well protected area.
2. Excavate a flat bottom trench 12 inches deep and provide drainage.




3. Backfill the trench with 2 inches well rotted sawdust. Place a 2 inch layer of well rotted sawdust at a sloping angle at one end of the trench.



4. Place a single layer of plants against the sloping end so that the root collar is at ground level.




5. Place a 2 inch layer of well rotted sawdust over the roots maintaining a sloping angle.



6. Repeat layers of plants and sawdust as necessary and water thoroughly.


DIBBLE PLANTING METHOD USING THE KBC PLANTING BAR



1. Insert planting bar as shown and pull handle toward planter.

2. Remove planting bar and place seedling at correct depth.

3. Insert planting bar 2 inches toward planter from seedling.



4. Pull handle of bar toward planter, firming soil at bottom.

5. Push handle forward firming soil at top.

6. Leave compaction hole open. Water thoroughly.

PLANTING NOTES:

PLANTING BAG
During planting, seedlings shall be kept in a moist canvas bag or similar container to prevent the root systems from drying.



KBC PLANTING BAR
Planting bar shall have a blade with a triangular cross section, and shall be 12 inches long, 4 inches wide and 1 inch thick at center.



ROOT PRUNING
All seedlings shall be root pruned, if necessary, so that no roots extend more than 10 inches below the root collar.

REFORESTATION

- TREE REFORESTATION SHALL BE PLANTED 6 FT. TO 10 FT. ON CENTER, RANDOM SPACING, AVERAGING 8 FT. ON CENTER, APPROXIMATELY 680 PLANTS PER ACRE.

REFORESTATION

MIXTURE, TYPE, SIZE, AND FURNISH SHALL CONFORM TO THE FOLLOWING:

40% LIRIODENDRON TULIPIFERA	TULIP POPLAR	12 in - 18 in BR
30% PLATANUS OCCIDENTALIS	AMERICAN SYCAMORE	12 in - 18 in BR
30% BETULA NIGRA	RIVER BIRCH	12 in - 18 in BR

REFORESTATION DETAIL SHEET

N.C.D.O.T. - ROADSIDE ENVIRONMENTAL UNIT