
6

See Sheet 1A For Index of Sheets







STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

MADISON COUNTY

LOCATION: SCENIC OVERLOOK OFF I-26 WESTBOUND BETWEEN US-23 ALT & US-19

TYPE OF WORK: GRADING, STORM DRAINAGE, FILTRATION BASIN, EROSION CONTROL, AND SEEDING & MULCHING









DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

GRAPHIC SCALES

SCALE VARIES SEE PLANS



LETTING DATE: MAY 3, 2017



TGS ENGINEERS 706 HILLSBOROUGH ST RALEGH, NC 27603 PH (919) 773–8887 CORP. LICENSE NO.: C–0275

RANDY HENEGAR, PE PROJECT ENGINEER

Prepared by

PROJECT DESIGN ENGINEER

HYDRAULICS ENGINEER

SIGNATURE:

NCDOT CONTACT

BRIAN LIPSCOMB, P.E. HIGHWAY STORMWATER PROGRAM STATE OF NORTH CAROLINA HYDRAULICS UNIT STORMWATER GROUP

DIVISION OF HIGHWAYS



PROJECT ENGINEER

GENERAL NOTES INDEX OF SHEETS SHEET NUMBER SHEET DESCRIPTION **GRADING:** TITLE SHEET THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED OR FUTURE SURFACING AT GRADE POINTS SHOWN ON THE PLANS. GRADE LINES INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN. **CONVENTIONAL SYMBOLS CLEARING:** SURVEY CONTROL CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY 2D-1 BMP DETAILS 1 METHOD II. BMP DETAILS 2 2D-2 TRAFFIC CONTROL: DETAIL OF OUTLET CONTROL STRUCTURE 2D-3 USE APPROPRIATE STANDARDS PER DIVISION 11 AS REQUIRED TO COMPLETE WORK. COORDINATE TRAFFIC CONTROL WITH THE DIVISION. 2D-4 TRASH RACK DETAILS 3B/3D EARTHWORK, DRAINAGE & EROSION CONTROL SUMMARIES PLAN SHEET

2012 ROADWAY ENGLISH STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" HIGHWAY DESIGN BRANCH - N. C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N. C., DATED JANUARY, 2012 ARE APPLICABLE TO THIS PROJECTAND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD.NO. <u>TITLE</u>

METHOD OF CLEARING - METHOD II

DIVISION 3 - PIPE CULVERTS 300.01 METHOD OF PIPE INSTALLATION

DIVISION 2 - EARTHWORK

DIVISION 8 - INCIDENTALS 840.31 CONCRETE JUNCTION BOX - 12" THRU 66" PIPE

840.54 MANHOLE FRAME AND COVER DRAINAGE STRUCTURE STEPS 840.66

DIVISION 11 - WORK ZONE TRAFFIC CONTROL

WORK ZONE ADVANCE WARNING SIGNS FOR FACILITIES <= 55 MPH 1101.02 TEMPORARY LANE CLOSURES

DIVISION 16 - EROSION CONTROL AND ROADSIDE DEVELOPMENT TEMPORARY SILT FENCE 1605.01 1607.01 **GRAVEL CONSTRUCTION ENTRANCE**

1632.03 ROCK INLET SEDIMENT TRAP TYPE C 1633.01 TEMPORARY ROCK SILT CHECK TYPE A

CONSTRUCTION SEQUENCE NOTES

EC - 1

TC - 1

PROJECT REQUIRES A PRE-CONSTRUCTION CONFERENCE PRIOR TO INITIATING ANY EARTH DISTURBANCE ACTIVITIES.

- 1. ESTABLISH SIGNAGE AT OVERLOOK SITE TO INFORM PUBLIC OF PARTIAL LOT CLOSURE A MINIMUM OF 2 WEEKS PRIOR TO START OF CONSTRUCTION. INDICATE ANTICIPATED DATES OF PARTIAL CLOSURE ON THE SIGNAGE.
- 2. PROVIDE SIGNAGE AT OVERLOOK SITE ENTRANCE AND PARKING AREA AND MAINTAIN SOFT BARRIERS, SUCH AS CONES OR DRUMS. TO CLOSE AND RESTRICT PUBLIC ACCESS TO THE CLOSED PORTION OF THE GROUNDS AND PARKING LOT.
- 3. INSTALL TEMPORARY EROSION CONTROL DEVICES AS SHOWN ON PLANS.

EROSION CONTROL PLAN

TRAFFIC CONTROL PLAN

- 4. CONSTRUCT FILTRATION BASINS AND OTHER IMPROVEMENTS.
- 5. FOLLOW SEEDING/ MULCHING GUIDELINES ON THE PLANS TO STABILIZE ALL REMAINING DISTURBED SURFACES.
- 6. INSPECT ALL INLETS, PIPES, AND OUTLETS FOR SEDIMENT AND REMOVE SEDIMENT AS REQUIRED.
- 7. REMOVE ALL REMAINING TEMPORARY EROSION CONTROL MEASURES AFTER PERMANENT PERENNIAL VEGETATION IS ESTABLISHED.

EROSION CONTROL NOTES

- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST VERSION OF NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS.
- 2. CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL MEASURES DURING THE LIFE OF THE PROJECT UNLESS OTHERWISE INDICATED ON THE PLANS OR DIRECTED BY NCDOT INSPECTOR.
- 3. CONTRACTOR SHALL CONSTRUCT DIVERSION DITCHES AS NECESSARY TO ENSURE THAT ALL SEDIMENT IS DIRECTED INTO EROSION CONTROL MEASURES.
- 4. CUT AND FILL SLOPES SHALL BE STABILIZED WITHIN 14 DAYS OF ANY PHASE OF GRADING. SLOPES 3:1 OR STEEPER SHALL BE STABILIZED WITHIN 7 DAYS.
- 5. PROVIDE TEMPORARY MEASURES AS NECESSARY TO PREVENT SEDIMENT FROM MIGRATING INTO FILTER MEDIA OR SODDED AREAS.
- 6. ALL STREETS ADJACENT TO THIS PROJECT SHALL REMAIN CLEAN AT ALL TIMES OR A WASH STATION MAY BE REQUIRED.
- 7. IF USED, SILT FENCE SHALL BE MAINTAINED ON THE SITE UNTIL ALL SITE WORK IS COMPLETED AND THE FINAL SITE INSPECTION IS SCHEDULED.
- 8. RESEED OF PERMANENT GROUND COVER WILL BE ESTABLISHED IN 15 WORKING DAYS OR 30 CALENDAR DAYS, WHICH EVER IS SHORTER.
- 9. EROSION CONTROL MATTING SHALL BE STRAW MATTING. USE STD. DWG. 1631.01 FOR MATTING INSTALLATION.
- 10. PROVIDE GRAVEL CONSTRUCTION ENTRANCE PER 1607.01 AS NEEDED TO PREVENT TRACKING OFFSITE.

SURVEY

LOCATIONS AND ELEVATIONS SHOULD BE FIELD VERIFIED. CONSULT WITH ENGINEER IF SIGNIFICANT DEVIATIONS FROM THE PLAN ARE REQUIRED.

UTILITIES

THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATIONS AS TO THE LOCATION OF UTILITIES. EXISTING UTILITIES AND STRUCTURES (UNDERGROUND, SURFACE, OR OVERHEAD) ARE INDICATED ONLY TO THE EXTENT THAT SUCH INFORMATION WAS KNOWN, MADE AVAILABLE TO, OR DISCOVERED BY THE ENGINEER IN PREPARING THE DRAWINGS. THE LOCATIONS, CONFIGURATIONS, AND ELEVATIONS OF SUBSURFACE FACILITIES AND UTILITIES ARE APPROXIMATE, AND NOT ALL UTILITIES AND FACILITIES MAY BE INDICATED.

EARTHWORK

1. ALL EARTHWORK FOR BASIN CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST VERSION OF NCDOT STANDARD SPECIFICATIONS.

SEEDBED PREPERATION

- 1. PREPARE AND SEED ONLY DISTURBED AREAS. DO NOT SPREAD SEED ON AREAS TO RECEIVE SOD.
- 2. CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS IF AVAILABLE.
- 3. RIP THE ENTIRE AREA TO 6 INCHES DEPTH.
- 4. REMOVE ALL LOOSE ROCK, ROOTS AND OTHER OBSTRUCTIONS LEAVING SURFACES REASONABLY SMOOTH AND UNIFORM.
- 5. APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE UNIFORMLY AND MIX WITH SOIL (SEE BELOW*).
- 6. CONTINUE TILLAGE UNTIL A WELL-PULVERIZED, FIRM, REASONABLY UNIFORM SEEDBED IS PREPARED 4 TO 6 INCHES DEEP.
- 7. SEED A FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING.
- 8. MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH.
- 9. INSPECT ALL SEEDED AREAS AND MAKE ALL NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 70% DAMAGED, REESTABLISH FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES.
- 10. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED.

*APPLY: AGRICULTURAL LIMESTONE - 2 TONS/ACRE (34 TONS/ACRE ON CLAY SOILS) FERTILIZER - 1,000 LBS/ACRE - 10-10-10 SUPERPHOSPHATE - 500 LBS/ACRE - 20% MULCH - 2 TONS/ACRE - SMALL GRAIN STRAW ANCHOR - ASPHALT EMULSION @ 300 GAL. ACRE

MAINTENCE PLAN

- 1. ALL EROSION AND SEDIMENTATION CONTROL PRACTICES WILL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE A WEEK. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS DESIGNED.
- 2. SEDIMENT WILL BE REMOVED FROM BEHIND THE SILT FENCE WHEN IT BECOMES ABOUT 6-INCHES DEEP AT THE FENCE. THE SILT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER.
- 3. INLET PROTECTION DEVICES SHALL BE INSPECTED AFTER EVERY RAINFALL EVENT. DAMAGED SILT FENCE SHALL BE REPLACED AND GRAVEL SHALL BE CLEANED OR REPLACED WHEN INLET NO LONGER DRAINS PROPERLY.

PROJECT **ENGINEER** CESSIO,

SHEET NO.

/A

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PROJECT REFERENCE NO.

R-4436MI

randall heneger

3/1/2017


CONVENTIONAL PLAN SHEET SYMBOLS

BOUNDARIES AND PROPERTY:		RAILROADS: Note: Not to S	Scale *S
State Line		Standard Gauge —	
County Line		RR Signal Milepost	COX THANSI ON ALION
Township Line		Switch —	
City Line		RR Abandoned ————	SWII CH
Reservation Line		RR Dismantled —————	
Property Line		kk Dismantied	
Existing Iron Pin	EIP		ONTROI
Computed Property Corner	×	RIGHT OF WAY & PROJECT CO	ONIROL:
Property Monument	 ECM	Secondary Horiz and Vert Control Point ——	—
Parcel/Sequence Number	<u></u>	Primary Horiz Control Point	
Existing Fence Line	×××_	Primary Horiz and Vert Control Point	•
Proposed Woven Wire Fence		Exist Permanent Easment Pin and Cap	(*)
Proposed Chain Link Fence		New Permanent Easement Pin and Cap ——	\Diamond
Proposed Barbed Wire Fence		Vertical Benchmark ————————————————————————————————————	
Existing Wetland Boundary		Existing Right of Way Marker	\triangle
Proposed Wetland Boundary		Existing Right of Way Line	
Existing Endangered Animal Boundary ——		New Right of Way Line	
Existing Endangered Plant Boundary		New Right of Way Line with Pin and Cap—	
	нрв		
Known Contamination Area: Soil		New Right of Way Line with Concrete or Granite R/W Marker	
Potential Contamination Area: Soil		New Control of Access Line with	
Known Contamination Area: Water		Concrete C/A Marker	
		Existing Control of Access	$\left(\begin{smallmatrix} \bar{\mathbb{C}} \\ \underline{\mathbb{A}} \end{smallmatrix} \right)$
Potential Contamination Area: Water		New Control of Access	
Contaminated Site: Known or Potential		Existing Easement Line ————————————————————————————————————	——Е——
BUILDINGS AND OTHER CULT	URE:	New Temporary Construction Easement –	E
Gas Pump Vent or U/G Tank Cap	<u> </u>	New Temporary Drainage Easement ——	—— TDE ——
Sign —	<u> </u>	New Permanent Drainage Easement ——	PDE
Well —	O	New Permanent Drainage / Utility Easement	——DUE——
Small Mine	─	New Permanent Utility Easement ———	PUE
Foundation —		New Temporary Utility Easement	TUE
Area Outline		New Aerial Utility Easement	———AUE———
Cemetery			
Building —		ROADS AND RELATED FEATUR	EES:
School		Existing Edge of Pavement	
Church	— 此	Existing Curb	
Dam		Proposed Slope Stakes Cut	
HYDROLOGY:		Proposed Slope Stakes Fill —————	
Stream or Body of Water —		Proposed Curb Ramp	
Hydro, Pool or Reservoir —	_ []	Existing Metal Guardrail	
Jurisdictional Stream		Proposed Guardrail	
Buffer Zone 1		Existing Cable Guiderail	
Buffer Zone 2	BZ 2	Proposed Cable Guiderail	
Flow Arrow			
Disappearing Stream —	>	Equality Symbol	
Spring —	-0	Pavement Removal	
Wetland	-	VEGETATION:	2
Proposed Lateral, Tail, Head Ditch		Single Tree	-
False Sump	← FLOW	Single Shrub	-
-	~		

Hedge ————	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
Woods Line	(;,(;,(;,(;,(;,(;,(;,(;
Orchard ————	සි සි සි සි
Vineyard ————————————————————————————————————	Vineyard
EXISTING STRUCTURES:	
MAJOR:	
Bridge, Tunnel or Box Culvert — [CONC
Bridge Wing Wall, Head Wall and End Wall –) CONC WW [
MINOR:	
Head and End Wall	CONC HW
Pipe Culvert	
Footbridge	
Drainage Box: Catch Basin, DI or JB	СВ
Paved Ditch Gutter	
Storm Sewer Manhole —	S
Storm Sewer	s
UTILITIES:	
POWER:	
Existing Power Pole ————	•
Proposed Power Pole —	6
Existing Joint Use Pole —	
Proposed Joint Use Pole	-
Power Manhole ————	P
Power Line Tower —	\boxtimes
Power Transformer ———————————————————————————————————	otin
U/G Power Cable Hand Hole	
H-Frame Pole	•—•
U/G Power Line LOS B (S.U.E.*)	P
U/G Power Line LOS C (S.U.E.*)	——————————————————————————————————————
U/G Power Line LOS D (S.U.E.*)	P
TELEPHONE:	
Existing Telephone Pole ————	-
Proposed Telephone Pole ————	-0-
Telephone Manhole ————	\bigcirc
Telephone Pedestal ————	
Telephone Cell Tower ————	,
U/G Telephone Cable Hand Hole ———	H _H
U/G Telephone Cable LOS B (S.U.E.*)	T
U/G Telephone Cable LOS C (S.U.E.*)	
U/G Telephone Cable LOS D (S.U.E.*)	
U/G Telephone Conduit LOS B (S.U.E.*) —	
U/G Telephone Conduit LOS C (S.U.E.*)	
U/G Telephone Conduit LOS D (S.U.E.*)——	
U/G Fiber Optics Cable LOS B (S.U.E.*)	
•	—— — т ғо— —

U/G Fiber Optics Cable LOS D (S.U.E.*)—— T FO ——


WATER:	
Water Manhole	
Water Meter	
Water Valve	
Water Hydrant	
U/G Water Line LOS B (S.U.E*)	
U/G Water Line LOS C (S.U.E*)	
U/G Water Line LOS D (S.U.E*)	
Above Ground Water Line	
TV:	
TV Pedestal	
TV Tower	
U/G TV Cable Hand Hole	
U/G TV Cable LOS B (S.U.E.*)	
U/G TV Cable LOS C (S.U.E.*)	
U/G TV Cable LOS D (S.U.E.*)	
U/G Fiber Optic Cable LOS B (S.U.E.*)	
U/G Fiber Optic Cable LOS C (S.U.E.*)	
U/G Fiber Optic Cable LOS D (S.U.E.*)	- TV F0
GAS:	
Gas Valve	- ♦
Gas Meter —	→
U/G Gas Line LOS B (S.U.E.*)	
U/G Gas Line LOS C (S.U.E.*)	
U/G Gas Line LOS D (S.U.E.*)	
Above Ground Gas Line	A/G Gas
SANITARY SEWER:	
Sanitary Sewer Manhole	-
Sanitary Sewer Cleanout —	- -
U/G Sanitary Sewer Line —	ss
Above Ground Sanitary Sewer —	A/G Sanitary Sewer
SS Forced Main Line LOS B (S.U.E.*)	
SS Forced Main Line LOS C (S.U.E.*)	
SS Forced Main Line LOS D (S.U.E.*)	
MISCELLANEOUS:	
Utility Pole	•
Utility Pole with Base ————————————————————————————————————	
Utility Located Object ————————————————————————————————————	· •
Utility Traffic Signal Box ———————————————————————————————————	- <u>S</u>
Utility Unknown U/G Line LOS B (S.U.E.*)	
U/G Tank; Water, Gas, Oil ———————————————————————————————————	-
Underground Storage Tank, Approx. Loc. ——	UST
A/G Tank; Water, Gas, Oil ———————————————————————————————————	-
Geoenvironmental Boring ————————————————————————————————————	
U/G Test Hole LOS A (S.U.E.*)	
Abandoned According to Utility Records ——	AATUR
End of Information —	E.O.I.




DocuSign Envelope ID: 43E9E258-A6F4-4F62-A36A-1708EDCBB86C

BMP DETAILS 1

PROJECT REFERENCE NO. SHEET NO. R-4436MI 2D-I



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



TYPICAL SECTION - FILTER BASIN MEDIA


N.T.S.

OTE:

- 1. STONE TO BE STD. SIZE #57 (DIVISION 10 SECTION 1005), WASHED.
- 2. PLACE FESCUE SOD ON BASIN BOTTOMS, BERMS, AND SIDE SLOPES.
- 3. SEE SHEET 4 FOR UNDERDRAIN CONFIGURATION.
- 4. FILTRATION BASIN MEDIA SHALL CONSIST OF THE FOLLOWING BLEND:

 RECYCLED EXPANDED SLATE FINES 80%
 APPROVED COMPOST ORGANIC COMPONENT 20%


SEE SPECIAL PROVISIONS FOR ENGINEERED SOIL MEDIA REQUIREMENTS.



NOTES:

- ONLY UNDERDRAIN PIPE (LOCATED BENEATH ENGINEERED SOIL MEDIA) SHOULD BE PERFORATED.
- 2. SEE "TYPICAL SECTION FILTER BASIN MEDIA" (THIS SHEET) FOR PIPE DEPTH.

UNDERDRAIN DETAIL N.T.S.



NOTES:

- 1. LINING FABRIC SHOULD BE FOLDED BACK TO OVERLAP DIVIDING FABRIC AND SECURED WITH LANDSCAPE STAPLES TO ENSURE SEALING THE STONE FROM SOIL.
- 2. FABRIC SHOULD BE LAYED IN A WAY TO PREVENT WATER FROM FLOWING BETWEEN OVERLAPPED PIECES. (SEE BLOWUP)
- 3. FABRIC SHOULD BE OVERLAPPED A MINIMUM OF 12 INCHES AND SECURED WITH STAPLES.
- 4. NO OVERLAPPING SHOULD OCCUR UNDER DRAIN PIPES.


FABRIC INSTALLATION DETAIL

N.T.S

Userikgrau

2/22/2017

BMP DETAILS 2



NOTES:

- PROVIDE WATER TIGHT CONNECTIONS USING WATERSTOP OR COMPRESSION GASKET APPROVED BY ENGINEER ON ALL OUTLET STRUCTURE PENETRATIONS.
- 2. INSTALL STEPS IN ACCORDANCE WITH STD. 840.66
- 3. FOR UNDERDRAIN, USE SOLID (NON-PERFORATED) PIPE OUTSIDE OF FILTER.
- 4. SEE ENGINEERED SOIL MEDIA DETAIL SHEET 2–D1.
- 5. SEE DETAIL THIS SHEET FOR UNDERDRAIN UPTURNED ELBOW / OVERFLOW.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SHEET NO. 2D-2

PROJECT ENGINEER

PROJECT REFERENCE NO.

R-4436MI

randall henegar

3/1/2017


FILTRATION BASIN OUTLET STRUCTURE DETAIL

OUTLET PIPE — INV. EL.

N.T.S.

BASIN REF.	TOP BOX EL.	TOP BERM EL.	TOP BERM WIDTH	BOTTOM EL.	BOTTOM SOIL MEDIA EL.	SOIL MEDIA THICKNESS	BOTTOM STONE EL.	UNDERDRAIN INVERT	BOX / OUTLET PIPE INVERT	UNDERDRAIN OVERFLOW EL.
1	2632.0	2633.5	10.0′	2630.0	2627.0	36″	2626.0	2626.0	2624.0	2628.5

─ WATERTIGHT GASKET



FILTRATION BASIN FOREBAY


N.T.S.

NOTES:

- 1. DO NOT PLACE ENGINEERED SOIL MEDIA UNDERNEATH
- RIPRAP.


 2. ELEVATIONS INDICATE TOP OF RIPRAP.

BASIN REF.	TOP TRANSITION BERM	BERM LENGTH	BOTTOM EL.	BASE LENGTH	LINING
1	2631.0	5.00′	2629.0	18.5′	CLASS B RIPRAP



UNDERDRAIN UPTURNED ELBOW / OVERFLOW

N.T.S.



MININ	IUM [DIMENS	SIONS	S FOR	OUTLE	CONTROL	STRUCTURE
BASIN	PIPE D	OUTLET PIPE H INVERT		TOP OF BOX ELEV.	UNDER DRAIN INVERT		
1	18"	2624.0	8'-0"	2632.0'	2626.0'		

TABLE "A"

PIPE	"A"	BARS-X		"A" BARS-X BARS-Y		RS-Y	"F"	TOTAL CONCRETE QUANTITIES
D		QTY.	LENGTH	QTY.	LENGTH			
18"	4'-0"	6	5'-1"	6	5'-1"	5'-4"	4.4 CU.YDS.	

SEE NOTE **DOWEL DETAIL** 'B'

-#4 BAR 6"

DETAIL 'C'

TRANSITION BETWEEN

24"

(MIN.

9" (MIN.)

PERFORATED AND

SOLID HDPE

WATERTIGHT-

GASKETS

GENERAL NOTES:

- * CHANGES IN ELEVATIONS MUST BE APPROVED BY THE ENGINEER.
- * CLASS 'B' CONCRETE TO BE USED THROUGHOUT. PRECAST CONCRETE STRUCTURES TO BE SUBMITTED FOR APPROVAL. USE STD 840.45.
- * OPTIONAL CONSTRUCTION MONOLITHIC POUR, 2 INCH KEYWAY, OR #4 BAR DOWELS AT 12 INCH CENTERS, AS DIRECTED BY THE ENGINEER.
- * FORMS ARE TO BE USED FOR THE CONSTRUCTION OF THE BOTTOM SLAB.
- * IF REINFORCED CONCRETE PIPE IS SET IN BASE SLAB OF BOX, ADD TO BASE AS SHOWN ON STANDARD 840.00.
- * ALL DRAWDOWN STRUCTURES OVER 3 FEET IN DEPTH TO BE PROVIDED WITH STEPS 12 INCH ON CENTERS. STEPS SHALL BE INSTALLED IN ACCORDANCE WITH STANDARD 840.66.
- * PROVIDE WATER TIGHT CONNECTIONS USING WATERSTOP OR COMPRESSION GASKET APPROVED BY ENGINEER ON ALL OUTLET STRUCTURE PENETRATIONS.

11/2" #4 BARS "Y" **EQUALLY SPACED** -#3-"X" BARS **DOWEL BOTTOM SLAB**

DETAIL OF OUTLET CONTROL STRUCTURE

FASTEN WIRE MESH SCREEN

TO TOP PIPE W/ HOSE CLAMP

OR SIMILAR

HDPE TEE WITH

THREADED END CAP (SEE SHEET 2D-2)

(SEE SHEET 2D-2

FOR ELEVATION)

THIS DETAIL HAS BEEN MODIFIED FROM NCDOT PROJECT SERVICES UNIT-STANDARDS AND SPECIAL DESIGN 'DETAIL OF OUTLET CONTROL STRUCTURE' PROVIDED BY NCDOT HYDRAULICS UNIT, HSP.

project reference no.

R-4436MI

DocuSigned by:

randall benegar

B5F228A4319F47D...

3/1/2017


PROJECT ENGINEER H CARO SEAL 16600

SHEET NO.

2D-4

TRASH RACK DETAILS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



REBAR TRASH RACK
NOT TO SCALE

IIOS (N. 7730MIL) IAMS (N.7730MIL) IAMB (LZD. 7177) Serikarau DocuSign Envelope ID: 43E9E258-A6F4-4F62-A36A-1708EDCBB86C

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS


PROJECT REFERENCE NO. SHEET NO. R-4436MI 3B/3D

DocuSigned by:

randall hanger

B5F228A4319F47D...

3/1/2017



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SUMMARY OF EARTHWORK (for Stormwater BMP's)

		QUANTITY
ITEM DESCRIPTION	UNIT	PROJECT TOTALS
UNCLASSIFIED EXCAVATION	CY	360
EMBANKMENT	CY	90
ENGINEERED SOIL MEDIA	CY	135
WASHED NO. 57 STONE	TON	63
RIPRAP, CL B	TON	66

SUMMARY FOR EROSION CONTROL (for Stormwater BMP's)

		QUANTITY
ITEM DESCRIPTION	UNIT	PROJECT TOTALS
SEDIMENT CONTROL STONE (NO. 5 OR 57)	TON	14
EROSION CONTROL STONE CL. A	TON	49
EROSION CONTROL STONE CL. B	TON	8
SEEDING & MULCHING	ACR	0.5
SODDING	SY	730
WATER	M/G	25
1/4" HARDWARE CLOTH	LF	60

DRAINAGE SUMMARY (for Stormwater BMP's)


		QUANTITY
ITEM DESCRIPTION	UNIT	PROJECT TOTALS
12" CS PIPE CULVERT	LF	84
12" CS PIPE ELBOW	EA	2
UNDERDRAIN PIPE – 6" HDPE PERFORATED	LF	86
UNDERDRAIN PIPE – 6" HDPE NONPERFORATED	LF	8
6" CAP (THREADED)	EA	2
18" HDPE	LF	366
6" x 6" x 6" HDPE TEE	EA	1
GEOTEXTILE FOR DRAINAGE (TYPE 2, NON-WOVEN)	SY	252
POLYPROPYLENE NONWOVEN GEOTEXTILE FABRIC	SY	271
OUTLET STRUCTURE BOX (SEE SHEET 2D-3)	EA	1
REBAR TRASH RACK (SEE SHEET 2D-4)	EA	1
JUNCTION BOX	EA	3
FRAME W/COVER (840.54)	EA	3
ADJUSTMENT OF DI	EA	2
PIPE REMOVAL (18" RCP)	LF	290

LIST OF PIPES											
ICE	ŀ	IDPE PIPE		C.S. PIPE	IN. FT.						
REFERENCE	6" PERFORATED PIPE	6" SOLID	18"	12"	PIPE REMOVAL LIN. FT.	REMARKS					
BASIN 1	86	8				SEE DETAILS ON SHEETS 2D-1 AND 2D-2					
BASIN 1 TO 0406			68								
0402 TO BASIN 1				84							
0403 TO 0404			130								
0404 TO 0405			146								
0405 TO 0406			22								
0403 TO 0406					290	EXIST. 18" RCP					
TOTALS (FT)	86	8	366	84	290						


	LIST OF STRUCTURES											
STRUCTURE NO.	TOP ELEVATION INVERT IN ELEVATION INVERT OUT ELEVATION J.B. STD. 840.31 OR 840.32 MANHOLE FRAME AND COVER STD. 840.54		TRASH RACK	REMARKS								
0401	BASIN OUTLET STRUCTURE	2632.0	2626.0	2624.0	1			1	SEE DETAILS ON SHEETS 2D-3 AND 2D-4 EXTRA DEPTH BOX: PER EACH (0' THRU 5.0') = 1, 5.0' THRU			
0402	JUNCTION BOX 1	2654.0	2648.4	2647.5		1	1		10.0'= 3 LIN. FT. (FIELD VERIFY) EXTRA DEPTH BOX: PER EACH (0' THRU 5.0') = 1, 5.0' THRU 10.0'= 1.5 LIN. FT. (FIELD VERIFY)			
0403	EXIST. DI								TO BE ADJUSTED FOR NEW OUTLET PIPE. SEE SHEET 4.			
0404	JUNCTION BOX 2	2637.0	2630.5	2630.0		1	1		EXTRA DEPTH BOX: PER EACH (0' THRU 5.0') = 1, 5.0' THRU 10.0'= 2 LIN. FT. (FIELD VERIFY)			
0405	JUNCTION BOX 3	2631.5	2628.5	2626.5		1	1					
0406	EXIST. DI								TO BE ADJUSTED FOR NEW INLET PIPES. SEE SHEET 4.			
TOTALS (FT)					1	2	2	1				


TRAFFIC CONTROL PLAN


PROJECT REFERENCE NO. SHEET NO. R-4436MI TC-I




DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED









2/23/2017 4436\Hidrailles\R-436MI Plans\R-4436MI TC ten TC-1-0