


Site # 011-01-98254
Private Bridge Repair 814 North Turkey Creek Rd
over North Fork of Turkey Creek
in Buncombe County



NOTES:
 NO PROPOSED ROADWAY WORK
 BRIDGE REHABILITATION ONLY

CONTRACTOR SHALL NOT ALLOW MUD, DEBRIS OR AGGREGATE TO ACCUMULATE ON NORTH TURKEY CREEK ROAD. ANY MATERIAL ACCUMULATED ON THE ROAD SHALL BE IMMEDIATELY CLEANED OFF TO PRE-PROJECT CONDITIONS.

THE HYDRAULIC CONVEYANCE OF THE BRIDGE WILL NOT BE IMPACTED BY THE PROPOSED REPAIRS.


FINAL SURVEYS WERE NOT PROVIDED. LIDAR DATED 2017 AND AERIALS DATED 2023 WERE USED FOR DESIGN.

011-01-98254
 04
 NORTH CAROLINA
 EMERGENCY MANAGEMENT
 BUNCOMBE COUNTY

ROADWAY DESIGN
 ENGINEER
 12/19/2025
 SEAL
 035663
 MICHAEL B. LITTLEFIELD
 ENGINEER


Signed by:
 Michael B. Littlefield
 P-791-33186344491

PREPARED BY
Stantec
 Stantec Consulting Services Inc.
 801 Jones Farm Rd
 Suite 300
 Raleigh, NC 27606
 Tel: (919) 851-8886 Fax: (919) 851-7024
 www.stantec.com License No. F-0872




REVISIONS

BILL OF MATERIAL					
END BENT 1					
BAR NO.	SIZE	TYPE	LENGTH	WEIGHT	
A1	#4	STR	7'-11"	32	
A2	#4	STR	17'-0"	68	
A3	#4	STR	3'-2"	4	
L1	#4		4'-7"	49	
L2	#4		5'-11"	8	
U1	#4		9'-1"	97	
U2	#4		12'-0"	16	
REINFORCING STEEL				LBS.	274
POUR #1: FLOWABLE FILL				C.Y.	17.5
POUR #2: CASS A CONCRETE				C.Y.	2.1
FOUNDATION CONDITIONING MATERIAL				TONS	3.2
FOUNDATION CONDITIONING GEOTEXTILE				SO. YD.	55.2




- Ⓐ ADHESIVELY ANCHOR 'U' BARS USING AN EPOXY ADHESIVE ANCHORAGE SYSTEM. THE SYSTEM SHALL BE CAPABLE OF DEVELOPING 7KSI TENSION FOR A MINIMUM 6" EMBEDMENT IN 'CRACKED CONCRETE', $f'_c = 2,500$ PSI. INSTALLATION OF THE EPOXY ANCHORED BAR SHALL BE INSTALLED ACCORDING TO MANUFACTURER RECOMMENDATION.
- Ⓑ REINFORCEMENT SHALL BE PLACED 2" CLR. UNLESS NOTED OTHERWISE.

SECTION A-A



SECTION B-B

- NOTES**
- CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS PRIOR TO CONSTRUCTION.
 - ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2024 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N. C. DEPARTMENT OF TRANSPORTATION.
 - UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED $\frac{3}{4}$ " WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO $1\frac{1}{2}$ " RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A $\frac{1}{4}$ " FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A $\frac{1}{4}$ " RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.
 - ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS.
 - WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.
 - REINFORCING BARS MAY BE SHIFTED TO AVOID CONFLICT WITH EXISTING SITE CONDITIONS, BASED ON APPROVAL OF THE ENGINEER.
 - BRIDGE SHALL BE JACKED PRIOR TO FOUNDATION REPAIRS. SEE BRIDGE JACKING NOTES FOR ADDITIONAL DETAILS. THE COST OF JACKING SHALL BE CONSIDERED INCIDENTAL TO BRIDGE REPAIR COST.
 - FOR FLOWABLE FILL DETAILS RELATED TO PLACEMENT, PAYMENT, AND STRENGTH, SEE SPECIAL PROVISIONS.



PLAN VIEW

END BENT 1

PROJECT ID. 011-01-98254
BUNCOMBE COUNTY
 STATION: 10+70.00 -L-

**NORTH CAROLINA
EMERGENCY MANAGEMENT**
BUNCOMBE COUNTY

END BENT 1 REPAIRS


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	1
1			3			TOTAL SHEETS
2			4			2

DESIGNED BY: WCK	DATE: 11/7/25
DRAWN BY: WCK	DATE: 11/7/25
CHECKED BY: TRD	DATE: 11/10/25
DESIGN ENGINEER OF RECORD: T. DUDECK	DATE: 12/9/25

Stantec
 Stantec Consulting Services Inc.
 801 Jones Franklin Road
 Suite 300
 Raleigh, NC 27606
 Tel. (919) 851-6866
 Fax. (919) 851-7024
 www.stantec.com
 License No. F-0672


NORTH CAROLINA
PROFESSIONAL
SEAL
31462
ENGINEER
THOMAS J. DUDECK
DocuSigned by:
Tommy Dudeck
3/9/2025

BILL OF MATERIAL					
END BENT 2					
BAR NO.	NO.	SIZE	TYPE	LENGTH	WEIGHT
A4	6	#4	STR	16'-5"	66
A5	4	#4	STR	1'-8"	5
L1	8	#4	1	4'-7"	25
L2	4	#4	1	5'-11"	16
U1	8	#4	2	9'-1"	48
U2	4	#4	2	12'-0"	32
REINFORCING STEEL					LBS. 192
POUR #1: FLOWABLE FILL					C.Y. 11.4
POUR #2: CLASS A CONCRETE					C.Y. 1.4
FOUNDATION CONDITIONING MATERIAL					TONS 2.1
FOUNDATION CONDITIONING GEOTEXTILE					SO. YD. 37.0



Ⓐ ADHESIVELY ANCHOR 'U' BARS USING AN EPOXY ADHESIVE ANCHORAGE SYSTEM. THE SYSTEM SHALL BE CAPABLE OF DEVELOPING 7KSI TENSION FOR A MINIMUM 6" EMBEDMENT IN 'CRACKED CONCRETE', $f'_c = 2,500$ PSI. INSTALLATION OF THE EPOXY ANCHORED BAR SHALL BE INSTALLED ACCORDING TO MANUFACTURER RECOMMENDATION.


SECTION A-A



SECTION B-B

BRIDGE JACKING NOTES

- PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL INVESTIGATE THE BRIDGE ON THE PROJECT AND DEVELOP A JACKING PLAN TO BE SUBMITTED FOR REVIEW AND APPROVAL TO THE ENGINEER. THIS INCLUDES BUT NOT LIMITED TO ANY CRIBBING, BRACES OR TEMPORARY SHORING.
- PRIOR TO JACKING, THE CONTRACTOR SHALL ENSURE THERE ARE NO OBSTACLES PREVENTING THE BEAM(S) FROM BEING LIFTED.
- THE BEAM(S) SHALL BE LIFTED ONLY SUFFICIENTLY SO THAT THE BEAM CLEARS ITS BEARING, AND ALL LOADS ARE SUPPORTED BY THE JACKS. THIS SHOULD NOT EXCEED 1'-4" OF AN INCH. IF ADDITIONAL JACKING IS REQUIRED, THE ENGINEER SHALL BE NOTIFIED AND THE ADDITIONAL JACKING APPROVED. AFTER JACKING IS COMPLETE, AS NEEDED THE CONTRACTOR MAY NEED TO REMOVE THE JACKS AND SUPPORT THE BEAM FOR THE DEAD LOAD AND LIVE LOAD DURING THE REPAIR OPERATION. THE CONTRACTOR SHALL PROVIDE A PLAN TO THE ENGINEER FOR REVIEW AND APPROVAL. IF THE JACKS REMAIN IN PLACE DURING THE ENTIRE JACKING AND REPAIR OPERATION, THESE JACKS SHALL HAVE MECHANICAL LOCK OFF CAPABILITIES.
- IF, DURING THE JACKING PROCESS, OR WHILE THE BEAM IS BEING SUPPORTED, THE BEAM SHIFTS FROM ITS ORIGINAL POSITION, ALL WORK SHALL CEASE, AND THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY.
- ANCHOR BOLTS MAY BE LOOSENED TO AID JACKING OPERATIONS. ALL LOCATIONS SHALL BE DOCUMENTED AND ALL BEARING ANCHORS OR FASTENERS LOOSENED SHALL BE TIGHTENED BACK AFTER REPAIR OPERATIONS WERE COMPLETED AND THE JACKS AND BLOCKING HAVE BEEN REMOVED. THE TIGHTENING OF EACH DOCUMENTED LOCATION SHALL BE VERIFIED THAT THE CONNECTIONS ARE APPROPRIATELY TENSIONED.
- THE MAXIMUM DIFFERENTIAL BETWEEN ADJACENT BEAMS THAT ARE BEING JACKED SHALL BE LESS THAN 1'-4".
- THE CONTRACTOR SHALL DETERMINE THE EXPECTED DEADLOADS AND LIVE LOADS TO BE LIFTED DURING YOUR BRIDGE JACKING OPERATION. THESE LOADS SHALL BE PROVIDED TO THE ENGINEER FOR REVIEW AND APPROVAL.
- THE CONTRACTOR SHALL SUBMIT WORKING DRAWINGS AND CALCULATIONS OF JACKING PROCEDURES SEALED BY A PROFESSIONAL ENGINEER IN THE STATE OF NORTH CAROLINA TO THE ENGINEER FOR APPROVAL PRIOR TO BRIDGE JACKING OPERATIONS.
- PERMANENT STEEL CONNECTIONS, SUCH AS WELDED MEMBERS, SHALL REMAIN IN PLACE DURING JACKING OPERATIONS.
- TYPE 2 BRIDGE JACKING SHALL BE DONE WITH A HYDRAULIC JACKING SYSTEM THAT LIFTS EACH BEAM ALONG ENTIRE SPAN WITH EQUAL FORCE AND AT AN EQUAL RATE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE CAUSED TO THE EXISTING STRUCTURE BY BRIDGE JACKING OPERATIONS AT NO ADDITIONAL COST.



PLAN VIEW

END BENT 2

PROJECT ID. 011-01-98254
 BUNCOMBE COUNTY
 STATION: 10+70.00 -L-

**NORTH CAROLINA
EMERGENCY MANAGEMENT**
BUNCOMBE COUNTY

END BENT 2 REPAIR

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			2
2			4			TOTAL SHEETS 2

DESIGNED BY: W GK DATE: 11/7/25
 DRAWN BY: W GK DATE: 11/7/25
 CHECKED BY: TRD DATE: 11/10/25
 DESIGN ENGINEER OF RECORD: T. DUDECK DATE: 12/9/25

Stantec Consulting Services Inc.
 801 Jones Franklin Road
 Suite 300
 Raleigh, NC 27606
 Tel. (919) 851-6866
 Fax. (919) 851-7024
 www.stantec.com
 License No. F-0672


Tommy Dudeck
 1/9/2025

SOIL STABILIZATION TIMEFRAMES


SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HOW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 TO 4:1	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH WITH SLOPES STEEPER THAN 4:1. 7 DAYS FOR PERMETER DIKES, SWALES, DITCHES PERMETER SLOPES, AND HOW ZONES
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	7 DAYS FOR PERMETER DIKES, SWALES, DITCHES PERMETER SLOPES, AND HOW ZONES

EROSION & SEDIMENT CONTROL LEGEND

- Temporary Silt Fence ||| |||
- Temporary Rock Silt Check Type A [Cross-hatched symbol]
- Impervious Dike [Solid line symbol]
- Special Sediment Control Fence [Zig-zag symbol]



VICINITY MAP
NOT TO SCALE




011-01-98254

ECDI/CONST.04

NORTH CAROLINA
EMERGENCY MANAGEMENT
BUNCOMBE COUNTY



HYDRAULICS
ENGINEER




12/24/2025

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

SUNGATE DESIGN GROUP, P.A.




TOTAL IMPERVIOUS AREA = 0.028 AC
TOTAL DISTURBED AREA = 0.051 AC









NOTE:
NO PROPOSED ROADWAY WORK
BRIDGE REHABILITATION ONLY

NOTE:
FINAL SURVEYS WERE NOT PROVIDED. LIDAR DATED
2017 AND AERIALS DATED 2023 WERE USED FOR DESIGN.



REVISIONS



011-01-98254
ECO2
 NORTH CAROLINA
 EMERGENCY MANAGEMENT
 BUNCOMBE COUNTY

HYDRAULICS
 ENGINEER

Signed by:

SEAL
 ENGINEER
 JOSHUA G. DALTON

12/24/2025

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

SUNGATE DESIGN GROUP, P.A.
 800 S. WILKINSON ROAD
 FAYETTEVILLE, NC 28404
 704.336.8800
 800.368.8800

REVISIONS

Date: **GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT**

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes		
Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQW) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10 feet or less in length and are not allowed to be steeper than 2:1, 14 days are allowed -7 days for slopes greater than 5' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones
(d) Slopes 3:1 to 4:1	14	-10 days for Falls Lake Watershed
(e) Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
<ul style="list-style-type: none"> Temporary grass seed covered with straw or other mulches and tackifiers. Hydroseeding Roller erosion control products with or without temporary grass seed Appropriately applied straw or other mulch Plastic sheeting 	<ul style="list-style-type: none"> Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Roller erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.
- Provide ponding area for containment of treated Stormwater before discharging offsite.
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment.
- Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers.
- Provide a sufficient number and size of waste containers (e.g. dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- Dispose waste off-site at an approved disposal facility.
- On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE

- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

PORTABLE TOILETS


- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.

HAZARDOUS AND TOXIC WASTE

- Create designated hazardous waste collection area on-site.
- Place hazardous waste containers under cover or in secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.



CONCRETE WASHOUTS

- Do not discharge concrete or cement slurry from the site.
- Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- Do not stockpile these materials onsite.

Page:

Impervious Dike:

Description

This work consists of furnishing, installing, maintaining, and removing an *Impervious Dike* for the purpose of diverting normal stream flow around the construction site. The Contractor shall construct an impervious dike in such a manner approved by the Engineer. The impervious dike shall not permit seepage of water into the construction site or contribute to siltation of the stream. The impervious dike shall be constructed of an acceptable material in the locations noted on the plans or as directed.

Materials

Acceptable materials shall include but not be limited to sheet piles, sandbags, and/or the placement of an acceptable size stone lined with polypropylene or other impervious geotextile.

Earth material shall not be used to construct an Impervious dike when it is in direct contact with the stream unless vegetation can be established before contact with the stream takes place.

Measurement and Payment

Impervious Dike will be measured and paid as the actual number of linear feet of impervious dike(s) constructed, measured in place from end to end of each separate installation that has been completed and accepted. Such price and payment will be full compensation for all work including but not limited to furnishing materials, construction, maintenance, and removal of the impervious dike.

SPECIAL STILLING BASIN:

Description

This work consists of furnishing, placing, and removing special stilling basin(s) as directed. The special stilling basin can be used to filter pumped water during construction of drilled piers, footing excavation, and/or culvert construction. The special stilling basin can also be used for sediment storage at the outlet of temporary slope drain pipe(s).

Materials

Refer to Division 10

Item	Section
Filter Fabric for Drainage, Type 2	1056
Sediment Control Stone	1005

The filter fabric and sediment control stone shall be clean and shall not contain debris.

The special stilling basin shall be a water permeable fabric bag that traps sand, silt, and fines as sediment-laden water is pumped into it, or runoff flows into it through the temporary slope drain pipe(s).

The special stilling basin shall be a bag constructed to a minimum size of 10' x 15' made from a nonwoven fabric. It shall have a sewn-in 8" (maximum) spout for receiving pump discharge. The bag seams shall be sewn with a double needle machine using a high strength thread. The seams shall have a minimum wide width strength as follows:

Test Method	Minimum Specifications
ASTM D-4884	60 lb/in

The fabric used to construct the bag shall be stabilized to provide resistance to ultra-violet degradation and meet the following specifications for flow rates, strength, and permeability:

Property	Test Method	Minimum Specifications
Weight	ASTM D-3776	8.0 oz/yd
Grab tensile	ASTM D-4632	200.0 lb
Puncture	ASTM D-4833	130.0 lb
Flow rate	ASTM D-4491	80.0 gal/min/sf
Permittivity	ASTM D-4491	1.2 1/sec
UV Resistance	ASTM D-4355	70.0%

Construction Methods

The Contractor shall install the special stilling basin(s), filter fabric, and stone in accordance with Standard Drawing No. 1630.06 and at locations on the plans and as directed. The special stilling basin(s) shall be placed on level ground.

The special stilling basin(s) shall be constructed such that it is portable and can be used adjacent to each drilled pier, footing and/or culvert, as required by the project commitments. If needed, temporary slope drain pipe(s) or pump discharge hoses will be attached to the special stilling basin(s) to divert runoff or pumped effluent directly into the special stilling basin(s). The special stilling basin may be cut to allow slope drain pipe to be inserted if needed and tied off tightly. The remaining sleeve or spout of the bag, if present, may be used to connect more than one special stilling basin in series as directed. If not used in this manner, the sleeve shall be tied off tightly to allow the bag to contain the effluent and force it to filter through the sides of the special stilling basin. The special stilling basin(s) shall be placed so the incoming runoff or pumped effluent flows into and through it without causing erosion to adjacent slopes or streambanks. In areas of turbidity and water quality concern, the special stilling basin(s) shall be placed up grade and its runoff directed into a sediment control measure before being allowed to discharge into jurisdictional waters.

The special stilling basin(s) shall be replaced and disposed of when it is ¾ full of sediment or when it is impractical for the bag to filter the sediment out at a reasonable flow rate. Prior approval from the Engineer shall be received before removal and replacement.

The Contractor shall be responsible for providing a sufficient quantity of bags to contain silt from pumped effluent during construction of drilled piers, footing excavation, and/or culvert construction. A sufficient quantity of special stilling basins shall be provided to contain sediment from temporary slope drain runoff.

Measurement and Payment

Special Stilling Basin will be measured and paid as the actual number of bags used during temporary slope drain installation, drilled pier construction, footing excavation, and/or culvert construction as specified and accepted.

Filter Fabric for Drainage will be measured and paid for in accordance with Article 876-4 of the *Standard Specifications*.

Sediment Control Stone will be measured and paid for in accordance with Article 1610-4 of the *Standard Specifications*.

Such price and payment will be full compensation for all work covered by this section, including but not limited to, furnishing all materials, placing and maintaining the special stilling basin(s), and removal and disposal of silt accumulations and bag.

NCG-01 GROUND COVER & MATERIALS HANDLING



EFFECTIVE DATE: 11/12/2022

Date: **NON-INVASIVE PERMANENT SEEDING RECOMMENDATIONS FOR FALL** Page:

NON-INVASIVE PERMANENT SEEDING RECOMMENDATIONS FOR LATE WINTER AND EARLY SPRING

SEEDING MIXTURE		SEEDING MIXTURE	
Species	Rate	Species	Rate
Centipede	5 lbs/acre	Indian Woodoats	1.5-2.5 lbs/acre*
Indian Woodoats	1.5-2.5 lbs/acre*	Virginia Wild Rye	4-6 lbs/acre*
Virginia Wild Rye	4-6 lbs/acre*		

*Depending upon mix with other species. See table 6.11.d from Chapter 6 of the NC Erosion and Sediment Control Planning and Design Manual.

Seeding Dates
Coastal or Eastern Piedmont for Centipede- Sept. 1 - May 1
Coastal and Piedmont for Indian Woodoats and Virginia Wild Rye- Feb 15 - April 1
Mountains for Indian Woodoats and Virginia Wild Rye- March 1 - May 15

Maintenance:
Significant maintenance may be required to obtain desired cover once centipede is planted. Acceptable for sodding.

SEED BED PREPARATION:
LIMING- Apply lime according to soil test recommendations. If the pH (acidity) of the soil is not known, an application of ground agricultural limestone at the rate of 1 to 1 ½ tons/acre on coarse-textured soils and 2-3 tons/acre on fine-textured soils is usually sufficient. Apply limestone uniformly and incorporate into the top 4-6 inches of soil. Soils with a pH of 6 or higher need not be limed.
FERTILIZER- Base application rates on soil tests. When these are not possible, apply a 10-10-10 grade fertilizer at 700-1,000 lb/acre. Both fertilizer and lime should be incorporated into the top 4-6 inches of soil. If a hydraulic seeder is used, do not mix seed and fertilizer more than 30 minutes before application.
SURFACE ROUGHENING- If recent tillage operations have resulted in a loose surface additional roughening may not be required, except to break up large clods. If rainfall causes the surface to become sealed or crusted, loosen it just prior to seeding by raking, harrowing, or other suitable methods for fine grading. The finished grade shall be a smooth even soil surface with a loosen uniformly fine texture. All ridges and depressions shall be removed and filled to provide the approved surface drainage. Planting is to be done immediately after finished grades are obtained and seedbed preparation is completed.

NOTES:
1. Permanent seeding, sodding or other means of stabilization are required when all construction work is completed according to the NPDES timeframe's table.
2. A North Carolina Department of Agriculture soils test (or equal) is highly recommended to be obtained for all areas to be seeded, sprigged, sodded or planted.
3. Use a seeding mix that will produce fast growing nurse crops and includes non-invasive species that will eventually provide a permanent groundcover. Soil blankets may be used in lieu of nurse crops. Mat, tack or crimp mulch, as needed to stabilize seeded areas until root establishment. Mulch must be applied uniformly over the soil with a cover density of at least 80%.
4. Ground cover shall be maintained until permanent vegetation is established and stable against accelerated erosion.



EFFECTIVE DATE: 1/1/2020

PERMANENT SEEDING RECOMMENDATIONS

Date: **TEMPORARY SEEDING RECOMMENDATIONS FOR LATE WINTER AND EARLY SPRING** PAGE:

TEMPORARY SEEDING RECOMMENDATIONS FOR LATE WINTER AND EARLY SPRING

SEEDING MIXTURE		SEEDING MIXTURE	
Species	Rate	Species	Rate
Hard Fescue	15 lbs/acre	Rye (grain)	120
Switchgrass	2.5-3.5 lbs/acre*	Annual lespedeza (Kobe in Piedmont and Coastal Plain, Korean in Mountains)	50
Indian Grass	5-7 lbs/acre*		
Big Bluestem	5-7 lbs/acre*		
Indian Woodoats	1.5-2.5 lbs/acre*		
Virginia Wild Rye	4-6 lbs/acre*		

*Depending upon mix with other species. See table 6.11.d from Chapter 6 of the NC Erosion and Sediment Control Planning and Design Manual.

Seeding Dates
Mountains - Hard Fescue- Aug 1 - June 1
Mountains- Switchgrass, Indian Grass, Big Bluestem- Dec 1 - April 15
Piedmont and Coastal- Switchgrass, Indian Grass, Big Bluestem- Dec 1 - April 1
Coastal- Indian Woodoats and Virginia Wild Rye- Sept 1 - Nov 1

Maintenance:
Hard Fescue is not recommended for slopes > 5%.

SEED BED PREPARATION:
LIMING- Apply lime according to soil test recommendations. If the pH (acidity) of the soil is not known, an application of ground agricultural limestone at the rate of 1-1 ½ tons/acre on coarse-textured soils and 2-3 tons/acre on fine-textured soils is usually sufficient. Apply limestone uniformly and incorporate into the top 4-6 inches of soil. Soils with a pH of 6 or higher need not be limed.
FERTILIZER- Base application rates on soil tests. When these are not possible, apply a 10-10-10 grade fertilizer at 700 - 1,000 lb/acre. Both fertilizer and lime should be incorporated into the top 4-6 inches of soil. If a hydraulic seeder is used, do not mix seed and fertilizer more than 30 minutes before application.
SURFACE ROUGHENING- If recent tillage operations have resulted in a loose surface additional roughening may not be required, except to break up large clods. If rainfall causes the surface to become sealed or crusted, loosen it just prior to seeding by raking, harrowing, or other suitable methods for fine grading. The finished grade shall be a smooth even soil surface with a loosen uniformly fine texture. All ridges and depressions shall be removed and filled to provide the approved surface drainage. Planting is to be done immediately after finished grades are obtained and seedbed preparation is completed.



TEMPORARY SEEDING

Effective Date: 9/1/2023 in accordance with the 2013 Design Manual Updates

NOTATIONS

011-01-98254
E C O 3
NORTH CAROLINA
EMERGENCY MANAGEMENT
BUNCOMBE COUNTY

HYDRAULICS
ENGINEER

Signed by:
Josh Dalton
Professional Engineer
No. 26971
NORTH CAROLINA

12/24/2025

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

SUNGATE DESIGN GROUP, P.A.
100 EAST TRANSCENDENTAL ROAD
SUITE 200
FAYETTEVILLE, NC 28404


GEOTECHNICAL BORING REPORT BORE LOG

SHEET 1

WBS 0		TIP 0	COUNT BUNCOMBE		GEOLOGIST Zhuo. Z	
SITE DESCRIPTION Site 011-01 -98254 814 N Turkey Creek Rd				ALIGNMENT N/A		GROUND WTR (ft)
BORING NO. B-1		STATION N/A		OFFSET N/A		0 HR. N/A
COLLAR ELEV. 2,299.0 ft		TOTAL DEPTH 39.3 ft		NORTHING 712,551		EASTING 880,227
DRILL RIGHAMMER EFF. DATE		TER4106 Geoprobe 3126GT 98% 01/24/2025		DRILL METHOD NW Casing w/ Advancer		HAMMER TYPE Automatic
DRILLER Burnette, B.		START DATE 10/30/25		COMP. DATE 10/30/25		SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT	SAMP NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft						
2300											
	2,298.0	1.0	2	2	2				GROUND SURFACE Topsoil: 1.5 inches	0.0	
	2,295.5	3.5	8	8	10				ARTIFICIAL FILL Well-Graded Sand with Silt (A-1), trace mica and gravel, brown, moist, loose	4.5	
	2,293.0	6.0	38	12	12				ALLUVIAL Poorly graded sand (A-3), fine to medium grained, brown, moist, medium dense	6.0	
	2,290.5	8.5	0	1	1				ALLUVIAL Poorly Graded Gravel with Sand (A-1), light brown, moist, medium dense	8.5	
	2,285.5	13.5	9	12	12				RESIDUAL Silty Sand (A-1), gray and white, moist, very loose to medium dense	18.5	
	2,280.5	18.5	10	18	26				RESIDUAL Sandy Silt (A-4), trace mica, gray and white, moist, hard	18.5	
	2,275.5	23.5	100/0.5						WEATHERED ROCK (Brown Biotite Gneiss)	23.5	
	2,270.5	28.5	23	17	83				gray and white		
	2,265.5	33.5	13	22	43						
	2,260.5	38.5	57	43/0.3					brown and gray Boring Terminated at Elevation 2,259.7 ft in weathered rock (biotite gneiss)	39.3	
									Cave in 17 ft		

Grain Size Distribution ASTM D422 / ASTM C136



Boring ID	Depth (Ft)	USCS Classification	Gravel		Sand		Silt or Clay				
			coarse	fine	coarse	medium	fine	LL	PL	PI	Cc
● B-1	1 - 2.5	WELL-GRADED SAND with SILT	SW-SM	A-1-b (0)	NP	NP	NP	NP	NP	1.29	10.29
⊠ B-1	6 - 7.5	POORLY GRADED GRAVEL with SAND	GP	A-1-a (0)	NP	NP	NP	NP	NP	0.86	30.48
▲ B-1	13.5 - 15	SILTY SAND	SM	A-1-b (0)	NP	NP	NP	NP	NP		
Boring ID	Depth (Ft)	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Cobbles	%Gravel	%Sand	%Fines	%Silt	%Clay
● B-1	1 - 2.5	19	0.712	0.252		0.0	6.4	82.5	11.1		
⊠ B-1	6 - 7.5	37.5	11.57	1.945	0.38	0.0	56.6	39.8	3.6		
▲ B-1	13.5 - 15	9.5	0.69	0.224		0.0	0.8	80.0	19.2		