



ABC STONE ROADWAY SURFACE
COMPACTED IN ACCORDANCE
WITH NCDOT STANDARD
SPECIFICATION (TYP.)

STEEL GUARDRAIL
(BY MANUFACTURER)
(TYP. EACH SIDE)

MODULAR PANEL
(TYP.)

1'-7" (TYP.)

CONTRACTOR SHALL ESTABLISH
APPROACH ROAD GRADE AS
REQUIRED AND SHALL PROVIDE
SMOOTH TRANSITION TO
EXISTING GRADE (TYP.)

1 1/2:1 SLOPE
(TYP.)

4'-0" (TYP.)

CLASS II
RIP RAP
(TYP.)

3'-0" (TYP.)

TYPE 4a
GEOTEXTILE
(TYP.)

SELECT MATERIAL
(CLASS V OR VI)
(TYP.)

1'-6" (TYP.)

CONTRACTOR SHALL CONSTRUCT
APPROACH FILL IN ACCORDANCE WITH
NCDOT STD DRAWING 423.01 (TYP.)

COMPACTED FILL (AS REQ'D.)
ACCORDING TO NCDOT
STANDARD SPECIFICATIONS
(TYP.)

LIMITS OF APPROACH
FILL EXCAVATION &
TYPE 1 GEOTEXTILE
(TYP.)

6"Ø SCH. 40 PERFORATED PVC PIPE
LOCATED 3" BELOW BOTTOM OF CAP
GRADE TO DRAIN & EXTEND TO
DAYLIGHT (TYP.)

HP 12X53
STEEL PILES
(TYP.)

TYPE 1
GEOTEXTILE
(TYP.)

APPROXIMATE
EXISTING
GROUND

"C" - C PILE & CAP TO C PILE & CAP

(SHOWING DRIVEN 12X53 STEEL
PILES FOUNDATION)

THE MODULAR BRIDGE SHALL BE POSITIONED TO PROVIDE A UNIFORM OVERHANG BEYOND THE FILL FACE OF EACH END BENT. THE OVERHANG SHALL BE SUPPORTED FULL LENGTH. THE CONTRACTOR SHALL PROVIDE A COMPACTED AGGREGATE BEARING SURFACE TO SUPPORT THE SUPERSTRUCTURE OVERHANG.

1'-7"

1 1/2:1 SLOPE

4'-0"

CLASS II RIP RAP

3'-0"

1'-6"

APPROXIMATE EXISTING GROUND


TOP OF ROCK

HP 12X53 STEEL PILES CASED AS NESSECARY

SEE 'BRIDGE ELEVATION' FOR APPROACH FILL AND ROAD GRADE INFORMATION

1" - C PILE & CAP TO C PILE & CAP

(SHOWING DRILLED-IN 12X53 STEEL
PILES FOUNDATION)




(SHOWING SPREAD FOOTING
FOUNDATION)




GENERAL DRAWING DRIVEN PILES




REVISIONS						SHEET NO. S-01
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 6
2			4			



DATE: 05/2026
DATE: 05/2026
DATE: 05/2026





\\pwworking.com\\jmt\\dwg\\01\\Documents\\Projects\\2025\\25-00529\\25-00529-001\\Design\\Structures\\NC PRB-Panel Bridge Standards 003-ME Bridge_End Bent_Driven Piles.dwg
DATE: 6/2/2026
TIME: 6/2/2026



PILE SPLICE DETAILS

△ POSITION OF PILE DURING WELDING.



BILL OF MATERIAL FOR ONE END BENT					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	#9	1	16'-1"	437
B2	8	#4	STR	13'-8"	73
B3	4	#4	STR	2'-5"	7
S1	14	#4	3	7'-5"	69
S2	14	#4	2	3'-2"	30
S3	6	#4	4	6'-6"	26
REINFORCING STEEL (FOR ONE END BENT)					642 LBS.
CLASS A CONCRETE (FOR ONE END BENT)					3.6 C.Y.

GENERAL NOTES

CONTRACTOR SHALL SLOPE TOP OF CAP TO MATCH LONGITUDINAL GRADE OF THE BRIDGE. SLOPES SHALL MATCH ON BOTH END BENT 1 AND END BENT 2 CAPS.

MODULAR BRIDGE SUPERSTRUCTURE SHOWN IS SCHEMATIC ONLY. ACTUAL MODULAR BRIDGE SYSTEM CONFIGURATION AND MEMBER SIZING SHALL BE DETERMINED BY THE CONTRACTOR TO MEET THE SPECIFIED DESIGN LOADS.

FOUNDATION NOTES

DRIVEN PILES

INSTALL PILES IN ACCORDANCE WITH SECTION 450 OF THE STANDARD SPECIFICATIONS.


DO NOT INSTALL PILES UNTIL FILL HAS BEEN PLACED.

DRIVE PILES TO A MINIMUM PENETRATION OF AT LEAST 10'-0" INTO NATURAL GROUND OR CHANNEL BOTTOM.

DRIVE ALL PILES TO REFUSAL BELOW MINIMUM PENETRATION.

PREDRILLING OR SPUDDING MAY BE REQUIRED TO ACHIEVE THE MINIMUM PILE PENETRATION.

SUBMIT THE PROPOSED PILE DRIVING METHODS AND EQUIPMENT FOR ACCEPTANCE BY THE ENGINEER.



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT
PRIVATE DRIVEWAY
BRIDGE STANDARDS
MODULAR PANEL BRIDGE



END BENT
DRIVEN PILES

REVISIONS						SHEET NO. S-03
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 6
2			4			

JMT Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097


DWN. BY: BC/WDC
CHKD. BY: CFW
DES. EGR. OF RECORD: GFW
DATE: 05/2026
DATE: 05/2026
DATE: 05/2026

\\pwworking.com\\jmt-jw-01\\Documents\\Projects\\2025\\25-00529\\25-00529-001\\Design\\Structures\\NC PRB-Panel Bridges Standards\\004-ME Bridge_End Bent_Drilled Piles.s4dgn
DATE: 6/2/2026
TIME: 6:22:02 PM



PILE SPLICE DETAILS

△ POSITION OF PILE DURING WELDING.



BILL OF MATERIAL

FOR ONE END BENT

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	#9	1	16'-1"	437
B2	8	#4	STR	13'-8"	73
B3	4	#4	STR	2'-5"	7
S1	14	#4	3	7'-5"	69
S2	14	#4	2	3'-2"	30
S3	6	#4	4	6'-6"	26

REINFORCING STEEL
(FOR ONE END BENT)

642 LBS.

CLASS A CONCRETE
(FOR ONE END BENT)

3.6 C.Y.

GENERAL NOTES

CONTRACTOR SHALL SLOPE TOP OF CAP TO MATCH
LONGITUDINAL GRADE OF THE BRIDGE. SLOPES SHALL
MATCH ON BOTH END BENT 1 AND END BENT 2 CAPS.

MODULAR BRIDGE SUPERSTRUCTURE SHOWN IS SCHEMATIC ONLY.
ACTUAL MODULAR BRIDGE SYSTEM CONFIGURATION AND MEMBER
SIZING SHALL BE DETERMINED BY THE CONTRACTOR TO MEET
THE SPECIFIED DESIGN LOADS.

FOUNDATION NOTES

DRILLED-IN PILES

ROCK QUALITY DESIGNATION (ROD)
GEOLOGICAL STRENGTH INDEX (GSI)

INSTALL DRILLED-IN PILES IN ACCORDANCE WITH SECTION
450 OF THE STANDARD SPECIFICATIONS.

MINIMUM PILE PENETRATION OF 10-FT INTO NATURAL GROUND
OR CHANNEL BOTTOM IS REQUIRED.




MINIMUM ROCK SOCKET DEPTHS, UNLESS OTHERWISE INDICATED
ON PROJECT SPECIFIC DATA SHEET:

4'-0" MINIMUM (ROD >70, GSI >50)
6'-0" MINIMUM (ROD 30-70, GSI 30-50)
8'-0" MINIMUM (ROD <30, GSI <30)

REFER TO BORING LOGS FOR ROD AND GSI DATA.

PILES SHALL BE SEATED IN THE BOTTOM OF THE EXCAVATION.
PILE DRIVING IS NOT REQUIRED.

BACKFILL WITH CONCRETE ONLY. DO NOT PROCEED WITH
CONSTRUCTION ACTIVITIES UNTIL THE 28 DAY STRENGTH IS
ACHIEVED.



06/02/2026

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT

PRIVATE DRIVEWAY BRIDGE STANDARDS

MODULAR PANEL BRIDGE

END BENT DRILLED IN PILES

REVISIONS


NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S-04
2			4			TOTAL SHEETS 6



Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097

DWN. BY: BC/WDC
CHKD. BY: CFW
DES. EGR. OF RECORD: GFW

DATE: 05/2026
DATE: 05/2026
DATE: 05/2026



SECTION A-A



NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT

**PRIVATE DRIVEWAY
 BRIDGE STANDARDS**

MODULAR PANEL BRIDGE

**END BENT
 SPREAD FOOTING**

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-05 TOTAL SHEETS 6
1			3			
2			4			

**BILL OF MATERIAL					
FOR ONE END BENT					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	16	#4	STR	13'-8"	146
B2	4	#9	STR	13'-8"	186
M1	56	#8	3	10'-5"	1,558
M2	4	#5	STR	7'-6"	31
T1	18	#5	1	16'-8"	313
T2	16	#5	1	9'-2"	153
T3	16	#8	1	9'-10"	420
U1	30	#4	2	8'-1"	162
V1	50	#4	4	6'-7"	220
REINFORCING STEEL				3,189 LBS.	


CLASS A CONCRETE BREAKDOWN		
POUR #1	FOOTING	12.7 C.Y.
POUR #2	END BENT STEM	11.4 C.Y.
TOTAL		24.1 C.Y.

*** THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE QUANTITIES AND REINFORCING BARS SHOWN IN THE BILL OF MATERIAL ARE BASED ON AN 8'-0" MAXIMUM STEM WALL HEIGHT. THE CONTRACTOR IS RESPONSIBLE FOR THE FINAL QUANTITIES BASED ON THE ACTUAL STEM WALL HEIGHT.

NORTH CAROLINA OFFICE OF EMERGENCY MANAGEMENT					
PRIVATE DRIVEWAY BRIDGE STANDARDS					
MODULAR PANEL BRIDGE					
GENERAL NOTES					
REVISIONS					SHEET NO. S-06
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
					TOTAL SHEETS 6



DIMENSIONS TABLE



*SEE BSR FOR RIP RAP LIMITS

TIMBER DECKING SHALL BE 2X8 BOARDS. 4X6 TIMBER DECKING (6" DIMENSION HORIZONTAL) MAY BE USED IN LIEU OF 2X8 DECKING; SEE OPTIONAL TYPICAL SECTION ON SHEET S-03 FOR DETAILS.

CONTRACTOR SHALL ESTABLISH
APPROACH ROAD GRADE AS
REQUIRED AND SHALL PROVIDE
SMOOTH TRANSITION TO
EXISTING GRADE

TYPE 4a
GEOTEXTILE

TYPE 1 GEOTEXTILE

SELECT MATERIAL
(CLASS V OR VI)

CONTRACTOR SHALL
CONSTRUCT APPROACH FILL
IN ACCORDANCE WITH NCDO
STD DRAWING 423.01

COMPACTED FILL
(AS REQ'D.) ACCORDING
TO NCDOT STANDARD
SPECIFICATIONS

← "E" - C PILE & CAP
TO C PILE & CAP

CONTRACTOR SHALL ESTABLISH
— APPROACH ROAD GRADE AS
REQUIRED AND SHALL PROVIDE
SMOOTH TRANSITION TO
EXISTING GRADE

TYPE 4a
GEOTEXTILE

COMPACTED FILL
(AS REQ'D.) ACCORDING
TO NCDOT STANDARD
SPECIFICATIONS

TYPE 1 GEOTEXTILE

CONTRACTOR SHALL
CONSTRUCT APPROACH FILL
IN ACCORDANCE WITH NCDOT
STD DRAWING 423.01

NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT

PRIVATE DRIVEWAY BRIDGE STANDARDS

SINGLE LANE STEEL BEAM BRIDGE
TIMBER DECK

GENERAL DRAWING

REVISED SHEET NO.						S-01
REVISIONS						
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS 13
1			3			
2			4			




Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097

ic.	DWN. BY: BC
	CHKD. BY: GFW
	DES. EGR. OF


DATE: 04/2026
DATE: 04/2026
DATE: 04/2026

BC:\dcs9\pwr\jmt\pwr\ben\jmt\jmt_2w-01\Documents\Projects\2025\25-00629\25-00629-001\Design\Structures\NC PRB-Steel Beam with Timber Deck Standards\Single Lane Steel Beam with Timber Deck Standards\Drawings\20-TO FT - 12 FT DECK WIDTH\002-S2-Typical Section.dgn
DATE: 5/18/2026




TYPICAL SECTION


MATERIALS TABLE				
SPAN	BEAM	DIAPHRAGM CHANNEL	DECK PLANK	DECKING SQ. FT.
20'-0"	W16X36	C12X20.7	2X8	244
30'-0"	W21X48	C12X20.7	2X8	364
40'-0"	W24X76	C12X20.7	2X8	484
50'-0"	W24X104	C12X20.7	2X8	604
60'-0"	W30X116	C12X20.7	2X8	724
70'-0"	W33X130	C12X20.7	2X8	844




SECTION AT END BENT



END ANGLE DETAIL




DETAIL 'A'




VIEW B-B

DECK CLIP DIMENSIONS		
SPAN	BEAM	*A
20'-0"	W16X36	1/2"
30'-0"	W21X48	1/2"
40'-0"	W24X76	3/4"
50'-0"	W24X104	13/16"
60'-0"	W30X116	15/16"
70'-0"	W33X130	15/16"


* DIMENSION A IS FOR INFORMATION ONLY. IT IS BASED ON THE FLANGE THICKNESS PLUS A 1/16" TOLERANCE. THE CONTRACTOR SHALL VERIFY THIS DIMENSION WITH DECK CLIP SUPPLIER. THE DECK CLIP SHALL HAVE A SNUG FIT TO THE BEAM FLANGE.




WHEEL GUARD DETAIL AT END BENTS




SECTION A-A



WHEEL GUARD SPLICE DETAIL



DECK CLIP DETAIL



WHEEL GUARD ELEVATION



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED




Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097

DWN. BY: BC
CHKD. BY: CFW
DES. EGR. OF RECORD: GFW


DATE: 04/2026
DATE: 04/2026
DATE: 04/2026

REVISIONS						SHEET NO. S-02
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 13
2			4			


NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT
PRIVATE DRIVEWAY
BRIDGE STANDARDS
SINGLE LANE STEEL BEAM BRIDGE
2X8 TIMBER DECK
TYPICAL SECTION
& RAIL DETAILS




TYPICAL SECTION




VIEW B-B




WHEEL GUARD SPLICE DETAIL



WHEEL GUARD DETAIL AT END BENTS




SECTION A-A




SECTION AT END BENT

DECK CLIP DIMENSIONS		
SPAN	BEAM	*A
20'-0"	W16X36	1/2"
30'-0"	W21X48	1/2"
40'-0"	W24X76	3/4"
50'-0"	W24X104	13/16"
60'-0"	W30X116	15/16"
70'-0"	W33X130	15/16"


* DIMENSION A IS FOR INFORMATION ONLY. IT IS BASED ON THE FLANGE THICKNESS PLUS A 1/16" TOLERANCE. THE CONTRACTOR SHALL VERIFY THIS DIMENSION WITH DECK CLIP SUPPLIER. THE DECK CLIP SHALL HAVE A SNUG FIT TO THE BEAM FLANGE.



DECK CLIP DETAIL



DETAIL 'A'



WHEEL GUARD ELEVATION

MATERIALS TABLE				
SPAN	BEAM	DIAPHRAGM CHANNEL	DECK PLANK	DECKING SQ. FT.
20'-0"	W16X36	C12X20.7	4X6	244
30'-0"	W21X48	C12X20.7	4X6	364
40'-0"	W24X76	C12X20.7	4X6	484
50'-0"	W24X104	C12X20.7	4X6	604
60'-0"	W30X116	C12X20.7	4X6	724
70'-0"	W33X130	C12X20.7	4X6	844

NOTES

FOR TIMBER BRIDGE DECK SYSTEM DETAILS, SEE "PLAN OF SPAN" SHEET.

FOR OPTIONAL TIMBER RAILS, SEE "OPTIONAL TIMBER BRIDGE RAIL" SHEET.

FOR BEAM AND DIAPHRAGM DETAILS, SEE "FRAMING PLAN & BEAM DETAILS" SHEET.

TREAT ALL DRILLED OR NEWLY EXPOSED HOLES IN TIMBER MEMBERS BY PUMPING WITH BITUMINOUS ASPHALT-BASED ROOFING CEMENT, OR APPROVED PRESERVATIVE SYSTEM BEFORE INSTALLING HARDWARE.


SEE "PLAN OF SPAN" SHEET FOR NUMBER OF WHEEL GUARDS AND WHEEL GUARD SPACING.

STAINLESS STEEL DECK CLIPS SHALL BE FABRICATED FROM 12 GAUGE STEEL.

THE 2"x10" TIMBER RUNNERS SHALL BE LAID OUT SYMMETRICALLY ABOUT THE CENTERLINE OF THE BRIDGE. ANY REQUIRED WIDTH ADJUSTMENT SHALL BE MADE AT THE CENTER RUNNER.

PLACE 2X10 WEARING SURFACE BOARDS PARALLEL TO TRAFFIC WITH A UNIFORM 1/4" CLEAR LONGITUDINAL GAP BETWEEN ADJACENT BOARDS. DO NOT BUTT BOARDS TIGHT. THIS GAP SHALL BE MAINTAINED TO FACILITATE SURFACE DRAINAGE AND PREVENT MOISTURE ENTRAPMENT AT THE INTERFACE OF THE STRUCTURAL DECK.

INSTALL 2X10 WEARING SURFACE BOARDS WITH GROWTH RINGS CURVING DOWNWARD TO PROMOTE DRAINAGE.




DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

JMT Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097

DWN. BY: BC
CHKD. BY: CFW
DES. EGR. OF RECORD: GFW
DATE: 04/2026
DATE: 04/2026
DATE: 04/2026

NORTH CAROLINA OFFICE OF EMERGENCY MANAGEMENT					
PRIVATE DRIVEWAY BRIDGE STANDARDS					
SINGLE LANE STEEL BEAM BRIDGE 4X6 TIMBER DECK					
OPTIONAL TYPICAL SECTION & RAIL DETAILS					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
SHEET NO. S-03					TOTAL SHEETS 13




ELEVATION OF OPTIONAL BRIDGE RAIL

OPTIONAL BRIDGE RAIL NOTES


BRIDGE RAILS SHALL BE CONTINUOUS FROM END POST TO
END POST WITH NO GAPS. RAIL LUMBER LENGTHS SHALL BE
ATTACHED TO A MINIMUM OF THREE POSTS.

TREAT ALL DRILLED OR NEWLY EXPOSED HOLES IN TIMBER MEMBERS BY PUMPING WITH BITUMINOUS ASPHALT-BASED ROOFING CEMENT, OR APPROVED PRESERVATIVE SYSTEM BEFORE INSTALLING HARDWARE.


SEE "PLAN OF SPAN" SHEET FOR NUMBER OF POSTS AND
POST SPACING.




SECTION A-A




VIEW B-B



WHEEL GUARD SPLICE DETAIL



OPTIONAL RAIL DETAIL AT END BENTS



05/18/2026

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT

PRIVATE DRIVEWAY BRIDGE STANDARDS

SINGLE LANE STEEL BEAM BRIDGE
TIMBER DECK

OPTIONAL TIMBER
BRIDGE RAIL

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-04
1			3			TOTAL SHEETS
2			4			13



Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097

ac.	DWN. BY: BC CHKD. BY: GFW DES. EGR. OF R
-----	--

DATE: 04/2026
DATE: 04/2026
DATE: 04/2026


BC:\dcs9\25616\pwworking\jmt.com\jmt_cw-01\Documents\Projects\2025\25-00629\25-00629-001\Design\Structures\NC PRB-Steel Beam with Timber Deck Standards\Single Lane Steel Beam Bridge Standards\Timber Deck Plans\2 Standard Drawings\20-70 FT - 12 FT DECK WIDTH\005-SS_Plan of Span.dgn
DATE: 5/18/2026 TIME: 5/18/2026

DIMENSIONS TABLE				
SPAN	A	B	C	D
20'-0"	20'-0"	22'-6"	5 SPA. @ 3'-8"	10"
30'-0"	30'-0"	32'-6"	7 SPA. @ 4'-0"	1'-0"
40'-0"	40'-0"	42'-6"	9 SPA. @ 4'-3"	10½"
50'-0"	50'-0"	52'-6"	11 SPA. @ 4'-4"	1'-2"
60'-0"	60'-0"	62'-6"	13 SPA. @ 4'-5½"	1'-0¼"
70'-0"	70'-0"	72'-6"	15 SPA. @ 4'-6"	1'-3"

NOTES

FOR ADDITIONAL NOTES, SEE "TYPICAL SECTION & RAIL DETAILS" SHEET, "OPTIONAL TYPICAL SECTION & RAIL DETAILS", AND "GENERAL NOTES" SHEET.

COUNTERSINK FLATHEAD STRUCTURAL TIMBER SCREW HEADS TO BE FLUSH WITH TIMBER SURFACE.




END BENT 1

DECK LAYOUT


2" X 8" TIMBER DECKING SHOWN. 4" X 6" TIMBER DECKING (6" DIMENSION HORIZONTAL) MAY BE USED IN LIEU OF 2" X 8" DECKING.

END BENT 2




DECKING BOARD BUTT JOINT DETAIL

BUTT JOINTS SHALL BE OVER THE CENTERLINE OF A BEAM. JOINTS SHALL BE STAGGERED EVERY FOURTH DECK BOARD. NONE ALLOWED AT THE EXTERIOR BEAMS.




SIDE VIEW
TIMBER RUNNER BEVEL DETAIL

(TYP. AT EACH END OF BRIDGE)



TIMBER RUNNER BUTT JOINT DETAIL



05/18/2026

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT
PRIVATE DRIVEWAY
BRIDGE STANDARDS
SINGLE LANE STEEL BEAM BRIDGE
TIMBER DECK
PLAN OF SPAN

REVISIONS						SHEET NO. S-05
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 13
2			4			




Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097


DWN. BY: BC
CHKD. BY: CFW
DES. EGR. OF RECORD: GFW

DATE: 04/2026
DATE: 04/2026
DATE: 04/2026

B:\projects\2025\25-00529\25-00529-001\Design\Structures\NC PRB-Steel Beam with Timber Deck Standards\Single Lane Steel Beam with Timber Deck Plans\2 Standard Drawings\20-70 FT - 12 FT DECK WIDTH\006-SG-Framing Plan.dgn
DATE: 5/18/2026
TIME: 5:18:26 PM




FRAMING PLAN
EXPANSION BEARING SHALL BE PLACED ON THE "UPHILL" END OF THE BRIDGE.



BEAM FLANGE ELEVATION
SHOWING DIAPHRAGM HOLES FOR ALL BEAMS, AND RAIL POST HOLES FOR EXTERIOR BEAMS.

BEAM DIMENSION TABLE							
SPAN	BEAM	CHANNEL	A	B	C	D	E
20'-0"	W16X36	C12X20.7	20'-0"	2 SPA. @ 7'-0"	3'-0"	10"	5 SPA. @ 3'-8"
30'-0"	W21X48	C12X20.7	30'-0"	2 SPA @ 12'-0"	3'-0"	1'-0"	7 SPA. @ 4'-0"
40'-0"	W24X76	C12X20.7	40'-0"	2 SPA. @ 17'-0"	3'-0"	10 1/2"	9 SPA. @ 4'-3"
50'-0"	W24X104	C12X20.7	50'-0"	2 SPA. @ 22'-0"	3'-0"	1'-2"	11 SPA. @ 4'-4"
60'-0"	W30X116	C12X20.7	60'-0"	4 SPA. @ 13'-6"	3'-0"	1'-0 3/4"	13 SPA. @ 4'-5 1/2"
70'-0"	W33X130	C12X20.7	70'-0"	4 SPA. @ 16'-0"	3'-0"	1'-3"	15 SPA. @ 4'-6"



SECTION VIEW - BRG. STIFFENER

STIFFENER DIMENSION			
BEAM	F	G	H
W16X36	1'-3"	3 3/8"	2"
W21X48	1'-7 3/4"	3 7/8"	2"
W24X76	1'-10 3/16"	4 1/4"	2 7/16"
W24X104	1'-10 3/16"	6 1/8"	2 3/4"
W30X116	2'-4 1/4"	5"	3 1/16"
W33X130	2'-7 3/8"	5 1/2"	3 1/8"

NOTES

NO SALVAGED BEAMS SHALL BE USED, UNLESS OTHERWISE NOTED ON THE PLANS.


NO SHOP CAMBER REQUIRED, TURN NATURAL MILL CAMBER UP.

ALL STRUCTURAL STEEL FIELD CONNECTIONS SHALL BE 3/8" DIA. GALVANIZED HIGH STRENGTH BOLTS UNLESS OTHERWISE NOTED.


BEAMS SHALL BE PLACED PARALLEL TO THE CHORD.

CONTRACTORS OPTION TO WELD CONNECTOR TO BEAM PRIOR TO SHOP COATING.


SEE "GENERAL NOTES" SHEET FOR COATING.



DIAPHRAGM DETAILS



ANGLE DETAILS



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT
**PRIVATE DRIVEWAY
BRIDGE STANDARDS**
SINGLE LANE STEEL BEAM BRIDGE
TIMBER DECK
**FRAMING PLAN &
BEAM DETAILS**

REVISIONS						SHEET NO. S-06
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 13
2			4			



Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097


DWN. BY: BC
CHKD. BY: CFW
DES. EGR. OF RECORD: GFW

DATE: 04/2026
DATE: 04/2026
DATE: 04/2026



DIMENSIONS TABLE

ADHESIVELY ANCHORED ANCHOR BOLTS SHALL BE
THREADED FULL LENGTH.






P2 SOLE PLATE DETAILS
(6 REQ'D)
FIXED



BEARING DETAILS

REVISIONS



BACKWALL HEIGHT			
SPAN	BEAM	A (2X8 DECKING)	A (4X6 DECKING)
20'-0"	W16X36	2'-2 $\frac{5}{8}$ "	1'-10 $\frac{7}{8}$ "
30'-0"	W21X48	2'-7 $\frac{3}{8}$ "	2'-3 $\frac{5}{8}$ "
40'-0"	W24X76	2'-10 $\frac{5}{8}$ "	2'-6 $\frac{7}{8}$ "
50'-0"	W24X104	2'-10 $\frac{3}{4}$ "	2'-7"
60'-0"	W30X116	3'-4 $\frac{3}{4}$ "	3'-1"
70'-0"	W33X130	3'-7 $\frac{3}{4}$ "	3'-4"

DIMENSION "A" (BACKWALL HEIGHT) VARIES BASED ON DECKING TYPE. USE VALUES CORRESPONDING TO SELECTED DECKING OPTION.

GENERAL NOTES

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO
CLEAR ANCHOR BOLTS.

CONTRACTOR SHALL SLOPE TOP OF CAP TO MATCH LONGITUDINAL GRADE OF THE BRIDGE. SLOPES SHALL MATCH ON BOTH END BENT 1 AND END BENT 2 CAPS.

WINGS MAY BE REQUIRED AT THE DIRECTION OF THE
ENGINEER OR DESIGNEE.

FOR OPTIONAL WINGS FOR END BENT, SEE SHEET S-10.

FOR BEARING DETAILS, SEE SHEET S-10.

FOR PILE SPLICE DETAILS, SEE SHEET S-10.

"V" BARS BASED ON SHORTEST BACKWALL HEIGHT USING
2X8 DECKING. ADJUST LENGTH TO MAINTAIN REQUIRED
MIN. CLEARANCE AT BOTTOM OF CAP AND TOP OF BACKWALL.

FOUNDATION NOTES

DRILLED-IN PILES

ROCK QUALITY DESIGNATION (RQD)
GEOLOGICAL STRENGTH INDEX (GSI)

INSTALL DRILLED-IN PILES IN ACCORDANCE WITH SECTION 450 OF THE STANDARD SPECIFICATIONS.

MINIMUM PILE PENETRATION OF 10-FT INTO NATURAL GROUND
OR CHANNEL BOTTOM IS REQUIRED.


MINIMUM ROCK SOCKET DEPTHS, UNLESS OTHERWISE INDICATED
ON PROJECT SPECIFIC DATA SHEET:

- 4' MINIMUM (RQD >70, GSI >50)
6' MINIMUM (RQD 30-70, GSI 30-50)
8' MINIMUM (RQD <30, GSI <30)


REFER TO BORING LOGS FOR RQD AND GSI DATA.

PILES SHALL BE SEATED IN THE BOTTOM OF THE EXCAVATION.
PILE DRIVING IS NOT REQUIRED.

BACKFILL WITH CONCRETE ONLY. DO NOT PROCEED WITH
CONSTRUCTION ACTIVITIES UNTIL THE 28 DAY STRENGTH
IS ACHIEVED.



SHEET 1 OF 2



DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED


NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT

PRIVATE DRIVEWAY BRIDGE STANDARDS

SINGLE LANE STEEL BEAM BRIDGE TIMBER DECK

END BENT DRILLED-IN PILES


REVISIONS						SHEET NO. S-09
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 13
2			4			



BEARING DETAIL


(TYP. EACH BEARING LOCATION)

REFER TO DIMENSIONS TABLE ON SHEET
S-07 FOR DIMENSIONS A AND B.




PILE SPLICE DETAILS

△ POSITION OF PILE DURING WELDING.




ELEVATION OF WING

(OPTIONAL)



PLAN OF WING

(OPTIONAL)



SECTION X-X

(OPTIONAL)

RIGHT SIDE WING SHOWN,
LEFT SIDE WING SIMILAR.

WING HEIGHT DEPENDENT
ON BACKWALL HEIGHT.



05/18/202

DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED

SHEET 2 OF 2

NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT

PRIVATE DRIVEWAY BRIDGE STANDARDS

SINGLE LANE STEEL BEAM BRIDGE TIMBER DECK

OPTIONAL WINGS FOR DRIVEN OR DRILLED-IN PILES

REVISIONS						SHEET NO. S-10
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 13
2			4			



Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097

C. DWN. BY: BC
CHKD. BY: GFW
DES. EGR. OF F

DATE: 04/2026
DATE: 04/2026
DATE: 04/2026

Q:\Millon\DWG\1\m1-pw-bentley.com\m1-pw-01\Documents\Projects\2025\25-00629\25-00629-001\Design\Structures\NC PRB-Steel Beam with Timber Deck Standards\Single Lane Steel Beam with Timber Deck Plans\2 Standard Drawings\20-70 FT - 12 FT DECK WIDTH\015-SIS-General Notes.dgn
DATE: 6/3/2026
TIME:

STRUCTURAL STEEL / HARDWARE NOTES:

ALL STRUCTURAL STEEL SHALL BE AASHTO M270 GRADE 50 AND PAINTED IN ACCORDANCE WITH SYSTEM 1 OR GALVANIZED IN ACCORDANCE WITH THE STRUCTURAL STEEL COATINGS PROGRAM AND ARTICLE 442-8 OF THE STANDARD SPECIFICATIONS UNLESS OTHERWISE NOTED ON THE PLANS.

COATING APPLICATION FOR ALL STRUCTURAL STEEL SHALL NOT BE PERFORMED UNTIL SHOP FABRICATION INCLUDING CUTTING, DRILLING AND WELDING HAS BEEN COMPLETED.

ALL HARDWARE SHALL BE GALVANIZED IN ACCORDANCE WITH SECTION 1076 OF THE STANDARD SPECIFICATION, UNLESS OTHERWISE NOTED ON THE PLANS.

DO NOT DRIVE LAG/STRUCTURAL SCREWS WITH A HAMMER, SCREW OR TORQUE LAG/STRUCTURAL SCREWS.

SCREWS SHALL BE OF SUFFICIENT LENGTH TO PROVIDE FULL THREAD ENGAGEMENT INTO RECEIVING MEMBERS.

REPAIR ANY DAMAGED GALVANIZED SURFACES IN ACCORDANCE WITH STANDARD SPECIFICATION ARTICLE 1076-7.

REPAIR ANY DAMAGED PAINTED SURFACES IN ACCORDANCE WITH SECTION 442 OF THE STANDARD SPECIFICATIONS.

STRUCTURAL WOOD SCREWS SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH SECTION 1076 OF THE STANDARD SPECIFICATION.

TIMBER / LUMBER NOTES:

ALL TIMBER AND LUMBER MEMBERS SHALL BE TREATED NO.1 SOUTHERN PINE AND CONFORM TO SECTION 1082 OF THE STANDARD SPECIFICATIONS.

ALL TIMBER DIMENSIONS SHOWN ON THE PLANS ARE NOMINAL DIMENSIONS. DESIGN IS BASED ON ACTUAL DRESSED DIMENSIONS.

PRE-DRILL HOLES IN TIMBER MEMBERS RECEIVING BOLTS TO ELIMINATE SPLITTING. PRE-DRILL HOLES FOR SCREWS AS NECESSARY TO PREVENT SPLITTING IN TIMBER MEMBERS.

DESIGN LOADS:

LIVE LOAD:

TRUCK LOAD:

THIS BRIDGE WAS DESIGNED FOR:

HS20
GVWR = 72,000 LBS
NUMBER OF AXLES: 3
AXLE WEIGHTS:
GAWR FRONT = 8,000 LBS
GAWR INTERMEDIATE = 32,000 LBS
GAWR REAR = 32,000 LBS

EV2
GVWR = 57,500 LBS
NUMBER OF AXLES: 2
AXLE WEIGHTS:
GAWR FRONT = 24,000 LBS
GAWR REAR = 33,500 LBS

EV3
GVWR = 86,000 LBS
NUMBER OF AXLES: 3
AXLE WEIGHTS:
GAWR FRONT = 24,000 LBS
GAWR INTERMEDIATE = 31,000 LBS
GAWR REAR = 31,000 LBS

LIVE LOAD FACTORS:

HS-20 = 1.30
EV2 = 1.3
EV3 = 1.3

LIVE LOAD FACTORS LOAD RATING:

HS-20 = 1.35
EV2 = 1.0
EV3 = 1.0

MULTIPLE PRESENCE FACTOR:

MPF = 1.0

LANE LOAD:

NO LANE LOAD WAS APPLIED.

IMPACT:

DYNAMIC IMPACT FOR WOOD/TIMBER COMPONENTS IS ZERO. DYNAMIC IMPACT FACTOR FOR ALL OTHER COMPONENTS IS 33%.

DEAD LOADS:

WEARING SURFACES SHALL NOT BE ALLOWED.

WEIGHT OF TIMBER = 40 PCF.

DESIGN ASSUMPTIONS/PARAMETERS:

SUPERSTRUCTURE WILL BE SIX LINES OF I-BEAMS.

BRIDGE IS SINGLE SPAN.

BRIDGE WIDTH = 12'-0" OUT TO OUT.

GENERAL NOTES:

THIS BRIDGE IS DESIGNED IN ACCORDANCE WITH THE NORTH CAROLINA DEPARTMENT OF TRANSPORTATION (NCDOT) "STRUCTURES MANAGEMENT UNIT MANUAL", DATED 6/15/23, 2024 NCDOT IN-KIND TIMBER BRIDGE REPLACEMENT PROGRAM, AND THE AASHTO "LRFD BRIDGE DESIGN SPECIFICATIONS", 9th EDITION.

THESE DRAWINGS ARE INTENDED ONLY FOR USAGE IN THE INSTALLATION OF SINGLE SPAN I-BEAM BRIDGES FOR PRIVATE DRIVEWAYS IN COUNTIES AS LISTED IN THE CONTRACT DOCUMENTS BY NORTH CAROLINA OFFICE OF EMERGENCY MANAGEMENT IN RESPONSE TO THE DAMAGE CAUSED BY HURRICANE HELENE.

BRIDGE CONSTRUCTION, WORKMANSHIP, AND MATERIALS SHALL BE IN ACCORDANCE WITH THE NCDOT "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES", 2024 EDITION.

THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.

IT IS ASSUMED THAT THERE ARE NO UTILITY CONFLICTS. THE CONTRACTOR SHALL INVESTIGATE THE PRESENCE OF UTILITIES BEFORE COMMENCING WORK.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

FOR ASBESTOS ASSESSMENT, SEE SPECIAL PROVISIONS.

ALL DIMENSIONS SHOWN ARE HORIZONTAL OR VERTICAL, UNLESS OTHERWISE NOTED.

CONTRACTOR SHALL SET BRIDGE ELEVATIONS SUCH THAT WATER WILL DRAIN AND NOT POND ON THE BRIDGE DECK AND MINIMUM LONGITUDINAL GRADE SHALL BE 0.5% AND MAXIMUM GRADE SHALL BE 6%.

FOR PILE-SUPPORTED END BENTS, PLACE APPROACH EMBANKMENT (CORE MATERIAL) PRIOR TO PILE INSTALLATION.

THIS BRIDGE HAS BEEN DESIGNED FOR ADTT < 100.

EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON SHEET EC-01 ARE FOR GENERAL GUIDANCE ONLY AND REPRESENT MINIMUM REQUIREMENTS. THE CONTRACTOR SHALL PROVIDE, INSTALL, AND MAINTAIN ALL REQUIRED EROSION AND SEDIMENT CONTROL MEASURES IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS, CONTRACT DOCUMENTS, AND APPLICABLE REGULATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MODIFYING THESE MEASURES AND PROVIDING ANY ADDITIONAL DEVICES NECESSARY TO ACCOUNT FOR ACTUAL SITE CONDITIONS, INCLUDING GROUNDWATER CONDITIONS AND WEATHER EVENTS, AND TO PREVENT SEDIMENT FROM LEAVING THE PROJECT SITE.

ALL REFERENCES WITHIN THESE PLANS TO "STANDARD SPECIFICATIONS" OR "NCDOT SPECIFICATIONS" SHALL BE GOVERNED BY THE NCDOT "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" DATED JANUARY 2024.

TRAFFIC CONTROL SHALL BE PROVIDED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, INCLUDING THE SPECIAL PROVISIONS, AND IN CONFORMANCE WITH THE NCDOT STANDARD SPECIFICATIONS, NCDOT ROADWAY STANDARD DRAWINGS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING, INSTALLING, AND MAINTAINING ALL TRAFFIC CONTROL DEVICES NECESSARY TO SAFELY CONDUCT THE WORK AND PROTECT THE TRAVELING PUBLIC.

MATERIAL PROPERTIES:

CONCRETE: MINIMUM COMPRESSIVE STRENGTH, f'c = 3,000 psi (CLASS A)

STRUCTURAL STEEL: AASHTO M270, GRADE 50.




WELDS: SMAW, 70 KSI ELECTRODES PER NCDOT STANDARD SPECIFICATIONS.


ANCHOR BOLTS: ASTM F1554, GRADE 55.

BOLTS SHALL CONFORM TO ASTM F3125, GRADE A325. PROVIDE GALVANIZED NUTS AND WASHERS COMPATIBLE WITH THE BOLTS.


TIMBER: ALL TIMBER & DIMENSIONAL LUMBER SHALL BE NO. 1 VISUALLY GRADED, SOUTHERN PINE WITH REFERENCE DESIGN VALUES OF: Fbo = 1.35 ksi AND Fvo = 0.175 ksi OR GREATER.

ELASTOMER IN ALL BEARINGS SHALL BE 50 DUROMETER HARDNESS WITH A SHEAR MODULUS OF 0.110 KSI.

DESIGN VEHICLES	
REF.#	SCHEMATIC
HS-20	
EV2	
EV3	



DOCUMENT NOT CONSIDERED
FINAL UNLESS ALL
SIGNATURES COMPLETED



Johnson, Mirmiran, & Thompson Inc.
108 Asheville Commerce Parkway
Candler, NC, 28715
License No: C-3097

DWN. BY: BC
CHKD. BY: CFW
DES. EGR. OF RECORD: GFW
DATE: 04/2026
DATE: 04/2026
DATE: 04/2026

NORTH CAROLINA OFFICE OF
EMERGENCY MANAGEMENT

PRIVATE DRIVEWAY
BRIDGE STANDARDS

SINGLE LANE STEEL BEAM BRIDGE
TIMBER DECK

GENERAL NOTES

REVISIONS						SHEET NO. S-13
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS 13
1			3			
2			4			