

DF18313.2012023.PR

Aug 19, 2026

DM00470

TIP NO

0.052 MILES

FED AID NO HELENE

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 110316 ON SR-1962 (ROSE CARSWELL RD) OVER UT TO DOUBLE BRANCH

				TAG CONTRACTING INC		KEMP SIGMON CONSTRUCTION CO INC		MOUNTAIN CREEK CONTRACTORS INC	
				OLD FORT, NC		CLAREMONT, NC		MT PLEASANT, SC	
ROADWAY ITEMS									
0001	0000100000-N	800	MOBILIZATION	Lump Sum		79,000.00		41,000.00	50,000.00
0002	0043000000-N	226	GRADING (226)	Lump Sum		65,000.00		60,000.00	148,850.00
0003	0050000000-E	226	SUPP CLEARING & GRUBBING	1 ACR	1,000.00	1,000.00	100.00	100.00	2,500.00
0004	0057000000-E	226	UNDERCUT EXCAVATION	225 CY	5.00	1,125.00	10.00	2,250.00	15,750.00
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	240 CY	15.00	3,600.00	20.00	4,800.00	7,200.00
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY	30.00	6,000.00	10.00	2,000.00	15,000.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	200 SY	2.00	400.00	1.00	200.00	1,032.00
0008	0318000000-E	300	FND CONDIT MATL MINOR STRS	9 TON	35.00	315.00	10.00	90.00	765.00
0009	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	26 SY	3.00	78.00	1.00	26.00	100.10
0010	0335200000-E	305	15" DRAINAGE PIPE	16 LF	90.00	1,440.00	100.00	1,600.00	2,400.00
0011	0343000000-E	310	15" SIDE DRAIN PIPE	56 LF	90.00	5,040.00	100.00	5,600.00	8,400.00
0012	0995000000-E	340	PIPE REMOVAL	54 LF	5.00	270.00	10.00	540.00	1,350.00
0013	0996000000-N	350	PIPE CLEAN OUT	1 EA	100.00	100.00	2,500.00	2,500.00	2,500.00
0014	1099500000-E	505	SHALLOW UNDERCUT	50 CY	5.00	250.00	20.00	1,000.00	5,309.50
0015	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	100 TON	20.00	2,000.00	35.00	3,500.00	7,933.00
0016	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	150 SY	2.00	300.00	3.00	450.00	433.50
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON	36.00	1,800.00	40.00	2,000.00	3,750.00
0018	1330000000-E	607	INCIDENTAL MILLING	175 SY	25.00	4,375.00	36.00	6,300.00	8,750.00
0019	1491000000-E	610	ASP CONC BASE CRS B25.0C	210 TON	190.00	39,900.00	110.00	23,100.00	23,100.00
0020	1519000000-E	610	ASP CONC SURF CRS S9.5B	150 TON	190.00	28,500.00	178.00	26,700.00	26,700.00
0021	1575000000-E	620	ASP FOR PLANT MIX	20 TON	700.00	14,000.00	948.00	18,960.00	18,960.00
0022	2022000000-E	815	SUBDRAIN EXCAVATION	22 CY	7.00	154.00	10.00	220.00	939.40
0023	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	100 SY	2.00	200.00	2.00	200.00	567.00
0024	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	17 CY	36.00	612.00	85.00	1,445.00	2,711.16
0025	2044000000-E	815	6" PERF SUBDRN PIPE	100 LF	15.00	1,500.00	10.00	1,000.00	2,112.00
0026	2070000000-N	815	SUBDRN PIPE OUTLET	1 EA	300.00	300.00	400.00	400.00	1,000.00
0027	2077000000-E	815	6" OUTLET PIPE	6 LF	50.00	300.00	50.00	300.00	300.00
0028	2286000000-N	840	MASNRY DRAINAGE STRUCT	1 EA	2,500.00	2,500.00	2,500.00	2,500.00	4,500.00
0029	2367000000-N	840	FRAME W/2GRTS 840.29 STD	1 EA	1,500.00	1,500.00	1,250.00	1,250.00	1,400.00
0030	2556000000-E	846	SHOULDER BERM GUTTER	130 LF	200.00	26,000.00	75.00	9,750.00	6,500.00
0031	3030000000-E	862	STL BEAM GUARDRAIL	150 LF	35.00	5,250.00	25.00	3,750.00	3,750.00
0032	3140000000-E	862	25' CLR SPAN GR SECTIONS	2 EA	3,000.00	6,000.00	1,750.00	3,500.00	3,500.00
0033	3150000000-N	862	ADDIT GUARDRAIL POSTS	5 EA	60.00	300.00	11.00	55.00	55.00
0034	3288000000-N	862	GR END TYPE TL-2	4 EA	3,500.00	14,000.00	3,250.00	13,000.00	13,000.00
0035	3628000000-E	876	RIP RAP, CLASS I	165 TON	60.00	9,900.00	75.00	12,375.00	18,150.00
0036	3649000000-E	876	RIP RAP, CLASS B	2 TON	60.00	120.00	100.00	200.00	200.00
0037	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	600 SY	2.00	1,200.00	4.00	2,400.00	3,588.00
0038	4400000000-E	1110	WORK ZONE SIGNS (STAT)	351 SF	10.00	3,510.00	8.00	2,808.00	2,193.75
0039	4410000000-E	1110	WORK ZONE SIGNS (BARR)	89 SF	25.00	2,225.00	8.00	712.00	623.00
0040	4445000000-E	1145	BARRICADES (TYPE III)	40 LF	20.00	800.00	30.00	1,200.00	1,360.00
0041	4810000000-E	1205	PAINT PVMT MARKINGS 4"	2,200 LF	2.00	4,400.00	3.00	6,600.00	1,650.00

DF18313.2012023.PR

Aug 19, 2026

DM00470

TIP NO

0.052 MILES

FED AID NO HELENE

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 110316 ON SR-1962 (ROSE CARSWELL RD) OVER UT TO DOUBLE BRANCH

						TAG CONTRACTING INC	KEMP SIGMON CONSTRUCTION CO	MOUNTAIN CREEK CONTRACTORS			
						OLD FORT, NC	CLAREMONT, NC	MT PLEASANT, SC			
0042	5325600000-E	1510	6" WATER LINE	225	LF	150.00	33,750.00	200.00	45,000.00	250.00	56,250.00
0043	5329000000-E	1510	DI H2O PIPE FITTINGS	300	LB	15.00	4,500.00	20.00	6,000.00	25.00	7,500.00
0044	5540000000-E	1515	6" VALVE	2	EA	3,000.00	6,000.00	3,500.00	7,000.00	5,400.00	10,800.00
0045	5800000000-E	1530	ABANDON 6" UTILITY PIPE	211	LF	20.00	4,220.00	20.00	4,220.00	30.00	6,330.00
0046	6000000000-E	1605	TEMPORARY SILT FENCE	815	LF	3.00	2,445.00	3.50	2,852.50	6.00	4,890.00
0047	6006000000-E	1610	EROS CONTRL STONE CL A	100	TON	20.00	2,000.00	20.00	2,000.00	100.00	10,000.00
0048	6009000000-E	1610	EROS CONTRL STONE CL B	185	TON	20.00	3,700.00	20.00	3,700.00	105.00	19,425.00
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	140	TON	20.00	2,800.00	20.00	2,800.00	100.00	14,000.00
0050	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	1,500.00	3,750.00	1,800.00	4,500.00	2,200.00	5,500.00
0051	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	5.00	1,000.00	5.00	1,000.00	10.00	2,000.00
0052	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	900.00	900.00	1,800.00	1,800.00	2,000.00	2,000.00
0053	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	15.00	3,000.00	10.00	2,000.00	25.00	5,000.00
0054	6029000000-E	SP	SAFETY FENCE	860	LF	2.00	1,720.00	3.00	2,580.00	6.00	5,160.00
0055	6030000000-E	1630	SILT EXCAVATION	320	CY	5.00	1,600.00	1.00	320.00	10.42	3,334.40
0056	6036000000-E	1631	MATTING FOR EROS CONTROL	9,400	SY	2.00	18,800.00	2.00	18,800.00	4.00	37,600.00
0057	6037000000-E	1629	COIR FIBER MAT	704	SY	5.00	3,520.00	10.00	7,040.00	15.00	10,560.00
0058	6042000000-E	1632	1/4" HARDWARE CLOTH	120	LF	4.00	480.00	8.00	960.00	6.00	720.00
0059	6069000000-E	1638	STILLING BASINS	205	CY	5.00	1,025.00	40.00	8,200.00	30.00	6,150.00
0060	6070000000-N	1639	SPECIAL STILLING BASINS	2	EA	500.00	1,000.00	500.00	1,000.00	750.00	1,500.00
0061	6071002000-E	1642	FLOCCULANT	25	LB	200.00	5,000.00	10.00	250.00	1.00	25.00
0062	6071010000-E	1642	WATTLE	60	LF	5.00	300.00	12.00	720.00	15.00	900.00
0063	6071030000-E	1640	COIR FIBER BAFFLE	135	LF	5.00	675.00	10.00	1,350.00	15.00	2,025.00
0064	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	1,500.00	4,500.00	3,200.00	9,600.00	4,500.00	13,500.00
0065	6087000000-E	1660	MOWING	3	ACR	1,500.00	4,500.00	500.00	1,500.00	500.00	1,500.00
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	5.00	250.00	5.00	250.00	10.00	500.00
0067	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,000.00	250.00	1,800.00	450.00	1,500.00	375.00
0068	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	5.00	250.00	5.00	250.00	10.00	500.00
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	1,000.00	1,250.00	1,800.00	2,250.00	1,500.00	1,875.00
0070	6111000000-E	SP	IMPERVIOUS DIKE	210	LF	286.00	60,060.00	100.00	21,000.00	104.80	22,008.00
0071	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	50.00	500.00	75.00	750.00	250.00	2,500.00
0072	6117000000-N	1675	RESPONSE FOR EROS CONTROL	75	EA	15.00	1,125.00	25.00	1,875.00	200.00	15,000.00
0073	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	500.00	500.00	1,500.00	1,500.00	586.45	586.45
0074	6120000000-E	SP	CULVERT DIVERSION CHANNEL	335	CY	20.00	6,700.00	50.00	16,750.00	37.18	12,455.30
0075	6126000000-E	SP	STREAMBANK REFORESTATION	0.1	ACR	5,000.00	500.00	5,000.00	500.00	4,831.00	483.10
0076	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	2	EA	500.00	1,000.00	1,000.00	2,000.00	411.81	823.62
CULVERT ITEMS											
0077	8056000000-N	402	REMOV EXIST STR ***** CULV (402) (13+08.00 -L-)	Lump Sum		100,000.00		150,000.00		30,000.00	
0078	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum		3,000.00		1,500.00		1,250.00	

TIP NO

0.052 MILES

FED AID NOHELENE

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 110316 ON SR-1962 (ROSE CARSWELL RD) OVER UT TO DOUBLE BRANCH

				TAG CONTRACTING INC		KEMP SIGMON CONSTRUCTION CO		MOUNTAIN CREEK CONTRACTORS	
				OLD FORT, NC		CLAREMONT, NC		MT PLEASANT, SC	
0079	8130000000-N	414	BOX CULV EXCAV @ ***** (13+08.00 -L-)	Lump Sum		50,000.00		45,000.00	75,000.00
0080	8133000000-E	414	FND CONDIT MAT, BOX CULV	73 TON	50.00	3,650.00	80.00	5,840.00	7,300.00
0081	8196000000-E	420	CLASS A CONCRETE (CULV)	120.9 CY	900.00	108,810.00	1,200.00	145,080.00	163,215.00
0082	8245000000-E	425	REINF STEEL (CULVERT)	14,564 LB	2.00	29,128.00	2.00	29,128.00	35,681.80
CONTRACT TOTAL					TOTAL	813,422.00	TOTAL	825,696.50	1,015,105.08
ROADWAY ITEMS					SUB-TOTAL	518,834.00	SUB-TOTAL	449,148.50	702,658.28
CULVERT ITEMS					SUB-TOTAL	294,588.00	SUB-TOTAL	376,548.00	312,446.80

DF18313.2012023.PR

Aug 19, 2026

DM00470

TIP NO

0.052 MILES

FED AID NO HELENE

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 110316 ON SR-1962 (ROSE CARSWELL RD) OVER UT TO DOUBLE BRANCH

				BELUCA LLC		BIRDSALL EXCAVATION AND CONSTRUCTION LLC		
				GREENSBORO, NC		CLARKSVILLE, NY		
ROADWAY ITEMS								
0001	0000100000-N	800	MOBILIZATION	Lump Sum		100,000.00	89,949.06	
0002	0043000000-N	226	GRADING (226)	Lump Sum		98,000.00	120,000.00	
0003	0050000000-E	226	SUPP CLEARING & GRUBBING	1	ACR	3,500.00	3,500.00	18,000.00
0004	0057000000-E	226	UNDERCUT EXCAVATION	225	CY	5.00	1,125.00	45.00
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	240	CY	5.00	1,200.00	45.00
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200	CY	10.00	2,000.00	55.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	200	SY	2.00	400.00	7.00
0008	0318000000-E	300	FND CONDIT MATL MINOR STRS	9	TON	40.00	360.00	80.00
0009	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	26	SY	6.00	156.00	8.00
0010	0335200000-E	305	15" DRAINAGE PIPE	16	LF	95.00	1,520.00	175.00
0011	0343000000-E	310	15" SIDE DRAIN PIPE	56	LF	125.00	7,000.00	100.00
0012	0995000000-E	340	PIPE REMOVAL	54	LF	50.00	2,700.00	55.00
0013	0996000000-N	350	PIPE CLEAN OUT	1	EA	1,250.00	1,250.00	1,500.00
0014	1099500000-E	505	SHALLOW UNDERCUT	50	CY	5.00	250.00	55.00
0015	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	100	TON	30.00	3,000.00	50.00
0016	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	150	SY	3.00	450.00	6.00
0017	1220000000-E	545	INCIDENTAL STONE BASE	50	TON	50.00	2,500.00	60.00
0018	1330000000-E	607	INCIDENTAL MILLING	175	SY	35.00	6,125.00	40.00
0019	1491000000-E	610	ASP CONC BASE CRS B25.0C	210	TON	350.00	73,500.00	118.27
0020	1519000000-E	610	ASP CONC SURF CRS S9.5B	150	TON	178.00	26,700.00	164.88
0021	1575000000-E	620	ASP FOR PLANT MIX	20	TON	948.00	18,960.00	1,065.63
0022	2022000000-E	815	SUBDRAIN EXCAVATION	22	CY	20.00	440.00	45.00
0023	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	100	SY	6.00	600.00	6.00
0024	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	17	CY	75.00	1,275.00	80.00
0025	2044000000-E	815	6" PERF SUBDRN PIPE	100	LF	35.00	3,500.00	30.00
0026	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	250.00	250.00	750.00
0027	2077000000-E	815	6" OUTLET PIPE	6	LF	50.00	300.00	35.00
0028	2286000000-N	840	MASNRY DRAINAGE STRUCT	1	EA	2,500.00	2,500.00	3,500.00
0029	2367000000-N	840	FRAME W/2GRTS 840.29 STD	1	EA	2,350.00	2,350.00	2,500.00
0030	2556000000-E	846	SHOULDER BERM GUTTER	130	LF	125.00	16,250.00	45.00
0031	3030000000-E	862	STL BEAM GUARDRAIL	150	LF	31.00	4,650.00	25.00
0032	3140000000-E	862	25' CLR SPAN GR SECTIONS	2	EA	2,500.00	5,000.00	1,750.00
0033	3150000000-N	862	ADDIT GUARDRAIL POSTS	5	EA	10.00	50.00	11.00
0034	3288000000-N	862	GR END TYPE TL-2	4	EA	3,500.00	14,000.00	3,250.00
0035	3628000000-E	876	RIP RAP, CLASS I	165	TON	150.00	24,750.00	70.00
0036	3649000000-E	876	RIP RAP, CLASS B	2	TON	135.00	270.00	100.00
0037	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	600	SY	8.00	4,800.00	6.00
0038	4400000000-E	1110	WORK ZONE SIGNS (STAT)	351	SF	22.00	7,722.00	8.00
0039	4410000000-E	1110	WORK ZONE SIGNS (BARR)	89	SF	8.00	712.00	8.00
0040	4445000000-E	1145	BARRICADES (TYPE III)	40	LF	60.00	2,400.00	30.00
0041	4810000000-E	1205	PAINT PVMT MARKINGS 4"	2,200	LF	1.50	3,300.00	1.50

TIP NO

0.052 MILES

FED AID NO HELENE

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 110316 ON SR-1962 (ROSE CARSWELL RD) OVER UT TO DOUBLE BRANCH

						BELUCA LLC GREENSBORO, NC	BIRDSALL EXCAVATION AND CONSTRUCTION LLC CLARKSVILLE, NY	
0042	5325600000-E	1510	6" WATER LINE	225	LF	310.00	69,750.00	180.00 40,500.00
0043	5329000000-E	1510	DI H2O PIPE FITTINGS	300	LB	22.00	6,600.00	15.00 4,500.00
0044	5540000000-E	1515	6" VALVE	2	EA	4,000.00	8,000.00	3,500.00 7,000.00
0045	5800000000-E	1530	ABANDON 6" UTILITY PIPE	211	LF	35.00	7,385.00	20.00 4,220.00
0046	6000000000-E	1605	TEMPORARY SILT FENCE	815	LF	6.00	4,890.00	8.00 6,520.00
0047	6006000000-E	1610	EROS CONTRL STONE CL A	100	TON	15.00	1,500.00	52.00 5,200.00
0048	6009000000-E	1610	EROS CONTRL STONE CL B	185	TON	15.00	2,775.00	50.00 9,250.00
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	140	TON	15.00	2,100.00	52.00 7,280.00
0050	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	800.00	2,000.00	1,000.00 2,500.00
0051	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	2.00	400.00	6.00 1,200.00
0052	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	500.00	500.00	1,500.00 1,500.00
0053	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	1.00	200.00	18.00 3,600.00
0054	6029000000-E	SP	SAFETY FENCE	860	LF	0.50	430.00	4.00 3,440.00
0055	6030000000-E	1630	SILT EXCAVATION	320	CY	0.50	160.00	35.00 11,200.00
0056	6036000000-E	1631	MATting FOR EROS CONTROL	9,400	SY	0.50	4,700.00	2.50 23,500.00
0057	6037000000-E	1629	COIR FIBER MAT	704	SY	5.00	3,520.00	9.00 6,336.00
0058	6042000000-E	1632	1/4" HARDWARE CLOTH	120	LF	4.00	480.00	10.00 1,200.00
0059	6069000000-E	1638	STILLING BASINS	205	CY	15.00	3,075.00	60.00 12,300.00
0060	6070000000-N	1639	SPECIAL STILLING BASINS	2	EA	1,000.00	2,000.00	4,000.00 8,000.00
0061	6071002000-E	1642	FLOCCULANT	25	LB	5.00	125.00	15.00 375.00
0062	6071010000-E	1642	WATTLE	60	LF	5.00	300.00	15.00 900.00
0063	6071030000-E	1640	COIR FIBER BAFFLE	135	LF	5.00	675.00	18.00 2,430.00
0064	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	3,000.00	9,000.00	2,500.00 7,500.00
0065	6087000000-E	1660	MOWING	3	ACR	450.00	1,350.00	500.00 1,500.00
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	2.00	100.00	8.00 400.00
0067	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	500.00	125.00	2,000.00 500.00
0068	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	2.00	100.00	8.00 400.00
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	500.00	625.00	1,200.00 1,500.00
0070	6111000000-E	SP	IMPERVIOUS DIKE	210	LF	65.00	13,650.00	232.14 48,749.40
0071	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	25.00	250.00	50.00 500.00
0072	6117000000-N	1675	RESPONSE FOR EROS CONTROL	75	EA	0.01	0.75	950.00 71,250.00
0073	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	4,000.00	4,000.00	2,000.00 2,000.00
0074	6120000000-E	SP	CULVERT DIVERSION CHANNEL	335	CY	15.00	5,025.00	74.40 24,924.00
0075	6126000000-E	SP	STREAMBANK REFORESTATION	0.1	ACR	800.00	80.00	10,000.00 1,000.00
0076	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	2	EA	3,500.00	7,000.00	1,500.00 3,000.00
						CULVERT ITEMS		
0077	8056000000-N	402	REMOV EXIST STR ***** CULV (402) (13+08.00 -L-)	Lump Sum		150,000.00		70,000.00
0078	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum		50,000.00		5,000.00

TIP NO

0.052 MILES

FED AID NOHELENE

GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 110316 ON SR-1962 (ROSE CARSWELL RD) OVER UT TO DOUBLE BRANCH

						BELUCA LLC	BIRDSALL EXCAVATION AND CONSTRUCTION LLC		
						GREENSBORO, NC	CLARKSVILLE, NY		
0079	8130000000-N	414	BOX CULV EXCAV @ ***** (13+08.00 -L-)	Lump Sum		43,000.00		65,000.00	
0080	8133000000-E	414	FND CONDIT MAT, BOX CULV	73	TON	85.00	6,205.00	75.00	5,475.00
0081	8196000000-E	420	CLASS A CONCRETE (CULV)	120.9	CY	2,000.00	241,800.00	1,800.00	217,620.00
0082	8245000000-E	425	REINF STEEL (CULVERT)	14,564	LB	3.00	43,692.00	5.66	82,432.24
CONTRACT TOTAL						TOTAL	1,143,382.75	TOTAL	1,198,740.00
ROADWAY ITEMS						SUB-TOTAL	608,685.75	SUB-TOTAL	753,212.76
CULVERT ITEMS						SUB-TOTAL	534,697.00	SUB-TOTAL	445,527.24
BIDDERS IN ORDER						CONTRACT TOTAL			
TAG CONTRACTING INC						1	813,422.00		
KEMP SIGMON CONSTRUCTION CO INC						2	825,696.50		
MOUNTAIN CREEK CONTRACTORS INC						3	1,015,105.08		
BELUCA LLC						4	1,143,382.75		
BIRDSALL EXCAVATION AND CONSTRUCTION LLC						5	1,198,740.00		