

BP13.R020.3

TIP NO

FED AID NO STATE FUNDED

REPLACE BRIDGE 036

OVER MIDDLEFORK CREEK ON SR-1515 (BUCKNER BRANCH RD)

				BUCKEYE BRIDGE LLC	KEMP SIGMON CONSTRUCTION CO	WHALEY CONSTRUCTION LLC			
				CANTON, NC	CLAREMONT, NC		KODAK, TN		
ROADWAY ITEMS									
0001	0000100000-N	800	MOBILIZATION	Lump Sum	67,900.00	67,000.00			572,000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	16,000.00	15,000.00			45,000.00
0003	0043000000-N	226	GRADING (226)	Lump Sum	85,000.00	250,000.00			75,000.00
0004	0050000000-E	226	SUPP CLEARING & GRUBBING	1 ACR	1.00	100.00	100.00	15,000.00	15,000.00
0005	0057000000-E	226	UNDERCUT EXCAVATION	400 CY	28.00	11,200.00	10.00	75.00	30,000.00
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	135 CY	20.00	2,700.00	25.00	75.00	10,125.00
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY	90.00	36,000.00	10.00	75.00	30,000.00
0008	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	400 SY	5.00	2,000.00	2.00	23.00	9,200.00
0009	0199000000-E	SP	TEMPORARY SHORING	150 SF	335.00	50,250.00	500.00	500.00	75,000.00
0010	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1 BRIDGE APPROACH FILL, STATION 13+22 -L-	Lump Sum	24,000.00	15,000.00			40,000.00
0011	0318000000-E	300	FND CONDIR MATL MINOR STRS	10 TON	100.00	400.00	40.00	108.00	1,080.00
0012	0321000000-E	300	FND CONDIR GEOTEXTILE (4A)	20 SY	5.00	100.00	2.00	62.00	1,240.00
0013	0335200000-E	305	15" DRAINAGE PIPE	60 LF	105.00	6,300.00	125.00	130.00	7,800.00
0014	0995000000-E	340	PIPE REMOVAL	42 LF	15.00	630.00	10.00	35.00	1,470.00
0015	1099500000-E	505	SHALLOW UNDERCUT	100 CY	20.00	2,000.00	10.00	98.50	9,850.00
0016	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	200 TON	50.00	10,000.00	25.00	83.50	16,700.00
0017	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	300 SY	5.00	1,500.00	3.00	23.00	6,900.00
0018	1121000000-E	520	AGGREGATE BASE COURSE	25 TON	90.00	2,250.00	60.00	90.00	2,250.00
0019	1220000000-E	545	INCIDENTAL STONE BASE	50 TON	90.00	4,500.00	30.00	90.00	4,500.00
0020	1330000000-E	607	INCIDENTAL MILLING	230 SY	24.00	5,520.00	20.00	54.00	12,420.00
0021	1491000000-E	610	ASP CONC BASE CRS B25.0C	160 TON	270.00	43,200.00	225.00	300.00	48,000.00
0022	1519000000-E	610	ASP CONC SURF CRS S9.5B	220 TON	270.00	59,400.00	225.00	330.00	72,600.00
0023	1575000000-E	620	ASP FOR PLANT MIX	25 TON	750.00	18,750.00	750.00	1,080.00	27,000.00
0024	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY	35.00	1,568.00	10.00	80.00	3,584.00
0025	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200 SY	5.00	1,000.00	2.00	23.00	4,600.00
0026	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6 CY	90.00	3,024.00	75.00	65.00	2,184.00
0027	2044000000-E	815	6" PERF SUBDRN PIPE	200 LF	20.00	4,000.00	5.00	25.00	5,000.00
0028	2070000000-N	815	SUBDRN PIPE OUTLET	1 EA	250.00	250.00	250.00	7,850.00	7,850.00
0029	2077000000-E	815	6" OUTLET PIPE	6 LF	40.00	240.00	30.00	200.00	1,200.00
0030	3045000000-E	862	SBGR SHOP CURVED	112.5 LF	26.50	2,981.25	26.50	32.00	3,600.00
0031	3150000000-N	862	ADDIT GUARDRAIL POSTS	5 EA	11.00	55.00	11.00	14.00	70.00
0032	3180000000-N	862	GR ANCHOR TYPE ***** (III SHOP CURVED)	4 EA	2,850.00	11,400.00	2,850.00	3,420.00	13,680.00
0033	3195000000-N	862	GR END TYPE AT-1	2 EA	1,100.00	2,200.00	1,100.00	1,320.00	2,640.00
0034	3288000000-N	862	GR END TYPE TL-2	4 EA	3,200.00	12,800.00	3,200.00	3,840.00	15,360.00
0035	3380000000-E	862	TEMP STL BM GUARDRAIL	200 LF	36.50	7,300.00	36.50	44.00	8,800.00
0036	3389150000-N	862	TEMP GDRL END UNITS ***** (TL-2)	4 EA	1,850.00	7,400.00	1,800.00	2,220.00	8,880.00
0037	3628000000-E	876	RIP RAP, CLASS I	13 TON	200.00	2,600.00	150.00	100.00	1,300.00
0038	3635000000-E	876	RIP RAP, CLASS II	12 TON	200.00	2,400.00	150.00	100.00	1,200.00

BP13.R020.3

TIP NO

FED AID NO STATE FUNDED

REPLACE BRIDGE 036

OVER MIDDLEFORK CREEK ON SR-1515 (BUCKNER BRANCH RD)

				BUCKEYE BRIDGE LLC		KEMP SIGMON CONSTRUCTION CO INC		WHALEY CONSTRUCTION LLC			
				CANTON, NC		CLAREMONT, NC		KODAK, TN			
0039	3649000000-E	876	RIP RAP, CLASS B	2	TON	200.00	400.00	150.00	300.00	455.00	910.00
0040	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	490	SY	5.00	2,450.00	3.00	1,470.00	23.00	11,270.00
0041	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	130	LF	7.65	994.50	7.50	975.00	9.00	1,170.00
0042	4102000000-N	904	SIGN ERECTION, TYPE E	7	EA	250.00	1,750.00	85.00	595.00	102.00	714.00
0043	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	9	EA	15.00	135.00	20.00	180.00	22.00	198.00
0044	4400000000-E	1110	WORK ZONE SIGNS (STAT)	244	SF	7.30	1,781.20	7.50	1,830.00	9.00	2,196.00
0045	4405000000-E	1110	WORK ZONE SIGNS (PORT)	96	SF	8.55	820.80	8.50	816.00	11.00	1,056.00
0046	4410000000-E	1110	WORK ZONE SIGNS (BARR)	32	SF	8.85	283.20	7.50	240.00	9.00	288.00
0047	4424500000-N	SP	TEMP PORT TRAF SIGNAL SYS	1	EA	30,000.00	30,000.00	50,000.00	50,000.00	58,200.00	58,200.00
0048	4430000000-N	1130	DRUMS	55	EA	50.00	2,750.00	100.00	5,500.00	60.00	3,300.00
0049	4435000000-N	1135	CONES	20	EA	40.00	800.00	20.00	400.00	30.00	600.00
0050	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	25.00	800.00	28.00	896.00	34.00	1,088.00
0051	4455000000-N	1150	FLAGGER	180	DAY	50.00	9,000.00	200.00	36,000.00	550.00	99,000.00
0052	4810000000-E	1205	PAINT PVMT MARKINGS 4"	3,390	LF	0.50	1,695.00	1.75	5,932.50	0.60	2,034.00
0053	4835000000-E	1205	PAINT PVT MKG LINES 24"	40	LF	10.00	400.00	7.50	300.00	12.00	480.00
0054	4850000000-E	1205	LINE REMOVAL 4" WIDE	100	LF	7.00	700.00	2.00	200.00	9.00	900.00
0055	4870000000-E	1205	LINE REMOVAL 24" WIDE	20	LF	15.00	300.00	4.00	80.00	18.00	360.00
0056	6000000000-E	1605	TEMPORARY SILT FENCE	1,410	LF	5.00	7,050.00	3.50	4,935.00	6.00	8,460.00
0057	6006000000-E	1610	EROS CONTRL STONE CL A	75	TON	90.00	6,750.00	25.00	1,875.00	103.00	7,725.00
0058	6009000000-E	1610	EROS CONTRL STONE CL B	135	TON	90.00	12,150.00	25.00	3,375.00	104.00	14,040.00
0059	6012000000-E	1610	SEDIMENT CONTROL STONE	155	TON	90.00	13,950.00	25.00	3,875.00	81.00	12,555.00
0060	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	1,900.00	950.00	1,900.00	950.00	3,038.00	1,519.00
0061	6018000000-E	1620	SEED FOR TEMP SEEDING	100	LB	6.00	600.00	6.00	600.00	6.00	600.00
0062	6021000000-E	1620	FERT FOR TEMP SEEDING	0.5	TON	2,400.00	1,200.00	2,400.00	1,200.00	2,048.00	1,024.00
0063	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	15.00	3,000.00	10.00	2,000.00	65.00	13,000.00
0064	6029000000-E	SP	SAFETY FENCE	2,120	LF	2.00	4,240.00	3.00	6,360.00	5.00	10,600.00
0065	6030000000-E	1630	SILT EXCAVATION	260	CY	20.00	5,200.00	1.00	260.00	20.00	5,200.00
0066	6036000000-E	1631	MATTING FOR EROS CONTROL	6,905	SY	1.95	13,464.75	1.95	13,464.75	3.00	20,715.00
0067	6037000000-E	1629	COIR FIBER MAT	370	SY	4.00	1,480.00	4.00	1,480.00	13.00	4,810.00
0068	6042000000-E	1632	1/4" HARDWARE CLOTH	165	LF	8.00	1,320.00	8.00	1,320.00	12.00	1,980.00
0069	6070000000-N	1639	SPECIAL STILLING BASINS	4	EA	500.00	2,000.00	300.00	1,200.00	5,500.00	22,000.00
0070	6071002000-E	1642	FLOCCULANT	30	LB	12.00	360.00	15.00	450.00	14.00	420.00
0071	6071012000-E	1642	COIR FIBER WATTLE	30	LF	7.00	210.00	12.00	360.00	20.00	600.00
0072	6084000000-E	1660	SEEDING AND MULCHING	0.5	ACR	2,900.00	1,450.00	2,900.00	1,450.00	6,134.00	3,067.00
0073	6087000000-E	1660	MOWING	0.5	ACR	1,000.00	500.00	1,000.00	500.00	474.00	237.00
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	9.00	450.00	9.00	450.00	7.00	350.00
0075	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	2,500.00	625.00	2,500.00	625.00	3,540.00	885.00
0076	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	6.00	300.00	6.00	300.00	11.00	550.00
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5	TON	2,400.00	1,200.00	2,400.00	1,200.00	2,654.00	1,327.00
0078	6111000000-E	SP	IMPERVIOUS DIKE	88	LF	150.00	13,200.00	100.00	8,800.00	225.00	19,800.00
0079	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	75.00	750.00	75.00	750.00	274.00	2,740.00

BP13.R020.3

TIP NO

FED AID NO STATE FUNDED

REPLACE BRIDGE 036

OVER MIDDLEFORK CREEK ON SR-1515 (BUCKNER BRANCH RD)

				BUCKEYE BRIDGE LLC		KEMP SIGMON CONSTRUCTION CO INC		WHALEY CONSTRUCTION LLC			
				CANTON, NC		CLAREMONT, NC		KODAK, TN			
0080	6117000000-N	1675	RESPONSE FOR EROS CONTROL	13	EA	400.00	5,200.00	50.00	650.00	730.00	9,490.00
0081	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	500.00	500.00	2,000.00	2,000.00	2,500.00	2,500.00
0082	6126000000-E	SP	STREAMBANK REFORESTATION	0.04	ACR	20,000.00	800.00	20,000.00	800.00	35,000.00	1,400.00
0083	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT STRUCTURE ITEMS	1	EA	500.00	500.00	1,000.00	1,000.00	2,500.00	2,500.00
0084	8021000000-N	SP	REMV EXIST STR ***** BRG (SP) (13+22 -L-)	Lump Sum			85,000.00		125,000.00		75,000.00
0085	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			10,000.00		75,000.00		3,300.00
0086	8121000000-N	412	UNCL STR EXCAV STA ***** (13+22 -L-)	Lump Sum			75,000.00		150,000.00		10,000.00
0087	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	40.5	CY	2,300.00	93,150.00	2,000.00	81,000.00	2,300.00	93,150.00
0088	8210000000-N	422	BRG APPR SLAB ***** (13+22 -L-)	Lump Sum			72,000.00		40,000.00		57,000.00
0089	8217000000-E	425	REINF STEEL (BRIDGE)	4,903	LB	2.50	12,257.50	3.00	14,709.00	3.00	14,709.00
0090	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (HP12X53)	10	EA	2,500.00	25,000.00	2,500.00	25,000.00	2,600.00	26,000.00
0091	8364000000-E	450	HP12X53 PILES	330	LF	68.50	22,605.00	40.00	13,200.00	180.00	59,400.00
0092	8391000000-N	450	STEEL PILE POINTS	10	EA	500.00	5,000.00	175.00	1,750.00	500.00	5,000.00
0093	8394000000-N	450	DYNAMIC PILE TESTING	1	EA	2,200.00	2,200.00	3,000.00	3,000.00	14,600.00	14,600.00
0094	8475000000-E	460	TWO BAR METAL RAIL	95	LF	350.00	33,250.00	175.00	16,625.00	220.00	20,900.00
0095	8517000000-E	460	1'-***X*****CONC PARAPET (1'-2" X 2'-8 3/4")	110	LF	488.00	53,680.00	200.00	22,000.00	280.00	30,800.00
0096	8608000000-E	876	RIP RAP II (2'-0")	235	TON	105.00	24,675.00	80.00	18,800.00	69.00	16,215.00
0097	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	265	SY	5.00	1,325.00	3.00	795.00	23.00	6,095.00
0098	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			3,000.00		2,500.00		5,000.00
0099	8762000000-E	430	3'-0"X 1'-9"PRESTR SLABS	550	LF	315.00	173,250.00	250.00	137,500.00	500.00	275,000.00
CONTRACT TOTAL						TOTAL	1,355,271.20	TOTAL	1,508,692.50	TOTAL	2,259,110.00
ROADWAY ITEMS						SUB-TOTAL	663,878.70	SUB-TOTAL	781,813.50	SUB-TOTAL	1,546,941.00
STRUCTURE ITEMS						SUB-TOTAL	691,392.50	SUB-TOTAL	726,879.00	SUB-TOTAL	712,169.00

BIDDERS IN ORDER

CONTRACT TOTAL

BUCKEYE BRIDGE LLC	1	1,355,271.20
KEMP SIGMON CONSTRUCTION CO INC	2	1,508,692.50
WHALEY CONSTRUCTION LLC	3	2,259,110.00