

BP13.R004.3

Oct 15, 2025

DM00403

TIP NO

0.360 MILES

FED AID NO STATE FUNDED

REPLACE BRIDGE NUMBER 076

OVER PUZZLE CREEK ON SR-1576 (E. CHURCH ST)

KEMP SIGMON CONSTRUCTION  
CO INC  
CLAREMONT, NC

NHM CONSTRUCTORS INC  
ASHEVILLE, NC

ROADWAY ITEMS

0001	0000100000-N	800	MOBILIZATION	Lump Sum			109,000.00		123,000.00
0002	0036000000-E	225	UNDERCUT EXCAVATION	450	CY	10.00	4,500.00	82.00	36,900.00
0003	0043000000-N	226	GRADING (226)	Lump Sum			525,000.00		460,000.00
0004	0050000000-E	226	SUPP CLEARING & GRUBBING	1	ACR	100.00	100.00	1.00	1.00
0005	0195000000-E	265	SELECT GRANULAR MATERIAL	400	CY	20.00	8,000.00	88.00	35,200.00
0006	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	700	SY	2.00	1,400.00	5.50	3,850.00
0007	0199000000-E	SP	TEMPORARY SHORING	230	SF	200.00	46,000.00	87.00	20,010.00
0008	0223000000-E	275	ROCK PLATING	150	SY	125.00	18,750.00	222.00	33,300.00
0009	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE I APPROACH FILL STATION 14+11.00	Lump Sum			20,000.00		26,000.00
0010	0318000000-E	300	FND CONDIT MATL MINOR STRS	10	TON	50.00	500.00	112.00	1,120.00
0011	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	20	SY	2.00	40.00	5.50	110.00
0012	0335200000-E	305	15" DRAINAGE PIPE	20	LF	125.00	2,500.00	165.00	3,300.00
0013	0582000000-E	310	15" CS PIPE CULV 0.064"	20	LF	125.00	2,500.00	165.00	3,300.00
0014	0636000000-E	310	*** CS ELBOW ***** THICK (15", 0.064")	2	EA	750.00	1,500.00	667.00	1,334.00
0015	0995000000-E	340	PIPE REMOVAL	40	LF	10.00	400.00	27.50	1,100.00
0016	1099500000-E	505	SHALLOW UNDERCUT	100	CY	10.00	1,000.00	40.00	4,000.00
0017	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	200	TON	20.00	4,000.00	67.00	13,400.00
0018	1121000000-E	520	AGGREGATE BASE COURSE	3	TON	250.00	750.00	110.00	330.00
0019	1220000000-E	545	INCIDENTAL STONE BASE	50	TON	50.00	2,500.00	72.00	3,600.00
0020	1330000000-E	607	INCIDENTAL MILLING	200	SY	25.00	5,000.00	28.00	5,600.00
0021	1491000000-E	610	ASP CONC BASE CRS B25.0C	370	TON	175.00	64,750.00	205.00	75,850.00
0022	1519000000-E	610	ASP CONC SURF CRS S9.5B	480	TON	175.00	84,000.00	205.00	98,400.00
0023	1575000000-E	620	ASP FOR PLANT MIX	50	TON	670.00	33,500.00	850.00	42,500.00
0024	2022000000-E	815	SUBDRAIN EXCAVATION	45	CY	10.00	450.00	44.00	1,980.00
0025	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200	SY	2.00	400.00	5.50	1,100.00
0026	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34	CY	75.00	2,550.00	78.00	2,652.00
0027	2044000000-E	815	6" PERF SUBDRN PIPE	200	LF	10.00	2,000.00	28.00	5,600.00
0028	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	350.00	350.00	278.00	278.00
0029	2077000000-E	815	6" OUTLET PIPE	6	LF	50.00	300.00	110.00	660.00
0030	2286000000-N	840	MASNRY DRAINAGE STRUCT	1	EA	2,500.00	2,500.00	4,200.00	4,200.00
0031	2367000000-N	840	FRAME W/2GRTS 840.29 STD	1	EA	1,250.00	1,250.00	1,350.00	1,350.00
0032	2556000000-E	846	SHOULDER BERM GUTTER	16	LF	100.00	1,600.00	115.00	1,840.00
0033	3030000000-E	862	STL BEAM GUARDRAIL	450	LF	24.00	10,800.00	27.00	12,150.00
0034	3045000000-E	862	SBGR SHOP CURVED	50	LF	25.00	1,250.00	28.00	1,400.00
0035	3150000000-N	862	ADDIT GUARDRAIL POSTS	5	EA	11.00	55.00	11.00	55.00
0036	3195000000-N	862	GR END TYPE AT-1	1	EA	950.00	950.00	1,200.00	1,200.00
0037	3215000000-N	862	GR ANCHOR TYPE III	4	EA	2,350.00	9,400.00	2,800.00	11,200.00
0038	3288000000-N	862	GR END TYPE TL-2	5	EA	3,200.00	16,000.00	3,600.00	18,000.00
0039	3360000000-E	863	REMOVE EXISTING GUARDRAIL	300	LF	1.00	300.00	1.10	330.00

BP13.R004.3

Oct 15, 2025

DM00403

TIP NO

0.360 MILES

FED AID NO STATE FUNDED  
 REPLACE BRIDGE NUMBER 076  
 OVER PUZZLE CREEK ON SR-1576 (E. CHURCH ST)

				KEMP SIGMON CONSTRUCTION CO INC CLAREMONT, NC			NHM CONSTRUCTORS INC ASHEVILLE, NC		
0040	3380000000-E	862	TEMP STL BM GUARDRAIL	200	LF	9.25	1,850.00	10.50	2,100.00
0041	3389150000-N	862	TEMP GDRL END UNITS ***** (TL-2)	4	EA	2,000.00	8,000.00	2,500.00	10,000.00
0042	3628000000-E	876	RIP RAP, CLASS I	363	TON	65.00	23,595.00	100.00	36,300.00
0043	3649000000-E	876	RIP RAP, CLASS B	27	TON	65.00	1,755.00	100.00	2,700.00
0044	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	694	SY	2.00	1,388.00	5.60	3,886.40
0045	4400000000-E	1110	WORK ZONE SIGNS (STAT)	16	SF	8.50	136.00	14.50	232.00
0046	4410000000-E	1110	WORK ZONE SIGNS (BARR)	36	SF	7.50	270.00	10.00	360.00
0047	4430000000-N	1130	DRUMS	71	EA	125.00	8,875.00	55.00	3,905.00
0048	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	30.00	960.00	30.00	960.00
0049	4810000000-E	1205	PAINT PVMT MARKINGS 4"	11,990	LF	0.55	6,594.50	0.50	5,995.00
0050	4835000000-E	1205	PAINT PVT MKG LINES 24"	20	LF	5.00	100.00	5.00	100.00
0051	6000000000-E	1605	TEMPORARY SILT FENCE	2,660	LF	4.50	11,970.00	5.00	13,300.00
0052	6006000000-E	1610	EROS CONTRL STONE CL A	40	TON	85.00	3,400.00	78.00	3,120.00
0053	6009000000-E	1610	EROS CONTRL STONE CL B	75	TON	30.00	2,250.00	78.00	5,850.00
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	285	TON	30.00	8,550.00	56.00	15,960.00
0055	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	1,500.00	3,750.00	2,670.00	6,675.00
0056	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	6.00	1,200.00	4.85	970.00
0057	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	1,800.00	1,800.00	550.00	550.00
0058	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	10.00	2,000.00	60.00	12,000.00
0059	6029000000-E	SP	SAFETY FENCE	260	LF	4.00	1,040.00	5.00	1,300.00
0060	6030000000-E	1630	SILT EXCAVATION	100	CY	5.00	500.00	70.00	7,000.00
0061	6036000000-E	1631	MATTING FOR EROS CONTROL	1,675	SY	1.95	3,266.25	3.90	6,532.50
0062	6037000000-E	1629	COIR FIBER MAT	100	SY	4.00	400.00	22.00	2,200.00
0063	6042000000-E	1632	1/4" HARDWARE CLOTH	220	LF	4.00	880.00	4.25	935.00
0064	6070000000-N	1639	SPECIAL STILLING BASINS	6	EA	500.00	3,000.00	2,000.00	12,000.00
0065	6071002000-E	1642	FLOCCULANT	50	LB	1.00	50.00	1.10	55.00
0066	6071012000-E	1642	COIR FIBER WATTLE	170	LF	15.00	2,550.00	16.50	2,805.00
0067	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	2,350.00	7,050.00	4,500.00	13,500.00
0068	6087000000-E	1660	MOWING	3	ACR	300.00	900.00	275.00	825.00
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	7.00	350.00	5.50	275.00
0070	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	2,100.00	525.00	1,000.00	250.00
0071	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	6.00	300.00	3.50	175.00
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5	TON	1,900.00	2,850.00	1,350.00	2,025.00
0073	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	65.00	650.00	275.00	2,750.00
0074	6117000000-N	1675	RESPONSE FOR EROS CONTROL	25	EA	200.00	5,000.00	275.00	6,875.00
0075	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,500.00	1,500.00	4,000.00	4,000.00
0076	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	1	EA	1,000.00	1,000.00	200.00	200.00

BP13.R004.3

Oct 15, 2025

DM00403

TIP NO

0.360 MILES

FED AID NO STATE FUNDED

REPLACE BRIDGE NUMBER 076

OVER PUZZLE CREEK ON SR-1576 (E. CHURCH ST)

			KEMP SIGMON CONSTRUCTION CO INC CLAREMONT, NC			NHM CONSTRUCTORS INC ASHEVILLE, NC		
STRUCTURE ITEMS								
0077	8035000000-N	402	REMV EXIST STR ***** BRG (402) (14+11 -L-)	Lump Sum		125,000.00		36,500.00
0078	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum		50,000.00		850.00
0079	8105520000-E	411	3'-0" DRILLD PIER IN SOIL	76.5	LF	1,000.00	76,500.00	835.00 63,877.50
0080	8105620000-E	411	3'-0" DRILLD PIER NO SOIL	21	LF	2,000.00	42,000.00	2,200.00 46,200.00
0081	8111200000-E	411	PERM STL CASING FOR 3' PIER	57	LF	236.25	13,466.25	475.00 27,075.00
0082	8115000000-N	411	CSL TESTING	1	EA	2,500.00	2,500.00	2,950.00 2,950.00
0083	8121000000-N	412	UNCL STR EXCAV STA ***** (14+11.00 -L-)	Lump Sum		5,000.00		12,800.00
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	67.9	CY	1,250.00	84,875.00	1,800.00 122,220.00
0085	8210000000-N	422	BRG APPR SLAB ***** (14+11.00 -L-)	Lump Sum		30,000.00		55,000.00
0086	8217000000-E	425	REINF STEEL (BRIDGE)	17,007	LB	2.00	34,014.00	1.75 29,762.25
0087	8238000000-E	425	SPIRAL COL REINF STL BRG	1,842	LB	2.50	4,605.00	5.50 10,131.00
0088	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (12X53)	14	EA	1,500.00	21,000.00	1,500.00 21,000.00
0089	8364000000-E	450	HP12X53 PILES	425	LF	50.00	21,250.00	65.00 27,625.00
0090	8391000000-N	450	STEEL PILE POINTS	14	EA	160.00	2,240.00	185.00 2,590.00
0091	8394000000-N	450	DYNAMIC PILE TESTING	2	EA	2,000.00	4,000.00	2,600.00 5,200.00
0092	8505000000-E	460	VERT CONC BARRIER RAIL	280	LF	185.00	51,800.00	230.00 64,400.00
0093	8608000000-E	876	RIP RAP II (2'-0")	239	TON	70.00	16,730.00	90.00 21,510.00
0094	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	265	SY	3.00	795.00	11.00 2,915.00
0095	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum		5,000.00		10,000.00
0096	8753100000-E	430	3'-0"X 2'-9" PRESTR BOX BEAM	1,540	LF	350.00	539,000.00	430.00 662,200.00
CONTRACT TOTAL						TOTAL	2,235,875.00	TOTAL 2,469,671.65
ROADWAY ITEMS						SUB-TOTAL	1,106,099.75	SUB-TOTAL 1,244,865.90
STRUCTURE ITEMS						SUB-TOTAL	1,129,775.25	SUB-TOTAL 1,224,805.75

BIDDERS IN ORDER

CONTRACT TOTAL

KEMP SIGMON CONSTRUCTION CO INC

1

2,235,875.00

NHM CONSTRUCTORS INC

2

2,469,671.65