

BP13.R023.3

Oct 15, 2025

DM00448

TIP NO

0.096 MILES

FED AID NO STATE FUNDED

REPLACE BRIDGE 087

OVER CHANDLER CREEK ON SR-1347 (CHANDLER CREEK RD)

KEMP SIGMON CONSTRUCTION
CO INC
CLAREMONT, NC

ROADWAY ITEMS

0001	0000100000-N	800	MOBILIZATION	Lump Sum			108,000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum			20,000.00
0003	0043000000-N	226	GRADING (226)	Lump Sum			395,000.00
0004	0050000000-E	226	SUPP CLEARING & GRUBBING	1	ACR	100.00	100.00
0005	0057000000-E	226	UNDERCUT EXCAVATION	400	CY	10.00	4,000.00
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20	CY	25.00	500.00
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	400	CY	10.00	4,000.00
0008	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	400	SY	2.00	800.00
0009	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1 BRIDGE APPROACH FILL, STATION 13+46 -L-	Lump Sum			15,000.00
0010	0318000000-E	300	FND CONDIT MATL MINOR STRS	30	TON	40.00	1,200.00
0011	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	70	SY	2.00	140.00
0012	0576000000-E	310	*** CS PIPE CULV ***** (78", 0.168")	48	LF	1,000.00	48,000.00
0013	0995000000-E	340	PIPE REMOVAL	48	LF	150.00	7,200.00
0014	0996000000-N	350	PIPE CLEAN OUT	1	EA	2,500.00	2,500.00
0015	1099500000-E	505	SHALLOW UNDERCUT	100	CY	15.00	1,500.00
0016	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	200	TON	30.00	6,000.00
0017	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	300	SY	5.00	1,500.00
0018	1121000000-E	520	AGGREGATE BASE COURSE	50	TON	60.00	3,000.00
0019	1220000000-E	545	INCIDENTAL STONE BASE	50	TON	50.00	2,500.00
0020	1275000000-E	600	PRIME COAT	50	GAL	25.00	1,250.00
0021	1297000000-E	607	MILL ASP PVMT ***** DTH (1-1/4")	470	SY	10.00	4,700.00
0022	1330000000-E	607	INCIDENTAL MILLING	115	SY	20.00	2,300.00
0023	1491000000-E	610	ASP CONC BASE CRS B25.0C	80	TON	215.00	17,200.00
0024	1519000000-E	610	ASP CONC SURF CRS S9.5B	160	TON	205.00	32,800.00
0025	1575000000-E	620	ASP FOR PLANT MIX	15	TON	675.00	10,125.00
0026	2022000000-E	815	SUBDRAIN EXCAVATION	44.8	CY	10.00	448.00
0027	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	200	SY	2.00	400.00
0028	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	33.6	CY	80.00	2,688.00
0029	2044000000-E	815	6" PERF SUBDRN PIPE	200	LF	10.00	2,000.00
0030	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	350.00	350.00
0031	2077000000-E	815	6" OUTLET PIPE	6	LF	50.00	300.00
0032	3030000000-E	862	STL BEAM GUARDRAIL	12.5	LF	24.00	300.00
0033	3045000000-E	862	SBGR SHOP CURVED	25	LF	25.00	625.00
0034	3150000000-N	862	ADDIT GUARDRAIL POSTS	5	EA	11.00	55.00
0035	3180000000-N	862	GR ANCHOR TYPE ***** (B-83 SHOP CURVED)	1	EA	2,750.00	2,750.00
0036	3180000000-N	862	GR ANCHOR TYPE ***** (III SHOP CURVED)	3	EA	2,950.00	8,850.00

BP13.R023.3

TIP NO

0.096 MILES

FED AID NO STATE FUNDED

REPLACE BRIDGE 087

OVER CHANDLER CREEK ON SR-1347 (CHANDLER CREEK RD)

KEMP SIGMON CONSTRUCTION
CO INC
CLAREMONT, NC

0037	3195000000-N	862	GR END TYPE AT-1	3	EA	950.00	2,850.00
0038	3288000000-N	862	GR END TYPE TL-2	1	EA	3,250.00	3,250.00
0039	3380000000-E	862	TEMP STL BM GUARDRAIL	62.5	LF	10.00	625.00
0040	3389150000-N	862	TEMP GDRL END UNITS ***** (TL-2)	4	EA	2,000.00	8,000.00
0041	3628000000-E	876	RIP RAP, CLASS I	50	TON	75.00	3,750.00
0042	3635000000-E	876	RIP RAP, CLASS II	37	TON	75.00	2,775.00
0043	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	690	SY	3.00	2,070.00
0044	4400000000-E	1110	WORK ZONE SIGNS (STAT)	250	SF	15.00	3,750.00
0045	4405000000-E	1110	WORK ZONE SIGNS (PORT)	138	SF	10.00	1,380.00
0046	4410000000-E	1110	WORK ZONE SIGNS (BARR)	48	SF	9.00	432.00
0047	4424500000-N	SP	TEMP PORT TRAF SIGNAL SYS	1	EA	50,000.00	50,000.00
0048	4430000000-N	1130	DRUMS	30	EA	125.00	3,750.00
0049	4435000000-N	1135	CONES	15	EA	30.00	450.00
0050	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	36.00	3,456.00
0051	4455000000-N	1150	FLAGGER	180	DAY	250.00	45,000.00
0052	4810000000-E	1205	PAINT PVMT MARKINGS 4"	3,254	LF	0.50	1,627.00
0053	4835000000-E	1205	PAINT PVT MKG LINES 24"	68	LF	3.00	204.00
0054	4870000000-E	1205	LINE REMOVAL 24" WIDE	34	LF	2.00	68.00
0055	5325400000-E	1510	4" WATER LINE	141	LF	250.00	35,250.00
0056	5329000000-E	1510	DI H2O PIPE FITTINGS	395	LB	20.00	7,900.00
0057	5538000000-E	1515	4" VALVE	1	EA	2,000.00	2,000.00
0058	5835000000-E	1540	*** ENCASMENT PIPE (8")	50	LF	300.00	15,000.00
0059	6000000000-E	1605	TEMPORARY SILT FENCE	1,100	LF	3.00	3,300.00
0060	6006000000-E	1610	EROS CONTRL STONE CL A	95	TON	25.00	2,375.00
0061	6009000000-E	1610	EROS CONTRL STONE CL B	30	TON	60.00	1,800.00
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	160	TON	25.00	4,000.00
0063	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	1,600.00	800.00
0064	6018000000-E	1620	SEED FOR TEMP SEEDING	100	LB	5.00	500.00
0065	6021000000-E	1620	FERT FOR TEMP SEEDING	0.5	TON	1,800.00	900.00
0066	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	10.00	2,000.00
0067	6029000000-E	SP	SAFETY FENCE	1,060	LF	2.50	2,650.00
0068	6030000000-E	1630	SILT EXCAVATION	70	CY	27.14	1,899.80
0069	6036000000-E	1631	MATting FOR EROS CONTROL	6,250	SY	1.95	12,187.50
0070	6037000000-E	1629	COIR FIBER MAT	350	SY	4.00	1,400.00
0071	6042000000-E	1632	1/4" HARDWARE CLOTH	170	LF	5.00	850.00
0072	6070000000-N	1639	SPECIAL STILLING BASINS	6	EA	250.00	1,500.00
0073	6071012000-E	1642	COIR FIBER WATTLE	30	LF	8.00	240.00
0074	6084000000-E	1660	SEEDING AND MULCHING	0.5	ACR	2,600.00	1,300.00
0075	6087000000-E	1660	MOWING	0.5	ACR	1,000.00	500.00

BP13.R023.3

Oct 15, 2025

DM00448

TIP NO

0.096 MILES

FED AID NO STATE FUNDED

REPLACE BRIDGE 087

OVER CHANDLER CREEK ON SR-1347 (CHANDLER CREEK RD)

KEMP SIGMON CONSTRUCTION
CO INC
CLAREMONT, NC

0076	609000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	8.00	400.00
0077	609300000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	2,200.00	550.00
0078	609600000-E	1662	SEED FOR SUPP SEEDING	50	LB	5.00	250.00
0079	610800000-E	1665	FERTILIZER TOPDRESSING	0.5	TON	2,100.00	1,050.00
0080	611100000-E	SP	IMPERVIOUS DIKE	160	LF	100.00	16,000.00
0081	611450000-N	1667	SPECIALIZED HAND MOWING	10	MHR	75.00	750.00
0082	611700000-N	1675	RESPONSE FOR EROS CONTROL	13	EA	50.00	650.00
0083	611750000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,500.00	1,500.00
0084	612600000-E	SP	STREAMBANK REFORESTATION	0.07	ACR	15,000.00	1,050.00
0085	613200000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	1	EA	1,000.00	1,000.00
0086	613300000-N	SP	GENERIC EROSION CONTROL ITEM (LS) STREAM RESTORATION	Lump Sum			10,000.00
STRUCTURE ITEMS							
0087	803500000-N	402	REMV EXIST STR ***** BRG (402) (13+46 -L-)	Lump Sum			750,000.00
0088	806500000-N	SP	ASBESTOS ASSESSMENT	Lump Sum			140,000.00
0089	809600000-E	450	PILE EXCAVATION IN SOIL	45	LF	450.00	20,250.00
0090	809700000-E	450	PILE EXCAVATION NOT IN SOIL	50.7	LF	450.00	22,815.00
0091	812100000-N	412	UNCL STR EXCAV STA ***** (13+46 -L-)	Lump Sum			5,000.00
0092	818200000-E	420	CLASS A CONCRETE (BRIDGE)	55.5	CY	1,250.00	69,375.00
0093	821000000-N	422	BRG APPR SLAB ***** (13+46 -L-)	Lump Sum			30,000.00
0094	821700000-E	425	REINF STEEL (BRIDGE)	6,585	LB	2.50	16,462.50
0095	832820000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (HP12X53)	10	EA	1,500.00	15,000.00
0096	836400000-E	450	HP12X53 PILES	190	LF	50.00	9,500.00
0097	839100000-N	450	STEEL PILE POINTS	10	EA	140.00	1,400.00
0098	839400000-N	450	DYNAMIC PILE TESTING	1	EA	3,000.00	3,000.00
0099	850500000-E	460	VERT CONC BARRIER RAIL	80	LF	280.00	22,400.00
0100	860800000-E	876	RIP RAP II (2'-0")	245	TON	65.00	15,925.00
0101	862200000-E	876	GEOTEXTILE FOR DRAINAGE	270	SY	3.00	810.00
0102	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum			2,500.00
0103	876200000-E	430	3'-0"X 1'-9"PRESTR SLABS	400	LF	250.00	100,000.00
CONTRACT TOTAL						TOTAL	2,197,507.80
ROADWAY ITEMS						SUB-TOTAL	973,070.30
STRUCTURE ITEMS						SUB-TOTAL	1,224,437.50

BIDDERS IN ORDER

CONTRACT TOTAL

KEMP SIGMON CONSTRUCTION CO INC

1

2,197,507.80