STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

INDEX OF SHEETS

1	TITLE SHEET
1A	INDEX OF SHEETS, GENERAL NOTES AND LIST OF STANDARDS
1B	CONVENTIONAL SYMBOLS
1C	SUMMARY OF EARTHWORK, GUARDRAIL, DRAINAGE AND GUTTER
2	TYPICAL SECTIONS
4-5	PLAN SHEETS
6	SURVEY CONTROL SHEET
EC1-EC5	EROSION CONTROL PLANS
TMP1-TMP4	TEMPORARY DETOUR SHEETS
PM1-PM3	PAVEMENT MARKING PLANS
X1-X18	CROSS SECTIONS
P1	PROFILE SHEET
W1-W8	RETAINING WALL DETAILS

GENERAL NOTES

GENERAL NOTES: 2018 SPECIFICATIONS
EFFECTIVE: 01-16-2018

1 CARE SHALL BE TAKEN TO PREVENT DAMAGE TO EXISTING UTILITIES DURING CONSTRUCTION. ANY DAMAGE TO THESE UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

2 THE CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY.

LIST OF ROADWAY STANDARDS

2018 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 16, 2018 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

STD. NO.	TITLE
DIVISION 2 - EARTHWORK	
225.02	Guide for Grading Subgrade
225.04	Method of Obtaining Superelevation
DIVISION 3 - PIPE CULVERTS	
300.01	Method of Pipe Installation
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS	
560.01	Method of Shoulder Construction
DIVISION 7 - CONCRETE PAVEMENTS AND SHOULDERS	
700.05	Tying Proposed Pavement to Existing Pavement
DIVISION 8 - INCIDENTALS	
840.17	Concrete Drop Inlet - 12" thru 72" Pipe
840.22	Frames and Wide Slote Sag Grates
846.01	Concrete Curb, Gutter and Curb & Gutter
846.04	Drop Inlet Installation in Shoulder Berm Gutter
862.01	Guardrail Placement
862.02	Guardrail Installation
862.03	Structure Anchor Units
876.02	Guide for Rip Rap at Pipe Outlets
DIVISION 11 - WORK ZONE TRAFFIC CONTROL	
1101.01	Detail Drawing for Two Way Divided Work Zone Warning Signs
1101.02	Temporary Lane Closures
1101.04	Temporary Shoulder Closures
1101.11	Traffic Control Design Tables
1110.01	Stationary Work Zone Signs
1130.01	Drum
1145.01	Barricades - Type III
1160.01	Temporary Crash Cushion - Reflective End Treatment
1145.01	Barricades - Type III
DIVISION 12 - PAVEMENT MARKINGS, MARKERS AND DELINEATION	
1205.01	Line Types and Offsets
1250.01	Pavement Marking Spacing
1253.01	Snowplowable Raised Pavement Markers
1261.01	Guardrail and Barrier Delineator Spacing
1261.02	Guardrail and Barrier Delineator Types
DIVISION 16 - EROSION CONTROL AND ROADSIDE DEVELOPEMENT	
1605.01	Temporary Silt Fence
1606.01	Special Sediment Control Fence
1632.03	Rock Inlet Sediment Trap Type C
1631.01	Matting Installation
1640.01	Coir Fiber Baffle