PROJECT REFERENCE NO.	SHEET NO.
WBS: 41665.10B	PM-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PAVEMENT MARKING PLAN

GRAHAM COUNTY

LOCATION: ALONG US HWY 129 1.4 MILES EAST OF INTERSECTION WITH US HWY 19/74

TYPE OF WORK: RETENTION WALL, GRADING, DRAINAGE AND PAVING

ROADWAY STANDARD DRAWINGS

2012 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 16, 2018 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

STD. NO.	TITLE
1205.01	Pavement Markings - Line Types and Offsets
1253.01	Snowplowable Raised Pavement Markers

INDEX

PM-1	PAVEMENT MARKING PLAN TITLE SHEET
PM2-PM3	PAVEMENT MARKING DETAILS

PAVEMENT MARKING SCHEDULE

4" WHITE LINE EDGE- ET1

4" CENTER LINE- CL1

CRYSTAL/RED PAVEMENT MARKER-

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR AS DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
US 129	THERMOPLASTIC	SNOWPLOWABLE

PLACE ONE (1) APPLICATION OF THERMOPLASTIC PAVEMENT MARKINGS ON THE FINAL WEARING SURFACE.

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

WBS ELEMENT:41665.10B

CONTRACT: DN00615

09/08/99
30-NOV-2017 09:59
S:\Dist3\Graham\DN00615_NC129 WallFailNear Topton\New folder\NC129 WallFailNear Topton WORKING\dgn\STRIPING\STRIPING_Sgn_SGN.dgn
jechastain AT DIV14-277129