GEOTECHNICAL ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 23481 ENGINEER J. DEAN HARDISTER

DocuSigned by: J. Dean Hardister

6E978DAA0DBD403... DATE

ENGINEER

SIGNATURE DATE

12/18/2017

NOTES:

FOR ANCHORED RETAINING WALLS, SEE ANCHORED RETAINING WALLS PROVISION.

FOR STEEL BEAM GUARDRAIL, SEE ROADWAY PLANS AND SECTION 862 OF THE STANDARD SPECIFICATIONS.

A FENCE IS REQUIRED ON TOP OF RETAINING WALL NO. 1. SEE ROADWAY PLANS FOR FENCE ATTACHMENT DETAILS.

DESIGN RETAINING WALL NO. 1 FOR INTERNAL, EXTERNAL, AND GLOBAL STABILITY.

BEFORE BEGINNING ANCHORED WALL DESIGN FOR RETAINING WALL NO. 1, SURVEY WALL LOCATION AND SUBMIT A REVISED WALL PROFILE VIEW (WALL ENVELOPE) FOR REVIEW. DO NOT START WALL DESIGN OR CONSTRUCTION UNTIL THE REVISED WALL ENVELOPE IS ACCEPTED.

DESIGN RETAINING WALL NO. 1 FOR THE FOLLOWING:
1) H = DESIGN HEIGHT + EMBEDMENT
2) DESIGN LIFE = 100 YEARS
3) IN-SITU ASSUMED MATERIAL PARAMETERS (SOIL):
   UNIT WEIGHT, γ = 120 LB/CF
   FRICTION ANGLE, ϕ = 30 DEGREES
   COHESION, c = 0 LB/SF
4) IN-SITU ASSUMED MATERIAL PARAMETERS (WEATHERED ROCK):
   UNIT WEIGHT, γ = 135 LB/CF
   FRICTION ANGLE, ϕ = 40 DEGREES
   COHESION, c = 50 LB/SF

DESIGN RETAINING WALL NO. 1 FOR A LIVE LOAD (TRAFFIC) SURCHARGE.

DESIGN RETAINING WALL NO. 1 FOR A PIPE EXTENDING UNDER OR THROUGH THE WALL. VERIFY PIPE LOCATION AND ELEVATION BEFORE BEGINNING ANCHORED WALL DESIGN OR CONSTRUCTION.

EXISTING OR FUTURE OBSTRUCTIONS SUCH AS FOUNDATIONS, GUARDRAIL, FENCE OR HANDRAIL POSTS, PAVEMENTS, PIPES, INLETS OR UTILITIES WILL INTERFERE WITH GROUND ANCHORS FOR RETAINING WALL NO. 1.





SECTION A-A

REINFORCED WEB DETAILS

*DETAILS SHOWN ARE FOR 12" H-PILES WITH 6" DIA. GROUND ANCHORS. FOR DIFFERENT DIAMETER ANCHORS, SUBMIT ALTERNATE REINFORCED WEB DETAILS FOR ACCEPTANCE.

TOTAL STRUCTURE QUANTITIES - OPTION #1		
RETAINING WALL NO. 1	6,250	SQ. FT.

PROJECT NO.: 41665.10B

GRAHAM ***COUNTY***

STATION: 13+21.00 -L-

SHEET 2 OF 2

GEOTECHNICAL ENGINEERING UNIT

☐ *EASTERN REGIONAL OFFICE*
☒ *WESTERN REGIONAL OFFICE*
☐ *CONTRACT OFFICE*

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

RETAINING WALL NO. 1
OPTION #1
ANCHORED RETAINING WALL

REVISIONS

NO.	BY	DATE	NO.	BY	DATE
1	-	-	3	-	-
2	-	-	4	-	-

SHEET NO. 3
TOTAL SHEETS 4

PREPARED BY:	D. Hardister, PE	DATE: 12/2017
REVIEWED BY:	E. Williams, PE	DATE: 12/2017