

LOCATION SKETCH



GEOTECHNICAL ENGINEER	ENGINEER
NORTH CAROLINA PROFESSIONAL SEAL 23481 ENGINEER J. DEAN HARDISTER DocuSigned by: J. Dean Hardister C8D9A0AFB2D0403...	
DATE	SIGNATURE DATE

12/18/2017

RETAINING WALL ELEVATIONS

STATION	RIGHT OFFSET	TOP OF WALL	EXISTING GRADE	TOP OF LEVELING PAD	H
13+21	25.80	2677.00	2677.00	2674.00	2.50
13+30	25.89	2677.19	2670.47	2667.84	8.85
13+50	26.17	2677.63	2658.83	2655.16	21.97
13+70	26.57	2678.07	2653.19	2648.69	28.88
13+90	27.62	2678.51	2652.81	2647.81	30.20
14+10	27.62	2678.95	2650.55	2645.55	32.90
14+30	27.45	2679.39	2647.67	2642.67	36.22
14+50	25.51	2679.83	2652.63	2647.63	31.70
14+70	25.71	2680.27	2654.82	2649.82	29.95
14+90	24.27	2680.71	2660.03	2655.03	25.18
15+10	23.99	2681.18	2663.86	2658.86	21.82
15+30	24.22	2681.59	2670.31	2665.31	15.78
15+50	24.73	2682.03	2673.44	2668.44	13.09
15+70	24.50	2682.47	2676.83	2674.83	7.14
15+94.5	24.60	2682.79	2682.79	2679.79	2.50

PROJECT NO.: 41665.10B

GRAHAM ***COUNTY***

STATION: 13+21.00 -L-

SHEET 1 OF 1

PREPARED BY:	D. Hardister, PE	DATE:	12/2017
REVIEWED BY:	E. Williams, PE	DATE:	12/2017

GEOTECHNICAL ENGINEERING UNIT

☐ *EASTERN REGIONAL OFFICE*

☒ *WESTERN REGIONAL OFFICE*

☐ *CONTRACT OFFICE*

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

RETAINING WALL NO. 1

REVISIONS							SHEET NO.
NO.	BY	DATE	NO.	BY	DATE		1
1			3				TOTAL SHEETS
2			4				4