DocuSign Envelope ID: F282C47B-248B-4AF2-8985-7229EC284258

GENERAL NOTES

1. IF THE CONTRACTOR DETERMINES THE CONDITION OF THE EXISTING VCP SEWER MAIN TO BE UNFIT TO INSTALL A DOGHOUSE MANHOLE UPON, AND IF TEMPORARY BYPASS PIPING MUST BE INSTALLED ACROSS THE GSMR TRACKS:
   - A. THE CONTRACTOR SHALL CONTACT GSMR (TOM FALICON, 828-736-4777, RAILDAWG@GTE.NET) AT THE BEGINNING OF CONSTRUCTION AND AT LEAST TWO WEEKS PRIOR TO THE SCHEDULED PLACEMENT OF ANY TEMPORARY BYPASS PIPE ACROSS THE TRACKS.
   - B. THE TEMPORARY BYPASS PIPE SHALL NOT BE INSTALLED ACROSS THE TRACKS AT ANY TIME FROM NOVEMBER 1 - JANUARY 31.
   - C. THE TEMPORARY BYPASS PIPE MAY NOT BE PLACED UNTIL ALL TRAIN OPERATIONS (INCLUDING SWITCHING) HAVE BEEN COMPLETED FOR THE DAY.
   - D. THE TEMPORARY BYPASS PIPE SHALL BE REMOVED ONE HOUR PRIOR TO ANY TRAIN MOVEMENTS ARE SCHEDULED TO TAKE PLACE IN THE MORNING.
   - E. GSMR TRAIN AND MAINTENANCE OF WAY EQUIPMENT SHALL TAKE PRIORITY OF TEMPORARY BYPASS PLACEMENT.
   - F. COST ASSOCIATED WITH TEMPORARY BYPASS PUMPING REQUIRED FOR THE INSTALLATION OF SSMH-01 SHALL BE PAID FOR UNDER PAY ITEM SP-01. THE TEMPORARY BYPASS PUMPING REQUIRED FOR THE INSTALLATION OF SSMH-02 THROUGH SSMH-07 SHALL BE PAID FOR UNDER PAY ITEM SP-02.

Kimley»Horn

PROJECT REFERENCE NO.	SHEET NO.
R-5843	UC-6
DESIGNED BY: DGB	
DRAWN BY: DGB	
CHECKED BY: NDR	
APPROVED BY:	
REVISED:	
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION	
UTILITIES ENGINEERING SEC. PHONE:(919)707-6690 FAX:(919)250-4151	UTILITY CONSTRUCTION PLANS ONLY

NORTH CAROLINA PROFESSIONAL SEAL 036808 ENGINEER DANIEL G. BULA
DocuSigned by: Daniel G. Bula 6B2A1212DD4F5...
7/24/2019

UTILITY CONSTRUCTION



DETAIL 1

SPECIAL LATERAL 'V' DITCH
(Not to Scale)

FROM STA. 10+35 -Y4- TO STA. 10+75 -Y4-