DocuSign Envelope ID: C5BA7BA5-C816-42D7-AB72-45C416F5E31B

PROJECT REFERENCE NO.	SHEET NO.
R-5843	EC-2

Kimley»Horn



GENERAL NOTES

1) CONTRACTOR TO INSTALL ALL EROSION CONTROL MEASURES BEFORE ANY CLEARING AND GRUBBING IS PERFORMED.
2) SILT FENCE TO BE INSTALLED A MINIMUM OF 3' OUTSIDE OF FILL SLOPES.
3) CONTRACTOR TO ENSURE THAT ALL ROADWAYS AND CURB LINES ADJACENT TO THIS PROJECT ARE FREE OF DEBRIS, DIRT, AND EQUIPMENT DURING THE PROJECT DURATION UNLESS DIRECTED BY THE ENGINEER. ANY DAMAGE TO EXISTING CURB AND GUTTER AT CONSTRUCTION ENTRANCES MUST BE REPAIRED AT THE CONTRACTORS EXPENSE.
4) PIPES SHALL BE INSTALLED IN THE DRY (WITH A MIN.3 DAYS OF DRY WEATHER DURING INSTALLATION.) CONTACT ENGINEER AND INSPECTOR 24 HOURS PRIOR TO INSTALLATION OF STORMDRRAIN SYSTEMS.
5) AFTER STORMDRAIN SYSTEMS ARE SET, CONTRACTOR IS TO STABILIZE ALL DISTURBED AREAS AND SLOPES USING EROSION CONTROL MATTING, SEEDING, AND MULCH TO MAINTAIN A VIGOROUS, DENSE, VEGETATIVE COVER.
6) ADDITIONAL MATTING MAY BE USED ON STEEP SLOPES AS DIRECTED BY THE ENGINEER.

LEGEND

CONSTRUCTION LIMIT	C F	LIMITS OF DISTURBANCE (SHADED)	
TEMPORARY SILT FENCE		ROCK INLET SEDIMENT TRAP, TYPE C	
ROCK SILT CHECK, TYPE B		FABRIX INSERT PROTECTION DEVICE	
SPECIAL SEDIMENT CONTROL FENCE / SILT FENCE OUTLET		CONCRETE WASHOUT STRUCTURE	

K:\RAL_Roadway\011036387 - Div 14 (R-5843 Bryson Int)\Erosion Control\Plan Sheets\R-5843_ero_psh_2.dgn

12/14/2021