DocuSign Envelope ID: 90CA573C-A947-4DCB-A157-F8C379D0DA9B

PROJECT REFERENCE NO.	SHEET NO.
R-5843	1.0

TABLE OF OPERATION

SIGNAL FACE	INTERVAL 1	INTERVAL 2
11, 12	ON	OFF
21, 22	OFF	ON
13, 14	ON	OFF
23, 24	OFF	ON

SIGNAL FACE I.D.

All Heads L.E.D.



2 CIRCUIT FLASHER

NOTES

1. Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
2. Flash all Beacons continuously.



STOPLINE AND CROSSWALK LOCATION DIAGRAM



LEGEND

PROPOSED		EXISTING
	Traffic Signal Head	
	Modified Signal Head	N/A
	Sign	
	Pedestrian Signal Head With Push Button & Sign	
	Signal Pole with Guy	
	Signal Pole with Sidewalk Guy	
	Inductive Loop Detector	
	Controller & Cabinet	
	Junction Box	
	2-in Underground Conduit	
N/A	Right of Way	
	Directional Arrow	
N/A	Curb Ramp	
A	"STOP" Sign (R1-1)	A
B	"YIELD TO PEDESTRIAN IN CROSSWALK" Sign	B
C	"STOP FOR PEDESTRIAN IN CROSSWALK" Sign	C
D	Pedestrian Sign (W11-2) Downward Diagonal Arrow (W16-7P)	D

NC Dept of Transportation
Division of Highways
Final Drawing Date: 1/25/2019
DocuSigned by: R. N. Zinser
ITS & Signals Unit

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SIGNAL UPGRADE

Prepared For: Transportation Mobility and Safety Division, Signal Design Section, STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION
750 N.Greenfield Pkwy,Garner,NC 27529

SR 1321 (BRYSON WALK) AT SLOPE STREET

DIVISION 14 SWAIN COUNTY BRYSON CITY

PLAN DATE:	JUNE 2018	REVIEWED BY:	SL PHILLIPS
PREPARED BY:	SP PENNINGTON	REVIEWED BY:	

SCALE 0 20' 1"=20'

REVISIONS	INIT.	DATE

SEAL: NORTH CAROLINA PROFESSIONAL SEAL 032607 ENGINEER STACIE L. PHILLIPS

DocuSigned by: 1/18/2019
SIGNATURE DATE
SIG. INVENTORY NO. 14-1233

PLANS PREPARED IN THE OFFICE OF:
Kimley»Horn
NC License #F-0102
421 Fayetteville Street, Suite 600
Raleigh, NC 27601
(919) 677-2000

1/17/2019 12:00:55 PM susan.pennington K:\RAL_Roadway\011036387 - Div 14 (R-5843 Bryson Int)\Traffic Signal\S4 - Signal Design\14-1233_2018.dgn