PROJECT: EB-5756

CONTRACT: DNI2002273

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	EB-5756	PMP-1	

STATE PROJ. NO.	F. A. PROJ. NO.	DESCRIPTION
50433.3.1	TAP-1729(004)	CONSTRUCTION

PAVEMENT MARKING PLAN
MACON COUNTY

LOCATION: ALONG SR-1729 (DEPOT ST) BEGINNING AT INTERSECTION WITH SR-1667 (WAYAH ST/WELLS GROVE RD) AND ENDING AT INTERSECTION WITH US-441/NC-28 (EAST MAIN ST)

TYPE OF WORK: CURB & GUTTER, SIDEWALK INSTALLATION, DRAINAGE

LIST OF ROADWAY STANDARDS

2018 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 16, 2018 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

STD. NO.	TITLE
DIVISION 12 - PAVEMENT MARKINGS, MARKERS AND DELINEATION	
1205.01	Pavement Markings - Line Types and Offsets
1205.07	Pavement Markings - Pedestrian Crosswalks

GENERAL NOTES

GENERAL NOTES: 2018 SPECIFICATIONS
EFFECTIVE: 01-16-2018

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

1 INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
COOK ST	PAINT	
W DEPOT ST	PAINT	
MILL ST	PAINT	

2 TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

3 REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

INDEX OF SHEETS

PMP-1	PAVEMENT MARKING PLAN TITLE, INDEX OF SHEETS, LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, GENERAL NOTES, FINAL PAVEMENT MARKING SCHEDULE
PMP-2 THRU PMP-8	PAVEMENT MARKING PLAN

PAVEMENT MARKING SCHEDULE

PAVEMENT MARKINGS

SYMBOL	DESCRIPTION
T2	WHITE STOP BAR
T3	WHITE CROSSWALK LINE