PROJECT REFERENCE NO.	SHEET NO.
EB-5756	EC-4
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

**NOTE: ALL EXPOSED AREAS AND SLOPES WILL BE SEEDED AND MULCHED, WATTLES WITH PAM TO BE USED IF DIRECTED BY ENGINEER

Place Matting for Erosion Control on Slope as Work Allows.

Impervious Dike:

The work covered by this section consists of furnishing, installing, maintaining, and removing an impervious dike for the purpose of diverting normal stream flow around the construction site. The Contractor shall construct an impervious dike in such a manner approved by the Engineer. The impervious dike shall not permit seepage of water into the construction site or contribute to siltation of the stream. The impervious dike shall be constructed of an acceptable material in the locations noted on the plans or as directed by the Engineer.

Acceptable materials shall include but not be limited to sheet piles, sandbags, and/or the placement of an acceptable size stone lined with polypropylene or other impervious fabric.

Earth material shall not be used to construct an impervious dike when it is in direct contact with the stream unless vegetation can be established before contact with the stream takes place.

No direct payment shall be made for the work of installation, maintenance, and removal of impervious dike(s) as described in this provision. Payment for such work shall be included in the contract bid price for "Lump Sum for Erosion Control".

REVISIONS

8/17/99

30-AUG-2021132
S:\Dist3\Macon\DN00610_Macon Co. Depot St 2021\dgn\Plans\EC_pages\EB-5756EC-4.dgn
jeckstein A1 DIV(4-31)173