DocuSign Envelope ID: 58703E78-C47E-4378-9DA0-B56087085F61

PROJECT REFERENCE NO.	SHEET NO.
R-5864	2C-1

SECTION A-A
RETAINING WALL

ELEVATION VIEW
OF RETAINING WALL

EMBED CHAIN LINK FENCE 11″ INTO PROPOSED WALL IN A SLEEVE OR BLOCKOUT WITH EPOXY OR CONCRETE GROUT ANCHORING SYSTEM. PRE-MEASURE AND CENTER THE PROPOSED FENCE ON TOP OF WALL FOR POST SPACINGS. IFF DRILLING THE HOLES FOR POSTS, USE A ROTARY DRILL TO DRILL HOLES IN THE CONCRETE. NO IMPACT DRILLS WILL BE ALLOWED, TO ELIMINATE ANY POSSIBILITY OF STRUCTURAL DAMAGES TO THE PROPOSED WALL.

07-01-2019

NORTH CAROLINA PROFESSIONAL SEAL 022966 ENGINEER JOHN HOWERTON

DocuSigned by: John Howerton
873F3D17DCDC45F...

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

CONTRACT STANDARDS AND DEVELOPMENT UNIT
Office 919-707-6950 FAX 919-250-4119

CHAIN LINK FENCE ON RETAINING WALL

ORIGINAL BY: _____ DATE: _____
MODIFIED BY: K.A. KEMPF DATE: SEP. 2017
CHECKED BY: _____ DATE: _____
FILE SPEC.: usr/detials/jhowerton/chain link on retaining wall.dgn

$$$$$$SYSTIME$$$$$$
$$$$$$$$$$$$$$$$DGN$$$$$$$$$$$$$$$$$$$$
$$$$$$USERNAME$$$$