DocuSign Envelope ID: 9833A9B8-8E41-408F-80BE-2E07FCA6FEB8

5/14/99

COMPUTED BY: TB DATE: 6/10/2019
CHECKED BY: DG DATE: 6/10/2019

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
R-5864	3B-1
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SUMMARY OF EARTHWORK

Station L_Alt2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+40.00	0	0
13+60.00	10	1
13+80.00	12	3
14+00.00	18	4
14+20.00	24	4
14+40.00	27	6
14+60.00	32	7
14+80.00	43	6
15+00.00	67	6
15+20.00	103	4
15+40.00	131	2
15+60.00	131	2
15+80.00	131	2
16+00.00	137	3
16+20.00	131	5
16+40.00	124	3
16+60.00	118	2
16+80.00	104	3
17+00.00	83	7
17+20.00	79	6
17+40.00	78	1
17+60.00	66	1
17+80.00	52	2
18+00.00	39	4
18+20.00	29	4
18+40.00	29	3
18+60.00	24	1

SUMMARY OF EARTHWORK

STATION	STATION	UNCL. EXCAV. (CY)	EMBANK. +15% (CY)	BORROW (CY)	WASTE (CY)
13+40 -L-	18+60 -L-	1,822	106		1,822
GRAND TOTALS:		1,822	106		1,822
SAY:		1,830			

NOTE:

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING."

7/1/2019
ar\R-5864\Roadway\Estimate\Row\Earthwork\R5864_rdy_EW_Summary.dgn
Bart