DocuSign Envelope ID: ED997AEC-1384-43B7-918A-A6DBD5B83941

PROJ. REFERENCE NO.	SHEET NO.
17BP.14.R.141	PMP-1

NOTE: TEMPORARY PAVEMENT MARKINGS = 1 COAT OF PAINT
FINAL PAVEMENT MARKINGS = 2 COATS OF PAINT

TEMPORARY PAVEMENT MARKING LINES

SYMBOL	DESCRIPTION	QUANTITY BREAKDOWN	PAY ITEM	TOTAL QUANTITY
PA	WHITE SOLID EDGE LINE (4")	1140 FT	4810000000-E	1140 FT
P2	WHITE STOPBAR (24")	25 FT	4835000000-E	25 FT

REMOVAL OF PAVEMENT MARKING LINES

DESCRIPTION	QUANTITY BREAKDOWN	PAY ITEM	TOTAL QUANTITY
REMOVAL OF PAVEMENT MARKING LINES (4")	840 FT	4850000000-E	840 FT
REMOVAL OF PAVEMENT MARKING LINES (24")	25 FT	4870000000-E	25 FT

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	QUANTITY BREAKDOWN	PAY ITEM	TOTAL QUANTITY
PA	WHITE SOLID EDGE LINE (4")	1068 FT	4810000000-E	2136 FT
PI	YELLOW DOUBLE CENTER LINE (4")	1442 FT	4810000000-E	2884 FT
P8	2 FT. - 6 FT./SP WHITE MINISKIP (4")	20 FT	4810000000-E	40 FT
P2	WHITE STOPBAR (24")	13 FT	4835000000-E	26 FT

30 15 0 30 60
SCALE 1"=30'

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

V&M
Vaughn & Melton
Consulting Engineers
Asheville, North Carolina 828-253-2796
Charlotte, North Carolina 704-357-0488
Tri-Cities, Tennessee 423-467-8401
Knoxville, Tennessee 865-546-5800
Middlesboro, Kentucky 606-248-6600
Spartanburg, South Carolina 864-574-4775
Copyright © 2006 Vaughn & Melton, Inc.
All Rights Reserved

APPROVED DocuSigned by: Lloyd DWayne Brown DATE: 11/17/2016

NORTH CAROLINA PROFESSIONAL SEAL 20119 ENGINEER LLOYD D. BROWN

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
WORK ZONE TRAFFIC CONTROL

PERMANENT PAVEMENT MARKING PLAN

11/17/2016
S:\Transportation\3I235-I2 I4AH Polk 2\Traffic\TrafficControl\TCP\BD-5I4AH_PMP-1.dgn
User:cjmartell