



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

January 20, 2023

ADDENDUM # 1

To: Plan Holders

From: Wes Jamison, P.E. 
Project Development Engineer

RE: **Special Provision Revision and Special Provision Addition**
Contract ID: DN01017
County: Haywood and Jackson
Letting Date: January 24, 2023

The above contract has experienced the following revisions:

Special Provision Revision

On page G-27 of the proposal, remove and replace SP1 R07R SHOULDER RECONSTRUCTION PER SHOUDLER MILE with the attached revised shoulder reconstruction special provision.

Special Provision Addition

On page G-38 of the proposal, after SP12 R05 EXTRUDED THERMOPLASTIC PAVEMENT MARKING THICKNESS, add SP8 R98R ADJUSTMENT OF CATCH BASINS, MANHOLES, DROP INLETS, METER BOXES, AND VALVE BOXES. See special provision attached to this addendum.

These revisions do not change bid items or the associated quantities.

Thank you for your attention to this matter.

SHOULDER RECONSTRUCTION PER SHOULDER MILE:

(1-18-00) (Rev 9/28/18)

SP1 R07 BR (Rev)

Description

The Contractor shall place graded stone material along the completed edge of pavement and construct shoulders as shown on the sketch map or as directed by the Engineer. The area shall be backfilled and compacted to the satisfaction of the Engineer.

Materials

The graded stone material shall meet the requirements of Section 545-2 of the *2018 Standard Specifications*. Acceptance of graded stone material will be made by visual inspection and approval by the Engineer as being satisfactory.

Construction Methods

Prior to adding the graded stone material, the existing shoulder shall be scarified to provide the proper bond and the placed graded stone material compacted to the satisfaction of the Engineer.

Measurement and Payment

Shoulder Reconstruction will be measured and paid as the actual number of miles of shoulders that have been reconstructed. Measurement will be made along the surface of each shoulder to the nearest 0.01 of a mile. Such price will be full compensation for furnishing the graded stone material, hauling, placing, and compaction.

Payment will be made under:

Pay Item

Shoulder Reconstruction

Pay Unit

Shoulder Mile



DocuSigned by:

02EE828795674A5...
8/11/2021

**ADJUSTMENT OF CATCH BASINS, MANHOLES, DROP INLETS, METER BOXES
AND VALVE BOXES:**

(11-15-22)

858

SP8 R98R

Revise the *2018 Standard Specifications* as follows:

Page 8-38, Article 858-4 MEASUREMENT AND PAYMENT, lines 10-11, delete and replace the fifth paragraph with the following:

Where any catch basin, drop inlet, manhole, meter box or valve box is adjusted more than once because of milling operations, each adjustment will be measured and paid.