



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

January 21, 2022

ADDENDUM # 1

To: Plan Holders

From: Josh Deyton, P.E. 
Project Team Lead

RE: **Pay Item Addition and Special Provision Addition**
Contract ID: DN00488
County: Clay
Letting Date: January 25, 2022

The above contract has experienced the following revisions:

1. Pay Item Addition

On page T-3 of the proposal, after item 0053 REFORESTATION, add the following pay item:

0069 588800000-E SP GENERIC UTILITY ITEM (6" STEEL ENCASMENT) 86 LF

See attached revised page T-3 showing this addition.

2. Special Provision Addition

After the Roadway Special Provisions section of the proposal, add Utilities Construction Special Provisions section and the Steel Encasement Special Provision. See attached page UC-1.

Please access ebs addenda files on Bid Express®.

Thank you for your attention to this matter.

County : Clay

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500		
					SY	
0039	6037000000-E	SP	COIR FIBER MAT	100		
					SY	
0040	6042000000-E	1632	1/4" HARDWARE CLOTH	55		
					LF	
0041	6070000000-N	1639	SPECIAL STILLING BASINS	1		
					EA	
0042	6071020000-E	SP	POLYACRYLAMIDE (PAM)	15		
					LB	
0043	6084000000-E	1660	SEEDING & MULCHING	1		
					ACR	
0044	6087000000-E	1660	MOWING	0.5		
					ACR	
0045	6090000000-E	1661	SEED FOR REPAIR SEEDING	50		
					LB	
0046	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25		
					TON	
0047	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50		
					LB	
0048	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75		
					TON	
0049	6111000000-E	SP	IMPERVIOUS DIKE	205		
					LF	
0050	6114500000-N	1667	SPECIALIZED HAND MOWING	3		
					MHR	
0051	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13		
					EA	
0052	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2		
					EA	
0053	6123000000-E	1670	REFORESTATION	0.1		
					ACR	
0069	5888000000-E	SP	GENERIC UTILITY ITEM 6" STEEL ENCASEMENT	87		
					LF	

STRUCTURE ITEMS

0054	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** 13+10.00-L-	Lump Sum	L.S.	
------	--------------	-----	--	----------	------	--



434 Fayetteville Street
Suite 1500
Raleigh, NC 27601
Main: 919-836-4040
www.wsp.com

Project: 17BP.14.R.169

UC-1

County: Clay

PROJECT SPECIAL PROVISIONS
Utility Construction

Revise the 2018 Standard Specifications as follows:

Page 15-18; Section 1540. The steel encasement pipe for the steel well sleeve at approximately station 11+90 -L- shall meet the requirements of Article 1036-4(B). No other materials may be used.

Measurement and Payment:

Steel Encasement shall be measured from end to end and paid at the contract unit price per linear foot. Such price and payments will be full compensation for all labor, materials, excavation, backfilling and any incidentals necessary to complete the work as required.

Pay Item:

Generic Utility Item (6" Steel Encasement Pipe)

Pay Unit

Linear Foot



DocuSigned by:
Thomas Harris
F9EBC057AC1A4EF...

1/20/2022