DocuSign Envelope ID: 8D7B612F-ED1F-457E-90C3-84CCF18144AC

PROJ. REFERENCE NO.	SHEET NO.
17BP.14.R.169	PMP-01

PAVEMENT MARKING SCHEDULE

P1 PAINT WHITE EDGELINE (4″, 2 COATS)
P13 PAINT YELLOW DOUBLE CENTER LINE (4″, 2 COATS)

ROADWAY STANDARD DRAWINGS

1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - DIVIDED AND UNDIVIDED ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1261.01	GUARDRAIL AND BARRIER DELINEATOR SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATOR TYPES
1262.01	GUARDRAIL END DELINEATION
1264.01	OBJECT MARKERS
1264.02	PLACEMENT OF OBJECT MARKERS

GENERAL NOTES

THE FOLLOWING NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD	MARKING	MARKER
ALL ROADS	PAINT	NONE

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.
D) ALL PAVEMENT MARKINGS ARE EXISTING UNLESS OTHERWISE NOTED.
E) RELOCATE ALL EXISTING SIGNS AS REQUIRED BY THE ENGINEER.



PAVEMENT MARKING QUANTITIES

P1	PAY ITEM LENGTH = 1000 LF	TOTAL QUANTITY = 2000 LF
P13	PAY ITEM LENGTH = 500 LF	TOTAL QUANTITY = 2000 LF

APPROVED: Richard A. Odiyski
DocuSigned by:
BF5B7EA00AF814E4
DATE: 11/23/2021
SEAL

NORTH CAROLINA PROFESSIONAL SEAL 037467 ENGINEER RICHARD A. ODIYSKI

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
WORK ZONE TRAFFIC CONTROL

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PAVEMENT MARKING PLAN