

8/17/99


REVISIONS

01-DEC-2025 14:27
R:\Roadway\Proj\Nrl173 BRIDGES.Rdj_tup.dgn
harris

PAVEMENT SCHEDULE (FINAL PAVEMENT SCHEDULE)	
C1	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
E1	PROP. APPROX. 5½" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 627 LBS. PER SQ. YD.
J1	8" ABC
T	EARTH MATERIAL

NOTE: ALL PAVEMENT SLOPES ARE 1:1 UNLESS LABELED OTHERWISE.

CULVERTS NO. 430187, 430188, 430189 & 430190

PROJECT REFERENCE NO.	SHEET NO.
BPI4.R002	2A-2
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	PAVEMENT DESIGN ENGINEER
	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

RS&H 8521 SIX FORKS ROAD, SUITE 400
RALEIGH, NC 27615
NC FIRM LICENSE No: F-0493

