

PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.14.05.10881, 2026CPT.14.05.20881	12	

THERMOPLASTIC AND PAINT QUANTITIES

												4413000000-E	4457000000-N	4688000000-E		4709000000-E	4725000000-E			4890000000-E		4895000000-N		
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)(WHITE)	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)(YELLOW)	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)(WHITE)	THERMO LT ARROW 90 M	THERMO STR ARROW 90 M	THERMO RT ARROW 90 M	WHITE HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES (4", 60 MILS)	YELLOW HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES (4", 60 MILS)	POLYCARBONATE H-SHAPED MARKERS		
								MI	FT					SF	LS	LF	LF	LF	EA	EA	EA	LF	LF	EA
																			26,948				12	
2026CPT.14.05.10881	Transylvania	1	US-64	FROM SR 1135 TO SR 1329	1	2	2WD	2.39	35	12	14.39	247	0.39	14,877	12,071	34	4	4	4			330.00		
TOTAL FOR MAP NO. 1								2.39				247	0.39	14,877	12,071	34	4	4.00	4			330.00		
TOTAL FOR PROJ NO. 2026CPT.14.05.10881								2.39				247	0.39	14,877	12,071	34	4	4.00	4			330.00		
2026CPT.14.05.20881	Transylvania	2	SR-1528 / CRAB CREEK RD	FROM US 64 TO HENDERSON CO	2	2	2WD	4.09	22	0	4.09	459	0.45			30				43,876	43,724	271.00		
TOTAL FOR MAP NO. 2								4.09				459	0.45			30				43,876	43,724	271		
2026CPT.14.05.20881	Transylvania	3	SR-1541 / WILLIAMSON CREEK RD	FROM SR 1540 TO PVMNT CHANGE	2	2	2WD	0.76	21	0	0.76	86	0.06							8,026	8,026			
TOTAL FOR MAP NO. 3								0.76				86	0.06							8,026	8,026			
2026CPT.14.05.20881	Transylvania	4	SR-1309 / SILVERSTEEN RD	FROM SR 1313 TO US 64	2	2	2WD	0.64	20	7.46	8.1	72	0.06							6,758	6,758			
TOTAL FOR MAP NO. 4								0.64				72	0.06							6,758	6,758			
2026CPT.14.05.20881	Transylvania	5	SR-1130 / POWELL TOWN RD	FROM SR 1107 TO EOM	3	2	2WD	0.35	18	0	0.35	40	0.04							1,848	3,696			
TOTAL FOR MAP NO. 5								0.35				40	0.040							1,848	3,696			
TOTAL FOR PROJ NO. 2026CPT.14.05.20881								5.84				657	0.610			30				60,508	62,204	271.00		
																						122,712		
GRAND TOTAL								8.23				904	1.000	14,877	12,071	64	4	4.00	4	60,508	62,204	601.00		
																						122,712		