

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

J.R. "JOEY" HOPKINS
SECRETARY

January 23, 2025

ADDENDUM #2

Contract No. DN01085

TIP No.: N/A Federal Aid No.: Helene

WBS Element: 18314.1045046, 18314.1045118

County: Henderson

Description: Emergency Repair: Drainage, Erosion Control, Grade, Pave, Pavement

Marking, Traffic Control, Wall At Various Locations Along SR 1171

And SR 2155

Letting Date: January 28, 2025

Plan Holders

Content Summary: Pre-Bid Meeting Minutes and Sign in Sheet, Addition of

Moratorium provision, Bidder Questions/Concerns, Associated Department Responses, Revision of Summary of Quantities

The above contract has experienced the following revisions:

- 1. Pre-Bid Meeting Minutes
- 2. Pre-Bid Sign in Sheet
- 3. Addition of Provision SP1 G18C CONSTRUCTION MORATORIUM on page G-5 of the Proposal

Question/Concern 1: The drawings for DN01085 show quantities of micropiles on page 4, but there is no detail showing micro piles, please provide a detail to follow for contract DN01085.

Department Response 1: There are no micro piles for this contract, please see revised Summary of Quantities attached.

Question/Concern 2: Are any cross sections or profiles available for the grading?

Department Response 2: No cross-sections are available for this project.

Question/Concern 3: Is there a disturbed area (approximate) of where we will be working?

Department Response 3: For this case, emergency contracts for Hurricane Helene, the goal is to restore the roadway to its original location prior to the hurricane. Those routes the Department solely has state-maintained ROW. The Resident Office Staff can and will assist in defining the work limits during construction – each slope failure is identified as a site that the Resident Office will provide limits to. Please note: limits of the sites and their respective WBSs are listed under the SOQ.

Question/Concern 4: Will the rock embankment subgrade need to be stepped or just placed on the existing slope?

Department Response 4: The rock embankment will need to be placed against the existing slope, which must be cleaned prior to placement. Stepping the subgrade is not required, unless recommended by Geotech.

Question/Concern 5: What type of pipe will be allowed for the drainage pipe?

Department Response 5: While the pay item does not specify which type of drainage pipe, the Department prefers reinforced concrete pipe (RCP) or aluminized pipes. Plastic pipe (HDPE) is not recommended since this is a Federal route.

These revisions do not change bid items or the associated quantities.

There is no ebsx addenda file associated with this addendum.

Thank you for your attention to this matter.

If you have any questions, please contact the Division Proposal Engineer at (828) 331-5200.

Sincerely,

DocuSigned by:

-29BD93927CF24F6...

Jeanette L. White, P.E. Division 14 Project Team Lead



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

JOSH STEIN GOVERNOR J.R. "JOEY" HOPKINS SECRETARY

January 22, 2025

CONTRACT NO.: DN01085

TIP NO.: N/A FEDERAL: Helene

WBS: 18314.1045046, 18314.1045118

COUNTY: Henderson

DESCRIPTION: Emergency Repair: Drainage, Erosion Control, Grade, Pave, Pavement

Marking, Traffic Control, Wall

LOCATION: Various Locations Along SR 1171 and SR 2155

SUBJECT: Mandatory Prebid Meeting

A mandatory Prebid meeting was held on site at the intersection of Hebron Rd. and Finely Cove Rd. for the above reference project from 2:05pm - 3:19pm.

Attendees: Company:

All Contractors are attached.

Patrick Eubanks **NCDOT** Mike Patton RK&K Kevin Mitchell **NCDOT** Kevin Barnett NCDOT Justin Brook **GBI** Lee Sheppard **NCDOT** Reid Whitehead **NCDOT** Dean Hardister NCDOT Donald Pope **NCDOT** Jonathan Almond **NCDOT** Nathan Tanner **NCDOT**

Mailing Address: NC DEPARTMENT OF TRANSPORTATION OFFICE OF RESIDENT ENGINEER 4142 HAYWOOD ROAD MILLS RIVER, NC 28759 Telephone: (828) 891-5367 Fax: (828) 891-8842 Customer Service: 1-877-368-4968 Location: 4142 HAYWOOD ROAD MILLS RIVER, NC 28759

Website: www.ncdot.gov

General Items:

2 Locations on SR 1171 and SR 2155

Contractor's Plan of Operation Start Date:

N/A

Contract Time:

Date of Availability: February 24, 2025 Completion Date: March 27, 2026

Begin Work Date: N/A
Original Calendars to Complete: 397

ICT 1:

Date of Availability: February 24, 2025 Completion Date: September 27, 2025

Begin Work Date: N/A
Original Calendars to Complete: 216

Contract Review:

Patrick Eubanks reviewed the Contract with all parties.

Construction Moratorium:

Trout moratorium has been waived but the bat moratorium is still valid.

Traffic Control:

- Always keep a minimum of one lane of traffic open.
- If full roadway closure is needed, to be discussed with DOT prior as to inform the public with ample notice.

Erosion Control Review:

- Refer to best measurement practices.

Utilities:

- Need to be investigated first to see what they are and what can be done with them.
- Need to be relocated as soon as possible.

General Comments:

- All sites are the same project, however use different WBS elements.
- Hebron needs at least one lane to be open at all times.
- Debris removal needs to be documented.
- Site 499 needs debris clean up.
- If rock is available, then it would be recommended to be used to help stabilize the slope.
- Hebron needs to be safer than the current state for one lane.
- Jurisdictional stream is present.
- Dewatering options need to be further discussed.
- Tree clearing is available until April 1, 2025.
- The slopes on Finley can be changed to a 1.25:1 if Class VII rock embankment is used.
- Chase debris to survey line on ROW or ROE and let the Department know if more is needed.
- Asphalt reestablishment may be needed further up from Finely site.
- Guardrail replacement will be needed throughout Finely site.
- Need to check with the Hydraulics Department for any further assessment.

Questions

- How many sites?
 - o Just Hebron and Finely (2 sites)
- Micro piles needed?
 - o Needs to be taken off summary of quantities.
- What is the haul routes?
 - o Needs to be further investigated, a risk that needs to be in bid.
- One lane on ICT 2?
 - o ICT can be waived where the road is already down to one lane due to failure.

Plan Review:

NCDOT staff and all attending contractors met along Hebron Rd. Scoped and discussed prospected sites, including but not limited to roadway sites # 499 and #1205. Contractors could ask questions, see above for any answered questions. Any unanswered questions to be answered and posted to the contract bid site prior to bidding date.

Patrick Eubanks

Engineering Specialist II

| Construction Meeting 2:05 3:19 | Project Number = | PNO1085 |
|--------------------------------|------------------|---------|
|--------------------------------|------------------|---------|

| NAME | COMPANY | COMPANY ADDRESS | EMAIL | PHONE # | | |
|------------------|-------------------------|--|-----------------------------------|------------------|--|--|
| Joseph Hammonel | Stewarts Grading | 3420 NC 8+65 Germanton NC 27019 | J. Hammond Ostewartschine con | 336-240-8485 | | |
| Caleb Johnson | Site Development Corp | 0. 0 00 00 | asouthards quitedevelopment corp | | | |
| Joh Swort | Tennoca Construction | 1575 Snoty Pt. Huy, Caroller NC 28715 | icshuce terroca, com | 828-808-3151 | | |
| Aden Que | NHM Const | 1121 Bracerd Rd. Asherille UC | arise a phononstratorian | | | |
| Jerry Balled | NHM Const | 121 Brever Rt. Asherille M | 5 billed a num constructors con | 82X-776-7446 | | |
| CHOD WEICH | PAGGISH CONTE | 3370 BINSON CITY RD FEANISIONS | | | | |
| Shay Excher | Eclipse Co | 11554 East Washington Street Chay , Fall, OH WAS | shay@eclipsecoll.com | 336-550-0626 | | |
| Chris Perry | South Mitn Willes | 7398 (SAN HILL RO COUNTY Springs NC | Creary 4997 Wannil, com | 276 971 2220 | | |
| Shawn McClanahan | Natural Innovations | 19629 Story Mila Rd Attingdon VA 24210 | Shawn_d_was@hotmail.com | 774 492-1930 | | |
| Scott Ando son | Adam's CONT | 95 STATE Shed Rd. Rebbrio 118 NC | adams contracting 39 Gmailices | 824-735-3616 | | |
| Landon Bradker | Bradley & Conner) | 224 Good Neighbor's Breverd Nagria | bradlergrading & Yaboo Com | 828.506.2641 | | |
| Clark Morley | CRWLand services | 90 Hodges Creek Dr old Fort NC28762 | criviant services Qymail.com | 8287785259 | | |
| Keun Watson | WATSON Contraty | | Keung Worten Contracting | com 828-421-2423 | | |
| Josh Parker | Arrowhen Contractor | 1192 Tsali Blod Charker N2 8719 | arrowhead contractor/ 11 w grades | | | |
| Day Jones | ste verlament co | P.O.Box 397 cliffede NE 290011 | worthand, 65, to Devilountinger | 11 829-371-2017 | | |
| Thomas Partin | | 55 Grandma + Grandpa W Bakem Grove | Thomas amceals gradings on | | | |
| Tom Edge | Buchanen and Sins, Inc. | P.O. Box 123 Whither NC 28789 | estimator @ bsi-construction. | en 828-497-9720 | | |
| (ad Bucharan I | Buland & Suis The | 11 | Carl @ bsi- Construction, Com | (B2=) 224-1966 | | |
| CHEIS BYERS | Bryants Land | 159 DEPOT ST BUZUSVILLE NIC ZUM/4 | cbyers@bryantldi, coil | 828 329-4690 | | |
| Hunter Hall | Trace and Comp. | TV TITLE TO THE TOTAL TO THE TOTAL T | hunter atrace and company, con | 828-551-1125 | | |
| Austin Patton | | 565 Long Shoals Rd Aden | Austine pattanconstruction | 828-777-0853 | | |
| Brent Adrock | L: Site Contract | + 753 S Allen Rd Flot Pork 28731 | beentadiock@lawing on dson a | n 828-674-4679 | | |
| Cameron Lowing | L'35 site contrador | | Canera Alowingardson, com | 878-243-5854 | | |
| LEE SHEAPHRI) | NCDOT REU FIELD OPS | 693 Mountain Rd Hendersonville, | Inshippard@nedot.gov | 871.644-2197 | | |
| PON AGRESTA | ECLIPSE | 11554 EWASHINGTON ST CHAGAEN FALLS ONTO ME | 123 donny Declipsecolle . com | 440-341-20 00 | | |
| Stephen Jahnes | | DOBOX 1376 Ditts beight 273 | Stephen Ochatham Vil | an 919-704-4442 | | |
| sing Whitson | Bonch Civil | 3635 Ferres Crick Sol marke VA 2461 | Topy Whitester Downson | | | |
| Lewis Terphone | IKECO Construct | in POBEX 337 Handersonville NC | licento were ike construct | 8283376643 | | |
| Nich Daily | I APAL | 1140 soushing park they complex, NE 28715 | Mich. gring @ harrison cc. com | (828) 574-2763 | | |

|) | Construction | n ivieeting Project | Number = | | |
|--------------------------------|--------------|--|---------------------------------------|------------------|--|
| NAME | COMPANY | COMPANY ADDRESS | EMAIL | PHONE # | |
| Zelo Virnelson | Branch Cmil | 36235 Peters Creek Rd Roanoke VA 24019 | Zelgulon. Virrelson Claranencirii-com | 828 - 385 - 2635 | |
| 1 the Patton | | | | | |
| 1. Ke Putten Northan Tanner | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | _ | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | + | |
| | | | | | |

PERMANENT VEGETATION ESTABLISHMENT:

(2-16-12)(Rev. 1-16-24) 104 SPI G16

Establish a permanent stand of the vegetation mixture shown in the contract. During the period between initial vegetation planting and final project acceptance, perform all work necessary to establish permanent vegetation on all erodible areas within the project limits, as well as, in borrow and waste pits. This work shall include erosion control device maintenance and installation, repair seeding and mulching, supplemental seeding and mulching, mowing, and fertilizer topdressing, as directed. All work shall be performed in accordance with the applicable section of the *Standard Specifications*. All work required for initial vegetation planting shall be performed as a part of the work necessary for the completion and acceptance of the Intermediate Contract Time (ICT). Between the time of ICT and Final Project acceptance, or otherwise referred to as the vegetation establishment period, the Department will be responsible for preparing the required National Pollutant Discharge Elimination System (NPDES) inspection records.

Once the Engineer has determined that the permanent vegetation establishment requirement has been achieved at an 80% vegetation density (the amount of established vegetation per given area to stabilize the soil) and no erodible areas exist within the project limits, the Contractor will be notified to remove the remaining erosion control devices that are no longer needed. The Contractor will be responsible for, and shall correct any areas disturbed by operations performed in permanent vegetation establishment and the removal of temporary erosion control measures, whether occurring prior to or after placing traffic on the project.

Payment for Response for Erosion Control, Seeding and Mulching, Repair Seeding, Supplemental Seeding, Mowing, Fertilizer Topdressing, Silt Excavation, and Stone for Erosion Control will be made at contract unit prices for the affected items. Work required that is not represented by contract line items will be paid in accordance with Articles 104-7 or 104-3 of the Standard Specifications. No additional compensation will be made for maintenance and removal of temporary erosion control items.

CONSTRUCTION MORATORIUM:

(1-19-16) SPI G18C

No tree cutting will be allowed from **APRIL 1** through **OCTOBER 15** of any year.

MAJOR CONTRACT ITEMS:

(2-19-02)(Rev. 1-16-24) 104 SPI G28

The following listed items are the major contract items for this contract (see Article 104-5 of the *Standard Specifications*):

| Line# | Description |
|-------|---------------------------------------|
| 0004 | BORROW EXCAVATION |
| 0013 | ASPHALT CONC BASE COURSE, TYPE B25.0C |
| 0016 | SHOULDER BERM GUTTER |

SUMMARY OF QUANTITIES

| | | | | | | | | 0314000000-E | 0222000000-Е | 1077000000-E | 3642000000-E | 3649000000-E |
|------------------------------------|----------------------------------|--------|--------------------------|--------|-------|----------|--------|------------------|--------------------|--------------|----------------|----------------|
| PROJECT NO | COUNTY | MAP NO | ROUTE | LENGTH | WIDTH | BEGIN MP | END MP | SELECT | GEOTEXTILE | #57 STONE | RIP RAP, CLASS | RIP RAP, CLASS |
| | | | | | | | | MATERIAL | FOR ROCK | | Α | В |
| | | | | | | | | CLASS VII | EMBANKMENTS | | | |
| | | | | MI | FT | | | TON | SY | TON | TON | TON |
| 18314.1045046 | Henderson | 1 | SR-1171 / FINLEY COVE RD | 0.08 | 18 | 5.5 | 5.58 | | | | | |
| TOTAL FOR MAP NO. 1 | | | 0.08 | | | | | | | | | |
| TOTAL FOR REQUINO 40044 4045040 | | | 0.08 | | | | | | | | | |
| | TOTAL FOR PROJ NO. 18314.1045046 | | | | | | | | | | | |
| | | | | | - | - | | | | | | |
| 18314.1045118 | Henderson | 2 | SR-2155 / HEBRON RD | 0.08 | 18 | 0.2 | 0.28 | 2,000 | 2,350 | 300 | 300 | 300 |
| TOTAL FOR MAP NO. 2 | | 0.08 | | | | 2,000 | 2,350 | 300 | 300 | 300 | | |
| TOTAL FOR DROLLIO 4004 4 40 454 40 | | | 0.08 | | | | 2,000 | 2,350 | 300 | 300 | 300 | |
| | TOTAL FOR PROJ NO. 18314.1045118 | | | | | | | | | | | |
| | | | | | - | - | | | | | | |
| ODAND TOTAL | | 0.16 | | | | 2,000 | 2,350 | 300 | 300 | 300 | | |
| GRAND TOTAL | | | | | | _ | | | | | | |