

DF18314.2075090

Josh Deyton
CF757BC4CC1041E...

Jan 13, 2026

DN01119

TIP NO

Bid Tab Reports reviewed by:

0.057 MILES

FED AID NO HELENE

Josh Deyton, P.E., Division 14 Bid Review Committee Chair

BRIDGE REPLACEMENT: GRADING, DRAINAGE, PAVING, AND STRUCTURE

Date Reviewed: 01/22/2026

BRIDGE 740112 OVER PACOLET RIVER ON SR 1179 (EDNEY ROAD)

				KEMP SIGMON CONSTRUCTION CO INC CLAREMONT, NC			NHM CONSTRUCTORS INC ASHEVILLE, NC		WRIGHT BROTHERS CIVIL CONSTRUCTION LLC CHARLESTON, TN	
ROADWAY ITEMS										
0001	0000100000-N	800	MOBILIZATION	Lump Sum		81,000.00		102,000.00		125,000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		12,500.00		54,540.00		37,800.00
0003	0008000000-E	200	SUPP CLEARING & GRUBBING	1	ACR	100.00	100.00	1,090.80	1,090.80	6,200.00
0004	0036000000-E	225	UNDERCUT EXCAVATION	100	CY	10.00	1,000.00	54.54	5,454.00	38.20
0005	0043000000-N	226	GRADING (226)	Lump Sum		200,000.00		121,822.00		510,000.00
0006	0194000000-E	265	SELECT GRANULAR MATL, CLASS III	100	CY	10.00	1,000.00	76.36	7,636.00	87.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	100	SY	1.00	100.00	5.45	545.00	6.60
0008	0248000000-N	SP	GENERIC GRADING ITEM (LS) TYPE 1 STANDARD APPROACH FILL STATION 12+15 -L-	Lump Sum		20,000.00		33,162.48		45,000.00
0009	0318000000-E	300	FND CONDIT MATL MINOR STRS	20	TON	25.00	500.00	87.26	1,745.20	66.00
0010	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	50	SY	1.00	50.00	5.45	272.50	8.50
0011	0344000000-E	310	18" SIDE DRAIN PIPE	96	LF	85.00	8,160.00	109.08	10,471.68	136.00
0012	0366000000-E	310	15" RC PIPE CULV III	68	LF	85.00	5,780.00	119.99	8,159.32	146.00
0013	0372000000-E	310	18" RC PIPE CULV III	112	LF	85.00	9,520.00	125.44	14,049.28	165.00
0014	0378000000-E	310	24" RC PIPE CULV III	56	LF	95.00	5,320.00	141.80	7,940.80	221.00
0015	0995000000-E	340	PIPE REMOVAL	216	LF	10.00	2,160.00	10.91	2,356.56	33.00
0016	1308000000-E	607	MILLN ASPHALT PVMT ***** - ***** (0" TO 1-1/2")	147	SY	35.00	5,145.00	38.18	5,612.46	56.00
0017	1491000000-E	610	ASP CONC BASE CRS B25.0C	45	TON	300.00	13,500.00	327.24	14,725.80	476.00
0018	1519000000-E	610	ASP CONC SURF CRS S9.5B	5	TON	1,500.00	7,500.00	1,636.20	8,181.00	1,100.00
0019	1575000000-E	620	ASP FOR PLANT MIX	5	TON	670.00	3,350.00	730.84	3,654.20	1,100.00
0020	2286000000-N	840	MASNRY DRAINAGE STRUCT	8	EA	2,500.00	20,000.00	4,363.20	34,905.60	6,445.00
0021	2366000000-N	840	FRAME W/2GRTS 840.24 STD	1	EA	1,000.00	1,000.00	1,636.20	1,636.20	1,700.00
0022	2367000000-N	840	FRAME W/2GRTS 840.29 STD	7	EA	1,200.00	8,400.00	1,636.20	11,453.40	1,700.00
0023	3030000000-E	862	STL BEAM GUARDRAIL	25	LF	25.00	625.00	26.18	654.50	27.30
0024	3045000000-E	862	SBGR SHOP CURVED	25	LF	30.00	750.00	30.54	763.50	31.80
0025	3150000000-N	862	ADDIT GUARDRAIL POSTS	5	EA	50.00	250.00	12.00	60.00	12.50
0026	3195000000-N	862	GR END TYPE AT-1	1	EA	750.00	750.00	1,199.88	1,199.88	1,300.00
0027	3210000000-N	862	GR END TYPE CAT-1	1	EA	1,500.00	1,500.00	1,199.88	1,199.88	1,300.00
0028	3215000000-N	862	GR ANCHOR TYPE III	4	EA	2,500.00	10,000.00	2,672.46	10,689.84	2,800.00
0029	3288000000-N	862	GR END TYPE TL-2	2	EA	4,500.00	9,000.00	2,563.38	5,126.76	3,700.00
0030	3649000000-E	876	RIP RAP, CLASS B	5	TON	150.00	750.00	109.08	545.40	79.50
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	150	SY	3.00	450.00	5.45	817.50	6.00
0032	4025000000-E	901	CONTR FURN, TYPE ***SIGN (E)	13	SF	16.50	214.50	28.01	364.13	26.90
0033	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	20	LF	9.00	180.00	8.93	178.60	8.55
0034	4102000000-N	904	SIGN ERECTION, TYPE E	2	EA	125.00	250.00	291.79	583.58	280.00
0035	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	2	EA	20.00	40.00	17.51	35.02	16.80
0036	4400000000-E	1110	WORK ZONE SIGNS (STAT)	231	SF	7.50	1,732.50	8.76	2,023.56	9.00
0037	4405000000-E	1110	WORK ZONE SIGNS (PORT)	96	SF	8.45	811.20	9.98	958.08	26.80
0038	4410000000-E	1110	WORK ZONE SIGNS (BARR)	64	SF	7.95	508.80	10.33	661.12	10.60

DF18314.2075090

Jan 13, 2026

DN01119

TIP NO

0.057 MILES

FED AID NO HELENE

BRIDGE REPLACEMENT: GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 740112 OVER PACOLET RIVER ON SR 1179 (EDNEY ROAD)

				KEMP SIGMON CONSTRUCTION CO INC CLAREMONT, NC		NHM CONSTRUCTORS INC ASHEVILLE, NC		WRIGHT BROTHERS CIVIL CONSTRUCTION LLC CHARLESTON, TN			
0039	443000000-N	1130	DRUMS	40	EA	100.00	4,000.00	53.69	2,147.60	64.75	2,590.00
0040	444500000-E	1145	BARRICADES (TYPE III)	8	LF	30.00	240.00	29.18	233.44	30.00	240.00
0041	445500000-N	1150	FLAGGER	12	DAY	350.00	4,200.00	490.86	5,890.32	1,100.00	13,200.00
0042	468500000-E	1205	THERMO PVT MKG LINES 4"90	1,224	LF	3.25	3,978.00	2.73	3,341.52	3.65	4,467.60
0043	470900000-E	1205	24"WIDE THERMO 90 MILS	14	LF	17.50	245.00	12.00	168.00	19.60	274.40
0044	481000000-E	1205	PAINT PVMT MARKINGS 4"	2,448	LF	1.50	3,672.00	0.33	807.84	1.70	4,161.60
0045	483500000-E	1205	PAINT PVT MKG LINES 24"	28	LF	5.00	140.00	2.18	61.04	5.60	156.80
0046	600000000-E	1605	TEMPORARY SILT FENCE	565	LF	3.00	1,695.00	4.36	2,463.40	4.50	2,542.50
0047	600600000-E	1610	EROS CONTRL STONE CL A	85	TON	10.00	850.00	76.36	6,490.60	76.00	6,460.00
0048	600900000-E	1610	EROS CONTRL STONE CL B	45	TON	10.00	450.00	87.26	3,926.70	78.25	3,521.25
0049	601200000-E	1610	SEDIMENT CONTROL STONE	120	TON	10.00	1,200.00	81.81	9,817.20	77.50	9,300.00
0050	601500000-E	1615	TEMPORARY MULCHING	0.5	ACR	1,500.00	750.00	4,363.20	2,181.60	4,500.00	2,250.00
0051	601800000-E	1620	SEED FOR TEMP SEEDING	100	LB	5.00	500.00	5.45	545.00	5.60	560.00
0052	602100000-E	1620	FERT FOR TEMP SEEDING	0.5	TON	1,500.00	750.00	2,181.60	1,090.80	2,200.00	1,100.00
0053	602400000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	10.00	2,000.00	43.63	8,726.00	28.20	5,640.00
0054	602900000-E	SP	SAFETY FENCE	260	LF	2.50	650.00	3.27	850.20	3.35	871.00
0055	603000000-E	1630	SILT EXCAVATION	100	CY	1.00	100.00	32.72	3,272.00	33.70	3,370.00
0056	603600000-E	1631	MATTING FOR EROS CONTROL	5,030	SY	2.00	10,060.00	2.18	10,965.40	2.25	11,317.50
0057	603700000-E	1629	COIR FIBER MAT	100	SY	10.00	1,000.00	10.91	1,091.00	11.20	1,120.00
0058	604200000-E	1632	1/4" HARDWARE CLOTH	220	LF	5.00	1,100.00	10.91	2,400.20	12.80	2,816.00
0059	607000000-N	1639	SPECIAL STILLING BASINS	1	EA	500.00	500.00	3,567.86	3,567.86	1,600.00	1,600.00
0060	6071002000-E	1642	FLOCCULANT	5	LB	20.00	100.00	27.27	136.35	28.00	140.00
0061	6071012000-E	1642	COIR FIBER WATTLE	30	LF	8.00	240.00	16.36	490.80	16.80	504.00
0062	608400000-E	1660	SEEDING AND MULCHING	0.5	ACR	2,500.00	1,250.00	4,363.20	2,181.60	4,500.00	2,250.00
0063	608700000-E	1660	MOWING	0.5	ACR	100.00	50.00	218.16	109.08	224.00	112.00
0064	609000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	5.00	250.00	10.91	545.50	11.20	560.00
0065	609300000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,500.00	375.00	2,181.60	545.40	2,200.00	550.00
0066	609600000-E	1662	SEED FOR SUPP SEEDING	50	LB	5.00	250.00	16.36	818.00	16.80	840.00
0067	610800000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	1,500.00	375.00	4,363.20	1,090.80	4,500.00	1,125.00
0068	611100000-E	SP	IMPERVIOUS DIKE	189	LF	100.00	18,900.00	87.26	16,492.14	240.00	45,360.00
0069	611450000-N	1667	SPECIALIZED HAND MOWING	10	MHR	50.00	500.00	109.08	1,090.80	112.00	1,120.00
0070	611700000-N	1675	RESPONSE FOR EROS CONTROL	13	EA	50.00	650.00	818.10	10,635.30	560.00	7,280.00
0071	611750000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,500.00	1,500.00	2,821.68	2,821.68	2,100.00	2,100.00
0072	613200000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	2	EA	1,000.00	2,000.00	404.80	809.60	1,200.00	2,400.00
STRUCTURE ITEMS											
0073	803500000-N	402	REMV EXIST STR ***** BRG (402) (12+15 -L-)	Lump Sum		200,000.00		210,036.00		42,500.00	
0074	806500000-N	SP	ASBESTOS ASSESSMENT	Lump Sum		1,500.00		818.10		840.00	
0075	809600000-E	450	PILE EXCAVATION IN SOIL	100	LF	250.00	25,000.00	402.98	40,298.00	580.00	58,000.00

DF18314.2075090

Jan 13, 2026

DN01119

TIP NO

0.057 MILES

FED AID NO HELENE

BRIDGE REPLACEMENT: GRADING, DRAINAGE, PAVING, AND STRUCTURE

BRIDGE 740112 OVER PACOLET RIVER ON SR 1179 (EDNEY ROAD)

				KEMP SIGMON CONSTRUCTION CO INC CLAREMONT, NC		NHM CONSTRUCTORS INC ASHEVILLE, NC		WRIGHT BROTHERS CIVIL CONSTRUCTION LLC CHARLESTON, TN			
0076	8108000000-E	411	***_*** DIA DRILLD PIERS (3'-6")	159	LF	1,200.00	190,800.00	800.53	127,284.27	1,050.00	166,950.00
0077	8111400000-E	411	PERM STL CASING FOR 3'-6" PIER	39	LF	236.25	9,213.75	257.70	10,050.30	368.00	14,352.00
0078	8113000000-N	411	SID INSPECTIONS	1	EA	1,000.00	1,000.00	1,090.80	1,090.80	1,700.00	1,700.00
0079	8115000000-N	411	CSL TESTING	1	EA	2,500.00	2,500.00	2,727.00	2,727.00	2,800.00	2,800.00
0080	8121000000-N	412	UNCL STR EXCAV STA ***** (12+15 -L-)	Lump Sum			5,000.00		13,635.00		27,600.00
0081	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	62	CY	1,500.00	93,000.00	2,155.00	133,610.00	4,000.00	248,000.00
0082	8210000000-N	422	BRG APPR SLAB ***** (12+15 -L-)	Lump Sum			25,000.00		43,000.00		50,800.00
0083	8217000000-E	425	REINF STEEL (BRIDGE)	20,224	LB	2.00	40,448.00	0.99	20,021.76	1.80	36,403.20
0084	8238000000-E	425	SPIRAL COL REINF STL BRG	3,705	LB	3.00	11,115.00	4.29	15,894.45	3.05	11,300.25
0085	8328200000-E	450	PILE DRV EQUIP SETUP ** STEEL PILES (HP 12X53)	10	EA	250.00	2,500.00	1,814.00	18,140.00	1,400.00	14,000.00
0086	8364000000-E	450	HP12X53 PILES	450	LF	50.00	22,500.00	64.00	28,800.00	131.00	58,950.00
0087	8391000000-N	450	STEEL PILE POINTS	10	EA	150.00	1,500.00	190.00	1,900.00	192.00	1,920.00
0088	8505000000-E	460	VERT CONC BARRIER RAIL	260	LF	175.00	45,500.00	256.00	66,560.00	257.00	66,820.00
0089	8608000000-E	876	RIP RAP II (2'-0")	630	TON	80.00	50,400.00	70.90	44,667.00	97.25	61,267.50
0090	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	665	SY	3.00	1,995.00	5.45	3,624.25	5.80	3,857.00
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum			5,000.00		7,068.64		20,100.00
0092	8753100000-E	430	3'-0"X 2'-9" PRESTR BOX BEAM	1,170	LF	350.00	409,500.00	533.24	623,890.80	466.00	545,220.00
0093	8860000000-N	SP	GENERIC STRUCTURE ITEM (LS) INSPECTION AND VIBRATION MONITORING	Lump Sum			15,000.00		32,550.00		24,100.00
0094	8860000000-N	SP	GENERIC STRUCTURE ITEM (LS) REMOVAL OF EXISTING TEMP BRIDGE	Lump Sum			20,000.00		1.00		32,700.00
0095	8897000000-N	SP	GENERIC STRUCTURE ITEM (EA) SCT TESTING	3	EA	5,000.00	15,000.00	7,500.00	22,500.00	3,100.00	9,300.00
CONTRACT TOTAL				TOTAL		1,691,888.75	TOTAL	2,053,247.77	TOTAL	2,577,566.60	
ROADWAY ITEMS				SUB-TOTAL		498,417.00	SUB-TOTAL	585,080.40	SUB-TOTAL	1,078,086.65	
STRUCTURE ITEMS				SUB-TOTAL		1,193,471.75	SUB-TOTAL	1,468,167.37	SUB-TOTAL	1,499,479.95	
BIDDERS IN ORDER						CONTRACT TOTAL					
KEMP SIGMON CONSTRUCTION CO INC						1	1,691,888.75				
NHM CONSTRUCTORS INC						2	2,053,247.77				
WRIGHT BROTHERS CIVIL CONSTRUCTION LLC						3	2,577,566.60				