

PROJECT: 18314.1044073

CONTRACT: DN01146

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING PLAN
HAYWOOD COUNTY

LOCATION: REPLACE BRIDGE 41 IN HAYWOOD COUNTY OVER
CRABTREE CREEK ON SR 1357 (CRABTREE CHURCH RD)

| | |
|---|-----------|
| TIP NO. | SHEET NO. |
| 18314.1044073 | PMP - 1 |
| APPROVED: <div>Signed by: Christopher R. Silver</div> | |
| DATE: 12/12/2025 | |
| SEAL | |
| <div>North Carolina Professional Engineer Seal 048473 Christopher R. Silver</div> | |
| DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED | |

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|----------|--|
| 1205.01 | PAVEMENT MARKINGS - LINE TYPES AND OFFSETS |
| 1205.02 | PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS |
| 1205.04 | PAVEMENT MARKINGS - INTERSECTIONS |
| 1261.01 | GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING |
| 1261.02 | GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING |
| 1262.01 | GUARDRAIL END DELINEATION |

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

- A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

| ROAD NAME | MARKING | MARKER |
|-----------|---------------|--------|
| -L- | THERMOPLASTIC | NONE |

- B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
- C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.
- D) STOP BAR LOCATION AT NON-SIGNALIZED INTERSECTIONS MAY BE ADJUSTED AS DIRECTED BY THE ENGINEER.
- E) UNLESS OTHERWISE SPECIFIED, HEATED-IN-PLACE THERMOPLASTIC MAY BE USED IN LIEU OF EXTRUDED THERMOPLASTIC FOR STOP BARS, SYMBOLS, CHARACTERS AND DIAGONALS. IF HEATED-IN-PLACE IS USED, IT SHALL BE PAID FOR USING THE EXTRUDED THERMOPLASTIC PAY ITEM.

INDEX

| SHEET NO. | DESCRIPTION |
|-----------|--|
| PMP-1 | PAVEMENT MARKING PLAN TITLE AND SCHEDULE SHEET |
| PMP-2 | PAVEMENT MARKING DETAIL |

PAVEMENT MARKING SCHEDULE

THERMOPLASTIC LINES(24", 90 MIL)


T61 WHITE STOPBAR

THERMOPLASTIC LINES(4", 90 MIL)

T1 WHITE EDGELINE
T5 2 FT.-6 FT./SP WHITE MINISKIP
T13 YELLOW DOUBLE CENTER

PLAN PREPARED FOR: N.C.D.O.T. SIGNING AND DELINEATION UNIT

ANDREW BUCHANAN NCDOT DIVISION CONTACT



P: (919) 878-9560
8601 Six Forks Road, Forum 1, Suite 700
Raleigh, North Carolina 27615-3960
NC License No. F-0112

Engineers | Construction Managers | Planners | Scientists
www.rkk.com

Responsive People | Creative Solutions

PLAN PREPARED BY: RK&K

Chris Silver, PE, PTOE Project Engineer

Allen Tutt Project Designer