

PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.14.04.10561	10	
2026CPT.14.04.20561		

SUMMARY OF QUANTITIES

												1245000000-E	1260000000-E	1519000000-E	1520000000-E	1523000000-E	1575000000-E	1704000000-E
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	SURFACE COURSE, S9.5B	LEVELING COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT
								MI	FT			SMI	TON	TONS	TONS	TONS	TONS	TONS
2026CPT.14.04.10561	Macon	1	US-64	ALONG US64	1	2	2WU	2.8	20	36.21	39.01	5.60	840			2,345	174	737
TOTAL FOR MAP NO. 1								2.8				5.60	840			2,345	174	737
TOTAL FOR PROJ NO. 2026CPT.14.04.10561								2.8				5.60	840			2,345	174	737
2026CPT.14.04.20561	Macon	2	SR-1538 / BUCK CREEK RD	FROM SR 1537 TO SR 1558	2	2	2WU	2.26	18	6.58	8.84	4.52	678	2,169			196	1,150
TOTAL FOR MAP NO. 2								2.26				4.52	678	2,169			196	1,150
2026CPT.14.04.20561	Macon	3	SR-1674 / NICKAJACK RD	FROM SR 1697 TO SR 1674	2	2		1.52	18	0	1.52	2.88	456	1,280			98	304
TOTAL FOR MAP NO. 3								1.52				2.88	456	1,280			98	304
2026CPT.14.04.20561	Macon	4	SR-1644 / RIVERSIDE RD	FROM US 441 TO SR1653	3	2	2WD	0.49	18	0	0.49	0.98	147		470		38	150
TOTAL FOR MAP NO. 4								0.49				0.98	147		470		38	150
TOTAL FOR PROJ NO. 2026CPT.14.04.20561								4.27				8.38	1,281	3,449	470		332	1,604
GRAND TOTAL								7.07				13.98	2,121	3,449	470	2,345	506	2,341