STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
HA-0004	3B

SUMMARY OF EARTHWORK

IN CUBIC YARDS

Station	Station	Uncl. Excav.	Embank. +%	Borrow	Waste
-L- 12+71.47	-L- 28+96.02	700		71	700
-Y1- 10+75.05	-Y1- 16+74.00	500		92	500
-DRWY- 13+29.64	-DRWY- 17+52.90	50		1170	50
SUBTOTALS:		1250		1333	1250
PROJECT TOTALS:		1250		1333	1250
GRAND TOTALS:		1250		1333	1250
SAY:		1250		1350	1250

MILLING OF ASPHALT PAVEMENT 3.0" DEPTH

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	YD^2
-L-	12+71.47	28+96.02	LT/RT	1000
-Y1-	10+75.05	16+74.00	LT/RT	2000
			TOTAL:	3000
			SAY:	3000

MILLING OF ASPHALT PAVEMENT VARIABLE DEPTH

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	YD^2
-Y1-	10+75.05	14+50.00	LT/RT	500
			TOTAL:	500
			SAY:	500

GUARDRAIL SUMMARY

SURVEY LINE	BEG. STA.	END STA.	LOCATION	LENGTH			WARRANT POINT		"N" DIST. FROM E.O.L.	TOTAL SHOUL WIDTH	FLARE LENGTH		W		ANCHORS								IMPACT ATTENUATOR TYPE 350		SINGLE FACED CONCRETE BARRIER	REMOVE EXISTING GUARDRAIL	REMOVE & STOCKPILE EXISTING GUARDRAIL	REMARKS
				STRAIGHT	SHOP CURVED	DOUBLE FACED	APPROACH END	TRAILING END			APPROACH END	TRAILING END	APPROACH END	TRAILING END	GREU TL-3	GREU CAT-1							G	NG				
-DRWY-	15+57.20	16+64.00	LT	57											1	1												