DocuSign Envelope ID: F6A3C50E-0FA9-4DF6-9D88-9D3C7B214EEE

PROJ. REFERENCE NO.	SHEET NO.
17BP.14.R.85	PMP-1

PAVEMENT MARKING SCHEDULE
TIP PROJECT # 17BP.14.R.85

SYMBOL	DESCRIPTION	FINAL PAVEMENT MARKINGS	PAY ITEM QUANTITY BREAKDOWN	TOTAL QUANTITY
PI	YELLOW DOUBLE CENTER	PAINT (4", 2 COATS)	460 LF	920 LF
PA	WHITE EDGELINE	PAINT (4", 2 COATS)	460 LF	920 LF

NOTES:
1. WHITE EDGE TO MATCH EXISTING LANE WIDTHS THROUGHOUT NEWLY CONSTRUCTED AREA.



DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

WSP
1001 Morehead Square Dr. Ste 610
Charlotte, NC 28203 - 704.342.5401
www.wspusa.com
LICENSE NO. F-0891

APPROVED: DocuSigned by: Richard Odynski DATE: 1/3/2019
9E04D05FEE1E4D1...

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 037467 ENGINEER RICHARD A. ODYNSKI

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
WORK ZONE TRAFFIC CONTROL

PAVEMENT MARKING PLAN

10/29/2018
T:\NCDOT_Divi4_LIBR\Group 1\Cherokee 65\TCP\17BP.14.R.85_TC_PSH_PMP.dgn
USR0604942